

VISIT...

LANZAROTE
Caliente.COM

Greg Demchak
Tatjana Dzambazova
Eddy Krygiel

Foreword by Matt Jezyk, Senior Design Manager, Autodesk

MASTERING

Revit® Architecture 2010

**Harness the Power of BIM
with Revit Architecture 2010**

**Master Key Revit Techniques
and Improve Your Productivity**



SERIOUS SKILLS.

Autodesk®
Authorized Publisher

Autodesk®
Authorized Author

Mastering

Revit® Architecture 2010



Mastering

Revit® Architecture 2010

Greg Demchak

Tatjana Dzambazova

Eddy Krygiel



Wiley Publishing, Inc.

Senior Acquisitions Editor: Willem Knibbe
Development Editor: Laurene Sorensen
Technical Editor: Phil Read
Production Editor: Liz Britten
Copy Editors: Liz Welch, Linda Recktenwald
Editorial Manager: Pete Gaughan
Production Manager: Tim Tate
Vice President and Executive Group Publisher: Richard Swadley
Vice President and Publisher: Neil Edde
Book Designer: Maureen Forsys, Happenstance Type-O-Rama; Judy Fung
Compositor: Craig W. Johnson, Happenstance Type-O-Rama
Proofreader: Word One, New York
Indexer: Ted Laux
Project Coordinator, Cover: Lynsey Stanford
Cover Designer: Ryan Sneed
Cover Image: © Pete Gardner/Digital Vision/Getty Images

Copyright © 2009 by Wiley Publishing, Inc., Indianapolis, Indiana

Published simultaneously in Canada

ISBN: 978-0-470-45649-1

No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning or otherwise, except as permitted under Sections 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, 222 Rosewood Drive, Danvers, MA 01923, (978) 750-8400, fax (978) 646-8600. Requests to the Publisher for permission should be addressed to the Permission Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, (201) 748-6011, fax (201) 748-6008, or online at <http://www.wiley.com/go/permissions>.

Limit of Liability/Disclaimer of Warranty: The publisher and the author make no representations or warranties with respect to the accuracy or completeness of the contents of this work and specifically disclaim all warranties, including without limitation warranties of fitness for a particular purpose. No warranty may be created or extended by sales or promotional materials. The advice and strategies contained herein may not be suitable for every situation. This work is sold with the understanding that the publisher is not engaged in rendering legal, accounting, or other professional services. If professional assistance is required, the services of a competent professional person should be sought. Neither the publisher nor the author shall be liable for damages arising herefrom. The fact that an organization or Web site is referred to in this work as a citation and/or a potential source of further information does not mean that the author or the publisher endorses the information the organization or Web site may provide or recommendations it may make. Further, readers should be aware that Internet Web sites listed in this work may have changed or disappeared between when this work was written and when it is read.

For general information on our other products and services or to obtain technical support, please contact our Customer Care Department within the U.S. at (877) 762-2974, outside the U.S. at (317) 572-3993 or fax (317) 572-4002.

Wiley also publishes its books in a variety of electronic formats. Some content that appears in print may not be available in electronic books.

Library of Congress Cataloging-in-Publication Data

Demchak, Greg.

Mastering Revit architecture 2010 / Greg Demchak, Tatjana Dzambazova, Eddy Krygiel. — 1st ed.

p. cm.

ISBN 978-0-470-45649-1 (paper/website)

1. Architectural drawing—Computer-aided design. 2. Architectural design—Data processing. 3. Autodesk Revit. I. Dzambazova, Tatjana. II. Krygiel, Eddy, 1972– III. Title.

NA2728.D455 2009

720.28'40285536—dc22

20090191730

TRADEMARKS: Wiley, the Wiley logo, and the Sybex logo are trademarks or registered trademarks of John Wiley & Sons, Inc. and/or its affiliates, in the United States and other countries, and may not be used without written permission. Revit is a registered trademark of Autodesk, Inc. Copyright © 2009 Autodesk, Inc. All rights reserved. All other trademarks are the property of their respective owners. Wiley Publishing, Inc., is not associated with any product or vendor mentioned in this book.

10 9 8 7 6 5 4 3 2 1

Dear Reader,

Thank you for choosing *Mastering Revit Architecture 2010*. This book is part of a family of premium-quality Sybex books, all of which are written by outstanding authors who combine practical experience with a gift for teaching.

Sybex was founded in 1976. More than 30 years later, we're still committed to producing consistently exceptional books. With each of our titles, we're working hard to set a new standard for the industry. From the paper we print on, to the authors we work with, our goal is to bring you the best books available.

I hope you see all that reflected in these pages. I'd be very interested to hear your comments and get your feedback on how we're doing. Feel free to let me know what you think about this or any other Sybex book by sending me an email at nedde@wiley.com. If you think you've found a technical error in this book, please visit <http://sybex.custhelp.com>. Customer feedback is critical to our efforts at Sybex.

Best regards,

A handwritten signature in black ink, appearing to read 'Neil Edde', with a stylized, flowing script.

Neil Edde
Vice President and Publisher
Sybex, an Imprint of Wiley

For Serene

—Greg

For all the fantastic friends that Revit brought to me,
from Norway to South Africa, I love and miss you all

— Tanja

For my family who puts up with me writing these
books evenings and weekends.

—Eddy

Acknowledgments

Hats off to the innovators who conceptualized, designed, and made Revit happen. You have changed the world!

Huge thanks to all the faithful followers! Without you, Revit wouldn't be what it is today.

Personal thanks to the Grand Master Philippe Drouant, without whose expertise, generous help, and amazing illustrations we wouldn't have been able to make this book. Many thanks to Guillermo Melantoni and Erik Egbertson, whose participation was crucial in getting a prior version of this book out of the door; to the inspirational leaders Mario Guttman and Ken Sanders for their contributions; to Matt Jezyk, Lira Nikolovska, Nathan Lockwood, Jaap van der Weide, Heather Lech, Zach Kron, Cindy Wang, Tamas Badics, and so many other colleagues for their heroic effort to create the fantastic new Conceptual Design tools in Revit 2010 that are paving a path to a whole new working paradigm.

Sincere thanks to all the hardworking developers, product designers, and quality assurance testers from the development team of Revit, for their dedication, passion, and love of Revit.

And finally, thanks are due to our friend and technical editor Phil Read and our excellent support team at Sybex, who helped us develop and focus the content. Thanks to Laurene Sorensen for helping us form complete sentences; to Liz Welch and Linda Recktenwald for dotting the i's and crossing the t's; to Liz Britten for keeping us honest; and a special thanks to Willem Knibbe, whose constant support and willingness to put up with our "issues" made us the high-maintenance authors we are today.

We would like to express our sincerest gratitude to our friends, the architects who generously shared their work, allowing us to inspire you with it: Håvard Vasshaug; DARK Arkitekter AS; To Pluss To arkitekter; Link Landskap; Dave Fano and Case Design; Mark Dietrich, James O'Toole, Jim Summers, Robin Shaffer, Robert Manna, and Burt Hill; Mike Hnastchenko; Rolly Stevens and Ellerbe Becket; Craig Barbieri, Richard Taylor, Kucarovik, Nemeth, Vlkovic, Polakova, and Senteska; Gensler; Montealegre Beach Arquitectos Ltda; Miles Walker, Lee Miller, Luis Fernandez de Ortega Barcenaz, Julio Gonzalez, and HOK; Jim Balding and WATG; E. N. Raycroft; T. Castro; A. Blood; D. Belcher; Krisztian Hegedues; and Josef Kendersky.

About the Authors



Greg Demchak is a designer, technology advocate, urban explorer, and post-apocalyptic film producer. He holds architectural degrees from the University of Oregon and Massachusetts Institute of Technology and is a LEED Accredited Professional. He is a product designer for Autodesk, and has been working with Revit since 2000. His latest work on Revit was the design of a new conceptual modeling environment. He has been teaching at the Boston Architectural College since 2003, and is currently the principal investigator for the 2009 Solar Decathlon competition. He resides in Massachusetts.



Tatjana Dzambazova became known to the AEC industry through her passionate evangelizing of Revit in its pioneer days (2001–2005) and for being the product manager for Revit Architecture (2005–2007). After this, she moved on to research of Web 2.0, social networking, and virtual worlds and later moved on to conceptual design, design computation, and digital fabrication in AEC, advocating the broader Autodesk technology portfolio relating to those trends. Before joining Autodesk in 2000, she practiced architecture for 12 years in Vienna and London. At Autodesk, she focused on advocating for technology and established herself as an internationally renowned, inspiring speaker who fosters relationships with architects and industry leaders all around the globe. Powered by seemingly unlimited sources of energy and passion, Tanja manages to make three days out of one, and is always on the hunt for what's new and exciting in the world of architecture and technology. Tanja is mad about wild animals, is a compulsive reader, and loves riding her Ducati Monster and playing Scrabble and Texas Hold 'Em. She currently lives in San Francisco.



Eddy Krygiel is a senior project architect, a LEED Accredited Professional, and an Autodesk Authorized Author at HNTB Architects headquartered in Kansas City, Missouri. He has been using Revit since version 5.1 to complete projects ranging from single-family residences and historic remodels to 1.12-million-square-foot office buildings. Eddy is responsible for implementing BIM at his firm and also consults for other architecture and contracting firms around the country looking to implement BIM. For the last four years, he has been teaching Revit to practicing architects and architectural students in the Kansas City area and has lectured around the nation on the use of BIM in the construction industry. Eddy also coauthored *Green BIM*, a book on sustainability and BIM, with Bradley Nies (Sybex, 2008).

Contents at a Glance

<i>Foreword</i>	<i>xxiii</i>
<i>Introduction</i>	<i>xxix</i>
Chapter 1 • Understanding BIM: From the Basics to Advanced Realities	1
Chapter 2 • Revit Fundamentals	15
Chapter 3 • Know Your Editing Tools	75
Chapter 4 • Setting Up Your Templates and Office Standards	97
Chapter 5 • Customizing System Families and Project Settings in Your Template. . .	147
Chapter 6 • Modeling Principles in Revit I	179
Chapter 7 • Modeling Principles in Revit II	199
Chapter 8 • Concept Massing Studies	227
Chapter 9 • From Conceptual Mass to a Real Building	265
Chapter 10 • Working with Design Options	299
Chapter 11 • Creating Custom 3D Content	319
Chapter 12 • Extended Modeling Techniques—Walls	351
Chapter 13 • Extended Modeling Techniques—Roofs and Floors	377
Chapter 14 • Extended Modeling Techniques—Railings and Fences	421
Chapter 15 • Presentation Techniques for Plans, Sections, and Elevations.	439
Chapter 16 • Presenting Perspective Views	461
Chapter 17 • Fine-Tuning Your Preliminary Design	481
Chapter 18 • Evaluating Your Preliminary Design: Sustainability	507
Chapter 19 • Annotating Your Model	531
Chapter 20 • Developing the Design with SmartWorkflows	583

Chapter 21 • Moving from Design to Detailed Documentation.....	611
Chapter 22 • Advanced Detailing Techniques.....	653
Chapter 23 • Tracking Changes in Your Model.....	673
Chapter 24 • Worksharing.....	689
Appendix A • The Bottom Line	709
Appendix B • Tips and Troubleshooting	731
<i>Index</i>	745

Contents

<i>Foreword</i>	<i>xxiii</i>
---------------------------	--------------

<i>Introduction</i>	<i>xxix</i>
-------------------------------	-------------

Chapter 1 • Understanding BIM: From the Basics to Advanced Realities 1

Identifying the Advantages of BIM	1
A Brief History of Design and Documentation	1
Building Information Modeling	2
BIM and Process Change	4
Revit Encourages Creativity	6
Every Element in Revit Has Properties	6
Elements Interact with Other Elements—All the Time	7
Duplicating Views Takes Two Clicks	7
Revit Fosters Problem Solving	8
Revit Lets You Leverage Other Tools to Support Your Workflow	8
Revit Allows You to Draft	9
The Family Editor Is a Powerful Tool	9
Revit Does Away with Layers and X-References	10
BIM Is More than a Technology Approach: It's a Change in Process	10
Revit Is the Most Advanced BIM Application	12
Where Can You Go from Here?	12
The Bottom Line	14

Chapter 2 • Revit Fundamentals 15

Understanding Revit Parametric Elements	15
Model Categories	17
Annotation Categories	19
Subcategories	20
Imported Categories/Subcategories	20
Views	20
Type and Instance Parameters	21
Bidirectional Relationships	22
Constraints	25
Revit Families	26
Overriding the Representation of Elements	32
Working with the Revit User Interface	34
Starting Revit	34
The Start Screen	34
The User Interface	35
The View Window	45
SteeringWheel and View Cube	45
The Project Browser	46

Modifying and Personalizing the Interface	47
Using the Project Browser	49
Views	49
Customizing the Project Browser's Organization	51
Sheets	52
Families	54
Links	54
Groups	55
Navigating Views and View Properties	55
Floor Plans	55
Creating a Plan View Using View Range and a Plan Region	62
Sections	66
Elevations	68
3D Views	71
The Bottom Line	74
 Chapter 3 • Know Your Editing Tools	 75
Selecting, Modifying, and Replacing Elements	75
Selection	75
Copying and Pasting	78
Create Similar	79
Editing Elements Interactively	79
Moving Elements	79
Copy	83
Rotating and Mirroring Elements	83
Array Elements	85
Scaling Elements	87
Aligning Elements	87
Trimming Lines and Walls	89
Extending Lines and Walls	90
Splitting Lines and Walls	90
Offsetting Lines and Walls	91
Keeping Elements from Moving	91
Exploring Other Editing Tools	92
Join Geometry	93
Split Face and Paint	94
Keyboard Shortcuts (Accelerators)	95
The Bottom Line	96
 Chapter 4 • Setting Up Your Templates and Office Standards	 97
Starting a Project with a Custom Template	97
Strategies for Making Templates	100
Settings for Graphic Consistency	100
Object Styles	100
Line Styles	102
Line Patterns	103

Creating a New Line Pattern	104
Materials	105
Fill Patterns (Hatches)	108
Dimension Styles	113
Text	117
Creating Custom Annotation Tags	119
View Tags	120
Customizing Element Tags	135
Keynotes and Textnotes	138
Creating Custom Title Blocks	140
Creating a Custom Title Block with the Family Editor	141
Revisions	143
Best Practices and Workarounds: Positioning Views on a Sheet	145
The Bottom Line	145

Chapter 5 • Customizing System Families and Project Settings

in Your Template	147
Creating New Types of System Families	147
Wall Types	147
Floor and Roof Types	155
Ceiling Types	156
Stair Types	157
Door and Window Types	161
Using Types and Type Catalogs	162
Creating Family Types in the Project Environment	162
Creating Family Types in the Family Editor	163
Creating Family Types with Type Catalogs	163
Loading from a Type Catalog	166
Customizing Project Settings in Your Template	166
Graphic Overrides of Host Objects	166
Additional Global Project Settings to Consider When Making Your Templates	168
The Bottom Line	177

Chapter 6 • Modeling Principles in Revit I 179

Grasping the Basics of Modeling with Revit	179
Understanding Sketch-Based Design	180
Floors and Roofs	181
Sketching Rules of Thumb	183
Understanding Work Planes, Levels, Grids, Reference Planes, and Reference Lines	183
Work Planes	183
Levels	185
Grids	185
Reference Planes	186
Reference Lines	187
Work Planes in a Nutshell	189
The Bottom Line	197

Chapter 7 • Modeling Principles in Revit II	199
Understanding the Principles of Modeling in Revit	199
Modeling with the Five Basic Sketch-Based Techniques	202
Extrusions	202
Revolve	206
Sweeps	209
Blends	215
Swept Blends	221
Combining Solids and Voids	222
Examples Showing Use of Voids	223
The Bottom Line	225
Chapter 8 • Concept Massing Studies	227
Understanding Massing Workflows	227
Massing Study Workflows	229
Revit's Massing Tools	234
Mass Creation and Visibility Tools	236
Visibility of Mass Elements	236
Starting a Conceptual Massing Study	237
Creating a Mass—Basics	237
Direct Manipulation of Mass	239
Boolean Operations	240
Join Geometry	241
Creating a New Mass Family	242
Understanding Form Making and Rationalization	243
Making a Parametric Extrusion	244
Making a Revolve	249
Making a Loft	252
Making a Sweep	256
Rationalization of Surfaces	259
Importing 3D Conceptual Models Created in Other Applications	262
The Bottom Line	263
Chapter 9 • From Conceptual Mass to a Real Building	265
Understanding Conceptual Design and Early Studies	265
Getting Site Data and Building the Context	266
Positioning Imported Files Relative to the Revit Project	268
Building the 3D Context	269
Program Check and Feasibility	271
Modeling by Face to Make a Building	274
Technical Details You Should Be Aware of When Scheduling Mass Elements	284
Applying 3D Components to a Divided Surface	286
Using Imported Geometry from Other Applications for Massing	290
SketchUp	290
Rhinoceros	292
Autodesk Maya	293

Autodesk Inventor	294
AutoCAD 2010	296
Using Smart Relationships between Building Mass and the Underlying Mass	297
The Bottom Line	298
Chapter 10 • Working with Design Options	299
Using Revit Design Options	299
Design Option Tools	300
Design Option Sets	300
Adding Elements to a Design Option	301
Editing a Design Option	304
Displaying Design Options	306
Deciding on a Design Solution	307
Putting Design Options into Practice	308
Using Design Options with Parametric Design	313
Showing Quantities and Cost Schedules for Multiple Options	313
Working with Rooms and Design Options	314
The Bottom Line	317
Chapter 11 • Creating Custom 3D Content	319
Modeling Parametric 3D Families	319
Choosing the Right Family Template	320
Types of Families	322
Family Categories and Parameters	333
Nesting One Family into Another	335
Scheduling Nested Families	337
Linking Parameters	337
Linking Parameters (Conditional Visibility)	338
Building Relationships between Parameters with Formulas	339
Making a Parametric Array	340
Encoding Design Rules	341
Building a Parametric 3D Family	345
The Bottom Line	350
Chapter 12 • Extended Modeling Techniques—Walls	351
Using Advanced Modeling Techniques for Standard Walls	351
Wall Core	351
Layer Join Cleanup	353
Editing Wall Joins	354
Disjoining Walls	354
Stacked Walls	355
Adding Wall Articulation	356
Wall Wrapping	361
Sweeps and Reveals	361
Creating Custom In-Place Walls	368

Using Advanced Modeling Design Techniques for Curtain Walls	369
Designing a Curtain Wall	370
Curtain Panels	373
Curtain Wall Doors and Windows	374
Complex Curtain Wall Panels	375
The Bottom Line	376

Chapter 13 • Extended Modeling Techniques—Roofs and Floors 377

Understanding the Various Roof Creation Methods	377
Roof by Footprint	378
Roof by Extrusion	383
Roof-in-Place	385
Creating All Kinds of Roofs	393
Flat Roof	393
Gable Roof with Asymmetric Slopes	394
Shed Roof	395
Hipped Roof	396
Hip Roof Following Recessed Walls	397
Gable Roof	398
Gable Roof with Extending Pergola	399
Hip and Gable Hybrid Roof	400
Gambrel Roof	401
Dutch Gable with Glazed Roof	402
Dutch Gable	403
Hipped Roof with Sloped Arrow Dormer	404
Hipped Roof with Two Dormers	405
Four-Sided Gable	406
Hipped Roof with Extruded Roof Dormer	407
Cone Roof	408
Dome	409
Barrel Roof	410
Multipitch Roof	411
Working with Advanced Roof and Floor Shape Editing	416
Sloped Roofs	417
Warped Surfaces	419
The Bottom Line	420

Chapter 14 • Extended Modeling Techniques—Railings and Fences 421

Working with Railings and Fences	421
Railings	422
Subelements of the Railing Element and Principles of Railing Structure	423
Railing Construction	425
Setting Up Rail Structure	425
The Bottom Line	437

Chapter 15 • Presentation Techniques for Plans, Sections, and Elevations	439
Using Shadows for Presentation Purposes	439
Analytical Drawings: Sun and Shadow Studies	441
Create Expressive Drawings with Shadows	444
Performance Considerations	445
Color-Coded Plans and Sections	445
Creating Presentation-Quality Plans and Sections	451
Coarse Scale Fill Patterns	451
Graphic Overrides and View Templates	452
Creating Elevations That Convey Depth	453
Linework	454
Drafting Lines	455
True-Color Elevations	455
Elevations with Transparent Materials	456
Using Images in Elevation Views	457
The Bottom Line	459
 Chapter 16 • Presenting Perspective Views	 461
Creating Perspective Views	461
Showing the Camera	463
Silhouetted Edge Display	464
Creating Photorealistic Renderings	465
The Rendering Dialog Box	466
Materials	472
Rendering Tips	476
Creating Animated Walkthroughs	477
Exporting the 3D Model for Use in Other Applications	478
The Bottom Line	479
 Chapter 17 • Fine-Tuning Your Preliminary Design	 481
Quantifying Your Preliminary Designs	481
The Foundation Model	481
Calculating Area Plans	483
Rooms and Room Tags	483
Area Plans	483
Adding Areas and Tags	491
Creating Schedules	492
Making a Simple Schedule (Rentable Area)	495
Placing the Schedule on a Sheet	499
Additional Schedule Capabilities	501
Using Schedules for Preliminary Cost Estimates	502
Editing the Graphic Appearance of a Schedule	503
The Bottom Line	506

Chapter 18 • Evaluating Your Preliminary Design: Sustainability	507
Incorporating a Sustainable Approach from the Beginning.	507
Preliminary Design Tools	508
The LEED Rating System.	508
Using Revit to Create Sun Studies.	509
Making a Solar Study.	511
Animated Sun Studies	515
Tracking Recycled Materials and Other Sustainability Strategies Using Schedules	519
Recycled Materials	519
Window Surface Percentage vs. Room Area	521
Energy Analysis	522
Daylighting	527
Quality Control Measures.	527
The Bottom Line.	530
 Chapter 19 • Annotating Your Model	 531
Annotating Views	531
Creating and Annotating Rooms.	532
Room Separation Lines	535
Selecting Rooms	537
Rooms and Room Tags.	538
Rooms in Section Views.	538
Room Properties	539
Area and Volume Computations	540
Using Schedule Keys	546
Creating a Schedule Key	546
Leveraging Tags	550
Loading Tags	550
Placing Tags	550
Changing a Tag Value	551
Tagging Untagged Elements.	552
Understanding Project and Shared Parameters	554
Creating a Custom Project Parameter	555
Creating Shared Parameters	558
Adding Text and Keynotes	568
Text	568
Keynotes and Textnotes.	570
Keynote Behavior and Editing	571
Keynote Filenaming Conventions	572
Keynote Settings.	573
Adding Keynotes to a View	573
Keynote Legends.	574
The Keynote Family	576
Predefining Keynotes.	580
The Bottom Line.	581

Chapter 20 • Developing the Design with SmartWorkflows	583
Working with Repetitive Elements	583
Understanding How to Use Groups	584
Using Groups for Repetitive Rooms	584
Creating and Managing Groups	585
Creating and Placing Repetitive Units Using Groups	585
Adding Rooms to a Group	589
Nesting a Group into Another Group	591
Adding Detail Elements to Groups	592
Nesting a Group from a Previous Project	593
Making Variations to a Group Instance	594
Repeating Groups on Other Levels	597
Making the Group a Part of the Project	598
Editing a Group in a Separate File	599
Detail Groups	600
Best Practices for Grouping	601
Understanding the Principles of Links	602
Common Link Use Cases	603
Linking Files	605
Special Link Features	606
Controlling the Visibility of Links	607
Deciding Whether to Use Groups, Links, or Both	607
Final Considerations	608
The Bottom Line	609
 Chapter 21 • Moving from Design to Detailed Documentation	 611
Advancing the Design	611
Creating Drafting Views	612
Importing and Linking CAD Details	612
Linking vs. Importing	613
Creating 2D Detail Components	619
Detail Groups	619
Detail Components	619
Masking Regions	620
Creating a Repeating Detail Element	621
Detail Component Properties	623
Creating Custom Line Types Using Repeating Details	623
Miscellaneous Line Tools	624
Linework	628
Using Callouts	628
Adding Information to Your Details	630
Embellishing the Wall Section: The SIM (Similar) Condition	632
Adding Detail Components	634
Embellishing the Wall Section: The Model Details	639
The Bottom Line	651

Chapter 22 • Advanced Detailing Techniques	653
Creating 3D Details	653
3D Details: Enabling a Section Box in 3D View	655
3D Details: Orienting to View	655
Adding Annotations to the 3D Detail	658
Adding Detail Components to Families	658
Adding Details to a Window Family	659
Visibility Settings	663
Adding More Information Using Symbolic Lines	665
Reusing Details from Other Revit Projects	667
Exporting Details from Revit Projects	667
Importing Views into Revit Projects	669
The Bottom Line	671
 Chapter 23 • Tracking Changes in Your Model	 673
Adding Revisions to Your Project	673
Placing Revision Clouds	676
Tagging a Revision Cloud	679
BIM and Supplemental Drawings	680
Using Autodesk Design Review	682
The Design Review User Interface	682
Exporting to Design Review	683
Marking Up the Model Using Design Review	686
Importing a Design Review Markup	687
The Bottom Line	688
 Chapter 24 • Worksharing	 689
Setting Up a Project with Worksets	689
Understanding Worksharing Basics	691
Workset Organization	694
Moving Elements Between Worksets	696
Managing Workflow with Worksets	698
Creating a Central File	698
Creating the Local File	699
Saving Shared Work	700
Loading Work from Other Team Members	701
Understanding Element Ownership in Worksets	701
Borrowing Elements	703
Requesting Permission	703
Granting Permission	704
Closing Revit	706
The Bottom Line	707

Appendix A • The Bottom Line	709
Chapter 1: Understanding Basic BIM: From the Basics to Advanced Realities	709
Chapter 2: Revit Fundamentals	710
Chapter 3: Know Your Editing Tools	710
Chapter 4: Setting Up Your Templates and Office Standards.....	711
Chapter 5: Customizing System Families and Project Settings in Your Template ...	712
Chapter 6: Modeling Principles in Revit I	713
Chapter 7: Modeling Principles in Revit II.....	714
Chapter 8: Concept Massing Studies	715
Chapter 9: From Conceptual Mass to a Real Building	716
Chapter 10: Working with Design Options	716
Chapter 11: Creating Custom 3D Content	718
Chapter 12: Extended Modeling Techniques—Walls.....	719
Chapter 13: Extended Modeling Techniques—Roofs and Floors.....	719
Chapter 14: Extended Modeling Techniques—Railing and Fences.....	720
Chapter 15: Presentation Techniques for Plans, Sections, and Elevations	721
Chapter 16: Presenting Perspective Views.....	722
Chapter 17: Fine-Tuning Your Preliminary Design	722
Chapter 18: Evaluating Your Preliminary Design: Sustainability	723
Chapter 19: Annotating Your Model.....	724
Chapter 20: Developing the Design with Smart Workflows	726
Chapter 21: Moving from Design to Detailed Documentation.....	727
Chapter 22: Advanced Detailing Techniques	727
Chapter 23: Tracking Changes in Your Model	728
Chapter 24: Worksharing	729
 Appendix B • Tips and Troubleshooting	 731
Optimizing Performance	731
Using Best Practices.....	733
Dealing with File Corruption.....	739
Getting Started in Revit	741
Finding Additional Resources.....	743
<i>Index</i>	745

Foreword

Revit Architecture will turn 10 years old in the coming year, possibly while you are reading this book. As such, it seems appropriate to reflect on the origins of this tool and describe a small portion of the history of Revit from my personal perspective, as well as some of the factors that influenced where we are now.

Change Was Coming

The basic tenets of building information modeling (BIM) and parametric building modeling have been discussed for 30 years. So why did it take so long for the architecture, engineering, and construction (AEC) industry to get there? I believe the software and AEC industries were uniquely aligned over the past 10 years and, in the context of macroeconomic conditions like booms and recessions, helped catalyze the changes we see today. Over that time, conditions were right for the inception, formation, and strengthening of the ideas and technologies inside Revit and for the development of the larger concept of BIM.

There were significant reasons why the AEC industry *should* have been primed for change in the late 1990s. The United States had come out of the recession that plagued it earlier in the decade. The construction industry was thriving, as were information technology and the Internet. There had been dramatic increases in computational power and networking. Adoption of CAD was increasing dramatically in architectural firms, and other solutions on the market also offered 3D modeling and building-specific modeling capabilities. Despite these innovations, the typical construction documentation process was tedious and error-prone. The typical design-bid-build construction process was inefficient and costly. Was that enough to cause the architectural design industry to change? No. The industry was simply not ready for dramatic process and technical change from a business, design process, or technology adoption standpoint. (The AEC industry is not known for moving quickly.)

The factors I've listed did not change the AEC industry overnight, but they did start to sow the seeds. A contributing factor in the evolution toward what we now understand as BIM can be found in the early history of Revit, which tells a story of how small teams, a clear vision, a little bit of venture capital money and a large amount of luck can contribute toward building an innovative software product.

There Are People Who Do

In 1999 I was happily working as a design architect who also happened to be interested in technology. Over time, I started reading WIRED and FastCompany more than Architectural Record. In Silicon Valley and the San Francisco Bay Area, venture capital money was flowing. A change was also happening on the East Coast: friends of mine had started to take jobs at software startups. I noticed they seemed to spend a good deal of time playing foosball.

I joined a small startup software company called Charles River Software in October of 1999 and was one of the first architects hired to work on a new parametric building modeler, code-named Perspective. At that point the software could do little more than draw walls and place windows. The roof tool was still a rough sketch on a whiteboard and the column tool had just

come online. It crashed when you clicked the button. There were a lot of crashes in those days. We had no shipping product, no customers, and did not even have a name for the company or the product. (The name Revit came later.) My expectations of playing foosball in a fun startup environment had vanished. There was a lot of work to do.

In retrospect, the most important things we had were a product vision and a small group of people who knew how to get things done. The software development team was literally a group of physicists and rocket scientists. They had experience building parametric modeling applications and maintaining a high level of bidirectional associativity, and they were comfortable solving hard math and logic problems. The marketing team proved to be quite adept as well. The quality assurance, product design, and technical support teams were from the AEC industry. The management team believed in the power of small teams and in accountability. They also knew how to ruthlessly prioritize and force a level of critical thinking. The team learned how to get things done and deliver results because it had to. Our survival depended on it.

As an impressionable novice in the realm of software development, I learned a great deal from the early Revit management team. Two books that informed their thinking were *Crossing the Chasm* by Geoffrey Moore (HarperBusiness, 1999) and *Rules for Revolutionaries* by Guy Kawasaki (Collins, 1999). They were popular in the late 1990s and are still good entry points into the field today. I dug them out of my basement to help write this foreword.

Great teams are usually small—under fifty in total head count...

Guy Kawasaki, *Rules for Revolutionaries*

In April 2000, I helped ship a crappy product (to paraphrase Guy Kawasaki). Revit 1.0 was launched at the AIA Convention in Philadelphia. It could only draw walls, roofs, floors and ceilings. There were only 14 creation commands and they all fit on the screen at one time. It was insanely hard to build your own windows and doors. Performance was horrible. Our baby was not perfect, far from it, but the fundamental concepts of the parametric building model were all there. The hardest part was convincing ourselves we were ready to ship. We had to learn it was okay not to be perfect.

Revolutionary products don't fail because they are shipped too early; they fail because they are not revised fast enough.

Guy Kawasaki, *Rules for Revolutionaries*

Iterating and Innovating in a Recession

It turns out our attitude toward technology adoption becomes significant any time we are introducing products that require us to change our current mode of behavior or to modify other products and services we rely on. In academic terms, such products are called discontinuous innovations.

The contrasting term, continuous innovations, refers to the normal upgrading of products that does not require us to change behavior.

Geoffrey Moore, *Crossing the Chasm*

Geoffrey Moore's book *Crossing the Chasm* is one of the must-reads for anyone attempting to deliver innovative products and services to a market. He introduces the Technology Adoption Life Cycle, which divides customers into segments like Innovators, Early Adopters, Early Majority, and Late Majority, following a traditional bell curve.

The first thing any new product needs to do is identify and work with the Innovators and Early Adopters in the industry. Accordingly, we spent the next 2 years (2000–2002) iterating and revising, designing, and developing the first few versions of Revit. The things we had during that time were a vision, and, most important, a small set of customers who definitely fit the mold of Innovators and Early Adopters. These customers believed in the vision and were not afraid to stick their necks out and try our software, and they were vocal in telling us what did and did not work. Ideas were tried and rapidly improved or discarded.

Listen to what your early adopters say about your product and improve it accordingly because while better is the enemy of good enough, better... better be coming.
Guy Kawasaki, *Rules for Revolutionaries*

By fall 2001, we still did not have very many customers and the economy was not doing well. The Internet boom was over and the United States was in another recession. Companies that sold pet food online had started to fail. Quite frankly, times were tough. Money was tight and it was not clear what the future would bring. We dug in and continued to listen and work with our customers and produce more versions. There was a remarkable sense of creativity and camaraderie in our second-rate office building in Boston as we designed, built, tested and supported a young product.

A lousy building and lousy furniture are necessary because suffering is good for revolutionaries. It builds cohesiveness; it creates a sense of urgency; and it focuses the team on what's important: shipping! If you are ever recruited by a team that claims to be revolutionary and see beautiful, matched Herman Miller furniture, run do not walk, from the interview. On the other hand, if you see a lousy building, lousy furniture, but fantastically creative workspaces, then sign up immediately.
Guy Kawasaki, *Rules for Revolutionaries*

Between 2000 and 2002, the team built the main features of Revit as a parametric building modeler and created the seeds of a discontinuous innovation and a disruptive technology, as defined by Clay Christensen in his book *The Innovator's Dilemma: When New Technologies Cause Great Firms to Fail* (Harvard Business School Press, 1997):

Disruptive technologies bring to a market a very different value proposition than had been available previously. Generally, disruptive technologies underperform established products in mainstream markets. But they have other features that a few fringe (and generally new) customers value. Products based on disruptive technologies are typically cheaper, simpler, smaller, and frequently more convenient to use.
Clay Christensen, *The Innovator's Dilemma*

It was not apparent to us at that time, but the core features of Revit that are the most disruptive and technologically innovative were developed during this time frame. Perhaps there is some correlation between the squeeze of the tech bust in the early 2000s and the activities of a small team of software engineers and architects hunkered down in an ugly office building outside of Boston. Interestingly, there are now publications that discuss how major innovations are more likely to happen in recessions. It's probably a good thing we did not spend those years playing foosball.

Consider the year 2001, by all accounts a rough year. It was clear that the Internet bubble had burst. The Nasdaq index was down close to 30%—and that was before the Sept. 11 terrorist attacks. But was it a bad year for disruption? Quite the contrary. In 2001, [there were] at least a dozen specific disruptive developments in the U.S. alone.
Scott D. Anthony and Leslie Feinzaig, "Innovating During a Recession," http://www.forbes.com/2008/07/08/recession-innovation-retailing_leadership_clayton_in_sa_0708claytonchristensen_in1.html

Nurturing a Young Technology

The business environment continued to prove challenging in the early 2000s. Revit needed a sales channel and customers. The saving grace came on April 1, 2002, when Revit Technology Corporation was acquired by Autodesk, Inc. There were now opportunities to continue nurturing a young technology and start utilizing the global reach of the Autodesk organization.

The seven years after the acquisition were spent nurturing and developing the product and the underlying platform. An investment was made by forward-looking industry executives inside Autodesk, not just in the acquisition of a small startup, but in the development of a new platform for the AEC industry. During that time, the expanded Revit product development team, also known as the “The Factory,” continued to develop software. Customers were listened to; features were added and refined; support, sales, and marketing organizations were exposed to the newly acquired product.

It is difficult to prove exactly when, but at some point along the way Revit Architecture “crossed the chasm” and started to be deployed in the larger market of Early Majority customers. Many products and services fail to make the treacherous crossing.

There were still large challenges to overcome. The product needed to be turned into a platform. Teams started to work on what are now Revit Structure and Revit MEP. Large customers needed to be supported. A large number of creative and passionate people started working on Revit. Forward-looking executives started to articulate the ideas we now know as building information modeling.

I feel extremely fortunate and honored to work with many creative, passionate people in the Autodesk organization, as well as many leading architectural and engineering firms.

Where Are We Now?

So what does the world look like in April 2009? BIM is decidedly the present. We are now living in a BIM-enabled world, where technologies like Revit have helped enable larger process and business-related changes. The small experimental software project from 10 years ago has been nurtured and supported. It has matured over time into the current Revit Architecture 2010. The number of new firms and individuals starting to use Revit is increasing rapidly.

Concepts like BIM are larger than any technology and, when combined with other trends like integrated project delivery (IPD), are helping the AEC industry to change very quickly, more quickly than any time in the last 10–15 years. It is important to understand that BIM is larger than just Revit. An old friend and colleague of mine sums this up:

The reason *Mastering Revit Architecture* is such a great book is because of its holistic approach to BIM. Eddy, Greg, and Tatjana have taken great care to help you understand the context of what you’re trying to accomplish within the application of important design principles. Many books mistakenly view BIM as mere “technology”—or even one particular technology. It’s not. BIM is a philosophical approach to architecture that emphasizes the integration of the design, development, and delivery process. It’s about understanding the implications, complications, and context of design decisions as early as possible.

It’s about being accountable for your own design decisions.

Phil Read, foreword to *Mastering Revit Architecture 2009* (Sybex, 2008)

So how can we help more professionals in the industry understand the implications, complications, and context of their design decisions as early as possible? Revit Architecture 2010 can

help. In this new release, the talented team of product managers, interaction designers, and software developers in the Factory have built a new user interface, added new conceptual modeling tools, and extended the underlying platform.

The process used to design, develop, and test this release has been thoughtful and rigorous. The teams working on these problems are professional and have worked closely with users. If you are interested in learning more about this process, I recommend you visit the “Inside the Factory” blog (<http://insidethefactory.typepad.com>). I am confident that our talented team of software designers and developers will continue to work with users in the field and, collectively, we can create better tools for the industry.

In this new release, we have added new conceptual modeling features to the Revit platform. We have built a set of tools in Revit that make it easier to create and manipulate geometric form, and then turn it into a building in Revit, something that historically has been quite difficult to do and often required additional software tools. We have worked with an exceptionally talented group of customers, product designers, software developers, quality assurance architects, user assistance professionals, marketing managers, and product managers. I feel extremely fortunate and honored to have been able to lead this effort and work closely with my colleagues (Lira Nikolovska, Greg Demchak, Nathan Lockwood, Laura Gutwillig, Heather Lech, Zach Kron, Scott Latch, and Jason Winstanley).

Revit is being implemented in mainstream architecture and engineering firms worldwide, and books like *Mastering Revit Architecture 2010* are instrumental in helping people make the transition from CAD to BIM. I applaud Greg, Tatjana, and Eddy for the dedication, time, and effort they have contributed to every edition of this book.

What’s Next?

Ten years ago, the environment was right for a few software visionaries to see the market opportunity in the AEC industry. Eight years ago, the challenging times of the last recession influenced the critical formation of a new technology. Five years ago, the environment was right for a strengthened technology to be piloted by more firms and used on significant projects like Skidmore Owens and Merrill’s Freedom Tower. During these years, the larger concept of BIM was formed and is now generally recognized as where the industry is headed.

So what’s next? What pressures, market conditions, and opportunities do we see in the current day? Here are two pressures affecting both the AEC and high-tech industry.

Economic Pressures

We are in the midst of a massive global economic downturn, perhaps the worst recession in our lifetime. What does this mean for the AEC industry and for how we think about technology? How can design teams work more effectively together and provide more value to their clients and owners? How can design teams produce a better built environment in these times? How can they use the tools we have more effectively, foster deeper insight into our designs, and ultimately make better design decisions?

Revit was conceived of as a platform for managing change and coordinating documents, but as people get past the building modeling part of BIM, they realize the middle letter of BIM stands for *information*. The data in the Revit model can help design teams make better decisions earlier in the process. We see firms using the building information model not just for coordinated documentation, but to perform efficiency calculations and what-if scenarios for

their clients. As design teams become more conversant with their tools and more design data is added to the model, the relative value of the model increases. This can help not only the core design team, but also the larger team, including the owner and contractor, especially when used in conjunction with integrated project delivery (IPD). When you combine the benefits of coordinated documentation, improved building insight, and sharing of valuable information with the extended design team, investing in BIM seems to make sense, even in the current downturn.

Environmental Pressures

We are also in the midst of severe environmental changes and have come to a collective realization that the way we use energy and our natural resources is not sustainable. We know our buildings have an enormous impact in terms of energy usage during construction and operation of a given building. Can we better understand how our current building stock is performing and where energy is being used today? Can we propose thoughtful and strategic modifications to existing buildings? Can we work to make our new designs more sustainable and energy-conscious?

Once again, the middle letter of BIM stands for *information*. As government officials and the general population become more aware of the impact buildings have on the environment, one might expect a renewed interest in energy-efficient design. The same information latent in the building model can be used to better understand and predict how a building will perform, through both whole building energy analysis and more detailed, specific analysis. If you are interested in finding out how, please visit <http://www.autodesk.com/green>.

What does the future look like? From a technology and software design standpoint, I can't help but wonder what the world will look like in another 5–10 years. Given the current economic and political climate, perhaps there is another round of increased innovation on the horizon. Only time will tell. Revit has certainly been a core part of advances in the industry over the past 10 years, and we look forward to working with you and other architects and engineers to design better tools for the AEC industry in the future.

All the best,
Matt Jezyk
April 2009

Matt Jezyk is an architect and product designer. He was one of the first product designers working on what is now called Revit Architecture. Since joining Autodesk with the Revit acquisition, he was a product designer for Revit Architecture, lead the design team working on Revit Structure, and most recently lead the team working on the new conceptual modeling tools in the 2010 release. Matt is now leading the user experience team working on analysis and simulation tools for the building industry.

Introduction

Welcome to the second edition of *Mastering Revit Architecture*, based on the Revit Architecture 2010 release.

This book follows on the heels of our updated *Introducing Revit Architecture 2010* (Wiley, 2009). In preparing the 2010 edition of the *Mastering* book, we took the opportunity to introduce some of the features new to the 2010 release of the software, to rewrite large portions of the text, and to polish up the rest, taking into consideration comments and suggestions from many readers and friends. Working as a team of three authors, we kept one another in constant check, each of us writing, reviewing, editing, and updating as chapters rolled out. One additional change we made to the previous edition of the book was to break some of the longer chapters into more bite-sized morsels, which we hope resulted in chapters that flow better and give you some breathing room as you move through the book.

Writing books looks easier than it truly is. What drives and inspires us is the feeling that we're doing something important: sharing our best knowledge and practices about Revit and building information modeling (BIM) with those who are already acquainted with its incredible power and feel the need to go deeper and further to fully leverage its abilities and values. We want to help you make better designs, be more efficient in creating correct documentation, learn some new techniques, and put some fun back into using software.

We also wanted to write a book that is as much about architectural design and practice as it is about software. We think we've succeeded, because the book follows real-life workflows and scenarios and is full of practical examples that show how to use Revit practically and creatively.

Who Should Read This Book

This book is written for architects who have already gotten their feet wet with Revit and are eager to learn more so they can optimize workflow and leverage the full power of this tool. It's for architects of any generation—you don't need to be a high-tech wizard to dive into this book. However, a basic understanding of Revit will make it easier to work through the book. Revit is very rich, and the topics we've selected include some of the most widely used ones, as well as some of the least understood. Many more books need to be written to cover the entire world of Revit.

This book is also for the seasoned user who has already received training or has started working on projects with Revit and is looking to discover useful best practices and tips that will make the work on a project smoother and the implementation easier. We've added many time-saving and inspiring concepts to the book, supported by examples from architect friends and colleagues from all around the world, to motivate you and help you on your journey into the

new era of building information modeling. For BIM managers, the book offers insights into the best practices for creating good project or office templates; these managers should also take a sneak peek into the powerful world of building content and Revit families.

What You Will Learn

This book will help you take the basics of Revit and BIM that you already know and expand on them using real-world examples. We will show you how to take a preliminary model and add layers of intelligence to help analyze and augment your designs.

In this particular volume, we go beyond introductory topics. Thus, we won't be starting a project from scratch or teaching you how to build a simplified BIM model from the ground up. (If you are interested in that approach, please see *Introducing Revit Architecture 2010* [Wiley, 2009], which is meant to be complementary to this book). Instead, our book begins with a brief overview of the BIM approach. As you are already aware, BIM is more than just a change in software; it's a change in architectural workflow and culture. To leverage the full advantages of both BIM and Revit in your office structure, you will need to make some changes to your practice. We've designed the book around an ideal, integrated workflow to help you make this transition.

Starting with the workflows for conceptual design and feasibility studies, it continues through best practices for design iteration and refinement. You'll learn about powerful modeling techniques, design documentation best practices, how to make compelling presentation graphics, parametric design with the family editor, workflow topics like tracking changes and worksharing, and some strategies for sustainable design. The book concludes with an appendix on troubleshooting and best practices so you can avoid common pitfalls. Throughout the book we've tried to share our practical experience with you, particularly in the form of Real-World Scenario sidebars.

Whether you're studying Revit on your own or in a class or training program, you can use the Master It questions in the Bottom Line section at the end of each chapter to test your mastery of the skills you've learned.

Also featured is a color project gallery containing inspirational Revit projects from friends and colleagues who were generous enough to share their good work with the rest of the world.

All the tutorial files necessary to complete the book's exercises plus sample families are hosted online at www.sybex.com/go/masteringrevit2010. To download the trial version of Revit Architecture, go to www.autodesk.com/revitarchitecture, where you'll also find complete system requirements for running Revit.

Enjoy! Revit has changed our lives. Maybe it will change yours as well.

We welcome your feedback! Please feel free to email us at GoRevit@gmail.com.

Go Revit!

Greg, Tanja, and Eddy

The Mastering Series

The *Mastering* series from Sybex provides outstanding instruction for readers with intermediate and advanced skills, in the form of top-notch training and development for those already working in their field and clear, serious education for those aspiring to become pros. Every *Mastering* book includes:

- ◆ Real-World Scenarios, ranging from case studies to interviews, that show how the tool, technique, or knowledge presented is applied in actual practice
- ◆ Skill-based instruction, with chapters organized around real tasks rather than abstract concepts or subjects
- ◆ Self-review test questions, so you can be certain you're equipped to do the job right

Chapter 1

Understanding BIM: From the Basics to Advanced Realities

In this chapter we'll cover the principles of a building information modeling (BIM) approach and summarize how BIM differs from a traditional 2D computer-aided design (CAD) process. We'll explain fundamental characteristics of Revit, how Revit delivers the benefits of a true BIM tool, and why Revit is the tool best suited for a process motivated by an integrated and collaborative practice.

In this chapter, you'll learn to:

- ◆ Identify the advantages of building information modeling
- ◆ Know what to expect from BIM

Identifying the Advantages of BIM

The production of design documents has traditionally been an exercise in drawing lines to represent a building. These documents become instruction sets: an annotated booklet that describes what the building should look like when complete. The plan, section, elevation, and detail are all skillfully drafted—line by line, drawing by drawing, sheet by sheet. Whether physical or digital, these traditional drawing sets are composed of annotated graphics where each line and text is part of a larger abstraction meant to convey design intent so that a building can eventually be constructed. By and large, this is still the reality we face today, but the process of creating these drawings is being fundamentally changed as a result of BIM.

Let's put this into an historical context for a moment and briefly walk through the evolution of architectural design and documentation.

A Brief History of Design and Documentation

Andrea Palladio's *Four Books on Architecture* (trans. Robert Tavernor and Richard Schofield, MIT Press, 1997) presents an amazing array of drawing techniques that show buildings cut in plan and section and even hybrid drawings that show elevations and sections in one drawing. You can see hints about construction techniques and structural gestures in the form of trusses, arches, and columns.

These representations were meant as simplified expressions of a project, and often they were idealized versions of the building—not necessarily how the building was built. The drawings were communication and documentation tools, themselves works of detailed craftsmanship. In those days (14th–17th centuries), the architect was brought up in the tradition of building and

had integral knowledge of how buildings were constructed. Palladio, like many other architects of his day, grew up as a stonemason. Building techniques were deeply embedded in the construction trades, which in turn spawned the great architects of the time. Other master masons and sculptors who were also architects include the likes of Filippo Brunelleschi, Giovanni Bernini, and Francesco Borromini. These architects are often referred to as the master builders, because they were involved in all facets of the design and construction of buildings.

Over time, however, architecture became more and more academic as building typologies solidified, and under the influence of Beaux Arts tradition, classical reconstructions on paper and in model form became part of the formative education of the architect. The design profession began its gradual separation from the building trades. The notion of design process and iterative problem solving became critical attributes of a design professional—in many cases superseding knowledge of construction means and methods.

With modern architecture, solving abstract spatial problems, accommodating programmatic elements, and experimenting with new materials became driving forces. The machine age and the promise of mass production were idealized and fully embraced. Le Corbusier's (1887–1965) romantic vision of steamships and automobiles inspired a new generation of architecture, and buildings became increasingly machine-like. Consider all the office towers and commercial office parks that have emerged, each with internal mechanical systems to keep them operational.

As buildings continued to grow in complexity, both technically and programmatically, the architect grew more removed from the act of physical construction. Modern materials such as steel and reinforced concrete became prevalent, and complex building systems were introduced. In turn, the production of more detailed drawings became a legal and practical requirement. Structural engineers and mechanical engineers were added to the process, as need for specialized knowledge of building systems grew. No longer could the architect expect to produce a few simple drawings and have a building erected. Complexity in building systems demanded greater amounts of information, and this information was delivered in the form of larger and more complex construction document sets. Architects today find themselves drafting, producing details, working with a wide range of consultants, and still having to create sketches for contractors in the field in order to resolve the complexity of construction assemblies.

The traditional production of plans, sections, and elevations continues to this day, but with far more drawings than in the days of Palladio. At the same time, we ask these questions: Will all these drawings be necessary in the near future? Will the adoption of BIM lead to new ways of communicating the design, new delivery methods, new forms of construction, and new roles for the architect? Can a shift in technology lead to a shift in thinking about the building process?

Building Information Modeling

Fast-forward to the present context and the advent of building information modeling. The production of drawings is now streamlined by creating a digital 3D model composed of virtual building elements. These elements are loaded with data that describe not only geometry, but also material, fire rating, cost, manufacturer, count, and just about any other metadata you can imagine. The focus moves from 2D abstractions to integrated model delivery. It's now possible to detect spatial clashes between the multitudes of complex systems in the building. You can know with confidence whether ductwork will interfere with the structural steel long before construction starts.

The goal of reducing errors and smoothing out the construction process is driving firms to be more efficient, effective, and productive. With BIM, all the plans, sections, and elevations are derivative representations of the model: producing these drawings is no longer a set of isolated, repetitive, and discontinuous tasks. A data-rich model also means that more analysis and iterative searching for optimal solutions can occur early in the design process. As detail is added, the model becomes an increasingly accurate representation of what will actually be built. The model itself can be used to generate parts lists, shop drawings, and instructions for industrially produced elements for the fabrication process. If you can send a digital file that can instruct machines to produce components, the need for traditional annotated drawings might disappear entirely. The ultimate benefits of BIM are still emerging in a market primed to change radically the way buildings are designed and built. A shift in process and expectation is happening in the architecture, engineering, and construction (AEC) world, with private and public sector owners beginning to demand BIM models as part of the delivery package.

The shift from traditional 2D abstractions to on-demand simulations of building performance, usage, and cost is no longer a futuristic fantasy but a reality. In the age of information-rich digital models, all disciplines involved with a project can share a single database. Architecture, structure, mechanical, infrastructure, and construction can be coordinated in ways never before possible.

Models can now be sent directly to fabrication numerically controlled machines (CNC), bypassing the need for traditional shop drawings. Energy analysis can be done at the outset of design, and construction costs are becoming increasingly predictable. These are just a few of the exciting opportunities that a BIM approach offers. Designers and contractors can begin to look at the entire building process—from preliminary design through construction documentation into construction—and rethink how buildings come together. The whole notion of paper-based delivery may become obsolete as more players adopt up-to-date, accurate, digital models.

With the Revit building information model, a parametric 3D model is created that produces traditional building abstractions such as plans, sections, elevations, details, and schedules. The drawings produced aren't discrete collections of manually coordinated lines, but interactive representations or, more accurately, different views of a model. Working in a model-based framework such as Revit guarantees that a change in one view will propagate to all other views of the model. As you shift elements in plan, they simultaneously change in elevation and section. If you change a level height, all the walls and floors associated with that level update automatically and adjust their base/height/length to the new condition. If you remove a door from your model, it's simultaneously removed from all other views, and your door schedule is updated automatically. This unprecedented level of coordination allows designers and builders to better control and display information, ensuring higher quality and a leaner process.

The immediate access to 3D visualization of the building and its spaces makes it much easier to understand and communicate the building design. One model can also contain many variations (Design Options), any of which can be explored at any stage in the design process. Integrated design and documentation keeps the data centralized and coordinated. This in turn leads to live and up-to-date schedules and quantity take-offs. That information can then be used to make decisions early in the design process, reducing risk and cost overruns. Not only that, but with the coordinated BIM model, you can start running energy analysis, solar studies, daylight simulations, and egress analysis much earlier in the process, allowing you to iterate through design decisions earlier, not later.

Coordination with BIM is now required for many buildings to come into existence. BIM is extremely useful for complex projects such as Daniel Libeskind's Denver Art Museum, with its extreme geometric configuration (Figure 1.1). Integrating the mechanical and structural systems into a 3D model is essential to completing a building of this complexity. Exact spatial organization of structural members could be modeled, which in turn led to fewer field errors and fewer requests for information. In addition, parts could be sent directly to fabrication from the model, eliminating the need for 2D drawings entirely.

FIGURE 1.1

BIM makes it possible to build more complex buildings with fewer errors.



Denver Art Museum, Daniel Libeskind

Let's not leave out some of the more pleasurable aspects of BIM that go beyond all the technical, economic, and ecological benefits. With a 3D model, you can expect to see changes in how you interact with your team and your clients and in the way you produce presentations. No longer are you stuck with using 2D drawings or outsourcing to create perspective images. You'll find yourself working with your team in close quarters, sharing a model, and exploring it together. With your clients, you can now take them through the building, in full 3D, from the beginning. The experience of working with and visualizing 3D space can't be overemphasized, and people enjoy it immensely. In the BIM era, 3D experience is the norm, not the exception.


BIM and Process Change

When moving to a BIM work environment, you'll experience a change in process and workflow. Perhaps the most immediate and obvious difference is that a traditional CAD system uses many separate files to document a building, whereas a BIM project typically has only one file. With CAD, all the separate files are created individually and have no intelligent connection between them. Each drawing represents a separate piece of work to be managed and updated throughout the design process. With such an unwieldy process, the possibility of uncoordinated data, and thus errors, is very high. The manual change management enforced by CAD is a tedious and error-prone process that requires diligent project management and lots of red lines. BIM provides a different approach to the problem: rather than many files, you work with one logical file. With BIM, all information is consolidated and networked together for you, and the resulting drawings all relate back to a single underlying database, guaranteeing an internally consistent model.

If you understand the basic premise of an integrated building model, then you'll by now have realized that BIM removes the concept of drawing lines to represent objects. Instead, you build walls, roofs, stairs, and furniture. You model the building and its systems. Figure 1.2 shows a 3D sectional view of a Revit model. You can see that the model incorporates façade elements, floors, roofs, parapets, curtain walls, and materials. All this information is modeled and must be designed as it is to be built. You then add information to the drawings to explain the model in the form of parametric tags and keynotes. Although the end result is still a set of printed lines, you rarely draw these lines. This concept of modeling is so simple, and matches more closely the process of building design that you as an architect are familiar with, that you'll get used to the idea in no time.

FIGURE 1.2

The BIM model keeps you honest and focused on solving the design problems of a model, rather than managing lines.




Revit is excellent at managing changes and keeping your model interconnected. Unlike CAD, the intent of BIM is to let the computer take responsibility for redundant interactions and calculations, leaving you, the designer, with more time to design and evaluate your decisions. With a BIM tool such as Revit, be prepared to change your expectations of how to use design software. Remember: you are modeling a building now—not drafting lines. You're doing what you do best: solving complex spatial problems.

Revit Encourages Creativity

Revit's tools are clustered in easy-to-access ribbon tabs that have collections of logically grouped tools. Most of these tools will get you where you need to go with minimal effort. For more complicated conditions, be prepared to put your creativity to use. Remember, Revit is a 3D modeling application that will let you build almost anything you want. For example, if you can't create the wall or roof you want with the explicit Wall or Roof tool, you can create your own custom-shaped walls or roofs using the Model in Place tool. This tool lets you make a 3D solid geometry of the wall that you can then assign to the Wall category and that will behave and schedule as a regular wall. Figure 1.3 shows an example of custom-designed railings, curtain walls, and structural elements—all possible for a creative and engaged designer. These custom elements participate in the underlying data structure of Revit, making them schedulable and quantifiable.

FIGURE 1.3

Be creative, and work out your design solutions in 3D.




Every Element in Revit Has Properties

Throughout the design process of a project, you'll often need to adjust elements and change the model. Get used to the idea of clicking the Element Properties button to make interactive changes to the model. Better yet, map Element Properties to a keyboard shortcut. A member of the Basic Wall family, for example, has properties like width, height, bearing or nonbearing, demolished or new, interior or exterior, fire rating, and material. You can even define how layers wrap when inserts are placed in the wall, add integrated wall sweeps, and build stacked walls. Figure 1.4 shows the assembly options embedded in the type properties of a Revit wall.

FIGURE 1.4

The Element Properties dialog box of a wall contains many powerful features allowing detailed editing of the wall assembly.



Elements Interact with Other Elements—All the Time

Remember: there is one model and many ways to look at it, called views; no matter in which view you change the model, the change will immediately be updated in all views. And in each view, you have total control over what information you want to display. Think of a view as a pair of glasses that can filter what you see—but the underlying model is still there, all the time.

A wall in Revit interacts with other walls to produce clean connections and appropriate levels of material abstraction. It connects to floors, levels, and roofs; forms rooms; and defines areas. Windows and doors placed in a wall move with the wall that hosts them when that wall is repositioned. Deleting a wall will delete all windows and doors in that wall and all dimensions associated with the wall. If you move a level, expect floors, roofs, walls, plumbing, and electrical features to also move as their parameters change. Keep the interaction of elements in mind, especially in multiuser scenarios where your changes to the model will affect many views at once.

Duplicating Views Takes Two Clicks

With Revit, you can duplicate floor plan views quickly, allowing you to generate plans as in-progress working drawings, others for presentation purposes, and still others for final construction documents (CDs). Note that this is very different from making a copy of a drawing of a floor plan: duplicating does not create any copy of elements in a model—what happens is that you are simply duplicating a view of the model and you can have as many different views of the same model as you wish.


Revit Fosters Problem Solving

An advantage of a BIM methodology is that you can't cheat the documentation of your design. Because the elements have properties based on real-life constraints, you'll find it difficult to fake elements within the design. When you get stuck trying to resolve a roof condition, it's most likely that you have a complex roof to solve. You can't just fake the elevations and call it a day. Of course, in CAD-based systems, faking annotations has always been possible and has no doubt led to some messy construction administration work. As you move into the BIM world, be prepared to take on some early design challenges.

Figure 1.5 shows what appears to be a simple house model, but it's more complex than it looks. With Revit, you model the dormers, the trusses, and the fascia and soffits. You need to determine how the walls and roofs connect to one another—and Revit is well suited to figuring these things out.

FIGURE 1.5

To build a BIM model, you need to solve problems in 3D space, from dormers to trusses.



Revit Lets You Leverage Other Tools to Support Your Workflow

Other software packages, such as SketchUp, Rhinoceros, Autodesk Alias Design Studio, Autodesk Maya, and Autodesk 3ds Max, are all excellent 3D modeling applications. While they can produce either quick 3D concepts or conceptually complex geometrical shapes, these modeling applications don't have the ability to document fully your design for construction, nor can they be leveraged downstream. Note, though, that even if these tools are not BIM, they can still play a role in a BIM workflow; many architects use them to generate concept models that can then be brought into a BIM application and progress through design, analysis, and documentation. If you prefer to work with other tools for concept modeling, doing so isn't a problem. When the design starts to gel, import the geometry into Revit, convert the imported conceptual models into real building elements, and start taking advantage of BIM.


Finally, not everything in a Revit model is modeled in 3D. You can create pure 2D drawings, drafting views, and details in Revit; import existing CAD details; and reuse details from other Revit projects.

Revit Allows You to Draft

The tools may be a bit different than those in AutoCAD or any other drafting application, but there is nothing you can draw in CAD that can't be drawn in Revit. By using the intelligence of Revit families, you can build your details into individual components, thereby embedding drafting elements into the 3D object. Figure 1.6 shows an example of a detail drawn entirely in Revit.

FIGURE 1.6


2D details can be drawn directly over the 3D model, allowing you to add much more information to the model.



The Family Editor Is a Powerful Tool

Most elements (families) in Revit are made with the Family Editor and can be built with incredibly powerful behaviors. Don't be afraid to dig in to the Family Editor and explore your creative side. We've seen many beautiful families and clever tricks put to use that make Revit fun to use. Figure 1.7 shows a curtain wall system with nested panels and attachment clamps. As we'll discuss in Chapter 5 and reinforce in Chapter 10, creating such families isn't too difficult, and requires no programming or scripting knowledge. Using 3D modeling tools and parametric dimensions, you can create reusable and dimensionally flexible components for any architectural element. By taking your time, being patient, and tackling problem solving, you'll be producing custom content in no time.

FIGURE 1.7
Using the Family
Editor, you can
model intelligent
part assemblies.



Revit Does Away with Layers and X-References


If you've already made the jump into Revit, then this will already be obvious: rather than user-defined layers, you use an intelligent architectural classification system to manage visibility, graphics, and selection. This may seem stringent at first, but once you get the hang of it, you'll see the benefits. Because a building model is an assembly of meaningful, to-be-built objects, you control the visibility and graphics of those objects using a rational list of well-understood categories. This also makes it easy to select similar elements and edit them. Figure 1.8 shows the list of classifications that manage visibility. You can't add to or alter this list, which means every project enjoys the same level of visual predictability. And of course, with an integrated model, you don't need to worry about referencing other drawings to keep the drawings up to date and in sync.

BIM Is More than a Technology Approach: It's a Change in Process

One of the powers of Revit is the ability to work in a single-file environment where the design and documentation of the building happens on a holistic model. This can be a disadvantage if it isn't taken seriously. Users who are quick to make changes without thinking about how such changes will ripple through the model can cause unintended problems. Revit is a parametric modeler that maintains relationships between building elements to streamline the design process. For example, deleting a roof underlay in a view doesn't just delete the roof in that view—it deletes it *everywhere* in the model. You need to think before you delete that wall or ignore that warning message!

FIGURE 1.8

The Visibility/Graphic Overrides dialog box contains the entire range of elements used in Revit.



Be prepared to work in much tighter, more collaborative teams. As soon as you enter the BIM multiuser world, you absolutely need to be communicating with your team all the time. The changes that you make in the model will affect the whole model and other people's work. We think this is a great—perhaps unintended—consequence of moving into a model-based design paradigm.

Anticipate that tasks will take different amounts of time when compared to a CAD production environment. You'll perform tasks in Revit that you never had in CAD; and conversely, some CAD tasks that took weeks (such as chamfering and trimming thousands of lines to draw walls properly or making a door schedule) take almost no time using Revit. On the other hand, some tasks may seem to take longer in Revit. This may initially seem true, but remember that as you're modifying or adding something in plan, you're also adding it in section, elevation, and detail. Be prepared to discover and embrace new tasks with BIM that were never part of a 2D workflow.

In Revit you'll often feel as if you are working in traditional types of 2D views—just keep in mind that it's still a 3D model. Moving walls, windows, and doors in plan feels like a 2D operation, but of course it's not. If you've never worked in a model-based environment, it can be jarring at first to see the drawing you've been working on change as a result of an edit in a different view. As we mentioned, this becomes even more dramatic when you start working in a team and sharing a model. You'll learn that preventing movement of elements becomes just as critical as being able to edit elements in the model. Pinning down grids, levels, and exterior walls will become part of your workflow, especially in larger projects with many users working in a single file.

Revit Is the Most Advanced BIM Application

Revit is the most technologically advanced BIM application, and it's under highly dynamic development. What began as a single tool for architects has expanded into a platform that is the base for the structural and mechanical disciplines as well. The evolution of the Revit software platform will continue. As with any new technology, you'll run into problems, get flustered, and no doubt pull out some hair. That said, no other application on the market delivers the advantages of BIM as well as Revit does. Consider this for a moment: most other architectural products in today's market are based on technology that is 20-plus years old, whereas Revit is a new technology that was designed from the ground up as a BIM tool to specifically address the AEC industry. From its inception, Revit has had the goal of improving design communication, coordination, and change management. It has a patented parametric change engine that is unmatched in sophistication. It's also the leading software package in the international market. Revit is not the only BIM package out there, but we feel it offers the most holistic approach.

As you complete more projects with Revit, you'll begin to understand some of its advanced functionality. In this book, we'll delve into advanced concepts and guide you through some really cool features. We'll touch on the fact that Revit is now a technological platform that supports architectural, structural, and mechanical disciplines. The fact that you can share a model with your structural and mechanical, electrical, plumbing engineers (MEP) without any intermediate translation methods or change to the base environment is an exciting prospect, and one that will continue to drive changes in process.

Where Can You Go from Here?

Building information modeling is a revolutionary approach to the design, analysis, and documentation of buildings that takes full advantage of modern-day computational technology. At its core, BIM manages the flow of information throughout the lifecycle of a building-design process, allowing you to experience the building before it is built. Using BIM from early conceptual design through construction documentation and into construction administration and beyond, it's possible to better predict, plan, and execute the complex task of creating architecture to meet today's demanding requirements.

The flow of information in this new world consists of virtually all imagined inputs that go into a building design: the gross area of the building; its impact on the environment; the number of windows, doors, and plumbing fixtures; the cost of materials; the size of heating and cooling equipment—you name it. All this information is stored in a digital model—a virtual 3D database chock-full of information primed for extraction, analysis, and representation. The input turns into output in the form of coordinated document sets that can be shared across multiple disciplines and that serve as a centralized design-management tool for an entire project.

The AEC industry is at the cusp of a major shift in technology, and the resulting impact on building—and by extension the greater environment—will be revolutionary. We can no longer build without considering the impact of the building, without considering the building as part of a larger network of interconnected flows. The promise of BIM lies in the ability to visualize and understand how a building participates in these complex networks: how it performs, how it will age, and how it will accommodate and adapt to dynamic economic and spatial requirements.

Revit, along with a change in process, can change the way you do business, structure your office, present ideas to clients, win new jobs, and ultimately build a new architecture.

Armed with the skills you'll develop in this book, you'll be able to take Revit to the edges of creative expression and maybe create something as ambitious as the skyscraper in Figure 1.9.

FIGURE 1.9

Taking Revit to the edges of creative expression.




Image courtesy of Phil Read

The Bottom Line

Identify the advantages of building information modeling. The traditional architectural design tools you've mastered are probably serving you well. New software and a new conceptual model of the building process will inevitably involve some adjustments, so they need to provide significant benefits.

Master It What are some of the advantages of using BIM over traditional CAD tools?

Know what to expect from BIM. A BIM project is based on a single, centralized database of information. You need to anticipate how that change can affect workflows based on more independent functions.

Master It How can your work process be affected by the adoption of BIM?

Chapter 2

Revit Fundamentals

The power of a database is that information can be easily accessed, managed, queried, and updated. A Revit project is essentially a database that makes it easy to quickly identify elements, control their visibility and graphics, and generate reports based on this information. The data is highly structured, but you have tremendous liberty when it comes to the representation of that data. This flexibility lets you have as many views as you want or need to convey your design intent. Every view is a filtered, graphical representation of an underlying database, and you're free to make as many views of this data as you deem necessary.

The sooner you embrace this concept and start exploring the opportunities it presents, the better. If you can't get your drawings to look just right, chances are you just haven't dug deep enough. Throughout this book we'll give you suggestions and techniques that we hope will inspire you to think creatively about how to exploit the data to get the output you want.


In this chapter, you'll learn to:

- ◆ Understand Revit parametric elements
- ◆ Work with the Revit user interface
- ◆ Modify the Revit user interface
- ◆ Use the Project Browser
- ◆ Navigate views and view properties

Understanding Revit Parametric Elements


Every element in Revit is considered a *family*, and each family belongs to a *category*. Figure 2.1 shows the basic Revit object model. In this section, we'll discuss how Revit organizes all these families into categories and why this makes sense from a workflow and consistency point of view. We'll next look at the different types of families, the principles of their behavior, and how to create them.

FIGURE 2.1
The essential categorization of Revit elements.



Revit uses a classification system to organize all the families in the model. This system of organization is based specifically on the AEC industry and is set up to help manage relationships between classes of elements as well as the graphical representation for each class. To see all the categories available in a Revit project, go to the Manage tab, and from the Project Settings panel, choose Settings ➤ Object Styles to open the dialog box shown in Figure 2.2.

FIGURE 2.2
The Object Styles dialog box.




At the core of this organization is a fixed list of *categories* to which all elements ultimately belong. Although this may seem stringent, it works well and will help you maintain a consistent graphical representation across your projects. As you can see, every element belongs to a category, and that category is either a model or an annotation object. In addition, each element

is either 2D or 3D in nature. Whenever the mouse hovers over an element, a tooltip appears and tells you what kind of element it is and what category it belongs to. In Figure 2.3, for example, the element on the left is part of an unshared project and omits the workset name. The element on the right is part of a workset named Shell and Core.

FIGURE 2.3

Using tooltips to define elements. The element on the left is part of an unshared project and omits the workset name; the element on the right is part of a workset named Shell and Core.



TOOLTIPS INFORMATION

If you aren't working in a worksharing (multiuser) project, then the first bit of text in the tooltip tells you what category the element belongs to. If you're in a worksharing project, the category is preceded by the name of the workset containing the element. (See Chapter 24 for more detail on worksharing.) The next part of a tooltip tells you the family name, and then comes the family type. So, the tooltip follows this logic.

Model Categories

Let's look quickly at some of the main types of model categories.

Model Object categories—the first tab in the Object Styles dialog box—include all the real-world types of objects typically found in buildings. These object categories include elements such as walls, floors, roofs, and furniture, along with other categories that make sense in an architectural project.


The model categories *Detail Items* and *Lines* are used for elements that represent real-world objects used for 2D detailing such as detail components. In Revit, these objects are not modeled as 3D elements but added as 2D representations, as shown in Figure 2.4.

For elements that don't fit into any obvious category, there is the *Generic Models* category. This can be used for objects or parts of an overall assemblage that do not need to be scheduled. An example might be a canopy or reception desk.

Model elements appear by default in all views. In other words, if you draw a wall in plan, it will show up in any other applicable plans, elevations, sections, and 3D views. Remember, you're working on a single building model: all views in Revit are just different ways to look at the same model. Detail components, on the other hand, appear only in the view in which they were placed. If you want them to appear in other views as well, you will need to manually copy them to those other views.

FIGURE 2.4

Details such as this steel connection at the roof are composed of 2D elements.



As we'll discuss in more detail shortly, you can turn the visibility on and off for any category or element in any view. For example, imagine you've placed furniture in your model. The furniture is 3D geometry that will be visible by default in many views. Revit lets you turn off the visibility of the furniture in one floor plan while leaving it visible in another floor plan, or turn it off in plan view while having it visible in section view. The furniture isn't deleted; it's made visible or not depending on the information you need to convey in particular drawings.

Because model elements appear in all other views, two types of graphic representation are defined for each category: *projection* and *cut*, as shown in the Object Styles dialog box in Figure 2.2. The *projection* graphics define the graphics for the element in elevation, 3D views, or any other view where the element isn't being cut by the view. The *cut* graphics define how the element will look when cut by sections and plan views. Typically, the section cut graphic is bolder than the projection lines, to emphasize that the element is being cut by the view plane.


Surface and cut patterns are always drawn with line weight 1 and can't be made thicker.

Figure 2.5 shows how the wall line weight differs between cut and projection. Also notice that patterns are applied to the walls and floors. Patterns can be added to give additional graphic representation to a material and are always drawn with a thin line weight.

Categories also make it easy to interchange elements. You can swap out elements of the same category with another type of element with only few clicks of the mouse. This deliberate limiting of choices to only those that make sense is what streamlines the process of swapping out types of elements. For example, you can swap a lighting fixture with another lighting fixture by selecting the element and then seeing what other lighting fixtures are available in the Type Selector. Choosing another type swaps out the type instantly.

Revit is smart about this interchange—it offers only different types of the same category of elements. For example, when you select a door, you don't get a list of plumbing fixtures or windows to swap it with; you get a list of other door families.

FIGURE 2.5
Cut and projec-
tion graphics are
defined for each
element.



Annotation Categories

Annotation Object categories include all the annotations, symbols, and descriptive data added to a view to describe the building. These are listed in the second tab of the Object Styles dialog box. Most annotations are view-specific 2D elements and appear only in the view in which they were created. Examples include dimensions, tags, callouts, and text notes. Annotations such as sections, levels, and grids are 2D graphics, but they have 3D characteristics and appear in other views. These elements (levels, grids, sections) appear in many views thanks to BIM application functionality. Levels, grids, and section marks extend throughout the model and can be edited from multiple views. You don't need to draw these elements in each view as separate, disconnected graphics. With Revit, they're truly 3D annotations. (Levels, grids, and section marks never appear in 3D views.)

DEPENDENT VIEWS

There is an exception to the rule that annotations appear only in the view in which they were placed. With *dependent views*, annotations are shared between views, so that if you change the annotation in one view, it affects other views as well.

Subcategories

Within each category are many subcategories that let you control the graphics of an element with finer precision. This is what makes the concept of categories so much more powerful and natural to work with than layers. Go to the Manage tab, and in the Project Settings panel, choose Settings > Object Styles, and look in the Modeling tab at the Door category: you can see that the category Doors (Figure 2.6) has a set of subcategories that relate to subelements in the door assembly, such as Elevation Swing, Frame/Mullion, Glass, Opening, Panel, Plan Swing, and any other user-defined elements that can be made when creating a door family. For each subcategory, independent line weight, color, and pattern can be assigned.

FIGURE 2.6
Subcategories allow finer graphic control over categories.

Doors	2	2	Black	Solid
Elevation Swing	1	1	Black	Dash 1/16"
Frame/Mullion	1	3	Black	Solid
Glass	1	4	Black	Solid
Hidden Lines	2	2	Blue	Dash
Opening	1	3	Black	Solid
Panel	1	3	Black	Solid
Plan Swing	1	1	Black	Solid

Imported Categories/Subcategories

When a CAD file is imported into Revit, all of its layers are represented as subcategories in the Imported Objects tab of the Object Styles dialog box. Layers have a projection line weight, a color, and a pattern.

IMPORTED FILE LIMITATIONS


There is no Cut line style for DWG, DXF, and DGN files. These files are just sets of lines, and lines can have only one line weight.

These can be overridden at any time to suit your requirements. Each import appears as a category in this dialog box, as shown in Figure 2.7. There is no need to remap CAD layers into Revit taxonomy. If you're used to the layer conventions set up in CAD, these will be mapped directly into the Object Styles dialog box with the same names, line weights, and colors. This is true unless you have consciously chosen Invert Colors during the CAD import.

Views

Views are also considered parametric elements in Revit, and they have many properties to help you define how they should display information. A view doesn't change the model in any way—it only acts as a filter through which you view the model. This also applies to schedules and material take-offs. Although schedules are more abstract ways to think of a view, they're still parametric views into the model. Throughout the book, you'll be asked to make views, and we'll guide you through various methods for making views convey specific information about your design.

FIGURE 2.7
Imported CAD lay-
ers represented as
subcategories.



Type and Instance Parameters

A *parametric element* is something that can change size, material, and graphic look but is still the same fundamental element. Most elements in Revit are designed with parameters that allow for the creation of variations of a base type. Take a typical Revit door family as an example. Each family can have many types built into it, where each type typically represents a variation in size, material, color, or other defining characteristic. Although each type can vary in shape and size, the base geometry for each type is derived from the same family.

THE DIFFERENCE BETWEEN CAD BLOCKS AND FAMILIES

In a typical CAD environment, for each size of the same door you might create a separate block; each of those blocks would be a separate element unrelated to any of the others. So, 20 door sizes would mean 20 floor-plan blocks, 20 (or 40) section blocks, 20 elevation blocks, and 20 3D blocks if you were going to use them as liberally as we use them in Revit. All of those in Revit are represented with *one* family that can display itself in 2D and 3D and whose size, material, and visibility can be changed at any time.

Depending on how the family is built, parameters can affect either the *type* or the *instance*. A change of *type parameters* affects all instances of this type in the same family used in the model, whereas *instance parameters* affect only the selected instance. This is an important distinction: you can change instance properties only when you have an element selected, but you can change type properties without selecting anything.

Consider a round table. You might define its shape using a type parameter for the radius. If you placed 20 types of tables with a 2' (60cm) radius and then changed that radius to 3' (90cm), all 20 tables would update automatically. Now, if the radius parameter were an instance parameter, changing the radius would affect only the table you currently had selected. The same logic can be applied to other dimensional constraints and materiality. Revit forces you to consider what an element is and what it means to change the element's defining characteristics. For example, most content in Revit doesn't let you arbitrarily change dimensions of every instance, on the fly, whenever you want—this would make tracking the notion of object type difficult and would make mass-updating more tedious. Think of a type as something you'll eventually have to schedule, spec, and install as a real-world commodity.


Bidirectional Relationships

Objects with parameters that can be edited are nothing new in the world of software. But what makes Revit unique is its ability to go beyond 3D objects with parameters and create relationships between objects. This ability, which includes the parametric relationships and the underlying change engine, is a core technological advantage built into Revit.

For example, walls can be attached to a roof, and if the roof changes to a new shape or size, all walls attached to the roof automatically adapt to the roof shape. Figure 2.8 shows that changing a roof pitch automatically adjusts other roofs and walls to keep them joined.

FIGURE 2.8

Changing the roof pitch updates walls automatically.




Another powerful manifestation of interrelationships occurs among walls, floors, roofs, components, and levels. They all have explicit relationships to levels, so that if a level changes elevation, all elements associated with that level update automatically. Not only do the bases of the walls attached to a level change, but the tops of the walls attached to this level also change. This is fundamentally different from other BIM software applications, where elements understand the relationship with the level on which they are placed but not the level to which they extend. Thus, if you change the height of a story (level), there will be a gap in the walls, columns, and other elements, and, due to the lack of relationship to the level above, they will not understand that they need to become taller. Similarly, when you change the size of a room by moving walls to new positions, you're changing not only the wall positions but also everything those walls affect in the model: the size of the room (area and volume), color-fill schemes applied to the

rooms, and the shape and size of ceilings and floors. Doors, windows, and any other wall-hosted elements, such as light fixtures or sockets, will move with the wall when the wall changes position, and any dimensions to that wall will automatically update.

Revit tries to keep things joined and connected in order to eliminate huge amounts of tedious editing. You'll begin to take it for granted after a few days with Revit, but remember: when you drag a wall that has other walls attached to it, those other walls will automatically stretch with your move. Not only that, but rooms, dimensions, floors, components, and tags will also move. Of course, if you don't want all this intelligent behavior, Revit provides other options. For example, if you right-click a wall's end control, you can disallow it from joining other walls (see Figure 2.9). Or you can select Disjoin available in the Options bar once you've selected a wall, and then selected the Move command—doing so will detach the smart relationships between the wall and the rest of the model and treat the wall as an independent entity.

FIGURE 2.9

By right-clicking the end of a wall join, you can stop the wall from autojoining to other walls.



This parametric behavior extends to annotations and sheet management as well. Tags aren't simple graphics and text; they're interactive graphical parameters of the element being tagged. To edit a tag is to edit the element or tag family, and vice versa. This is also known as a *bidirectional associativity*. You can edit the elements and the tag and maintain consistent data. A great example is easily demonstrated with a view and a sheet. When you place a section view onto a sheet, the section key automatically references the sheet number and detail number on the sheet. Change the sheet number, and the section tag updates instantly. This is what a real parametric engine is and what ensures total coordination of documentation. You've probably heard this phrase before, but it's worth repeating: the parametric engine guarantees that a "change anywhere is a change everywhere."




Real World Scenario


ADJUSTING A LEVEL AND ROOF SLOPE TO MEET DESIGN REQUIREMENTS

In a real-world project, the height of a level is bound to change in the design process, which in turn will change floor-to-ceiling heights and roof locations and will influence the building's overall height. Consider a scenario in which keeping the top of the roof below a maximum height was a design requirement. Not to worry—with Revit, changing the height of levels (floor-to-floor heights) at any point in the process updates all dimensions and elements associated with that level.

If changing the Roof level pushes the roof peak too high, this is easy to fix. By editing the roof and changing its slope parameter, you can lower the roof height, and all the walls attached to the roof update to reflect the change. There is no need to edit the walls independently in order to get the correct results.



With one edit, you change the roof height. The walls and roof update immediately.



With an edit to the roof property for slope, the roof updates, as do the walls attached to it.


Constraints

During the design phase, you may want to apply some dimensional rules to the design and make sure they aren't altered. These rules might be a minimum hallway width for code compliance or a maximum office square footage for a particular user. Whatever the restriction, Revit dimensions make it possible to lock it down and create a constraint. This constraint is independent, but it's related to the dimension. If you delete the dimension, you can keep the constrained condition and know that the model will maintain those relationships. The point is that a dimension can be much more than a 2D annotation.

These design rules are used all the time, but not many software applications let you capture this design intent in the model. If you run a dimension string from level to level and lock the dimensions (as in Figure 2.10), you're locking the relationship between these elements in the whole model. By locking down elements, you make it harder for other elements in the model to break this important design intent and thus keep the model more intact and predictable.

Some practical examples of situations in which this is particularly useful are when you want your door jamb always positioned 4" (10cm) from the wall corner; or you want three windows in a room to be always positioned at equal distances throughout the length of the exterior wall in a room. By defining and locking these relationships, you embed design intent into the model. And these relationships will react to any later change of the model; if the side wall moves, the door will move as well, to keep the locked 4" rule; or the windows will reposition to maintain the rule of being equally spaced.

FIGURE 2.10
Design intent
can be locked
down by adding
constraints.



OTHER, LESS EXPLICIT WAYS TO ASSOCIATE ELEMENTS TO ONE ANOTHER

Revit also provides a less explicit, automatic way to associate elements to other elements. When an element is selected, there is an option to make the element move with nearby elements in the Options bar; Revit will make its best guess as to which elements drive other elements to move. Good example of this is to have a bed move with the nearby wall.

Revit Families

Revit families are used to create your model. There are three overarching methods for creating families in Revit:

- ◆ System families
- ◆ Component (Standard) families
- ◆ In-place families

The difference between them lies in their creation method, in what context they're created, and the types of parameters available. Let's review each of these types of families.


SYSTEM FAMILIES

Model system families are made up of a limited set of categories: walls, roofs, floors, ceilings, stairs, railings, ramps, mullions, curtain panels, mechanical equipment, and toposurfaces (topography). See Figure 2.11 for examples of system families. These families are created in the context of each project, using some predefined types. These families also have various creation methods that are specific to the type of the family. For example, to make walls you can just start drawing (placing a wall), whereas to make a floor or roof, you enter a *Sketch mode* in which you define the outer shape with lines that then generate a 3D model of the floor. For stairs and railings, you enter a more detailed Sketch mode that has additional features not available for floors or roofs. When making toposurfaces, you use a Sketch mode that lets you edit 3D points specific to toposurfaces. As you can see, system families all have slightly different creation methods.

You can create new types of system families by duplicating existing types and editing their parameters. If you've been using Revit for any length of time, then this method of duplicating a type to create new types should be familiar territory for you.

You can't create new categories in Revit. These categories are predefined within Revit and limited to the list available. This is primarily to maintain control over the graphics from project to project.

FIGURE 2.11
System families.



If you aren't sure whether an element is a system family, open the Element Properties and in the Instance Properties dialog box, check the family name. If the element is a system family, it is embedded in the family name. Figure 2.12 shows that Basic Wall and Section are both system families.


FIGURE 2.12
System families include model and annotation elements.



System families are also used for many annotation categories, such as sections, elevations, levels, grids, text, and dimensions—they aren't limited to model elements.

Another characteristic of system families is that you can't save them outside of your project to a shared library as a standalone component. Even so, it's still possible to reuse system families in other projects. To transfer system families between projects, go to the Manage tab, and from the Project Settings tab, choose Transfer Project Standards to display the Select Items to Copy dialog box (Figure 2.13). This dialog box gives you a feel for the number of different types of system families used in a Revit project.

FIGURE 2.13
The Select Items to Copy dialog box.



COMPONENT FAMILIES

Component or “standard” families (see Figure 2.14) are created outside of the project environment using the Family Editor. They're stored in an external library (folders on your hard drive) and can be loaded into a project for use at any point. Every component family belongs to a specific Revit category so that when it's loaded into a project, it adopts the graphic rules defined for its category in the Object Styles dialog box. This guarantees graphic consistency throughout your project without your having to manage changes to new families constantly. This also guarantees that when you schedule a category, you get all elements that belong to that category.

For example, if you find a lighting fixture family on the Web and load it into your project, it will use the Lighting Fixtures object style in your project to represent the family. It will be scheduled with other lighting fixtures. You aren't forced to open the family and adjust line weights or colors or add metadata to the element, because this is all controlled at the project level. This illustrates the value of having a fixed number of categories to manage—you can rest

assured that the project won't inflate with endless, oddly named layers that are difficult, if not impossible, to decode.

Component families have their own file format extension (.rfa) and can be stored outside the project environment for later use in other projects. Revit ships with a predefined folder structure to help manage the vast numbers of families available. Go to the Insert tab and from the Load from Library panel, choose Load Family to see how Revit organizes information (see Figure 2.15).

FIGURE 2.14
Component (standard) families.






FIGURE 2.15
The Load Family dialog box.




ORGANIZING YOUR OFFICE LIBRARY

In your office you're free to organize your families in whatever way makes the most sense. You can use a read-only, shared office library or per-project mini-libraries. Whatever route you go, be sure to add your library locations to your Revit file load dialog box.


To do this from the Load Family dialog box, browse to your office library and choose **Tools** ➤ **Add Current Folder to Places**, located at bottom of the dialog box. The folder will appear in the list of default folder locations.



Another option is to use the Options dialog box located in the Applications menu. To open it, go to the Applications menu and click the Settings button located at the bottom right and then click the File Locations tab. Add a new path to the Libraries table.



Once you do this, a new link appears in the Open dialog box with the name of your library. Clicking the icon takes you directly to your office library.



To create variations of a component family, duplicate an existing one in the project and modify its properties. To make more radical geometrical changes to the family, you need to open it in the Family Editor and change the form there. The process of editing a family supports an iterative design workflow: by selecting any family, you have the option either to edit its properties or to open it in the Family Editor and make changes to it and then load it right back into your project. Families can be complex, but at least you won't need to learn any specialized scripting languages to create smart, parametric content. This goes for all forms of component families, from totally parametric windows and doors to one-off pieces of furniture or lighting fixtures.


Revit provides a set of starting family templates you can use to make content from scratch. When you want to start creating a new library element (family), you first need to select the correct template. To open a template, go to the Application Menu and choose **New > Family**. Choose the type of element you want to make, and the template will open. Embedded in each template are smart behavior characteristics of the family you're creating. Figure 2.16 illustrates a door family template, where geometry, parameters, and dimensions are already in place to help you get started.

Doors, windows, balusters, casework, columns, curtain wall panels, entourage, furniture, massing elements, generic objects, and plantings are all examples of standard Revit family categories.

To move families between projects, you can copy and paste them or save your families to disk and then load them into another project.

FIGURE 2.16

The template for this door family includes geometry, parameters, and dimensions to help get you started.



IN-PLACE FAMILIES

In-place families are custom elements that are specific to a project and the conditions of the project. An in-place family accesses functionality available in the Family Editor in the context of a project environment. The model grays out and becomes unselectable when you make such families. A nonvertical, sweeping wall shape is a good example for when you would use an in-place family.


You can copy and paste in-place families from project to project, but you can't save them as RFA (Revit projects have the extension .rvt, Revit families .rfa) as you can with standard families. Figure 2.17 shows an in-place family added to a façade in order to create some nonorthogonal mullions.

USING IN-PLACE FAMILIES

There are some more advanced features of building information modeling that you will inevitably want to pursue, such as energy modeling or daylighting or direct-to-fabrication. Some of these features do not interface well with in-place families. Try to limit your use of in-place families if possible.

FIGURE 2.17

Example of an in-place family used to add skewed mullions to the façade.



Overriding the Representation of Elements

There are no layers in Revit. Revit uses object categories and subcategories (not layers) to define the graphics for each element class as well as to control visibility (which is the purpose of layers in other software). The Object Styles dialog box (accessed from the Manage tab, in the Project Settings panel, under Settings) establishes the default graphics for every category; however, in any view, you can override these graphics using the Visibility/Graphics Overrides dialog box (on the View tab, in the Graphics panel click Visibility/Graphics) shown in Figure 2.18. The two dialog boxes look very similar—the difference is that Object Styles shows the defaults preset for a project, whereas Visibility/Graphics Overrides is the place to review and make changes to those default settings on a per-view basis. The same familiar categories and subcategories displayed in the Object Styles dialog box are displayed in this dialog box as well.

The same level of visual control for line weight, color, and pattern is provided here but in a slightly different interface. In addition to line overrides, you can override cut and surface patterns and choose to show a category as halftone, transparent, or at a different level of detail. Figure 2.19 shows the Roof category overridden to be transparent in the 3D view, allowing you to see through the roof and look into the rooms beneath while keeping the shape of the roof visible. Changes made using this dialog box are applied only to your current view.

FIGURE 2.18
The Visibility/
Graphic Overrides
dialog box.





FIGURE 2.19
The Roof category
has been over-
ridden to be
transparent in
the 3D view.



The same categories are used to control the visibility of elements in a view. You can turn off entire categories, subcategories, or individual elements in any view.

Working with the Revit User Interface

In this section we look at how Revit appears out of the box when you first open it and familiarize you with how the interface is organized. One of the things you'll notice from the beginning is that Revit is tailored for the architectural design community. The tools, commands, and objects that you use in Revit are based on tasks and requirements taken directly from the practice of architecture.

If you have used earlier versions of Revit, you will notice that the user interface (UI) of Revit 2010 is dramatically different from its previous version. Revit, along with an entire family of Autodesk products, has moved to the “ribbon” paradigm, allowing both easier use of Revit itself and easier adoption of multiple Autodesk products that have a similar user interface. To help current users, we will be calling out the location of certain commands that we believe are not obvious in their placement in the new ribbonized UI.


Starting Revit

There are several ways to start Revit: by double-clicking the Revit icon that was automatically created on your desktop during installation, by going to C:\Program Files\Revit Architecture 2010\Program and double-clicking Revit.exe, or by double-clicking on any file with the .rvt extension.

The Start Screen

When you start Revit, you should see the screen shown in Figure 2.20. (However, when you first start the new product, you might not see any project thumbnails, as they only show once you have worked on projects.)

FIGURE 2.20
The Revit 2010
startup screen.



The startup screen is also redesigned to this release of Revit 2010, offering the following possibilities:

Projects:

- ◆ Open a recent project (select one of the preview thumbnails)
- ◆ Open any existing project (click the Open button)
- ◆ Create a new project (click the New button)


Families:

- ◆ Open a recently created or modified family (select Open under Families)
- ◆ Create a new family (click the New button)
- ◆ Create a new Conceptual Mass (click New Conceptual Mass)—this option is new to Revit 2010
- ◆ Link to the Revit library on the Web (click the Web Library button)

The User Interface

The Revit interface (Figure 2.21), new to Revit 2010, is conceptualized around the ribbon paradigm: a simple idea of grouping workflow-based functions and tools in separate ribbons and exposing only task-relevant options to the user, saving workspace and making the UI less overwhelming.

FIGURE 2.21
The Revit
interface.



APPLICATION FRAME OVERVIEW


The application frame has nine main parts, which we'll now discuss in the following sections.

- ◆ Application button
- ◆ Quick Access toolbar
- ◆ Info Center toolbar
- ◆ Status bar
- ◆ The Ribbon itself
- ◆ Options bar
- ◆ Drawing Area
- ◆ View Controls
- ◆ Project Browser

Let's take a look at each of these components.

The Application Menu The big purple *R* letter on top left of your screen (Figure 2.22) is what we will be referring to as the *application button*. Pressing this button opens the Application Menu, which offers options for creating new projects or families; opening existing projects or families; saving projects or families; exporting the project in various CAD, schedule, and other formats; and publishing and printing. The Application Menu also displays the licensing information. All of this will be more or less extensively covered in the remainder of this book. In this chapter we will discuss in detail only those features that will not be covered later in the book.

FIGURE 2.22
The
Application Menu.



At the bottom right of the Application Menu, you will also find the Options button, which hosts options for various project settings. (Figure 2.23). Located in various tabs are different settings that you can change to accommodate your decisions about file location selection, rendering path, settings relevant to the SteeringWheels, the view cube, spelling, and macros, as well as some general settings such as setting the username, saving reminder intervals, and setting the application frame display theme.

FIGURE 2.23
The Options dialog box.



The Quick Access toolbar The quick access toolbar (Figure 2.24) is located at the top left of the application frame and is new in Revit 2010. It enables quick access to the most-used commands such as Open, Save, Undo-Redo, and Switch to 3D View, as well as options for forcing synchronization of local files to the central file when in a worksharing environment.

FIGURE 2.24
The Quick Access toolbar.



InfoCenter The InfoCenter is also new in the Revit 2010 interface. The Info Center toolbar is located in the same zone as the Quick Access toolbar and the title bar, on the far top right of the applications frame (Figure 2.25).

FIGURE 2.25
The InfoCenter toolbar.



Links to a variety of information sources are located in the Info Center toolbar. From left to right, the first feature is a search field where you can type a term (function, feature) that you are searching for. The search function (binoculars icon) looks into the Revit help file as well as various resources on the Web, thanks to the Autodesk Online services. The Subscription Center (key icon) links to various benefits and services available only to subscription users are accessible. The Communication Center (satellite dish icon) links to product updates and various product announcements. The favorites button (star icon) links to topics you identify as your favorites throughout your work with Revit. To add topics to your favorites, click the icon that appears next to the link on the Info Center Search results panel, Subscription Center panel or Communication Center panel. The last button is the help button, which links to the Revit Architecture help directory.

The status bar The status bar is located at the very bottom of the application window, on the far left. Here you will see helpful text that describes what you have selected and what you should do when in a command. Whenever you aren't sure what the next step should be, look at the status bar. See Figure 2.26 for three examples of the status bar in action.


FIGURE 2.26

The status bar when (top) selecting or hovering over a wall, (center) drawing a wall, and (bottom) using the Rotate command.



To the right of the status bar, in the same zone, you will find two more useful tools: the Count Selection tool and the Press & Drag option.


Count Selection tool The Count Selection tool is located on the far right in the same zone as the status bar. The Count Selection tool gives information about the number of Revit elements currently selected.



Clicking anywhere over the Count Selection tool invokes the Selection Filter dialog box, where you can narrow a selection if needed. You can also access the Count Selection tool by clicking the Filter button located in the Ribbon under the Multi-Select tab (a tab that is activated automatically upon multiple selections of elements of different categories) (Figure 2.27).

FIGURE 2.27

The Filter command appears in the Ribbon upon selection of multiple elements of different categories.




Next to the Count Selection tool, you will find a check box for Press & Drag. What that means is that when this option is checked, you can drag an element without having to select it.

The Ribbon The newly introduced Ribbon stores all Revit commands and tools necessary to create and edit your project information. The Ribbon displays automatically by opening a file or creating a new project in Revit.

The Ribbon can be minimized for maximum use of the drawing area and has three different display settings (Figure 2.28) accessible by selecting the drop-down arrow located to the far right of the tabs part of the Ribbon:

- ◆ Full Ribbon (displays the Ribbon in all its glory)
- ◆ Panel tiles (semi-minimized state of the Ribbon that shows only the Panel and Label tabs)
- ◆ Tabs


FIGURE 2.28
Different display settings of the Ribbon—from top down: Full Ribbon; Panel tiles, Tabs.



The Ribbon is organized in tabs that are themselves organized in panels. Each panel holds logically connected tools for executing a certain type of activity.

Figure 2.29 shows the Home tab. It has seven panels containing the creation tools for almost all modeling elements in Revit.

FIGURE 2.29
Organization of the Ribbon.



Let us just spend few minutes explaining the logic of the ribbon.

There are eight tabs in Revit: Home, Insert, Annotate, Modify, Massing & Site, Collaborate, View, and Manage. The Family Editor has one additional tab called the Create tab.


Home The Home tab contains all tools necessary to build 3D elements in Revit or to create the building model.



Create Available only in the Family Editor, the Create tab gives you a set of tools necessary to create a family.



Insert Raster images and CAD files are often inserted in a Revit file as a help/support or as additional information for your project. This tab contains tools for importing and managing these files.




Annotate To describe or enhance the display of the building model, we often use 2D elements. This tab contains all the tools for adding 2D elements in the project.



Modify Once they are created, all elements need to be changed or edited. This tab contains all editing tools. You first need to select the element to be edited and then the tool to edit it.



Massing & Site Creating and modifying conceptual mass studies is a way to start a project in Revit. You will find all conceptual massing tools under this tab.



Collaborate It is rare that only one person works on a project. Tools that aid in collaborating on the same project and managing that collaboration are located under this tab.



View The Revit project is described through many views that are different queries of the Revit database. Tools for creating and managing those views are located under this tab.



Manage Design options as well as many project-related settings and options are all located here.




If you notice additional tabs on your Revit ribbon, you (or someone you work with) probably have installed some separately purchased add-ins.

We have now covered almost all you need to know about the ribbon interface of Revit. To finish up, we just want to turn your attention to a few tools that are somewhat invisible or are hidden in the expanded panels and dialog launchers.

Expanded panels These are accessible upon selection of the drop-down arrow at the bottom of a panel. When you expand the panel, additional tools and controls will be displayed. To keep a panel expanded, click the push-pin icon in the bottom-left corner of the expanded panel.



Dialog launchers These are types of panels that when expanded, allow you to access additional settings or complete a task. A dialog-launcher arrow on the bottom of a panel opens a dialog. For example, the Structure panel has a dialog launcher. Clicking the arrow opens the Structural Settings dialog box.



As you work on a project, the contextual tabs automatically change to reflect what tool has been selected. If, for example, you select the Wall tool from the Home tab, the Place Wall contextual tab (Figure 2.30) will automatically appear, offering options for placement of new walls of that type, different shapes of the wall segment (straight, curved), as well as access to the Element properties of the Wall tool. This contextual menu will be automatically closed the moment you quit (escape) the Wall command. That is basically the principle that is applied to all Revit tools.

FIGURE 2.30

The contextual tab Place Wall is displayed while adding a wall.



The principle of contextual tabs is also applied when modifying elements. If, for example, you select one or multiple walls, a new contextual tab called **Modify Walls** (Figure 2.31) will be displayed on the Ribbon, offering tools that are logically dependent on your selection. The content of these contextual menus thus depends on what has been selected. As in the previous case, the moment the selection is undone, the contextual tab closes.

FIGURE 2.31

The contextual tab **Modify Walls** is displayed when a wall is selected.




Note that in both of the mentioned cases, the Element panel is present. This panel is very important as it contains the Type Selector (available under the Change Element Type button) and the Element Properties button.

The type selector allows selection of a family type. For example, for the Wall object (Wall family) you will find in the Type Selector a list of all available wall types in the project. For the Door tool, all door types available in the project will be listed under the type selector.


A notable improvement of the type selector in this release of Revit is that it gives you a little visual preview of the types in the list and then lists all sizes of the type (Figure 2.32).

FIGURE 2.32
The Type Selector displays only the type of element that is selected or being created.




Also new and improved in this release is access to Type properties. You can directly access the Type properties of an element without having to go through the Instance Properties dialog box. To do that, just expand the Element Properties button and pick Type Properties (Figure 2.33). Click the small arrow on the right-hand side of the Element Properties button to display a menu where you can choose to open Instance or Type properties.

FIGURE 2.33
Click the small arrow on the right-hand side of the Element Properties button to expand the menu where you can choose to open Instance or Type properties.




Some elements in Revit are created starting from a sketch. Examples include floors, ceilings, roofs, and stairs. A *sketch* is a collection of 2D lines that will define the base shape for a 3D object. The sketch tools vary depending on the object you will be creating or modifying (see Figure 2.34). A roof sketch becomes a roof by definition of the sketch shape as well as slopes of the roof; the stair sketch on the other side consists of the lines that defined the run, the landing, and so on. As a visual aid, the color of the background of the buttons in Sketch mode is changeable: It turns green and the button is automatically closed the moment you accept or cancel the line work.

FIGURE 2.34
The tools to create a stair are displayed automatically in a contextual tab.



One very useful addition to this new edition of Revit is the tooltip that appear when you hover over any of the tools in the panels. The tooltips appear in two levels: the first is just a textual description and the second textual description supported by visual graphical image as help for the description. To display just the first tooltip leave the mouse over any of the tools for one

second. If you want to see the visual tooltip, leave it a bit longer, approximately two seconds, over the tool in question.




If you have already used previous versions of Revit and cannot find some of the commands displayed in the old UI, go to the Where Is My Command? tool located in the list that appears when you click the Help button in the Info Center.



The Options bar The Options bar is located right below the Ribbon. Its content varies depending on the selected element that needs to be created or edited. Its purpose is to offer options relevant to that tool. In Figure 2.35, you can see four examples of how the Options bar looks when different elements or tools are selected.

FIGURE 2.35
The Options bar changes for different tools. From top down: Options bar for dimensions, walls, windows, and model in-place mass.



The View Window

The View window is where all the action takes place. Here you add elements, modify them, and construct and document your model. The view area can tile multiple views, allowing you to visualize the model from multiple vantage points concurrently. We don't recommend tiling the views if you have more than six or so open views because the views get too small and it becomes difficult to work effectively.

To arrange views, go to the View tab and in the Windows panel try the Cascade or Tile option. You'll also see the option Close Hidden Windows.


The Close Hidden Windows feature is a great way to clear your workspace when you have an unmanageable number of views open. Selecting Close Hidden Windows closes all but one view for each project or family you have open. This is advisable to improve performance when you're working on a complex project.

Views in Revit show the same model from different vantage points. Thus, when selecting an element in one view, you'll see that the element becomes selected in all views. You can try this by opening two views (click on the view names in the Project Browser) and tile the views (View tab, Windows panel, Tile). This simple interaction shows that when you make a change to an element in one view the change is instantly reflected in other views. This is a great way to conceptually understand the reality of a true BIM modeler.

VIEW CONTROLS

Each view has properties, and some of these properties are exposed at the bottom of the View window in what is called the View Control bar (Figure 2.36).

FIGURE 2.36
The View
Control bar.



These controls allow you to change the display of the view quickly without having to dig into a Properties dialog box. The available controls include View Scale, Detail Level, Model Graphic Style, Graphics Display Options, Rendering, Crop View, Show Crop Region, Temporary Hide/Isolate, and Reveal Hidden Elements.

SteeringWheel and View Cube

Whenever you open a 2D view in a project, you will see a floating palette located on the far right of the View window. (Figure 2.37). That palette is called Navigation bar.

FIGURE 2.37
The Navigation bar.



In a 2D view, in the Navigation bar you will see two tools: the Full Navigation Wheel and the Zoom tool. Upon selection of the Full Navigation Wheel, the SteeringWheel appears on the screen; it follows (travels with) the mouse to provide quick access to the navigation tools in the context of the work you do. When placed in 2D view, the wheel looks like Figure 2.38 and offers three functionalities: zoom, pan, and rewind.

FIGURE 2.38
SteeringWheel tool
in 2D view allows
for zoom, pan,
and rewind.



The SteeringWheel in 3D view looks slightly different, as shown in Figure 2.39, which displays the Full Navigation Wheel. You can choose different versions of the Navigation Wheel by expanding the list that appears when you select the arrow below the wheel icon on the floating palette. You can set the default appearance of the SteeringWheels from the Applications menu at the same time as you select the Options button and the SteeringWheels tab.

FIGURE 2.39
The full Navigation
Wheel in 3D view.




The Project Browser

The Project Browser allows you to navigate to all your views, create new views, access element properties, and place elements. All the views (including schedules and sheets), families, and linked files of your project are stored here, making it possible to organize and navigate through a project from one location.

Figure 2.40 shows a collapsed view of a typical Project Browser. The Project Browser is the backbone of your project. We'll devote much of the rest of this chapter to exploring its use.

FIGURE 2.40
The Project
Browser shows the
range of elements.



Modifying and Personalizing the Interface


Revit 2010's new ribbonized UI can be changed and customized, although not to the extent permitted by other software applications. This feature is new in this release of Revit. A full customization and change of the UI are still not possible, but you can make certain changes to it, such as changing the panel order or moving a panel off the Ribbon to your desktop.

This version of Revit also supports double screens, a response to a longstanding wish of the current users.

You can make the following changes to the UI:

Change order of panels You can change the order of the panels within the contextual tabs and also undock a panel from the Ribbon so to have it floating in the workspace and visible at all times. Figure 2.41 shows the Build panel undocked from the Home tab. With the double-screen monitor support you can position the floating menu on the second screen. To modify the order of the panels in the contextual tabs, click the title of the panel, hold the click, and move to another location.

FIGURE 2.41
The Build panel
undocked from the
Home tab.



Return panels to the Ribbon Once you've undocked it, you can place a floating toolbar back on the Ribbon by hovering the mouse over the undocked, floating bar and clicking the arrow that will appear on the top right of the dialog box that opens that activates the command Return Panels to Ribbon (Figure 2.42).

FIGURE 2.42
Returning an
undocked panel
to the Ribbon by
selecting Return
Panels to Ribbon.



All changes that you are making to the UI are memorized and stored so that they are there each time you open Revit from zero.

Restore original settings If, however, you played around with customization of the UI a bit too much and wish to revert to the original state of the Ribbon at installation, you can do that by deleting the file in which these changes have been recorded. The name of that file is UIState.dat. It is usually located as follows:

Windows XP C:\Documents and Settings\ UserName \Local Settings\Application Data\Autodesk\Revit\Autodesk Revit Architecture 2010

Windows Vista C:\Users\UserName\AppData\Local\Autodesk\Revit\Autodesk Revit Architecture 2010

Once you have deleted this file, restart Revit, and you will see the standard UI setup.

Undock the Project Browser As did previous releases of Revit, Revit 2010 lets you undock the Project Browser and make it float over the drawing area, as shown in the two images below.




Users with double screens can now place the Project Browser in the second screen. Revit2010 will remember all changes to the interface and will display them in the next launch of the application.

Use keyboard shortcuts Keyboard shortcuts are surely the fastest way to work with Revit. The shortcuts assigned to the existing Revit commands are unfortunately not as obvious in the new UI as they were previously. To visualize the assigned keyboard shortcuts, you have to hover over a tool, wait for the tooltip to appear, and then look for the assigned shortcut, which is described with two capital letters (Figure 2.43). To change the automatically assigned shortcuts, you should, as in previous releases of Revit, edit the KeyboardShortcuts.txt file located in \Program Files\Autodesk Revit Architecture 2010\.

FIGURE 2.43

Keyboard shortcuts are visible in the tooltip.




You will have to restart Revit after changing the keyboard shortcuts in the .txt file.

Display keytips Revit 2010 introduced a new concept called *keytips*. To display the keytips of the Quick Access toolbar or the main toolbars, press the Alt key (Figure 2.44).

FIGURE 2.44

Keytips display when you press the Alt key.



If you want to display the keytips for all the tools within a contextual tab, press the Alt key followed by the letter that describes that tab (*H* for Home; *N* for Manage, and so on).


Using the Project Browser

You can navigate through a Revit project in a number of ways. As you start working in real projects, the number of views and drawings that accumulate will become quite large. Being able to find your views and move between them is critical to an effective workflow. We'll look at the various methods of moving between views, explore best practices, and show you how to customize the display of these views using the Project Browser.

Views

A *view* is a graphical way to look at the database of information you're creating. Plan, section, schedule table, 3D view—all of these are just different ways to look at and query the same underlying database that describes your building. Revit organizes all the views of your project in the Project Browser. Your plans, sections, elevations, 3D views, and schedules are all stored there. Double-clicking a view name from the Project Browser opens the view in the View window. When you close a window using the controls at the top right on each window, you don't need to save the view first—it's always accessible from the Project Browser.

The default organization of the Project Browser is based on the view type and presented as nodes in a tree structure. The default organization when all the nodes are collapsed looks like this:




The Project Browser allows you to define an organization of views per your needs. We will go into how to do this in more detail later in this chapter.

With a node expanded, right-click a view name to access additional options for any view (see Figure 2.45). From the context menu, you can open views, rename them, duplicate them, and apply view templates.

FIGURE 2.45

Context menu
for a view.



Note that you can multiselect views in the Project Browser. When more than one view is selected, you can right-click to bring up the context menu (Figure 2.46).

FIGURE 2.46
Context menu for
a view.




For example, from the context menu you can create and apply view templates. This is a way to give views a consistent scale and graphical appearance, among other things. Let's look at how to use the Project Browser to drive properties from one view to another:

1. Open `Foundation_ch02.rvt` from the Chapter 2 folder on this book's companion website (www.sybex.com/go/masteringrevit2010).
2. Open Plan: Level 1.
3. Right-click the view and duplicate it.
4. Rename the view **Level 1 - Presentation**.
5. Type **VG** to open the Visibility/Graphic Overrides dialog box.
6. Select the Annotations tab, and turn off visibility of all annotations by clearing the Show Annotation Categories in This View check box at the top of the table.
7. Go back to the view in the Project Browser, and right-click the view. Select Create View Template from View (Figure 2.47).

FIGURE 2.47
Creating a new
view template.




8. Name the template **Presentation Graphics**.



9. Duplicate Level 2, and rename it **Level 2 - Presentation**.
10. Right-click the view name, and choose Apply View Template.
11. Choose Presentation Graphics from the list in the dialog box shown in Figure 2.48.
12. The plan now has the same properties as the Level 1 - Presentation view.

Working in a data-driven model, you can use View properties to customize how the browser sorts and organizes all your views. This is a great way to manage the large number of views that will fill your project. Clicking the top of the Project Browser window (not a view) makes it the active selection.

FIGURE 2.48
Choosing the Pre-
sentation Graphics
template.



Customizing the Project Browser's Organization

Use these steps to customize the Project Browser's organization:

1. With the Foundation_ch02.rvt file still open, select the Views icon in the Project Browser.
2. The Type Selector lists Browser - Views (all).



3. Right-click and open the Properties dialog box.
4. Change the Type to Not on Sheets. You'll see the browser reorganize the list and remove views that are on sheets.


Now let's make a custom sort based on your name (or initials) by applying a new Drawn By parameter to all views and then using that parameter to sort the views in the browser:

1. From the Manage tab, under the Project Settings panel, select Project Parameters.
2. In the resulting dialog box, click the Add button to add a new parameter.

3. Choose the Views category on the right side of the Parameter Properties dialog box (see Figure 2.49) under Categories, and under the Parameter Data give the parameter the name **Drawn by**. In the Group Parameter under drop-down list, select Identity Data. Click OK. Validate your choice in the Parameter Value dialog box that opens next.
4. Go back to the Project Browser.
5. Right-click View All and select Properties. Under Type make sure Not on Sheets is selected, and choose Duplicate. Name the duplicate **My Drawings**.

FIGURE 2.49

Create a new project parameter for views.



6. Click the Folders button.
7. Change the Group by setting to Drawn by (Figure 2.50), and click OK.
8. Go to any view, and open its View properties.
9. The project parameter you added appears in the Identity Data group as Drawn by. Type your initials or name in the Value field, and click OK (Figure 2.51).

FIGURE 2.50

Group views by the new parameter (Drawn by).




Sheets

Sheets are special views that are your final documents—the actual sheets you’ll be sharing with your contractor, client, or team members. This is where the collections of drawings that eventually get printed are stored. Under each sheet node you see all the views placed on that sheet. As with any other view in Revit, if you double-click the node, the sheet view opens in the View window.


To make a new sheet, go to the View tab, and from the Sheet Composition panel, select New Sheet. This lets you select a title block family to use.

FIGURE 2.51
Change the Drawn
by parameter for
any view.



ACTIVATING A VIEW ON A SHEET

Double-clicking a view on a sheet is the same as opening the view from the view's node. Double-clicking the sheet name opens the sheet. From the sheet, you can directly edit views on the sheet by right-clicking a view and choosing the Activate View option. This opens the view and grays out the sheet context, allowing you to edit elements in the view from the context of your sheet. To get back to the sheet, use the context menu again, and choose Deactivate View.




Families

In the Project Browser you can see all the loaded families in your project. *Loaded* means available from within the project and usually also indicates something loaded along with the template. You can load additional families while working on the project, and each one you load will be available in this location in the Project Browser. From here, you can drag and drop families into the drawing area, query their properties, create new types of elements, and even select all instances of a given element in the model in order to locate them or perform wholesale changes.


The context menu for families (Figure 2.52) is different from that for views. Note that if you choose the option to edit a family, you'll open the family in the Family Editor, where you can make changes to the component and then reload it. If you expand the family node to expose all the family types, you can right-click a type and choose Select All Instances from the context menu. All instances in the model become selected, even if you can't see them in your current view. This lets you make edits to the family type in one interaction. For example, you can select all instances of a door family and swap it with a different door type.

FIGURE 2.52
Options for families in the Project Browser.



Links

Revit *links* (other Revit files that are linked into your project) are also listed in the Project Browser. Using the context menu, you can reload, unload, open, copy, and visually identify the links in your project.



Groups

Groups are associated collections of elements that can be repeatedly placed throughout the model. Groups are used for repeating entities (furniture composed of a table and six chairs, a typical bathroom layout with fixtures and partitions, or a typical hotel room, for example). When one group changes, all other instances of that group also change. Whenever a group is created, it appears in the Project Browser. You can place a group from the Project Browser by dragging it into the View window.

Navigating Views and View Properties


As we've mentioned, all views have properties that determine characteristics such as scale, graphics display, and view depth. Each view type has special characteristics and options, and it is important to understand them when you're using Revit. We'll look at the different view types and explain their defining features and how to use them. To access View properties, use any of these access methods:

- ◆ Right-click anywhere in the View window, and select View Properties from the context menu
- ◆ Right-click a view in the Project Browser, and select Properties from the context menu
- ◆ From the Ribbon, select the View tab, and on the Graphics panel, click View Properties
- ◆ Use the keyboard shortcut **VP** to access the View Properties dialog box directly

Floor Plans

Plan views are used to show horizontal slices through your building. Each plan view in Revit is associated with a level. A *level* is a horizontal datum that establishes major floor-to-floor heights and other critical horizontal working planes. Figure 2.53 shows that each level generates a plan view. By default, the plan is cut 4" (1–1.2 m) above the actual level height, but this value can be customized to suit your requirements.

FIGURE 2.53
Levels generate
plan views.



USE CAUTION WHEN DELETING LEVELS!

If you delete a level in your project, you will delete all views and elements associated with that level, including any walls, roofs, and furniture—so be careful when deleting levels!

Each plan view can show a range of the model based on levels. This aspect of Revit is often misunderstood, so let's take a moment to demystify it.

VIEW RANGE


When creating your documents, you want them to represent your elements correctly. Using the Object Styles dialog box and graphic overrides, you can get your drawings to look exactly the way you want them to look. However, you also may often wish to add a level of abstraction to the drawing that involves elements that aren't typically visible in the view. For example, you may want to see rooflines overhead or see down into an atrium a few levels below. This is where the View Range options come in handy.

The options available in the View Range dialog box allow you to define how elements in a view are represented based on their location in space. View Range values are stored as a property of the view and are included when you save a view as a view template.

Figure 2.54 shows three ways to represent the same space and elements by using different View Range settings. Think of the mess you might end up with if you had to do this using a layering system!


FIGURE 2.54

Three different representations of the same model in plan view.



To access the View Range dialog box, go to the View properties of a plan or ceiling plan view, and choose to edit the View Range parameter. Doing so opens the dialog box shown in Figure 2.55.

FIGURE 2.55
The View Range dialog box.



The View Range dialog box is divided into two parameter groups: Primary Range and View Depth. Let's start by looking at the primary range. It is defined by horizontal planes. Three of them (Top, Cut Plane, and Bottom) define the primary range, and a fourth plane defines the view depth.

Top Defines the top limit of the view range.


Cut Plane Defines the height of the Cut plane.

Bottom Defines the bottom limit of the view range.

Note that the positioning of these is *always* relative to a level. The Cut plane *always* references the level of the view in which you're working, and the other two can reference *any* level of the project.


Revit doesn't offer a graphical representation of the View Range settings that we are describing here, but it shouldn't be difficult to imagine their position in space. Look at Figure 2.56, a representation of different positions of the horizontal planes of a view range. In a floor plan view, the direction of the view is from top to bottom—so you're looking from above.

FIGURE 2.56
Various positions of the view range (top) and the associated plan view (bottom).



In a ceiling plan, the view direction is exactly the opposite—you’re looking from below, upward (see Figure 2.57).

FIGURE 2.57
Position of the view range for ceiling plans (top) and the associated plan view (bottom)



Depending on the positioning of the elements with respect to the view range and its parameters, the graphical display of those elements can vary. The Cut Plane parameter can radically change the appearance of your view, because every element in Revit has a physical location in space. Elements look different depending on whether they’re cut *by* the Cut plane, *above* the Cut plane, or *below* the Cut plane.

DOES A CATEGORY ALLOW CUTTING?

How do you determine whether a category allows its elements to be cut? A fast way is to look it up in the Revit Help file under Revit Architecture 2010 User’s Guide ➤ Customizing Project Settings ➤ Detail Level ➤ Managing Family Visibility and Detail Level.


There is another method as well, which may be more practical. In the Visibility Graphic Overrides dialog box or the Object Styles dialog box is a Cut column. For certain categories, this column is grayed out; this is the indicator that the category doesn’t allow cutting.

Model Objects					
Annotation Objects					
Imported Objects					
Category	Line Weight		Line Color	Line Pattern	Material
	Projection	Cut			
Floors	2	2	Black		
Furniture	1		Black		
Furniture Systems	1		Black		
Generic Models	1	1	Black		
Lighting Fixtures	1		Black		
Mass	1	2	Black		
Mechanical Equipment	1		Black		

CUT PLANE

Not all Revit elements behave the same with respect to the Cut plane. Some Revit categories don't support the notion of being cut (furniture families, for example); even if a Cut plane intersects them, they're always represented as if viewed from above (not cut). Figure 2.58 shows that a stool looks the same, no matter where the Cut plane happens to intersect it.

FIGURE 2.58
Some categories, such as furniture, are not affected by the Cut plane.



THE PRIMARY RANGE


Now that you have a general understanding of how the Cut plane affects elements in a view, let's dig deeper into the primary range concept. As we mentioned, this range consists of two other planes, Top and Bottom, which are placed respectively above and below the Cut plane. The exact positioning of these two planes is defined by an offset value relative to a level:



The Top plane can reference any level above the current one. The Bottom plane can reference any level below the current one. Let's look at some examples:


- ◆ If an element is cut by a Cut plane, it's visible in the view, as shown in Figure 2.59.

FIGURE 2.59
The cabinet is cut by the Cut plane and is visible.




- ◆ If an element is *below* the Cut plane but within the primary range (partially or completely), it's visible in the plan view as if it were looked at from above, as shown in Figure 2.60.

FIGURE 2.60
The lower book-case isn't cut but is visible.




- ◆ If an element is *above* the Cut plane and completely within the view range, it doesn't appear unless it's the category Windows, Casework, or Generic Model. It appears as if seen from above, as shown in Figure 2.61. Because the wall shelf is the category Casework, and it's within the primary range, it appears in plan view.

FIGURE 2.61
The wall shelf appears.



VIEW DEPTH

The View Depth is defined by a horizontal plane that is below the view range. The positioning of this plane uses the same principle as the planes in the view range—it's defined by an offset referencing a level:



This plane is often confused with the Bottom plane of the view range. Remember this: the View Depth *cannot* be above the Bottom plane. View Depth allows you to see elements below. The default is set to show nothing, because it's associated with the active level and has no offset.

The View Depth is easy to misunderstand: it sounds confusing to have a Bottom plane in the view range and also have this additional View Depth parameter. The idea here is that you need the ability to control the display of elements that are below the primary range but within the View Depth. Consider a wall with a footing. The wall is placed on Level 0 and goes up to Level 1. In the plan view of Level 0, using the default settings, you don't see the footing (see Figure 2.62).

FIGURE 2.62
With the default View Depth, the footings aren't visible in plan view.





Figure 2.63 shows the effect of the default view range when it's set to be coincident with the view's associated level, in this case Level 0. Lowering the depth of the view makes the footings

visible in plan view. They're represented with the *Beyond* line style, which in this example uses a dashed line. To make the footing visible in the Level 0 plan view, you need to do one of the following:

- ◆ Lower the height of the Bottom plane in the primary range, and define the View Depth to be coincident with it
- ◆ Define the View Depth so that it's below the base of the footing

FIGURE 2.63

Modifying the view range for the footing of a wall makes the footing visible in plan view.




In the second case, you don't need to change anything about the Bottom plane. In addition, you can obtain a different graphic presentation for the footings (without modifying the Visibility/Graphic Overrides settings). The View Depth allows elements that are below the current level to appear in a unique line style named *Beyond*. To control that line style, go to the Manage tab, and in the Project Settings panel and from the Settings choose Line Styles.

To display the elements in view in a specific way, you'll need to play with various parameter settings in the View Range dialog box. See Figure 2.64, in which the View Range settings work in the vertical dimension (view shown in elevation) and affect plan views (corresponding plan view shown below).

FIGURE 2.64

The View Range settings work in the vertical dimension (view shown in elevation) and affect plan views (corresponding plan view shown below).



To fully understand this example, it's essential to understand the categories of the elements participating in this view (from left to right in Figure 2.65):

The door The door belongs to the Door category. It's cut by the Cut plane. Its graphic presentation is controlled by the Cut style in the Object Styles or Visibility/Graphic Overrides dialog box. The arc representing the door swing is a 2D symbolic element and thus can't be cut by the Cut plane.

The low cabinet The low cabinet belongs to the Furniture category. Because it's placed below the Cut plane but still within the View Depth, it's visible in plan view. It uses the Beyond line style.

The wall-mounted shelf The wall shelf belongs to the Furniture System category. The shelf is above the Cut plane but within the view range. Its category allows it to be represented in plan view. Its graphics are controlled by the Projection column in the Visibility/Graphic Overrides or Object Styles dialog box.

The desk-chair-drawer family The desk with a chair and a drawer (all one family) belongs to the Furniture category. This family is cut by the Cut plane. Its category doesn't allow for it to be cut, and its graphics are thus controlled by the Projection style in the Visibility/Graphic Overrides or Object Styles dialog box.

The window The window belongs to the Window category. It's cut by the Cut plane. Its graphics are controlled by the Cut style in the Visibility/Graphic Overrides or Object Styles dialog box.

Creating a Plan View Using View Range and a Plan Region

Figure 2.65 is a model of a simple space that we'll use to understand view range. We have chosen a split-level example to show you the power of various settings and resulting displays of the View Range parameters. The goal is to create a plan view of Level 0 that displays information from a lower level. We want to display elements placed on Level 00B with a dashed line style.

Follow these steps:

1. Open the file `ViewRange.rvt` from the Chapter 2 folder on the book's companion web page.

In the elevation view (South Elevation) you can see the various planes shown in Figure 2.65. The View Depth is defined to be the same as the Bottom plane.

2. From the Level 00 plan view, go to View Properties, and open the View Range dialog box (Figure 2.66).

The default Revit settings are currently being used. Notice in Figure 2.67 that Level 00B and all elements placed on it are *not* visible in this view. The low cabinet is visible in the view, because it's placed on Level 00 and is within the primary range. The wall shelf above the low cabinet belongs to the category Furniture Systems and is also visible, even though it's above the Cut plane.

FIGURE 2.65
Working with the
view range




FIGURE 2.66
View Range
settings.





FIGURE 2.67

You can see the effect of moving the Bottom plane and View Depth to Level 00B.



3. Change the Bottom and View Depth settings to Level Below (Level 00B), and click Apply.

Having defined the Bottom plane as well as the View Depth to be coincident to Level 00B, you've managed to show the elements of Level 00B in the Level 00 plan view. The problem is that it will be difficult to assign a dashed-line style to the elements placed on Level 00B, as you initially desired. You could manually override all the elements, but you'd have to do so in each view manually—let's look at a smarter way to do this.

4. The furniture in this level is below the Cut plane. To change the graphic display of it, you could use the Projection column in the Visibility/Graphic Overrides or Object Styles dialog box, but in that case, the presentation of the furniture on Level 00 would be affected—and that isn't what you want to happen.
5. Set the Bottom plane to Level 00, and give the View Depth a -4' (-1.2m) offset below Level 00. Click Apply. In the elevation in Figure 2.68, you can see the various planes in dashed-line style. As you'll notice, the chairs are now visible but not the table—this is because the chairs are partially within the view but the tables aren't (they're below the View Depth). The chairs belong to the Furniture category, which doesn't support a cut representation; they're shown as if they were seen from above, even though they're intersected by the View Depth.
6. Set View Depth to Level Below (Level 00B) and give it a -4' (-1m) offset. In the elevation in Figure 2.69, you can see the various planes in dashed-line style.

FIGURE 2.68
Modifying the
View Range
settings.






FIGURE 2.69
Lowering the
View Depth.



By changing the View Depth, you have achieved your goal of seeing the furniture from below in a dashed-line style; however, the windows don't look quite right. To fix that, Revit provides a tool that allows you to selectively alter the view range for certain parts of the view using a *plan region*. This tool lets you draw a rectangle and then define the view range for that rectangle as a way to override the View Range settings of the view.


7. In the View tab, under the Create panel, click Plan Views, select the Plan Region tool, and sketch a rectangle around the windows, as shown in Figure 2.70. This region will make it possible to show the windows as if they were cut.

FIGURE 2.70
Making a plan region, annotated here by the rectangle in the upper right.



8. From the Element panel, click Plan Region Properties, and change the view range of the plan region. In this example, to show the window, set the level the Cut plane is referencing to Level 00B (see Figure 2.71).

FIGURE 2.71
View Range properties of the plan region.



If you need to adjust the properties of the plan region later, select it, go to its Element Properties, select View Range, and go back to the settings.

Sections

Section views are traditionally live cuts through the building model. They can be generated using the Section View tool from the View or Basics Design bar. You can place section lines in plans, elevations, and other section views, and they will appear in other views that cross the section perpendicular to the Cut plane. A section has two graphic symbols associated with it that appear at either end of the section line. Check the Ribbon when placing a new section—you'll notice that you can choose a section type (Building, Wall, Detail) and in the Options bar you can preset the scale. These are the options available when placing a section:

You define the section line by making two clicks in the view. Once a section has been created, you can move it by dragging it. The amazing thing is that when you move the section line, the view it references is automatically regenerated. A section line always shows what it's cutting when the view is displayed. It's impossible to have a section that is out of sync with the model.


Some special properties are available for sections that help you create the drawings you want. We'll focus on those next.

BROKEN SECTION LINES

The default section graphic is shown as a solid line with a section head and section tail at the ends. You can break a section cut line by clicking the little squiggle icon in the center of the line. Doing this lets you create a graphic, as shown in Figure 2.72.

FIGURE 2.72

Clicking the squiggle icon breaks the section line.




JOGGED SECTIONS

As you draw a section line, you'll notice that you can only draw a straight segment. Often, however, you'll want the section line to pass through important parts of the building that don't lie on the same line—you'll need to break the section line and make it jog. You can jog the section line around elements in plan to change what is shown in the view. To do this, click the Split Segment button available in the Section panel when a section is selected. The cursor changes to a knife. Click to split the section, and begin dragging the segment. Figure 2.73 shows an example of a section split that jogs around an elevator core but cuts through classrooms.

FIGURE 2.73


Jogging a section line.



DEPTH OF A SECTION

When a section is selected, you can control the extents of the view interactively using the crop boundaries. The right and left sides directly affect the section view size on a sheet. The far clip limits how much geometry is visible in depth. To improve performance and get the right representation, be aware of how deep your sections are. Show only what is needed. By default, a new section extends the entire depth of the model. To change that, pull the far clip closer to the Cut plane (see Figure 2.74). The same logic applies to elevation depth.

FIGURE 2.74
Controlling the
section depth.



AUTOHIDING SECTIONS AND ELEVATIONS

It's possible for sections to disappear from time to time as you change the scale of a view. If you check the visibility settings or try Reveal Hidden Elements mode, it won't be clear why the sections aren't visible. This behavior is a result of a little-known feature: Hide at Scales Coarser Than. This parameter lets you set a scale beyond which the section will no longer be visible. In most circumstances, the benefit of this feature will be nearly invisible—Revit will do the right thing, and you'll go about your business as usual.

Elevations

Elevations are made by placing elevation tags in floor plan views. Depending on where you place the elevation in the model, you'll get different resulting views. Revit assumes that if you place an elevation in the model (in a room, for example), you're creating interior elevations. The view shows only the walls visible in that room. If you place an elevation outside your model, a building elevation is created that shows the entire façade.


Elevations are a lot like sections in terms of how they behave in Revit: they have a clip plane, a crop boundary, and a symbol; and they can be opened directly by double-clicking the symbol. Elevation tags can have as many as four views related to one tag for the purpose of creating interior elevations of rooms. This is great for interior elevations but limits your ability to customize the graphics of these tags.



Real World Scenario

HIDING SECTIONS AT COARSER VIEW SCALES

In a $\frac{1}{4}"$ (1:50) floor plan view, you may have many wall sections, building sections, and interior elevation tags visible. However, with a $\frac{1}{8}"$ plan (1:100), you want to see only the building sections and exterior elevation tags. Using the Hide at Scales Coarser Than option, you can do this. Select your interior elevation tags, and set their Type property to hide at scales coarser than $\frac{1}{4}"$ (1:50). (Make sure you select the view direction arrow, not the view reference part.) Next time you open the $\frac{1}{8}"$ (1:100) plan, they won't be visible. Do the same for your wall sections. Because this is an instance property, you must first select the elements to which you want to apply this rule.




In many scenarios, the symbol used for an exterior building elevation is identical to the symbol used for section heads. Currently in Revit, this can't be done with a standard elevation symbol. For this use case, we suggest a common workaround:

1. Create a building section, and open its properties. Click the Edit/New button, and then duplicate the section. Name the new type **Exterior Elevation**, as shown in Figure 2.75.
2. When you go to place an exterior elevation, choose the Section tool instead. Draw the section so that it creates an exterior view of the model.
3. Drag the section head to the middle of the model. Notice that the section extents stay where they are, so the view isn't affected by this graphical change.



4. Turn off the visibility of the section tail by clicking the cycle icon.


FIGURE 2.75
Making a new
section type for a
building section.



5. Drag the section line so it disappears into the section head.
6. Check your Project Browser. A new node appears for your exterior elevations.
7. In Figure 2.76, the elevation still appears in the sections node, but it's appended with the Exterior Elevation type. You can rename the section if needed. (Note that the elevation tag looks like the section tag.)

Sections (Exterior Elevation)
Section 3

FIGURE 2.76
The elevation tag
looks like the
section tag.



If you go this route, be aware that to adjust the cropping, you must select the section line you just worked so hard to hide. You'll need to zoom in close and use the Tab key to select that line again. Once it's selected, you'll have full access to the other controls associated with the section.

3D Views

One of the most obvious benefits of working with BIM is the 3D nature of the model. When using Revit, you'll find yourself constantly generating different 3D views, examining the space from various vantage points, and making presentations you would not be able to do using a 2D application. You can create two types of 3D views in Revit: axonometric and perspective. Each has special characteristics that you need to be aware of.

AXONOMETRIC 3D VIEWS




An *axon view* is a scaled drawing showing the model in three dimensions. These views allow you to dimension lengths in all three dimensions with no perspective distortion. The easiest way to make an axon view is to duplicate the default {3D} view using the Project Browser. Right-click the {3D} view name, and duplicate it. Once you do this, the next time you click the 3D icon, a new default {3D} view will be created automatically. Once you have a 3D view, use the mouse to spin it around. Hold down Shift and the middle mouse button to orbit around the model. If you first select something and then orbit, you'll orbit around your selection. To pan the view, hold down the middle mouse button and pan. To zoom, scroll the mouse wheel back and forth.

Orienting to Other Views

Perhaps the most compelling feature of the axon view is its ability to orient to other views. To do this, right-click on view cube to access the context menu, and then choose to Orient to View. When you do this, a 3D section box is enabled in the view that cuts the model with all six faces of the box. You can go from a very dense, hard-to-read model to a focused representation. Figure 2.77 shows a 3D view that was oriented to a section view. You're free to create new elements and edit the model from these types of views.

FIGURE 2.77
3D view oriented
to a section view
and then orbited




You can then spin the model to get a 3D representation. With Revit, these types of views are easily generated; they suggest a new type of drawing to be included in standard construction and presentation document sets.

PERSPECTIVE VIEWS (CAMERAS)


Perspectives in Revit (bird’s-eye and worm’s-eye views) follow the metaphor of placing a camera in space. To make a new camera, start from a floor plan, and use the Camera tool from the View Design tab. The first click establishes where the camera is placed in the model. Look at the Options bar: you can set the camera height prior to placement if you want. The default puts the camera 5’-6” (1.8m) above the active level you’re on. You then give the camera a direction and set the center of rotation by clicking a second time. The view automatically opens for you to reveal what your camera sees. The camera placement is shown in Figure 2.78.

FIGURE 2.78
Camera placement.



Once in the camera view, you can navigate by using the mouse buttons to orbit and pan. For even more options, enable the SteeringWheels from the Navigation panel in the main view window, shown in Figure 2.79.

FIGURE 2.79
The Navigation panel contains the SteeringWheels and Zoom tool.



Use the small arrow icon in the lower-right corner of the SteeringWheel to access additional options and change which wheel is active.


Once a camera has been placed, you won't see it in other views. Its default state is to be invisible. To make a camera visible, select the view in the Project Browser, and choose Show Camera from the context menu. You'll see a graphic of the camera and its available controls, such as the camera, target, and far clip plane (if it's enabled). Select any controls, and drag them around to alter the location of the camera. Clicking empty space or another element deselects the camera; it will disappear.

Unlike axon views, perspective cameras don't have a view scale that determines how big the view is. A perspective has no scale, so you use the crop region to define the size of the image. Click on one of the lines of the crop region, and from the Crop panel select Size Crop. This opens the Crop Region Size dialog box.

The width and height are controlled here—this is the size of the image if it was printed out on paper. If you start editing the values, you'll see the crop boundary resize. The default option (Field of View) adjusts the width and height independently, and the model becomes more or less cropped. Figure 2.80 shows the effect of changing Width from 16" to 12".

If you choose the Scale (Locked Proportions) option and change either Width or Height, the image looks exactly the same but is scaled up or down. If you like the proportions of your shot but you want a bigger version of it, choose this option.

FIGURE 2.80
Changing the crop
boundary.



The Bottom Line

Understand Revit parametric elements. Although you can find references to objects, families, instances, and components, in the end everything is an element.

Master It What are Revit elements, and how are they managed graphically?

Work with the Revit user interface. As in any software application, you need to know where all the major components are and what tasks they support.

Master It How do you change the graphics of a category for all views? What if you need to change the graphics for only one view?

Use the Project Browser. This UI component provides access to all elements in your model. Become accustomed to using it to locate views, families, groups, and links.

Master It Knowing how to navigate views in Revit is essential to completing work. What are some of the ways to open views in Revit?

Navigate views and view properties. Views are also elements. Just like the walls, floors, and roofs you add to the model, you'll also add views. They have properties you should become familiar with.

Master It You need to change the scale of a plan view from $\frac{1}{8}"$ to $\frac{1}{4}"$. How do you do this with Revit?

Chapter 3

Know Your Editing Tools

Get to know Revit's basic commands, tools, and techniques. The faster you learn to work with the interface, the more productive you'll become. With the new interface, most tools appear when an object is selected; however, some tools are located on the Modify tab. As you progress using Revit, you'll find that certain commands are better suited for certain tasks. For example, you'll develop a sense of when to copy and paste an element versus when to move and copy it; and when to use the spacebar instead of the Rotate tool. You will also get acquainted with the Join Geometry tools, the Split Face and Paint tools, and Revit's keyboard shortcuts.

In this chapter, you'll learn to:

- ◆ Select, change, and replace elements
- ◆ Edit elements interactively
- ◆ Use other handy editing tools

Selecting, Modifying, and Replacing Elements

Knowing how to select, modify, and replace elements of a Revit building model is fundamental to working with the software. These basic interface operations are the building blocks that you'll use throughout the process of making edits to your model.

Selection

Selection is straightforward in Revit: hover your cursor over an element and it highlights (turns purple); click the highlighted element, and it turns blue, meaning you have it selected. Once the item is selected, a special contextual ribbon tab appears that contains the tools relevant to the selected command or context (Figure 3.1).

FIGURE 3.1

The tool set offered in the ribbon depends on the type of element you've selected.



You can select multiple elements in several ways:

Additive selection Hold down the Ctrl key while clicking new elements to add them to your selection. To remove elements from the selection, hold down the Shift key and click the selected elements.

Window selection You can select many elements by dragging a selection window across the view. Do this by holding down the left mouse button and dragging. A left-to-right drag selects only elements completely within the selection window; a right-to-left drag selects anything within or intersecting the selection window.

Chain selection You can select connected lines and walls by placing your cursor over a line or wall (don't pick, just let it highlight) and then holding down the Tab key and selecting a wall or line. All walls/lines that are end-joined to that wall become selected.

Selection Count tool The selection count tool is displayed on the far right in the same zone as the status bar; its icon is a filter because it actually is an addition to the selection filter functionality and gives information about the number of Revit elements currently selected.

After making a selection of elements, you can see the number of elements you selected by double-clicking the count icon. This invokes the Filter dialog box, where you can narrow down your selection if needed. If you have nothing selected in the model, double-clicking on the count icon will not invoke the Filter dialog box.

You can also access the selection count tool by directly invoking the Filter dialog box from the Multiselect tab. This box is only active after you have made a selection of multiple different categories of elements in the model. Note that if you select elements of one category, the filter option does not exist

FILTERING YOUR SELECTION



You can filter what you've selected based on categories by using the Filter button (located in the Multiselect tab), which appears upon selection of multiple elements. This allows you to make large, nonspecific box selections and then focus your selection by removing categories from it. For example, if you box-select an entire floor plan, you'll end up selecting many categories of elements. Using the Filter dialog box, you can limit the selection to just the Windows category (or Doors, or whatever element you need). Note that you can open and access the Filter dialog box by double clicking on the previously mentioned count tool.

Try this out on any model you have open. Using a box selection, draw a big box around a portion of your model, and then click the Filter button from the Multiselect tab. You'll get a dialog box like the one shown in Figure 3.2. Here, you can deselect categories to limit what you've selected. Think of this as a shortcut. Let's say you need to change the properties of 20 doors in a plan view. It's much faster to box-select an area of your model and then filter out all the elements except the doors than it is to Ctrl-select all 20 doors one at a time.

SELECTING ALL INSTANCES

This option is available in the context (right-click) menu of an element and allows you to select all instances of a particular family in the entire model. This is great when you need to perform a wholesale swap of a certain family throughout the entire model. For example, if you placed some generic wood doors in your project and you now want to swap all those with metal doors, this command is perfect. To use it, select one door in the model, right-click, and choose Select

All Instances from the context menu to select all the wood doors. Then, select Change Element Type, which invokes the Type Selector in the Modify tab, to change the door type. With this command, elements become selected that may not be visible in your view (the elements might be hidden), because this type of selection isn't limited to what you see or have manually clicked. Remember that you're selecting all instances of that family type used in the *entire* model.

Whenever you make a selection of elements, you can look at the count tool on the bottom right of your screen. Figure 3.3 shows that four elements were selected.

FIGURE 3.2

Use the Filter dialog box to limit what you've selected.




FIGURE 3.3

Count showing the number of items selected.



USING THE TYPE SELECTOR

The best practices to model a building in BIM are to start to model using generic walls, floors, doors, and windows, and then over time, as you make more specific decisions and refine the details of the design intent, swap those for specific types of elements. Using Revit, you don't have to redraw elements when you decide to get more specific with your design. You make new types or load new content, and then swap out the elements using the Change Element Type (that invokes the Type Selector) in the Modify tab. The elements listed are all of the same category, making it easy to locate relevant content.

You can take advantage of this feature the moment you start placing any Revit families. During creation, you can use the Change Element Type tool to choose the type of element being placed. Once you select an element, the same list becomes available, making it simple to change the types.

MATCHING PROPERTIES



The Match Type button is located on the Modify tab under the Clipboard panel and allows you, upon selection of an element, to apply its properties (type and instance) to another element

of the same category. Once you select an element, the little brush icon attached to the cursor appears filled. Each subsequent click on elements of the same category will replace the selected element with the type currently active in the Match Type tool. Note that the Match Properties tool will only appear in the Modify tab when nothing is selected.

Be careful when you use this tool with walls, because not only does it change the wall type, but it also changes the top and bottom constraints of the walls being matched. Thus, the best practice for walls, if you need to change the type but don't want any of the level constraints to change, is not to use the Match Type tool but instead to use the Change Element Type button (Type Selector) from the Modify Walls tab that becomes available upon selection of a wall.

Copying and Pasting

Copying and pasting is a familiar technique used in almost all software applications, and Revit provides the basic features you'd expect with a copy and paste interaction (Ctrl+C and Ctrl+V). It also has some additional time-saving options that are specific to working on a 3D building model.

To copy any element to the clipboard, select it and press Ctrl+C. Elements are copied and now ready to be pasted. To paste, press Ctrl+V. In the majority of cases, Revit pastes the elements with a dashed bounding box around them. You then determine where to place the elements by clicking a point to define its position of placement. In the Options bar you will find an option called **Constrain** that when checked will only let you define the location of the copied element relative to the main constrain directions of the original element.

☒ Constrain

PASTE ALIGNED

Once you've copied elements to the clipboard, you can paste them into other views with a variety of options. This allows you to quickly duplicate elements from one view to another (an entire furniture set from one floor to another floor, for example) while maintaining a consistent location in the X-Y coordinate plane. After selecting elements and copying them to the clipboard using either Ctrl+C or the Copy button in the Clipboard Panel of the Modify tab, choose **Edit > Paste Aligned** from the main menu, as shown in Figure 3.4.

FIGURE 3.4
Paste Aligned
options.



Five options are available. Depending on the view from which you copy and what elements you copy, the availability of these options will change. For example, if you select a model element in a plan view, you'll have all the options shown in the figure. The options are as follows:

Select Levels This is a mode you can use to copy and paste elements between different levels. Once you select the elements and choose this option, you choose levels from a list in a dialog box, and you can paste to multiple levels at once. This is useful when you have a

multistory tower design and you wish to copy and paste a furniture layout that repeats on 20+ floors; in such a case, selecting levels graphically in a view can be tedious. The X-Y position of the selected elements is maintained, and the pasted elements are translated in the vertical dimension.

Select Views This option allows you to copy elements to other views by selecting views from a list of views in a dialog box. In the list available for selection, you don't see levels listed but rather a list of parallel views. For example, if elements are copied from a plan view, all other plan views are listed. Likewise, if you copy from an elevation view, only elevation views appear as possible views to paste into.

Current View This pastes the elements from the clipboard into the currently active view, in the same relative spatial location. For example, if you copy a series of walls in one view, switch to another view in the Project Browser, and choose Current View, Revit pastes the walls into exactly the same X-Y locations in the new view you switched to.

Same Place This option places an element from the clipboard in the exact same place from which it was copied or cut. One use for this tool is copying elements into a design option; see Chapter 10, "Working with Design Options," for an explanation of design options.

Pick Levels Graphics This is a mode you can use to copy and paste elements between different floors. Once you select the elements and choose this option, you're placed into a pick mode where you can select a level in section or elevation. You must be in an elevation or section view to have this option available. The level you select determines the Z location of the paste and preserves the X-Y location. You might use this type of paste to copy balconies on a façade from one floor to another.

Create Similar



Rather than hunting through a list of families or making copies using copy and paste, try using the Create Similar tool to add new instances of an element to your model.

The Create Similar tool is available in the Create panel of the Modify tab when an element is selected. You can also access the tool from the right-click menu. To use this tool, think about the type of element you need to make, and select an instance of it. Then, click the Create Similar tool, and you'll immediately be put into placement-creation mode. If you use this tool later to create a similar floor or roof (or any other sketch-based element), you're taken directly into sketch mode, where you can start sketching your new element.

Editing Elements Interactively

Revit provides a range of options to interactively edit elements in the model. The most obvious is to select elements to drag around the screen or use the blue control grips to extend walls and lines. However, you often need more precise ways of moving and positioning things. Let's look at some ways to do this.

Moving Elements

Revit provides several ways to move elements, ranging from traditional tools to intelligent dimensions that appear on the fly when you select elements. Become familiar with each method, and find what is best for your workflow.


USING TEMPORARY DIMENSIONS

You should have noticed by now that when elements are selected, dimensions appear. These dimensions are called *temporary* dimensions and are there to both inform you of the location of the elements relative to other elements in the model and help you reposition the elements. Clicking the blue dimension value makes it an active, editable value. Type in a new value and the element that was selected will move to that point. Keep this in mind: when editing a position of an element via the dimensions, it will always be the selected element that moves. By the same token, you can't edit a dimension if nothing is selected.

If a temporary dimension isn't referencing a meaningful element, you can choose a different reference by dragging the small blue square attached to the dimension witness line to a new parallel reference (Figure 3.5). Parallel references highlight when you mouse over them. For example, if you want to position a door opening at a specific dimension from the wall, you will need to drag the blue dot reference that currently references the door middle axis to the door opening so that the temporary dimension can read that distance and you can further edit to the value you wish. Parallel references highlight when the cursor moves over them.

FIGURE 3.5

Drag or click the small blue grip to change the reference of the temporary dimension.




If you click a blue grip, it cycles to the next possible reference in the element. For example, clicking the blue grip of a dimension to a door or window cycles between the left and right openings and the center of the element. The same is true for walls: try clicking the blue grip control of a temporary dimension that appears when you select the door, and see how the temporary dimension cycles through the various references in the wall (interior face, centerline, exterior face).

To change which references temporary dimensions go to first, use the Temporary Dimension Properties dialog box shown in Figure 3.6 (Manage tab > Settings > Temporary Dimensions). Here, you can specify how dimensions default to walls, doors, and windows independently.

FIGURE 3.6

The Temporary Dimension Properties dialog box lets you define default behaviors.



If you have many elements selected at the same time, temporary dimensions sometimes don't appear. Check the Options bar for the Activate Dimensions button; clicking it will make the temporary dimensions appear in the view.



USING THE MOVE TOOL




Use the Move tool to move elements precise distances by typing in values or using the temporary dimensions as helpers. Once you have selected an element, the Move tool will be enabled.


Moving elements is a two-click process: first you define a start point, and then you click to define an endpoint. If you know you need to move something to the left 10'-6", it doesn't matter where your two picks take place; all that matters is that the distance between the two clicks is 10'-6". (Figure 3.7 shows the graphics provided during a move operation.)

FIGURE 3.7

Use the Move tool to move elements precisely.



There are a few options on the Options bar to be aware of when the Move command is active.



Constrain When this option is selected, it constrains movements to horizontal and vertical directions. Deselecting it gives you free movement if the element is freestanding. Hosted elements such as windows and doors always move in a constrained manner parallel to their host axis.

Disjoin Hosted elements such as windows and doors can't change host and move to another host without explicitly being disjoined from their host. This option lets you disconnect inserts from their host and move them to new hosts. For example, if you need to move a door from one wall to another, you select the door, select the Move tool, select Disjoin on the Options bar, and move the door to another host.

Copy This option lets you make a copy of the element without moving the original element. In the strictest sense, this isn't really a move operation but a shortcut to making a copy.

Multiple This option, which is selectable only after you pick the Copy option, lets you make multiple copies of the selected element.

NUDGING ELEMENTS


Nudging is a great way to push things around quickly. When an element is selected, you can use the arrow keys on the keyboard to move the element horizontally and vertically, repositioning it in small increments. Each press of an arrow key nudges the element a specific distance based on your current zoom factor. The closer you zoom, the finer the nudge is. Likewise, as you zoom out, the nudge moves elements by larger increments. This is a good tool when you're working with views placed on sheets.

MOVING WITH NEARBY ELEMENTS

Another way to move freestanding elements, but in a more automatic way, is to use the Moves with Nearby Elements feature. This tool is designed to capture logical relationships between elements. When furnishing a space for example, you probably want to align the bed or dresser with a wall. If you change your design, you want the furniture to follow the wall to the new location. For this purpose, select the furniture and then select Moves with Nearby Elements on the Options bar. By doing so, you create an invisible relationship between the bed and the wall so that each time you move the wall, the bed moves with it (Figure 3.8).

FIGURE 3.8

Once the bed is selected, it can be set to move with nearby elements.



Copy



This is an interactive tool that is nearly identical to the Move tool but makes a copy of the selected element at the location of the second pick. This tool doesn't copy anything to the clipboard; it copies an instance of an element or selection of elements in the same view. If you change views while using this tool, your selection is dropped.

To activate this tool, first choose the element or elements you want to copy, and then select the Copy tool from the Modify tab. Using the Options bar, you can choose to make multiple copies in one interaction by selecting the Multiple option.



Rotating and Mirroring Elements

It's common to need to rotate an element. Just as with Move, Revit provides a few methods for rotating elements. The time-saving spacebar is a quick way to rotate elements in 90-degree increments. Just press the spacebar when an element is selected; each press of the spacebar will rotate the element another 90 degrees. If a diagonal reference (wall, grid, or reference plane) is nearby, then the spacebar will locate this as a rotation candidate. For more precision, the Rotate tool is provided, which you can use to rotate elements to any specific angle you require.


USING THE SPACEBAR

Revit uses the spacebar to rotate elements both at the time of placement and after an element has been placed. This is a great timesaving command to become familiar with, because you can forgo using more traditional tools such as Rotate and Mirror by taking advantage of the spacebar. Here are a few examples:

Doors and windows If you have a door with its swing in the wrong direction, select it and press the spacebar. You can cycle through all four possible orientations of the door with a few clicks. The same holds true for windows; however, many window families are built to only let you flip the window from inside to outside, because many windows are symmetrical in elevation. If you are creating an asymmetrical window on your own, be sure to add flip controls to the window family during its creation. These allow the spacebar to work on hosted elements. Figure 3.9 shows the window opened in the Family Editor and where to access the flip controls for placement from the Create tab.

FIGURE 3.9

Flip arrows, used to flip elements, can be added to families from the Family Editor.



Walls If you select a wall, pressing the spacebar flips the element as if it were being mirrored about its length. Walls flip based on the Wall Location Line, which often isn't the wall center-line. If you aren't sure which direction your wall is facing, select it and look for the flip-control arrows. These are always drawn on the exterior side of walls (Figure 3.10).

Freestanding elements If you select a freestanding element like the loveseat shown in Figure 3.11, the spacebar rotates the element about the center reference planes defined in the family. Depending on how the family was built, the rotation origin may not make the most sense, but you can quickly orient your furniture and casework. If you decide to edit a family to change the location of the geometry relative to the center reference planes, be careful: when loaded back into a project, all your elements will jump to a new X-Y location based on the changes you made!

FIGURE 3.10

The flip arrow is another way to reorient an element. For walls, the flip arrow is always on the exterior side.





FIGURE 3.11

Center reference planes defined in the family determine the rotation origin.



USING THE ROTATE TOOL



To rotate an element, select it and click the Rotate tool. This is a two-click operation similar to the Move and Copy tools. Alternatively, you can enter numeric values. Revit locates the geometric center of the selected element or elements and uses that as the default center of rotation. This is fine if you don't need to be precise and just want to rotate something by a known angle. However, in most cases you first must designate a meaningful center of rotation.



To do so, select and drag the center of the rotation—the rotation cursor—to a new location before clicking to set start and end picks. Once the origin is established, begin rotating the element using the temporary dimensions as a reference or by typing in the angle of rotation explicitly.

You'll notice that while moving the origin, you lose the ability to pan and zoom the view. To overcome this, drag the origin into the Project Browser and release the mouse button; then, move the cursor back into the view. The cursor changes to a rotation icon, and you can freely pan and zoom all you want. The next click you make places the origin, and you can then designate the rotation.


USING THE MIRROR TOOL



The Mirror tool allows you to mirror elements across an axis in order to create a mirror image of an element, like the sinks in Figure 3.12. You can either pick an existing reference in the model (the arrow icon) or draw the axis interactively (the pencil icon). In Figure 3.12, a mirror axis was drawn through the center of the top exterior wall.

FIGURE 3.12

The sinks, toilet fixtures, and door are mirrored about the middle of the wall at the top of the view.



Use the pick method when you have an existing element with a meaningful center axis. If nothing in the model exists as a mirror axis, use the Draw mode and draw your own axis.

Arraying Elements



An *array* allows you to copy instances of an element with equal spacing between instances. Revit provides intelligent arrays that can be parametrically grouped and associated, as well as one-off, unassociated arrays. Like all the other tools we've reviewed, the creation options are presented on the Options bar.






You can create two types of array: *linear* and *radial*.

Linear arrays are set as the default because they're the most common. As you would expect, a linear array creates a series of elements in a line. Each element in the line can be given a set distance from the previous element or be spaced equally based on a maximum line length. Figure 3.13 shows a linear array where the Move to 2nd option was selected in order to set the initial spacing correctly. Think of this type of array as additive and subtractive: if you change the number, the length expands or contracts.

FIGURE 3.13


Move to 2nd option used in the array tool to set a fixed distance between groups.



If you want to arrange elements in a fixed space, and the exact spacing between elements is a less important factor, use the Last option. Figure 3.14 shows an array where the location of the last element in the array was picked, and the elements (in this example, windows) were placed equally between the first and last elements in the array. With this option, the length is fixed, and the array squeezes elements within that constraint as the number changes. The examples in Figures 3.14 and 3.15 show that depending on your design criteria, you can use different arrays.

FIGURE 3.14


This array uses the Last option and backfills instances between the first and last group.



A radial array works in a similar fashion, but it revolves around a center point. With a radial array, elements auto-rotate so that each element faces the center of the array, as shown in Figure 3.15.

FIGURE 3.15

When you're making a radial array, you can specify the number of instances interactively.



Enabling the Group and Associate option allows you to treat an array as a group that can be modified later to adjust the number and spacing of the array. If this option is unchecked, then the array is a one-off operation, and you have no means of adjusting the array after you create it.


When an element in a *grouped* array is selected, a control appears, indicating the number of elements in the array. Editing that number changes the number of elements in the array. This tool comes in handy when you're creating certain families, because the array number can be parameterized. See the section "Parametric Arrays in the Family Editor" in Chapter 11, "Moving from Design to Documentation," for a detailed exercise.

Scaling Elements



The Scale tool lets you scale certain lines and graphic elements in 2D that make sense to scale, such as imported raster images and 2D line shapes. In Figure 3.16, the Scale tool was used to make the lines surrounding a door tag a bit larger. The first pick was the center of the family, the second pick was the center of one of the lines, and the final pick finished the resize.

FIGURE 3.16
The Scale command sequence is a three-click process.



This tool is also well suited for working with imported images that need to be scaled to match real-world dimensions. For example, it's common to import an aerial photograph of a site to use as a contextual underlay. The Scale tool works great to get the image to the right scale. You also can create a formula in the element properties of an image to rescale it very specific requirements.

This tool is active once you select an image. After you select the Scale tool, click a point to enter an origin (say, the lower-left corner of the image); click a second point to determine the width of the image that you want to fit within a certain size; finally, click a third time to get the new length you want.

Important note: Keep in mind that you're working with a building information model (BIM) made out of real-world objects, not abstract primitive forms. Don't expect to be able to scale most elements in Revit—it's not practical or meaningful. For example, you can't scale the size of a door, wall, or sink because they represent real-life types and scaling them would mean scaling all their components. This would probably lead to impractical or even meaningless results—for example, the door frame will scale in unreal proportions while the size of the panel might be still right.

Aligning Elements




If you've been using Revit for any amount of time, you should have discovered the incredible power of the Align tool. If not, take time to get acquainted with this tool, because it's a real time-saver and supplants the need to use many of the tools we've already discussed. The Align tool lets you line things up in an easy, quick, and intuitive manner.

With this tool, you explicitly align references from one element to another. For example, you can align windows in a façade so their centers are all in alignment. You will find the Align tool in the Modify tab, under the Edit panel. To use the Align tool, you will first select the target reference (a part or side of the element to which you want to align another element) and then select what you want to align to that reference (the part or side of the element whose position needs to be modified). The second element picked always moves into alignment. This selection sequence is the opposite of the other editing tools we've looked at so far, so remember: first you select the aligning reference, and then you select the element to move into alignment with the reference.

As soon as you make your second pick, a lock icon appears so you can constrain the alignment. Once you click the lock icon, if either element moves, it brings the constrained element along with it.

Figure 3.17 shows the use of the Align tool to align windows on a façade. The left opening of the topmost window was used to align multiple windows using the Multiple Alignment option on the Options bar.


FIGURE 3.17
The Align tool is great for lining up edges of windows in a façade.



The Align tool also works for aligning geometry with surface patterns like brick or stone. Select a line in the surface pattern, and then select the geometry you want aligned. Figure 3.18 shows how you can align the edge of a window to a brick pattern. Use the Tab key if you cannot get surface patterns selected with the first mouse click. The align tool will also rotate elements in the process of aligning them to objects which are not parallel. This is a real time saver compared to rotating and moving.

FIGURE 3.18

You can also align model elements to surface patterns.



Trimming Lines and Walls




You can trim and extend lines and walls to one another using the Trim tool on the Modify tab. With the Trim tool, you first select the tool and then operate on elements in the model, selecting two lines or walls that need to meet in a corner.

The Trim tool, which is called Trim / Extend to Corner, trims elements to one another, creating a cleaned-up end join between walls and lines. For example, Figure 3.19 shows two walls before and after using the Trim/Extend to Corner tool.

FIGURE 3.19

The result of trimming two walls to one another is a clean corner join.




The Trim tool is used a lot for editing sketches of floors and roofs, because it's easy to end up with overlapping lines that need to be neatly trimmed. Keep in mind that with the Trim tool, you're selecting pairs of elements to *remain*, not be removed. Use the temporary preview graphics to help you. If you do trim the wrong thing, you'll see it immediately—just undo, and pick again.

Extending Lines and Walls




Next to the Trim tool, you will find the Extend tool. There you will see two options: Trim/Extend Single Element and Trim/Extend Multiple Elements.



This tool lets you extend single or multiple instances of lines and walls. The first option, Trim/Extend Single Element, is for extending a single wall. To extend a wall, first select a target wall; then select the wall you want to extend to that target (Figure 3.20). The second option, Trim/Extend Multiple Elements, lets you extend many walls in one interaction.

FIGURE 3.20
Trim can be used to extend walls as well.




Splitting Lines and Walls



The Split tool operates on walls and lines. This tool lets you slice a line or wall into few pieces. To cut a wall, place the cursor over the edge of the wall. Before you click, you'll see a preview of the split line before clicking.

The Options bar offers a nice feature called Delete Inner Segment that removes the need to use the Trim tool. In Figure 3.21, you need to remove the middle section of the wall and end up with a clean set of wall joins. Using the Split tool with the Delete Inner Segment option checked, you can accomplish this with two clicks and get a clean condition without having to come back and use the Trim command

FIGURE 3.21
Using the Split tool with the Delete Inner Segment option checked.



Offsetting Lines and Walls




Offset is similar to the Move and Copy tools in that it moves or moves and makes a copy of an element by offsetting it parallel to an edge you select. You can find the Offset tool either in the Edit panel of the Modify tab or on the Options bar when you're sketching lines or walls.

This tool is especially useful in the Family Editor when you're making shapes that have a consistent thickness in profile, such as extruded steel shapes. Offset is also handy when you're making roof forms or soffits with known offsets from a wall. You can either offset a line and maintain the original (for that, make sure that the Copy option in the Options bar is checked) or offset the line, removing the original. Figure 3.22 shows roof creation done by offsetting the sketch lines in the Roof Editor where the offset has been defined as 1'-0". Each pick of the wall offsets the line by 1'-0".

FIGURE 3.22

Offset lets you pick existing elements and create new elements with a specific offset distance.



Keeping Elements from Moving

In many cases, you'll want to make sure some elements in the model never move. A good example of this is when you work on a renovation of an existing building. You surely would not like to move walls that already are built somewhere else in the model. Other examples are imported drawings, grids, levels, and exterior walls (once their position is set). Revit provides two ways to deal with this and lock certain elements preventing them from moving.

PINNING ELEMENTS



You can restrict an element's ability to move by pinning it down with the Pin tool. Use this tool to lock down critical elements that need to remain fixed for long periods of time. This is a great feature for imported CAD files, because it's *very* easy to accidentally select an import and drag it or move it. This kind of accident can lead to coordination problems, even in a BIM environment. Use pins to lock down gridlines as well, because you certainly don't want those to move accidentally.

This tool is located in the Modify panel of the Modify tab. Select the element you want to pin down and click the Pin tool. If you try to move the element, nothing will happen—you won't even get a ghost preview of a potential move. To unpin an element, select it and look for the pin icon. Clicking the pin removes it and frees the element. The Unpin All tool is essential for unpinning multiple elements rather than selecting and unpinning one at a time.

WARNING

Pinned elements can be deleted. This unfortunately is misunderstood by users who believe that a pinned element is safe from deletion. Revit will however give you a warning before it deletes an element.


CONSTRAINTS

Constraints aren't as rigid as the Pin tool, but they do allow you to create dimensional rules in the model so that elements remain fixed relative to one another. You can create a constraint using dimensions and alignments and then click the lock icon that appears upon creation or selection of elements.

A simple example of using constraints is keeping a door a fixed distance from a side wall, so that if the wall moves, the door also moves. If you do try to move the door, Revit will not let you do it. Look at Figure 3.23: the door has been locked to remain 5 $\frac{3}{8}$ " from the wall face. This is done by selecting the door and locking the padlock that appears next to the temporary dimension defining the position of the door to the wall. After locking the padlock and thus creating a constraint, if the wall moves, the door moves as well; but if you try to drag the door to a new location, you can't.

FIGURE 3.23

A door constrained to a wall can't be moved independently of the wall.



Another example is locking the head height of a series of windows relative to a level. This prevents users from accidentally dragging windows into undesired locations while guaranteeing that if the level moves, the windows also move.

Exploring Other Editing Tools

A range of other editing tools are available in Revit, and these will be covered in subsequent chapters when they're used in specific operations. There are a few tools you should know about now, however, because they're generic tools that you can put to use on any project immediately.


These tools, which will help you produce the drawings you need, have the added benefit of being intelligent and parametric.

Join Geometry



Joining floors to walls and walls to floors creates cleaner-looking drawings Revit does a good job of cleaning up joins between elements such as walls, floors, and roofs automatically. However, in many cases elements don't look right unless they're explicitly joined. This is where the Join Geometry tool, accessed by the Join button, is useful. This tool creates joins between floor, walls, ceilings, roofs, and slabs. A common use for this tool is in building sections, where floors and walls appear overlapped and not joined. Figure 3.24 shows a floor intersecting some walls that aren't joined. Using the Join Geometry tool, these conditions can be cleaned up nicely.

FIGURE 3.24
Intersections at
Level 2 have been
joined.



To fix this condition, select the Join Geometry tool, and then select the floor and wall in sequence.

You should be aware that joining host elements across a large model created significant regeneration issues. One way to avoid this is to apply the following workaround: Give a black solid fill to elements in the cut plane of your sections – and then selectively join for medium and fine views. Solid host elements also read better in section at smaller scales (like half-size sets).

Split Face and Paint




To support painting of surfaces without having to make new types of elements, Revit provides the Split Face and Paint tools located in the Edit Face panel of the Modify tab. You can paint the exterior faces of walls, floors, roofs, and ceilings with a material. This material has no thickness, but you can schedule it (with a materials take-off schedule) and tag it. A typical use case for this feature is the application of a carpet material or tile to a floor.

Figure 3.25 shows the floor that initially covered both of the restroom spaces being split with the Split Face tool. Once the face has been split, you can activate the Paint tool to apply material to it.

FIGURE 3.25


Use Split Face to sketch an area of the floor to be painted with a new material.



The Type Selector lists all the materials in your project (Figure 3.26).

FIGURE 3.26


The Paint tool lists all materials in your project in the Type Selector.



Choosing a tile material and then clicking the split face applies the material. The result is that the floor is unchanged structurally, and the bathroom appears with a tile finish (Figure 3.27).

FIGURE 3.27

You can apply a Tile material to the split face to get the desired effect.



Keyboard Shortcuts (Accelerators)

Many users like using keyboard shortcuts to speed up common commands and minimize the need to interrupt workflow. When you hover your cursor over any tool in the ribbon, the keyboard shortcut is indicated to the right of the tool name, as shown here.



Revit contains preset keyboard shortcuts when installed, but you can modify the default shortcuts by editing the `Keyboard.txt` file located in the `C:\Program Files\Revit Architecture 2010\Program` folder. Revit's shortcuts are two-key shortcuts and are available only for commands that already exist. When you change the shortcuts in the `Keyboard.txt` file, Revit shows these abbreviations in the menu.

The Bottom Line

Select, change, and replace elements Learning the basic mechanics of the interface is crucial to just about everything you'll do in Revit.

Master It Selecting elements in the model happens all the time. What are some of the capabilities that the Revit user interface provides when you select elements?

Edit elements interactively The architectural process inevitably involves revision, so be sure you know how to make changes on the fly.

Master It You need to make some major changes to a floor plan, moving the bathroom 20' down a corridor. How might you do this with Revit?

Use other handy editing tools Revit provides a wide range of tools for making changes in a project.

Master It In a section view, you notice that the walls and floors aren't cleaning up neatly—you're seeing lines overlap. What tool could you use to try to clean that up?

Chapter 4

Setting Up Your Templates and Office Standards

In this chapter we discuss how to set up your office standards and how to prepare a project template that is rich with information that goes beyond the out-of-the-box content. We show how templates are used to assure graphic consistency in your projects and how the reuse of work will increase productivity in the future, making the process of creating documents more seamless. We tackle the Family Editor and the creation of custom annotation symbols, title blocks, object styles, and view templates.

In this chapter, you'll learn to:

- ◆ Start a project with a custom template
- ◆ Create custom annotation tags
- ◆ Create custom title blocks


Starting a Project with a Custom Template

The type of building you're planning, the geographical area in which your building will be built, and even the style of the building you're designing will require settings and content that differ from the out-of-the-box Revit template. Software vendors make a great effort to provide locale-specific content libraries that respect local traditions as well as incorporate local regulations in their documentation, but as we all know, that is only a good starting point and can't cover all the types of elements you'll need in the course of a project. Like many other software packages, Revit allows you to start with a basic template and then spawn your own custom templates to suit your specific requirements.

As your knowledge of the software progresses, you'll begin to create new wall types, roof types, ceilings, stairs, and other families in order to meet your design and documentation needs. This is also the case with regard to the graphical language that you or your firm has established over the years *and* probably wants to continue using in Revit. How you graphically present elements like text, dimensions, annotations, keynotes, and hatch patterns defines your style of design documentation. The reality of the architectural profession is that we tend to develop stylized graphics, and Revit respects this need by letting you customize your starting templates. One possible example of graphic style in a CD phase of a project is shown in Figure 4.1.

FIGURE 4.1

Example of stylized annotations used in a custom template.



With Revit, you can expect to set up your templates by doing one or more of the following:

- ◆ Defining all the project settings to meet your graphic requirements
- ◆ Preloading model and annotation families
- ◆ Defining system families before you start a project

Once everything is in place, you can then save the file as a new template (.rte) and use that template whenever you start a new project. Once you've saved a new template, you can have Revit open that template when you're starting new projects. To do so, follow these steps:

1. Go to the Applications Menu, and at the bottom of the menu that opens, click Options.
2. In the Options dialog box, select the File Locations tab. The first option in the dialog box shows the default template location.
3. Click the Browse button to choose a new path to your default template (Figure 4.2).

Creating and reusing templates can increase your productivity and keep your documentation looking consistent. Specifically, using templates allows you to do the following:

- ◆ Easily reuse work that you've already created
- ◆ Maintain consistency in a project (very important when many team members work on one centralized file)
- ◆ Assure a graphic consistency across all your projects

FIGURE 4.2
Change the path
to your default
template.



In this chapter we focus on personalizing (customizing) the Revit template file (.rte). The following list lays out items we suggest you go through one by one when setting up templates. This doesn't represent *all* possible settings you can predefine in a template, but it includes those that we think are most pertinent.

- ◆ Settings for graphics
 - ◆ Object styles
 - ◆ Materials
 - ◆ Line styles
 - ◆ Line patterns
 - ◆ Fill patterns (hatches)
 - ◆ View templates
- ◆ Setting up annotations
 - ◆ Dimension styles
 - ◆ Text styles
 - ◆ View tags
 - ◆ Annotation tags

- ◆ Setting up title blocks
- ◆ Global project settings
 - ◆ Keynoting external file locations
 - ◆ Project units

Strategies for Making Templates

Architectural firms tend to address template files in one of two ways: a generic, one-size-fits-all office template or a project type-specific template. Some firms focus on one type of building (healthcare, office, retail, and so on) where a single template is sufficient, and others do a wide range of projects and may even work across cultures with very different requirements between project types. If you work all over the globe or have many types of projects, then a generic office template probably isn't the best strategy. Instead, create new templates for each type of project. On the other hand, if you're focused on predictable, similar projects, you can start all projects from the same template.

Templates not only contain all graphic and visibility settings but also contain loaded families that you are likely to use in each project. Don't overburden your template with too many families—especially if you don't intend to use them all. To systematically remove families from your template, use the Purge Unused option in the File menu and select what you want to remove. You'll experience better performance when launching Revit and reduce the file size footprint of your model by starting out with a lean template.

When creating your own personalized template, be sure to avoid starting from an empty file (do not select the No Template option); rather always use an existing RTE file. You'll save yourself a lot of time by doing this.

Settings for Graphic Consistency

One of the goals of using a template is to assure graphic consistency across a project or even across an office. To achieve that, you need to set up the object styles that control the graphic appearance of everything in your Revit project, from 3D elements to 2D lines and hatch patterns.

Object Styles

As we mentioned in Chapter 2, object styles control the graphics for all the categories in your project. To access these settings, switch to the Manage tab, choose Settings ➤ Object Styles. This dialog box has three tabs: Model Objects, Annotation Objects, and Imported Objects. In this section we'll discuss the first two types of objects. The third tab, for imported objects, is where all DWG, DXF, or DGN files that you import in your Revit file appear. Even though these file types are based on a layering system, Revit still gives you full control over the graphics of each individual layer by translating each layer into a subcategory. When you define your template, focus on the first two tabs: Model Objects and Annotation Objects. They both organize categories and subcategories into a collapsible tree structure. From here, you can define graphics for the main category as well as any subcategories. If we take a door family as an example, you can define

different graphic settings (line weight, color, and pattern) for the panel, the frame, and the door swing. The settings on these tabs are as follows:

Model Objects As shown in Figure 4.3, six columns are used to control graphic properties of model elements. The first holds the list of all available categories and their subcategories of model elements in Revit.


The next two columns define the line weight that will be used when these elements are drawn in projection (elevation and 3D) or section (plan or section) view. In some of the categories, you'll notice that the Cut column is grayed out; this indicates that the category of element will never be cut by Revit. The furniture category, for example, will not be represented as cut in plan or section views. The next two columns define the color and pattern of the lines used to draw the geometry of these elements. The last column on the right lets you define a default material that will be associated with the category or subcategory in the event that elements in that category don't have materials explicitly defined. If a family has materials set to By Category, it looks to the material set in the Object Styles dialog box.

Annotation Objects This tab is similar to the Model Objects tab. The difference lies in the material definition (lines don't have materials!) and the line weight (there is no distinguishing between projection and cut line weight), because annotation objects are 2D only.

All these settings may look like overkill at first, but you usually need to customize these values only at the beginning of a process when building your office templates. Once you've assigned all the desired line weights, colors, and materials, you shouldn't mess around with them as these settings will affect the appearance of the entire project. While object styles are global, you do have the ability to change the graphic style of any element for a specific view using overrides (right-click in any view to open the context menu of the View Properties ➤ Visibility/Graphic Overrides, or you can use the keyboard shortcut, VG).

FIGURE 4.3

The Object Styles dialog box gives you independent graphic control of all Revit categories and their subcategories.




Object styles allow you to establish the graphical standard for the drawings that leave your office, contributing to an appearance of professionalism, so be sure to take your time and invest in getting them right. These powerful settings shouldn't scare you—they will ensure that your drawings have a consistent look and feel.

Line Styles

Much like object styles, a *line style* is composed of a line weight, line color, and line pattern and controls how all 2D and 3D lines will appear. Keep in mind that these settings are for the more traditional use of nonintelligent lines. To put this in context, when you draw lines or detail lines, they use a line style. To access the line styles, switch to the Manage tab, and choose Settings ➤ Line Styles. The dialog box that opens (Figure 4.4) has three columns to control the appearance of each line type.

FIGURE 4.4
Line styles define weight, color, and pattern for all lines used in a project.



The Category column is organized in a tree structure, with all line styles listed as subcategories of lines. As you can see, each style is defined by Line Weight, Line Color, and Line Pattern. Line Weight can have a value between 1 and 16, corresponding to a physical pen thickness that varies slightly based on view scale. This is the actual thickness of the line when printed on paper at 100 percent. You'll notice that lines have different thickness as you zoom in and out of a view; this is because the lines have a real thickness.


Line weights are managed from the dialog box shown in Figure 4.5, which you access by switching to the Manage tab and choosing Settings ➤ Line Weights. As the scale gets coarser, line weights adjust so the drawing is still readable. Examining the Line Weights dialog box, you'll notice that line thickness for heavy pens varies between scales.

Back in the Line Styles dialog box, notice that some of the line style names are bracketed but others aren't. The bracketed line styles are internal, "system" types of lines, which can't be renamed or deleted. Any unbracketed line style can be renamed or deleted at any time.

CAUTION WHEN DELETING LINE STYLES

If you delete a line style that is used by elements in a project, those elements cannot reference that line style anymore. What happens is that the line style will appear retained but will actually be modified—its pattern will switch to Solid but the line weight will be the same. This could create undesirable results, so use caution when deleting line styles from your projects or templates.

FIGURE 4.5
Model line weights
vary depending on
the view scale.



To create a new line style, click the New button in the Modify Subcategories button group. Enter a new name in the dialog box that opens, and confirm it by clicking OK. The new style appears in the tree structure on the left, and you can now set the rest of the parameters (Line Weight, Line Color, and Line Pattern) to suit your needs.

Take particular care when modifying the line weights. There can be some confusion when the intended result is changing the weight of an element in a project. This should *not* be done by changing in the Line Weights dialog box, but rather through the Object Styles dialog box. For example, if you wanted the Cut value of a wall to increase from 5 to 7, don't increase the value of 5 in the Line Weights dialog box. You would change this value by selecting 7 as the Cut weight of a wall in the Object Styles dialog box.


Finally, don't delete the range of model line weights based on the various scales. This is really an important feature in Revit. Certain line weights are modified slightly based on the scale of a drawing. For example, a line weight of 1 is very thin and doesn't get any thinner as the scale decreases. But a line weight of 16, which is 1/2' wide at a scale of 1"=1'-0" rightfully decreases as the scale increases (to 0.20). Persistent line weights across all scales will produce illegible drawings!

Line Patterns

A *line pattern* is a repetitive series of line segments, spaces, and points. To create a new line pattern, switch to the Manage tab and choose Settings ➤ Line Patterns. The resulting dialog box

displays a list of existing line patterns in the project. On the right side are four buttons: New, Edit, Delete, and Rename (see Figure 4.6).

FIGURE 4.6
Line patterns are made of dashes, spaces, and dots.



To edit an existing line, click the Edit button. To create a new line pattern, click New. You can then create a line pattern by specifying line and space lengths that form a repeating sequence. To rename a pattern, click Rename. Be careful when naming line patterns: if you give a line pattern a name that already exists in the list, Revit overrides the existing pattern with the new one and overrides all elements that use that line pattern.

A pattern sequence can contain dashes, dots, and spaces. For dashes and spaces, you need to define their length; for points, a value isn't necessary. The construction of a sequence is simple: in the Type column, you select Dash or Dot from the drop-down list, and in the Value column, you provide a length (if it's a dash or space). For each row you add, only the available choices are shown in the drop-down list. Notice that in the first row, the drop-down offers only Dash and Dot as options—this is because Revit does not allow a sequence to begin with a space. Following the same logic, you can't have a dot after a dash or the opposite, because they will merge and the result will look like a longer dash.

Before deleting any line pattern, you must verify that it hasn't been used anywhere in your project. If you fail to do so, you'll lose information, as the lines using the deleted style will be assigned to the Line category. This can only be done manually by checking line patterns used in the Object Styles, Line Styles, and Visibility/Graphic Overrides dialog boxes.

Creating a New Line Pattern

Follow these steps to create a new line pattern:

1. Switch to the Manage tab and choose Settings > Line Patterns.
2. In the Line Pattern dialog box, click New.
3. Give the new line pattern a name.
4. Define the sequence, as shown in Figure 4.7.

- 5. Confirm by clicking OK.
- 6. The resulting line pattern looks like this:




FIGURE 4.7
Make a new pattern using this sample as a guide.



Materials


Defining materials in your project template is something you should not neglect. Materials fundamentally drive the graphic representation of elements. They don't just affect the display of an element in rendered views—a big misconception—they are responsible for representing the chosen material in symbolic patterns for documentation purposes. Materials are also responsible for cleanups, and they merge with one another when elements of the same materials are joined. For example, concrete walls join and appear contiguous with concrete floors when the elements' geometry is joined together. A material also defines how an element's surface looks in shaded views, when cut in plan or section, and when seen in 3D and elevation views. In Figure 4.8, the surface patterns are all derived from the material used in the element.

FIGURE 4.8
Materials define the surface and cut patterns, color, and render material of the elements.



To access the Materials Editor, switch to the Manage tab and choose Materials from the Project Settings panel. You'll see the dialog box shown in Figure 4.9.

FIGURE 4.9
Use the Materials Editor to define the hatch patterns on elements.



The Materials Editor has two components: a list and a tabbed properties interface. On the left is a list of all available Revit materials in the project. Below the list are options to duplicate, rename, and delete materials:

Duplicate Use this button each time you need to create a new material. As with most elements you want to customize in Revit, always duplicate a material before you change any of its properties—if you fail to do so, you may change a material definition already used in the project and risk inadvertently changing and thus losing a lot of work. To create a new material, find an existing material that closely matches what you want to make. Once you click the Duplicate button, you'll be prompted to provide a name for the newly created material.

Rename This works like all other Rename buttons in Revit. Clicking the button lets you rename the material. If you use a name that's not unique, Revit will warn you and prompt for a unique name.

Delete If for some reason you decide to do so, select the material that you wish to delete, and click the Delete button. You'll need to click OK to finalize the deletion. Be sure you don't delete a material that is already being used by elements.

On the right side of the editor are four tabs that contain material properties:

Graphics Defines shading color, surface patterns, and cut patterns.

Render Appearance Defines rendering attributes.

Physical Defines structural properties of a material (used for structural analysis).

Identity Defines schedule values and keynotes.


We'll concentrate on the Graphics and Render Appearance tabs, because those include the graphical properties of materials. The other tabs are used for scheduling and structural analysis and aren't critical to this chapter.

GRAPHICS

Here are the Graphics tab's options:


Shading This allows you to define the color and transparency used for the selected material when a view is set to Shaded or Shaded with Edges display mode (Figure 4.10). Note that the color can be dependent on the associated render appearance. In that case, when the option Use Render Appearance for Shading is checked, the color and transparency are taken from the render appearance, and the color and transparency controls will be disabled.

FIGURE 4.10
Shading properties.



Surface Pattern This allows you select a model pattern that will be displayed on the faces of the elements in elevation, plan, and 3D views. Click the button next to the preview to see a graphical list of available patterns (Figure 4.11). You can control the color of patterns here as well.

FIGURE 4.11
Use the visual pre-view to help choose the appropriate surface pattern.



Cut Pattern The fill pattern that you select here is a drafting pattern, and it will be the pattern displayed when an element is cut through. Some Revit elements can't be cut, as we discussed in Chapter 2, "Revit Fundamentals"; in these cases, this parameter has no effect on the graphic display and the pattern will not show.

RENDER APPEARANCE

Click the Render Appearance tab to view render properties. These properties will become visible only when you render a view and will not affect construction documentation graphics.

It may seem impossible to imagine all the materials you'll need in a project, making building a template seem daunting. Think of the basic materials you're likely to use—woods, brick, concrete, glass, and so on—and build from those. Remember, a template is just a starting point, and you can always expand it. If you end up making a lot of nice materials over the course of a project, use the Transfer Project Standards function to move materials back into your templates.

Fill Patterns (Hatches)

Materials are often represented with simple hatch patterns. For any material used in Revit, you can define a *surface pattern* and a *cut pattern*. For simple parallel hatches and crosshatches, you can use the patterns already supplied in Revit or you can make your own custom hatches.

For more complex patterns, you need to import an external pattern file (.pat). To create, modify, or view an available fill pattern, switch to the Manage tab and choose Settings > Fill Patterns (see Figure 4.12). On the left side of the Fill Patterns dialog box, you can view the names and small graphic previews of the patterns to help you visualize as you select and edit the patterns. Below those are the Pattern Type options, where you choose what type of patterns to create and specify what type of pattern you wish to edit (drafting or model). As with the Line Styles dialog box, the New, Edit, and Delete buttons appear on the right.

There are two types of fill patterns: *model patterns* and *drafting patterns*. Use the model patterns when you want to convey real-world dimensional patterns to represent a material. Use drafting patterns for symbolic representations. For example, a model pattern is used to show a brick pattern in 3D and elevation views, whereas a drafting brick pattern is used to represent the cut pattern in plan and section. Figure 4.13 shows how concrete masonry units (CMUs) are represented with a running bond pattern (model) as well as a crosshatch (drafting).

Another way of thinking about this is that model patterns are “glued” to a surface, while drafting patterns are not. Try this: rotate a wall with a model pattern and you'll notice that the pattern rotates with respect to the wall. Now rotate a wall with a drafting pattern (like Concrete or Diagonal Crosshatch). The drafting pattern is not “fixed” to the wall and rotates with respect to the screen.

FIGURE 4.12

Fill patterns are defined separately for drafting and model representations.





FIGURE 4.13

The CMU wall type has both a drafting pattern (cut) and a model pattern (surface) defined.



Model and drafting patterns have specific behaviors. In our example, we have a CMU wall with blocks that measure 16" × 8" (40mm × 20mm), regardless of the view scale. With a drafting pattern, the opposite is true: the pattern adjusts with the view scale so the pattern looks identical in all scales.


To create a new pattern, first choose either Model or Drafting, and then click the New button. A generic pattern appears in the New Pattern dialog box. You can then design your pattern and assign some behaviors.

The option Orientation in Host Layers is particularly useful when you're making drafting patterns. This allows you to specify how a pattern orients itself relative to host elements such as walls, floors, roofs, and ceilings when they're represented as cut. (Note that the option isn't available for model pattern types.)

The three options shown in Figure 4.14 are described here:

FIGURE 4.14

From left to right:
pattern orientation
Orient to View,
Keep Readable,
and Align with
Element.



Orient to View When this orientation is applied, the patterns used in the project all have the same orientation and the same origin. They're always perfectly aligned with the origin of the view.


Keep Readable This orientation is best understood when compared with the Keep Readable attribute of text—it stays readable (will not appear upside down) regardless of its orientation.

Align with Element This orientation ensures that the pattern orientation depends on the orientation of the host element. Patterns essentially run parallel with the element.

You can choose to make either simple or custom patterns with this dialog box, using the radio button options. Figure 4.15 shows the result of each option.

FIGURE 4.15

From left to right: simple fill pattern, simple fill pattern with the crosshatch option selected, and a custom fill pattern.



Simple These patterns are generated with parallel or crosshatch lines that can have different angles and spacing. With both the crosshatch and parallel options, you can specify only one angle for the entire pattern. Using crosshatch, you can set two spacing values. The exercise in the sidebar “Creating a Simple Fill Pattern” demonstrates creating a fill pattern.

Custom To create a more complex custom pattern, you have to import a pattern (.pat) file from an external source. This is often necessary due to Revit’s current limitation in creating natively complex patterns. Your office may have a set of established patterns they’ve been using for years, and the Custom option allows you to import and reuse them without having to make them again from scratch. Custom patterns let you import a PAT file from anywhere on your hard drive or on a network and use it as a base pattern for a new fill pattern in Revit. The next section shows some best practices for importing a PAT file.

CREATING A CUSTOM PATTERN USING A PATTERN FILE

Custom patterns require an external file that contains the definition of the pattern. The file extension of that pattern should be .pat, which is what you’ll make in this section by editing an existing AutoCAD PAT file. An advantage of specifying patterns in the template file is that the PAT file won’t need to be installed on each computer where Revit is installed; Revit stores each pattern internally in each template or project.

Before modifying PAT files, always make a copy of the original PAT file you intend to use as a base; you don’t want to risk messing up other files that might already be using that original PAT file. PAT files can be edited with Notepad, but any text-editing application will also do. For this exercise, you’ll choose the AutoCAD pattern called Grass, which you can find in acadiso.pat in metric units) or acad.pat (Imperial units) located in the Chapter 4 folder on the book’s companion web page (www.sybex.com/go/masteringrevit2010).

IMPORTING A CUSTOM PATTERN

Follow these steps to make a custom fill pattern by importing an existing pattern definition:

1. Using Notepad, open the file `acadiso.pat` or `acad.pat`.
2. Highlight the lines that define the pattern, and select them:


```
45, 6.35, 0, 4.49013, 4.49013, 1.5875, -5.80526, 1.5875, -8.98026
*GRASS, turfed surface
90, 0, 0, 17.9605, 17.9605, 4.7625, -31.1585
45, 0, 0, 0, 25.4, 4.7625, -20.6375
135, 0, 0, 0, 25.4, 4.7625, -20.6375
*GRATE, grid
0, 0, 0, 0, 0.79375
```
3. Choose **Edit** ➤ **Copy**.
4. Open a new text file, and paste the selection. (Note that you can also open the PAT file located in `C:\Program Files\Revit Architecture 2010\Data`, in which all Revit patterns are already saved. In that case, you can paste the selected text in that file.)
5. This is the important part: in the new text file where you pasted the selected text, add the two lines shown highlighted here:

```
;%UNITS=MM
*GRASS, turfed surface
;%TYPE=DRAFTING
90, 0, 0, 17.9605, 17.9605, 4.7625, -31.1585
45, 0, 0, 0, 25.4, 4.7625, -20.6375
135, 0, 0, 0, 25.4, 4.7625, -20.6375
```

The first line that you write before the pattern text, `;%UNITS=MM`, can appear only once in the text file. It defines the value for the units used in the pattern. In the example, the units are millimeters (MM); if you wanted to work in imperial units, it would be `;%UNITS=INCH`. (If you followed our second option to not create a new note for each file but collect them in one file, then this line already exists and you don't need to add it.)


The second statement, `;%TYPE=DRAFTING`, helps define whether you're creating a drafting or model pattern. In this example, the pattern is the drafting type.

6. Save your text file with a `.pat` file extension.
7. From the **Manage** tab, choose **Settings** ➤ **Fill Patterns**.
8. In the **Fill Patterns** dialog box, verify that the **Drafting** option is selected, and click **New**.
9. In the **New Pattern** dialog box, select the **Custom** option. The lower part of the dialog box offers new options.
10. Click **Import**.

11. Navigate to the place on your hard drive or network where you saved the PAT file, and click Open.
12. In the list that appears to the right of this button, you can see the name of the pattern you created: Grass. (If you have a PAT file with many patterns defined, you see all the other drafting patterns available in that list.) The name of the pattern automatically becomes the name of your fill pattern, but you can change that if you like. See Figure 4.16.

FIGURE 4.16

The New Pattern dialog box displays the imported PAT file in the Custom group.



13. If necessary, you can adjust the scales of the imported pattern. The Preview window displays the graphic of the pattern, always in 1:1 scale. This informs you if you need to scale the pattern up or down. You'll know that you need to scale the pattern if the preview appears as a solid black box—that means the pattern is too dense.
14. If you're happy with the result, confirm by clicking OK.

CREATING A SIMPLE FILL PATTERN

Often, the default templates don't have all the patterns you need. Following these steps, you can make a new simple fill pattern:

1. From the Manage tab choose Settings ➤ Fill Patterns.
2. In the Fill Patterns dialog box, choose to make either a model or a drafting pattern, and click New.

3. In the New Pattern dialog box, enter a new name for the fill pattern.



4. If Drafting is selected, also choose an option from the Orientation in Host Layers drop-down.
5. In the Simple group, enter a line angle. Choosing to create a crosshatched pattern lets you define the line spacing in both directions of the crosshatch. Note that a crosshatch always makes the second set of parallel lines perpendicular to the first.
6. The Preview window shows the pattern. Click OK to commit the pattern to the model.

IMPORTING PAT FILES

When you import a new pattern, the type of pattern needs to be the same as the new type of pattern you're making. In other words, if you're making a new model pattern, you can't import a drafting pattern. If you try to do so, you'll see a warning message like the one shown in Figure 4.17.

FIGURE 4.17

If you try to assign a drafting .pat pattern to a Revit model pattern, you'll see a warning.



Dimension Styles

Dimensions are system families used to dimension the model. Dimensions can be linear, angular, or radial; each of these has a set of type parameters that control their graphic characteristics. In Revit you have dimension styles in which predefined type parameters are set. When placing dimensions in the project, you can choose between aligned, linear, angular, radial, and arc length dimensions. Depending on the choice you make, a corresponding dimension style will be chosen for you:

- ◆ Aligned, linear, and arc length dimensions are associated with the system family Linear Dimension Style.
- ◆ The angular dimensions are associated with the system family Angular Dimension Style.
- ◆ The radial dimensions are associated with the system family Radial Dimension Style.

PROPERTIES OF DIMENSION STYLES

Dimension styles can vary from a rigid technical appearance to more creative and sketchy types. Figure 4.18 shows three variations of a linear dimension style, each using a different type of tick mark. A wide range of graphic controls is at your disposal. Most conventions can be achieved using the options located in the type properties of your dimension types. Options include tick marks, length of dimension lines, extension, text type, spacing of text, spacing between the text and the dim line, and so on. Figure 4.19 shows the type properties of a linear dimension.

FIGURE 4.18
Dimension string types can have various tick marks assigned.





FIGURE 4.19
Type properties are used to define different graphic styles for dimensions.



Let’s look at the various ways you can customize the appearance of dimensions:

Dimension String Type This parameter allows for control of how a string of multiple dimensions will appear. It has three options: Continuous, Baseline, and Ordinate. The continuous type is typical of architectural drawings; the others are seen in structural drawings. Figure 4.18 shows the difference between the appearances of the three string types.

Tick Mark This option allows you to select the type of graphic called a *tick mark* that marks the crossing between the dimension line and the extension lines. You can select the type of the tick mark but not its size. Adjusting the size isn’t possible directly from the Dimension

Type dialog box. To edit a tick mark or make a new one, from the Manage tab choose Settings ➤ Arrow Heads. You'll see the Type Properties dialog box shown in Figure 4.20.

FIGURE 4.20
Type properties of
a tick mark.




Line Weight This sets the thickness of the line that represents the dimension line and can be any value from 1 to 16. These numbers correspond to the weights defined in the Line Weights dialog box (Manage tab ➤ Settings ➤ Line Weights ➤ Annotation Line Weights).

Tick Mark Line Weight You can set the thickness of the tick mark to any value from 1 to 16.

Dimension Line Extension This setting allows you to define the length of the extension of the dimension line beyond the tick mark. In this example, the line extension has been highlighted in bold:



Flipped Dimension Line Extension This setting is grayed out unless Tick Mark is set to Arrow Head. It inverts the direction of the arrows when the space between them is too small to accommodate both arrows in the dimension space. This parameter controls the length of the extension of the dimension line after the arrow symbol.



Witness Line Control This setting controls the position of the witness lines with respect to the element that is dimensioned. You can choose one of the following options: Gap to Element or Fixed to Dimension Line.


Witness Line Length This parameter defines the length of the witness line. It's active only when Witness Line Control is set to Fixed to Dimension Line.

Witness Line Gap to Element This parameter sets the distance between the element that is dimensioned and the witness line. It's active only when Witness Line Control is set to Gap to Element.


Witness Line Extension This parameter controls the length of the witness line above the dimension line.




Centerline Symbol Some local standards require a specific graphic representation of the dimensions that reference to the center axis of an element. By loading custom annotation symbol families into your project, you'll be able to choose which one is best suited to your needs.



Centerline Pattern Using this parameter, you can define a line style when you're dimensioning to the center axis of an element. Again, this is to accommodate various local standards that require the center of elements to be graphically different from other dimensions.



Centerline Tick Mark This is the third graphical way to make the axes or centers of elements easily recognizable. This parameter allows for a different graphic to be used as a tick mark when dimensioning centerlines of elements.




Interior Tick Mark If more than one set of arrows don't fit in the space in a dimension chain, you can define smaller or simpler tick marks for the interior portions of the dimension segment.




Color This parameter allows you to define any color for a dimension style (text and lines are both affected).

Dimension Line Snap Distance Before you click the second line in a dimension chain, a dimension help line in a dashed green style appears, to help with positioning. The snap distance defines the automatic offset between two dimension lines. When you place a second dimension chain, the second one snaps to this designated offset.



Text Text height, offset from the dimension line, reading convention, text font, background (opaque or transparent), and unit format can all be set, allowing for a high level of customization when you create your own style.

Show Opening Height When selected, this parameter displays the opening height of the element that is dimensioned, as shown here:



You can customize and rename the existing types and also create your own. To create your own type, you need to select an existing type, duplicate it, give it a name, and then edit the parameters:

Create a new type In the Type Properties dialog box, click Duplicate, give the new type a name, and click OK.

Rename a type In the Type Properties dialog box, select a type from the Type list, click Rename, give the type a new name, and click OK.

Delete a type To delete a type, switch to the Manage tab, and from the Project Settings panel, choose Purge Unused. In the Purge Unused Elements dialog box, select the dimension types you wish to delete, and click OK.

Text

Text is used to add notes to your drawings and can be customized to suit your needs. By default, Revit provides a couple of styles for you—feel free to edit these and add more as you see fit. Standard graphical control over size, font, color, and style are provided as well as the ability to add leaders to text.

Text is another form of system family and offers a range of graphic options for customization. Realistically, Revit isn't a full-blown text-editing application and it would benefit from many improvements when it comes to text editing; so you won't see the same level of font and paragraph style control that you might find in regular text editors. However, a number of common parameters let you change the appearance of text.

PROPERTIES OF TEXT

Some text parameters are exposed directly in the Place Text tab appearing after selection of the Text tool in the Annotate tab or when text is selected for editing.




However, most properties are managed through the Type Properties dialog box accessible by clicking the Element Properties button in the same tab. The following text properties can be accessed by selecting text and going to the Type Properties dialog box:

Color Text can be assigned any color using a standard color picker.

Line Weight Any text note can be accompanied by leader lines—this parameter controls the weight of the leader lines.

Background The background on which text is written can be opaque or transparent. An opaque background is solid white and obscures other elements beneath it; a transparent background lets elements show through the text area. The usage of this parameter depends on the style of graphics you want to show. In busy drawings, setting the background opaque can help keep text readable. Figure 4.21 shows the effects of this parameter.

FIGURE 4.21
Text with (left)
opaque and (right)
transparent
backgrounds



Leader Arrowhead This parameter defines the leader arrowhead used in the leader line. You can't define the size of the leader arrowhead here. If you wish to create another size of leader arrowhead, go to the Manage tab, and from the Project Settings panel choose Settings > Arrowheads.

Keep Readable This parameter accommodates different reading conventions for the text with respect to the screen and sheet. The Keep Readable parameter is an Instance parameter.

Text Font This parameter controls the font that will be used for the text.

Text Size This parameter controls the height of the text in dimensional values. Revit doesn't support the use of standard point sizes; you type in values in inches (mm).

Tab Size This parameter controls the length of text when a tabulator is included in the text string.

Bold This parameter makes the text bold.

Italic This parameter makes the text italic.

Underline This parameter underlines the text.

Width Factor This parameter lets you control the length of text without affecting its height. The default value is 1. If you want the text to be narrower, change this value to less than 1. If you need the text to be wider, the value must be greater than 1. In the example shown here, on the left the width factor is 0.5, in the center it's 1.0, and on the right it's 2.0.

Revit Revit Revit

You can customize and rename the existing types and also create your own. To create your own type, you need to select an existing type, duplicate it, give it a name, and then edit the parameters to suit your requirements:

Create a new type In the Type Properties dialog box, click Duplicate, give the new type a name, and click OK.


Rename a type In the Type Properties dialog box, select a type from the Type list, click Rename, give the type a new name, and click OK.

Delete a type To delete a type, switch to the Manage tab and choose Purge Unused. In the Purge Unused Elements dialog box, select the dimension types that you wish to delete, and click OK.

Creating Custom Annotation Tags

Many kinds of annotations are used in design and construction documents. These range from door and window tags, to wall and room tags, to view tags for sections and elevations. You can see the full list of annotation categories in the Object Styles dialog box, under the Annotations Objects tab (Figure 4.22). Using the Family Editor, you can customize all of these tags (with the exception of elevation tags) to meet your graphic conventions. In this section, we'll walk through the creation of some common tags and show you how to make your own.

FIGURE 4.22
The Annotation
Objects tab of
the Object Styles
dialog box.




ARCHIVING AND MANAGING YOUR CUSTOM FAMILIES

Many new users of Revit are unsure where to store custom-created families. It isn't advisable to save them in the system folders created during the installation of Revit, because you may lose track of them or inadvertently delete them when you reinstall the software. Reinstalling Revit erases just about any folder and its entire contents. It is thus advisable to keep your personally created content somewhere else, under a separate independent folder; if you are not a single user, store that folder on a shared network drive.

You should also keep your templates up to date as you add more content; that way, you need only maintain a few template files rather than dozens of separate family files. It's even better if you can establish this as a role within the office so no one is making graphical changes to your templates.

View Tags

Section, callout, and elevation tags are graphic indicators that reference (link to) other views in your project. The graphics for these elements can be customized to meet most scenarios. To create a custom section tag, for example, you have to first create a custom section tag family. To access the view tags, switch to the Manage tab and choose Settings. From here, you can customize the Callout, Elevation, and Section tag view tags through their Type Properties dialog boxes. By default, there is a predefined view tag for each view type. The graphics can vary depending on the language version of Revit you have installed on your machine. The tags shown here are displayed and available by default in the USA English version:



You can use the existing tag, rename it or duplicate it, and amend its properties to create your own custom tag.

The creation of custom view tags slightly differs depending on which view tag you're working with. Some require you to load a family file (.rfa) that can be fully customized with the Family Editor; others don't have corresponding family files and allow only limited customization directly within the project.

SECTION VIEW TAGS

Before selecting a section tag, make sure you load multiple section tags from the family library so you'll have some options to choose from. This can be useful when you decide to use different section tags for building sections and wall sections as one example and maybe even different tags for presentation plans than for construction documents. To implement these options in your project, you need to create each set of tags and load them into the project environment so they're available to select from the tag's Type Properties. All the section tags are defined in the Manage tab, Project Settings panel, under Settings ➤ Section Tags. In the Type Properties dialog box, you will find the following parameters:

Section Head With this parameter, you can select different symbols for the section head. The drop-down list contains all loaded section view tag families (RFA files). Note that you can create your own fully customized section head using the Family Editor. Once selected from the list, the section head family appears at the beginning of the section line.


Section Tail In some countries, a section line is described with the same symbol at the beginning and the end; in others, a section head appears on only one end of a section line, and at the other end is a section tail (a simplified graphic). This parameter lets you select the tail graphic. Like the section head, this symbol can be fully customized in the Family Editor and loaded as a family (RFA file). Once selected from the list, the section head family appears at the beginning of the section line.

Broken Section Display Style It's usual practice when documenting a building to make *nonlinear sections*—sections that change direction and cut through the more important aspects of the design. With the section line selected, use the Split Segment tool from the Section panel of the Modify Views tab to split a section in many segments. To split a section line with gaps, click on the break icon located on the section line (see Figure 4.23).



FIGURE 4.23

Click the “gaps in segments” icon in the middle of the section line to split the line.



Creating a Custom Section Tag

To create your own section tag, you first need to select the tag family to which your new tag will belong. You have two options:

- ◆ The family already exists in your library, in which case all you need to do is load it into the template.
- ◆ The RFAs from the library don't correspond to your needs, and you wish to create a custom section tag. In this case, you first have to create a section tag in the Family Editor and then load it in the template.


This section's examples show how to create a custom tag family that you'll then use for your custom section tag.

Static Text and Parametric Labels Creating annotation families in the Family Editor is by no means difficult, but you must understand the principle of using parametric labels and text:

Text In the Family Editor, placing text in an annotation or title block means you're defining text that will always be the same and is unchangeable when that annotation is placed in the project environment. Figure 4.24 shows the words *AREA* and *VOLUME* as text. Regardless of where this room tag is placed, the text will always say *AREA* and *VOLUME*. Section tags work the same way: if you add static text, that text appears exactly the same for all section marks. This isn't typically used for sections, because each section is a reference to a unique view, and you want that information to be dynamic and parametric. That's where label functionality comes into play.

FIGURE 4.24

A custom room tag showing room name, number, area, and volume.



Labels A label offers textual information, but unlike static text, it's a live reference to a parameter value of an element in the project. It pulls information about a parameter directly from the BIM model. So, if you add an Area label, it will pull the value of the area of the room; if you add a Sheet Number label in a Section Head family in the Family Editor environment and then use that section head in a project, the label will automatically display the actual sheet number on which this section is placed in the project. If you move the section from one sheet to another, the label will automatically report the new sheet number. In Figure 4.24, *Unit 4* is a label of the room name; the number *201* is a label of the room number. The label behaves as dynamic text and is always fully coordinated with the value of the parameter it represents. Like text, labels have graphical properties such as height, color, and font.


Creating a Custom Section Tag Family

An exercise will clarify what we just discussed. Imagine you would like to create a section tag that looks like the one shown in Figure 4.25. You need to first create a section tag family using

the Family Editor and then load it into your template before you can create the tag in the project. Follow these steps:

1. From the Application Menu choose New > Family > Annotations.
2. In the Open dialog box, select the family called Section Head.rft or M_Section Head.rft, and click Open.
3. The Family Editor environment automatically opens, and the drawing area shows a view in which three green reference planes (two vertical and one horizontal) have already been drawn. Do *not* change the position of either the horizontal reference plane or the vertical reference on the right. In some templates, this is indicated with help text in red (which you should later remove).

FIGURE 4.25
Custom section tag.



The intersection of horizontal and right reference planes defines the connection location with the section line. This means your annotation will be located in between the two intersection points.


A proposed geometric shape is drawn for the annotation: a circle (two arcs) and a horizontal line. You're free to delete this default geometry and create your own tag shape. The default shape is there to help you visually understand where to begin drawing your new tag geometry.

4. Select the arcs that create the circle (use the Ctrl key for faster selection), and delete them.
5. From the Annotate panel on the Create Tab, click the Label button. Position your cursor between the two vertical reference planes and below the horizontal plane, and click to position the start of the label. The cursor changes as shown here:






- 6. In the Edit Label dialog box, select Sheet Number. Click the Add Parameter(s) to Label button. In the Sample Value column, you can enter a value; the default is A101.



This isn't an actual value that will be displayed—it's a sample value that is visible only in the Family Editor. The text is a placeholder for an eventual real parameter value and is only here to help as a reference with layout. Once you load the family into a project template or project, this value will be replaced with the actual parameter value pulled from the database of your model. The default value is logical, so confirm by clicking OK. The label is placed and displays blue grips when selected. These let you change the length of the label text field. The length is important, because any value that is added (in a project) that is longer than the length of this box will begin to wrap and could mess up your graphics.

- 7. Following the same principle, place the label **Detail Number** above the horizontal reference but still between the vertical references.




- 8. You can reposition a label by selecting it and using the Move button to move it around. For more precise positioning, use the arrow keys on your keyboard to nudge elements in small increments. You can also help yourself by zooming in for a better view. (Note that zooming in makes the increment for the nudge tools finer.)




- 9. From the Detail panel of the Create tab, click the Filled Region button. You'll be put into Sketch mode. Using the Line tool, draw the shape shown here. In the Region properties,

check that Color is set to Black and Cut Fill Pattern to Solid Fill. Make sure the lines form a closed loop (no gaps or overlapping lines).



10. Click Finish Region from the Create Filled Region Boundary tab. If you did everything correctly, you should have a custom-designed family, as shown here:



Save the tag you just created somewhere on your hard drive or network, and you're ready to use it in the template or a project. To load it into your project, click the Load into Project button located in the Family Editor panel of the Modify Filled Region tab. Choose the project you want to use the symbol in, and click OK.

In the next exercise, you'll assign this tag to a section mark in the context of a project.

Creating a Section Tag with a Custom Head/Tail Graphic

To create a section type that utilizes the section head family you created previously, you need to load the created section head in the template file:


1. Switch to the Insert tab and from the Load from Library panel, choose Load Family.
2. In the Load Family dialog box, find the section head you created previously, select it, and click Open.
3. Switch to the Manage tab and select Settings. From the Settings menu, click Section Tags.
4. In the Type Properties dialog box, click Duplicate.
5. In the Name dialog box (Figure 4.26), name the new tag **Filled Arrow** and click OK.

FIGURE 4.26
Naming the new
section view tag.



- 6. In the section head's Type Properties dialog box, click the drop-down menu and select your custom head family. For Section Tail, click <none>. This means the other end of the section line will not use a symbol (Figure 4.27). Click OK.

FIGURE 4.27
You just created a new section tag that you now wish to associate with a section type.



- 7. Switch to the View tab and from the Create panel, select Section.
- 8. From the Section tab, select Element Properties.
- 9. In the Instance Properties dialog box, click Edit, and from the Type Properties dialog box, select Duplicate.
- 10. Name the new type **Filled Arrow - No Section Tail**, and click OK (Figure 4.28).

FIGURE 4.28
Create a new section type with a unique name.



- 11. Under Section Tag, click the drop-down menu, select the tag you created, and click OK.
You can now place a section in your drawing area and see the results shown in Figure 4.29.

FIGURE 4.29
Draw one of your new sections—it should look like this.



Note that each time you create a new section type, Revit creates a new folder for it in the Project Browser. Our example uses two types of sections: building sections and detail sections. When you place one of each in a project environment, they're each placed in a new folder named by section type.

As you'll see next, the same principles apply when you make callout views.

CALLOUTS

In order to have a variety of different callout tags in the project environment, you must load some customized callout tags into the project. To do that, switch to the Insert tab, and from the Load from Library panel, select Load Family. Under Annotations, find the available callout tags. The properties of callout tags offer a few options:

Callout Heads This parameter defines the family and the callout type that will be used. The drop-down list contains all loaded callout head families (RFA files); you can also use no family (None). Using the Family Editor, you can create callout head families just as you can for section heads and tails.

Corner Radius A callout in Revit usually has a rectangular shape with filleted edges. This parameter lets you define the radius of those arcs on the corners of the callout tag.

Creating a Custom Callout Head

Figure 4.30 shows on the left the callout tag family you'll create in this exercise. Follow these steps:

1. From the Application Menu choose New ➤ Family ➤ Annotations.
2. In the Select Template dialog box, select the family template called Callout head.rft or M_Callout Head.rft, and click Open.

FIGURE 4.30


(left) Custom callout annotation;
(right) custom callout annotation associated with callout boundary.




3. The Family Editor opens, and a view with two crossing reference planes appears. Again, if you want to avoid problems later, don't move either of these two planes. In red, you'll see important guideline text: always read it before deleting it. This text informs you that the tag will be positioned in the center of the crossing of the two reference planes and that the callout leader will be trimmed (adjusted) to match the width of the drawn elements. Select the help text and delete it.
4. From the Annotate panel of the Create tab, click the Label button. Click the vertical reference plane and above the horizontal one to position the label.




5. In the Edit Label dialog box that opens, select Detail Number; in the Value zone, you can place a value as explained in step 6 of the exercise in the section “Creating a Custom Section Tag Family.”



6. Following the same principle, add another label—this time using Sheet Number—and position it below the horizontal reference plane.



7. Switch to the Create tab, and from the Detail panel, select Filled Region. Revit goes into Sketch mode. Using the Line tool, draw the shape that represents the graphic of the call-out tag you wish to create. Make sure the filled region uses a solid fill black pattern by editing its type properties.



8. Click Finish Region.
9. You can also adjust the text to be a different font or font size if desired. The annotation in the Family Editor should look like this:



10. Save your callout tag, and load it into your project.
11. In the project, switch to the Manage tab, and choose Settings ➤ Callouts. Make a new type, or edit an existing type by choosing the family you just loaded in. You should do this in order to take advantage of your custom tag. Simply loading it into your project won't automatically assign it to a callout.

CHANGING THE GRAPHIC APPEARANCE OF THE FILLED REGION IN A CALLOUT TAG

You may want to use colors other than black for the filled region, and you may want to make it transparent or opaque. This will result in a different graphic presentation when you place the tag in the project and a different graphical presentation when it's printed, because most reprographics companies don't print full-sized sheets in color.

Callout Views—Type Properties

The following are the type properties of a callout view:

Callout Tag Lists all available callout tags.

Reference Label The default label for referenced callouts.

Creating Callout Tags

You've already created your Callout Head family. Now you'll load it in the template file and associate it with a callout tag:

1. Switch to the Insert tab, and from the Load from Library panel, select Load Family.
2. In the Load Family dialog box, find the callout head you created previously, select it, and click Open.
3. Switch to the Manage tab, select Settings, and from Settings menu, choose Callout Tags.
4. In the Type Properties dialog box, click Duplicate.
5. In the Name dialog box, name the new tag **Filled Rectangle**, and click OK (Figure 4.31).


FIGURE 4.31
Give the callout tag type a unique name.



6. Next to Callout Head, click the drop-down list and select your callout family. Next to Corner Radius, set the angle that will be applied to the corners of the callout boundary line (Figure 4.32).

FIGURE 4.32


Choose the callout head, and set the radius for the callout corners.



7. Click OK. You just created a new callout tag that you can now associate with a callout type.
8. Switch to the View tab and from the Create panel, select Callout.
9. From the Callout tab, click the Element Properties button.
10. In the Instance Properties dialog box, click Edit and then from the Type Properties dialog box select Duplicate.
11. Give the new type a name (**Filled Rectangle - Corner Radius 3.5mm**), and click OK (Figure 4.33).
12. Under the Section Tag parameter, click the drop-down list and select the callout tag you created.
13. Click OK.

FIGURE 4.33


Create a new callout view type.



You can now place a callout in your drawing area and see the results shown in Figure 4.34.

FIGURE 4.34

The final appearance of the new callout type.




ELEVATION TAGS

Unlike all other tags in Revit, elevation tags don't reference a family file and are customizable only to a limited extent. You can't create custom elevation tags—the only thing Revit lets you do

is choose between a round or square-shaped elevation tag and make a few small modifications to those shapes. However, you can create different elevation tags for exterior and interior elevations. Figure 4.35 shows the properties for elevation tags.

FIGURE 4.35
Type Properties
dialog box of an
elevation tag.




Elevation Tag Properties

The following parameters are available in the Type Properties dialog box for elevation tags:


Shape This provides the two possible shapes for elevation tags: Circle and Square.

Text Position Each elevation tag allows text to show the number of the view when placed on a sheet. This value is empty until that elevation view is placed on a sheet. You can also decide to add the name of the view to the elevation tag. This can make the tag busy and illegible, so consider your options carefully. Figure 4.36 shows the options from left to right: Outside Left, Outside Center, Outside Right, and at the end, Inside. In the last case, it's preferable for better legibility to select an empty arrowhead.

FIGURE 4.36
Elevation varia-
tions, left to right:
Outside Left, Out-
side Center, Out-
side Right, Inside.



Arrow Angle The arrow indicates the direction of the view, and this parameter controls the angle of the arrow.



Filled This option controls whether or not the arrow associated with the tag is filled. Set this option depending on your graphical requirements.




Show View Name This parameter allows you to add the information about the name of the view in the elevation tag.

View Name Position If you've decided to add the view name in the elevation tag, this parameter allows you to control the position of the name.

Reference Label Position This parameter controls the position of the reference label with respect to the tag. Figure 4.37 shows the different positions, from left to right: Outside Left, Outside Center, Outside Right.

FIGURE 4.37
The name of the elevation can appear on each arrow.



Line Weight This parameter defines the weight of the lines used for the entire tag. The Line Weight value can be any number from 1 to 16.

Color This parameter defines the color of the lines.

Line Pattern This parameter defines the line pattern for lines used in the tag.

Text Font This parameter defines the font used in the tag.

Text Size This parameter defines the height of the text used in the tag.

Width This parameter defines the size of the shape. If you choose Circle, this value is the diameter; if the tag is square, this is the size of the square.

Elevation View Type Properties

The following parameters are available as elevation type properties:

Elevation Tag This parameter lists all available elevation tags in the project. You create elevation tags in the Settings > View Tags > Elevation Tags dialog box.

Callout Tag This parameter lists all available callout tags in the project. You create callout tags in the Settings > View Tags > Callout Tags dialog box.

Reference Label This parameter defines the default label for referenced elevations.



Real World Scenario

CUSTOM ELEVATION TAGS WORKAROUND

As we mentioned previously, elevation tags are the only tags in Revit for which you can't create your own graphics using the Family Editor. For example, many firms use the same symbol for sections as they do for exterior building elevations. A common workaround to this problem is to use sections in lieu of elevations to get the right graphic appearance.

This workaround works well and is simple. The only downside is that your building elevations will appear under the Section tree in the Project Browser.

Creating an Elevation Tag

Unlike section and callout tags, to create a new elevation tag you can't load an elevation family, because there are none. You can create your custom elevation tag only by duplicating an existing one and changing its properties. You will be able to change the appearance of the elevation tag to a degree and then associate it with a new elevation view type. Follow these steps:

1. Switch to the View tab, and from the Create panel, select Elevation.
2. Click the Element Properties button.
3. In the Instance Properties dialog box click Edit, and then from the Type Properties dialog box click Duplicate.
4. Give the new type a name (**Elevation Tag Presentation**), and click OK.



5. Under the Elevation Tag parameter, click the drop-down list and select the elevation tag you created.
6. Click OK.

You can now place an elevation in your drawing area and see the results, as shown here:



Assigning a Family to a View Tag

We discussed how to create custom annotation families that are used to create custom tags. To put these annotations to use, you need to assign them to a view tag type. For sections and callouts, you use a section head family and a callout family. To assign an annotation to a section or callout view tag, switch to the Manage tab, and choose Settings > Section Tags. In the resulting dialog box, you can choose what symbols to use for the section head and tail. The same procedure is used for callouts.

LEVELS

Levels in Revit usually indicate stories or represent levels used for referencing heights of certain elements. Graphically they are represented with a line and a level symbol that can be placed at one or both ends of the level line. Creating level types allows you to define the graphical characteristics of the level line, the level family symbol, and Z-coordinate system used by the level tags. All these parameters are stored in the level type properties; you can create as many as you please.

Level Properties

The following properties are available for levels:

Elevation Base You'll find two options for Elevation Base: Project and Shared. When you select Project, the project's coordinate system is used. When you select Shared, the coordinates correspond to the shared coordinates.

Line Weight This parameter allows you to set the line weight of the level line. Line Weight can be any number from 1 to 16. These numbers correspond to virtual pens with various thicknesses, which can depend on different scales applied to a view. To review the current settings, from the Manage tab, choose Settings > Line Weights > Annotation Line Weights.

Color This parameter defines the color of the level line.

Line Pattern This parameter defines the pattern of the line used for the level line.

Symbol This parameter provides a list of all available level symbols that can be placed at the ends of the level lines. This list shows all level head family files currently loaded into your project. Just as with other tag families, you can create custom level tags and load them in your template. To create a custom level tag family, you need to use the correct family template: Level Head.rft or M_Level Head.rft.

For the level tags shown in Figure 4.38, we created a custom level tag family and selected it in the custom level tag.

FIGURE 4.38
Level tags can be fully customized.



Symbol at End 1 Default and Symbol at End 2 Default These options allow you to define whether to place the level head symbol at both sides of the level line (in which case this and

the next option should be selected) or just one of them. End 1 is the start point when you draw the level line; End 2 is the end point.

GRIDS

The principle of customizing and creating grid types is similar to that of levels. The one parameter that grids don't have is Elevation Base. You can fully customize the appearance of a grid line, design your own symbol family, and define these in the Type properties of grids. For custom symbols, there is a Grid Head.rft or M_Grid_head.rft family template to use when you need to create your own.

Customizing Element Tags


During the construction documentation phase of a project, architects need to annotate various building components with symbolized descriptions (tags) in order to give additional information about the elements to be built. In the majority of cases, Revit allows automatic placement of the tags during the placement of components. If you don't want to fill your drawings with annotations early in the process (and to be honest, that might not even be possible, as in early design stages you might not be sure exactly which types you will be using), you can choose to not tag elements during placement. You can add the tags later, in a manual or automated way (see "Tag All Not Tagged" in Chapter 19, "Annotations"). The tags are annotation families, meaning that they are created in the Family Editor, loaded into a project, and then used wherever you need them. You can customize the graphics for all tags to meet your specific requirements.

It's advisable to load all tag families that you intend to use in your project or office template. That way, you can guarantee coherence and consistency in the way you document your project across the project team or office.

You can load the various tags in the template using several tactics:

- ◆ Switch to the Insert tab, and from the Load Library panel, select Load Family.
- ◆ Using Windows Explorer, select .rfa tag families and drag and drop them to place them in the Revit project environment. (You'll need to have the template file open.) When you try to load more than one family at the same time, Revit prompts you either to open each of those files in an independent window (so you can modify them) or to load them all in the current project. Choose the second option.
- ◆ Use the Loaded Tags tool available in the Annotate tab, when you expand the Tag panel (Figure 4.39). The advantage of this method is that you have a preview of all loaded and preset tags that will be used throughout the project.

FIGURE 4.39
Tags dialog box.




Certain tags are indispensable in a project template. These include door tags, window tags, room tags, revision tags, material tags, keynotes, and area tags. Out of the box, Revit offers at least one of each of these tags, but you'll probably want to create your own in the Family Editor and load them into your template.

CREATING A CUSTOM DOOR TAG

As an example of creating custom tags for a basic element, the following steps show you how to create the custom door tag shown in Figure 4.40:

FIGURE 4.40
The custom door tag you'll create in this exercise.




- 1. From the Application Menu choose New > Family > Annotations.
- 2. In the Select Template File dialog box, select the family template called Door Tag.rft or M_Door Tag.rft, and click Open.

The Family Editor opens in a view with two crossing reference planes. To avoid problems later, don't move the two reference planes. The intersection point is the center point of the tag.

- 3. From the Annotate panel of the Create tab, select Label. Click the intersection of the two planes to position the label.



- 4. In the Edit Label dialog box that opens, select Mark and click the Add Parameter(s) to Label button. In the Sample Value column, you can enter a value that will be a symbolic value visible only in the Family Editor and that will be replaced by the number of the door to which this tag is associated. In this case, accept the proposed value and click OK.




Everything you learned about repositioning and changing the length of the section tag label in the exercise in the section “Creating a Custom Section Tag Family” applies here as well.

5. Click to select the label you just placed. From the Modify Label tab, click the Element Properties button.
6. In the Instance Properties dialog box, click Edit.
7. In the Type Properties dialog box, select the text color, set the background to Transparent, and select a font style and size consistent with your office standards.

Parameter	Value
Graphics	
Color	RGB:000-128-255
Line Weight	1
Background	Transparent
Text	
Text Font	Metrial
Text Size	3.5000 mm
Tab Size	12.7000 mm
Fixed	☒
Italic	☐
Underline	☐
Width Factor	1.000000

8. Click OK. Your graphic should look like this if you’ve followed the steps so far:



9. From the Create tab, in the Detail panel, click the Filled Region button, and sketch the shape of the tag.
10. Click the Element Properties button, and in the Instance Properties dialog box, click Edit Type. In the Type Properties dialog box, change the color of the fill pattern (select a color that allows you to see the color of the text—gray or yellow). Set Cut Fill Pattern to Solid Fill.


Parameter	Value
Graphics	
Background	Opaque
Line Weight	1
Color	RGB:192-192-192
Other	
Cut Fill pattern	Solid Fill

11. Click OK in all open dialog boxes.
12. Select the Filled Region you just created, and from the Edit panel of the Modify Filled Region tab, select Edit Sketch.
13. Holding down the Tab key, click one of the lines in the sketch (and thus select all connected lines); from the Element panel select Line Styles and choose <Invisible Lines> from the list. When you do this, the defined shape of the tag, which has a colored fill, will have no drawn boundary around it, as shown previously in Figure 4.40.

Invisible lines are for reference only in the Family Editor and in Sketch mode. They're selectable but not visible in the project environment, and they never appear on printed documents.



14. Click Finish Region. The result should look like this:



15. Save your tag. It's ready to be reused in a project or a template.

CREATING TAGS FOR OTHER CATEGORIES THAT DON'T HAVE FAMILY TEMPLATES

While creating custom tags, you'll notice that family templates aren't available for all Revit categories that exist. For example, if you need to create a furniture tag, you won't find a corresponding template for the furniture tag. What do you do? For such tags, you use the template called *Generic Tag.rft* or *M_Generic Tag.rft*. As a first step when starting the template, you assign it to the category you wish it to be associated with. Here are the steps to do that:

1. In the Family Editor, switch to the Manage tab and choose Category and Parameters from the Family Properties tab. (This exists *only* in the Family Editor.)
2. In the resulting dialog box, select the desired category (Furniture, in this case), and click OK.
3. Select the red information text, and delete it.

You can now proceed, using the techniques shown in our previous examples.


Keynotes and Textnotes

Notes are a critical part of communicating design and construction intent to contractors, subcontractors, and owners. No drawing set would be complete without textual definitions and instructions on how to assemble the building. *Keynotes* are element specific and can be scheduled and standardized in the Revit database.

Keynotes are textual annotations that relate text strings to specific elements in the model, which are in turn linked to an external text file. You can format font style, size, and justification in the same manner as for standard text, but keynotes behave like a Revit family. This means you can insert different text family types in Revit, just as you would door or window families.

KEYNOTE TYPES

The Keynote command is located on the Annotate tab under the Tag panel. Adding keynotes in Revit gives you three options similar to those mentioned in our discussion of adding tags:



Element This option allows you to note an element in the model, such as a wall or a floor. This type of note is typically used if you want to note an entire assembly, such as a wall assembly. You can find this value in the Family properties of that element.

Material This option lets you note a specific material in Revit. You can add a note to concrete, gypsum board, or acoustical tile, for example. This value can also be found in the Manage tab under Materials. The Identity tab lets you add keynote values directly to each material.


User This option allows you to select any model-based component in Revit and define a custom keynote for it. Notes defined this way differ from those defined under Element or Material because they're unique to the particular object selected. They can be used in conjunction with element and material notes.

CREATING A CUSTOM KEYNOTE

To create a custom keynote, follow these steps:

1. From the Application Menu, choose Open ➤ Family, select the Imperial library (or Metric, depending on your installation), and then choose Annotations ➤ Keynote Tag.rfa. You'll use an existing note block to edit in lieu of making one from scratch; this note is great to use as a template because it has each type of note already created.

From the Family Properties panel, select Type. The Family Types dialog box includes Keynote Number, Keynote Number Boxed, and Keynote Text note types; checkboxes under each allow you to customize the notes further. As an example, here is Keynote Number Boxed:




2. For your keynote, select the Keynote Text option from the drop-down list, and click OK. As we discussed with the other tag families, you can add labels, text, lines, filled regions, and other graphic tools to customize your keynote.
3. Because you're using the text and not the numbers for this note, delete the box surrounding the note.
4. Select the label for the note (the 1), and go to the Label properties. Here, you can adjust the font size and style. Also change the justification from Center to Left. Click OK to exit the dialog boxes when you've finished editing.
5. A critical part of a keynote is the note length. The overall length of the note before the texts begins to wrap to a new line is controlled by the size of the box for the note label. In this case, you want your notes to be 25 characters long (roughly 2¼" at ⅜" scale). The

best way to do this is to number the characters. Remember, the value you enter in this box now is only an aid to create the family.



When you insert notes into the model and annotate a wall, you can see how the text responds, on one line or on two (Figure 4.41).

FIGURE 4.41
Examples of material keynotes.




Creating Custom Title Blocks

While you're building a rich BIM model and adding more detail and intelligence in each phase of the project, you also have to document each phase and share it—deliver drawings (sheets) for others. No matter whether you share this information digitally (DWF, PDF) or via printed documents, you need to place information that is company specific (logo and contact information), project specific, and sheet specific on those sheets. Consistency among sheets is essential.

Sheets in Revit can be created in the project environment. Their creation starts with the selection of a title block that can have any shape, graphic layout, and size. Figure 4.42 shows a couple of examples; you'll create the second in this section's exercise. Title blocks are external families—you can create any kind of a title block in the Family Editor and add project number, sheet number, or company-specific information on it, both textual and images. (You can include your logo, an image of your project, and any other graphic.) Companies have different title block styles for document sharing with different parties.

FIGURE 4.42
Different title blocks: left for presentations, right for construction documents.



To use the title block families you've created in the Family Editor on a sheet, you must load them in the project. If you've created office standards, the project templates are the best place to store title block families you created on your own. There is no need to create final sheets in the template file—loading the title block families is sufficient. However, different offices have different strategies.

Creating a Custom Title Block with the Family Editor

Revit lets you easily create sheets to any standard you require. Sheets usually have standard dimensions based on standard paper sizes. These vary from country to country but are more or less standardized within each country.

The first thing to think about when creating a title block is the paper size on which it will be printed. You then think about the layout graphics as well as the information you want included on the sheet. Various world standards (ARCH, DIN 680, BS 4264, SFS 2488, ISO 11180, ANSI/ASME Y14. 1, and U.S. National CAD Standards) define precise layout requirements for sheets and the content displayed in them.

Keep in mind that the default title blocks in Revit use the lower-left corner of the sheet as the origin. This is important if you start with a default title block or if you exchange one sheet size for another, since they'll be swapped out at the point of origin.

Revit accommodates all these requirements—many of them in an automated manner. You can add any shapes, graphics, and textual information as well as use parametric labels capable of extracting information from the project. As you'll see, labels are part of the coordinated BIM concept and will help streamline your process.

The following steps demonstrate how to create the custom title block illustrated in Figure 4.43.

1. From the Application Menu, choose New ➤ Title Block.
2. From the list, either select one of the prepared sheet sizes or select New Size. This opens a title block template, where you can start laying out your title block. Let's assume that the size you need to duplicate doesn't exist in the list; select New Size.
3. A blank template file opens with nothing but a rectangle. Click the lines of the rectangle to activate temporary dimensions. You can then edit the dimension text value to drive the size of the rectangle. Make the sheet 42"×32".
4. Draw lines with the Line tool, creating a layout, as shown in Figure 4.43. For each variation in line thickness or color, you'll need to make a new line style using the Line Styles dialog box. Add new subcategories to the Title Blocks category.

FIGURE 4.43

The vertical title block you'll make.



Once you’ve finished with the lines, you’ll continue by adding images, fill patterns, text, labels, and symbols.

- 1. Add an image by switching to the Insert tab, and from the Import panel select Image. Select the example on the book’s companion web page or any image on your computer. Place it anywhere, resize it using its grips when selected, and position it on the title block. This is how you can place your company logo into your title blocks.
- 2. Add fill patterns with the Filled Region tool to add a color banner or hatched area to your sheets. You can’t add a fill pattern on a sheet in the project environment, so you need to add them in the Family Editor.

Fill patterns added in the title block are always displayed *in front* of any views placed on the sheet. In other words, you can’t use a filled region to create a colored backdrop view. There are other ways to achieve that.

- 3. Add text with the Text tool. Text is always the same and is unchangeable from the project environment. *Drawn by*, *Scale*, and *Date* are all examples of text. For each variation in font or size, you need to create a new type of text.
- 4. Add labels with the Label tool. These are textual fields that report information stored in individual projects. As with text notes, you need to create new types for every variation in font or size. By adding the label *Project Name* to the title block, you can reuse the title block in many projects; the label will update in each project with the appropriate name. The same principle works for the other labels, shown in the Edit Label dialog box in Figure 4.44. In this example, Project No. is prefix text and remains unchanged in the project environment. The number 00.0000 is a label and will reflect the number of the project set in the project information. Using this dialog box, you can add prefixes to the label. Be sure to add some blank spaces after the prefix if you go this route.

Figure 4.45 illustrates the difference between text and label elements, which behave as described in “Static Text and Parametric Labels” earlier in the chapter.

- 5. Continue to build the title block by placing text and labels on the sheet in the manner of Figure 4.46.

FIGURE 4.44
Edit Label
dialog box.




FIGURE 4.45
Place labels
with standard
parameters.




FIGURE 4.46
Continue to build
the title block.



6. Add a revision schedule to the title block so you can track changes in your document set. Changes are stored as revisions and can be displayed parametrically in your title blocks. We'll review the revisions in more detail in Chapter 23, but you'll add the revision schedule now.

Revisions


You can control the appearance of your revision schedule in the Appearance tab of the Revision properties. From the View tab, under the Create panel, select Revision Schedule (Figure 4.47). The Revision Schedule dialog box opens, and you can choose which parameters to schedule. Choose Revision Number, Description, and Date. To adjust the font and size, use the Appearance tab. You can specify if the schedule adds new revision rows from bottom up or from top down. In addition, you can set the height to User Defined, which allows you to dynamically set the height in the title block family to a fixed number of rows. Choosing Variable for the height will allow the revision table to get taller as new revisions are added. See Figure 4.48. When you've finished, click OK. An empty schedule appears; close that view.

FIGURE 4.47
Place a revision
schedule.



FIGURE 4.48

You can control the appearance of your revision schedule in the Appearance tab of the Revision Properties dialog box.



7. In the Project Browser, click the Sheets node and open the title block sheet.
8. Still in the Project Browser, expand the Views node, and then open the Schedules node. Drag and drop the revision schedule into the title block to place it. The revision schedule appears empty, but don't worry—it will be filled automatically when used in a project. If you have set the height to be user defined, go ahead and adjust the height using the blue grip control (Figure 4.49).





FIGURE 4.49
User-defined
height control for
revision schedule.



Once you’ve placed all these elements, the title block is good to go. Save it to your hard drive with a unique name, and click the Load Into Project button. Choose a project file, and the title block will be loaded.

Best Practices and Workarounds: Positioning Views on a Sheet

Revit has no automated way to place similarly scaled floor plans in the exact same location across many sheets; you’ll have to eyeball the placement. However, a useful aid is available to help, which takes advantage of the invisible line type. Choose an origin in your title block by drawing two intersecting invisible lines. These lines aren’t visible in the project but provide a snappable intersection you can move views relative to. Another aid is to add tick marks to the title block to create a basic cell division. Another option would be to create a light graphic grid on your title block. The visibility of the grid can be controlled with a type parameter. This will allow you to turn off the grid on all sheets at once. Or if the grid is very light (light blue, for example) it will print but hardly be legible.

The Bottom Line

Start a project with a custom template. Creating a template that incorporates your firm’s styles and preferences is an essential first step in putting Revit to work.

Master It Your firm has some deeply established graphic conventions that were defined in AutoCAD. How would you go about matching these graphics and setting up a Revit template?

Create custom annotation tags. Styles for annotations, dimensions, and text are all governed by office standards, and the Family Editor is your tool for setting up those standards in Revit.

Master It You need to create dimensions, text, and annotations that match your office standards. How do you do this with Revit?

Create custom title blocks. Title blocks are another important element of office standards that you can configure in the Family Editor.

Master It Most offices have several title blocks with lots of information embedded in them. How would you add multiple title blocks to your project template file?

Chapter 5

Customizing System Families and Project Settings in Your Template

In this chapter, we'll dig into customizing the Revit system families (see Chapter 2, "Revit Fundamentals," for a definition of system families) so that you can make your office templates exactly as you need them. Knowing how to adapt the system families—by using view templates, type catalogs, and other global project settings—and include them in templates can save you headaches early in the design process. In addition, the documentation process will be a lot easier because the assemblies are created correctly from their inception.

In this chapter, you'll learn to:

- ◆ Create new types of system families
- ◆ Use type catalogs
- ◆ Customize project settings in your template

Creating New Types of System Families

System families in Revit are a bit different from the other family types. They represent a limited list of building elements (walls, curtain walls, floors, ceilings, roofs, stairs, mullions) that cannot be saved as files external to your project the way you can do with the component, standard families (RFA files). There are only three ways to create or add new system families to your model:

- ◆ Create them in your project by duplicating one that already exists and modifying its properties
- ◆ Copy and paste them in as objects from one project to another
- ◆ Use the Transfer Project Standards tool available from the Manage tab in the Project Settings panel (this technique again allows copying from one project to another)

The first way is the most commonly used one in Revit. In the following sections, we will review how to modify the system families in Revit, allowing you to create your own, unique types.

Wall Types

Walls are made from layers that represent the construction materials used to build real walls. In Revit, these layers can be assigned functional values, allowing them to join and react to other


layers in the model when walls, floors, and roofs meet. Each wall has at minimum a core, with the option to add layers of material to the core in order to create multilayered assembly wall types. These layers can be added inside the core or placed outside the core. As you'll see, this special wall *core layer* is a powerful element; understanding it is essential to mastering Revit.

A wall core is much more than a layer of material. The core identifies the structural part of the wall; it influences the behavior of the wall and how the wall interacts with other elements in the model such as floors and roofs. Every wall type in Revit has a core material with a boundary on either side of it. These core boundaries can be snapped and dimensioned to when you are laying out your model.

For example, when you draw a floor above your exterior walls and use the “pick walls” method, the option to extend to the core of the wall is available on the Options bar. You can choose to offset your floor from the core layer as well. This floor creation method results in an explicit relationship between the floor and the underlying wall core layer. If any wall changes position, the floor follows and stays related to the wall core layer—even if the wall type is changed. Figure 5.1, which shows a section through a wall and floor, demonstrates that the sketch of a floor representing its boundary can be constrained to a certain layer or offset from the core boundary of the wall. If you created your floor using the pick walls method, the relationship between the floor and the wall will happen automatically.

FIGURE 5.1

Section through wall and floor: the sketch of a floor representing its boundary can be constrained to a certain layer or offset from the core boundary of the wall.




If you decided to use the draw method instead of the pick walls method and you still want your floors to be dependent on the position of the walls and have a relationship with them, you need to manually lock the relationship so that the dependency is established. To get the locks that create constraints between aligned elements to appear, select and drag the sketch lines of the floor over the walls (or use the align tool) so that they are coincident with the boundary or core lines of the walls, and then click the blue lock icon to establish the relationship. If your floor sketch lines were already coincident with the wall lines, just select one, drag it away from the coincident wall line, and drag it back. Another way to do this is to use the align tool. The lock icon will appear and you will be able to lock it.

To access and edit wall-core boundaries and material layers, first select a wall and click the Element Properties button. In the Instance Properties dialog box, click the Edit Type button to open the Type Properties dialog box. Select the Structure parameter to open the Edit Assembly dialog box. Here you can define materials, move layers in and out of the core boundary, and assign functions to each layer (see Figure 5.2).

FIGURE 5.2


Each wall type is composed of layers of material, defined in the Layers portion of the Edit Assembly dialog box.



CREATING YOUR OWN WALL TYPES

If you have a series of wall types that are standard in your office, you'll want to create them and add them to your project template right from the beginning so that they are available to all team members at all times. Creating new wall types involves duplicating an existing type, and then modifying wall structure and type properties. A wall can be a simple structure (a single-layered wall, which is typically used for resolving early design decisions) or a complex structure (a multilayered wall, which is used when the design becomes more resolved in terms of level of detail). If you need to make new types that are not part of your template, you can create new wall types on the fly at any stage in a project by duplicating existing types, adding or removing wall layers, and adjusting parameters to meet your requirements. The Edit Assembly dialog box, shown in Figure 5.3, is where you define the layers of the wall type. This dialog box is divided into four zones: the Preview window, the Layers table, the Default Wrapping option, and the Modify Vertical Structure option (which is available only when the section preview is active).

FIGURE 5.3
The Edit Assembly
dialog box for
a wall.



The Preview Window

On the left side of the dialog box, you will see a graphical preview of the wall structure in plan view (the default one) or section view. (If you don't see the preview, click the Preview button at the bottom of the dialog box.) To switch from the default plan view preview to the section view preview, or vice versa, click the drop-down list under View to choose another viewing option. In the preview, the core boundaries of the wall are drawn with green lines. Note that in the section preview, when you select a row in the Layers table, the layer is highlighted in red.

The Layers Table

The Layers table is where you add, delete, move, and define layers of the wall structure. Each wall layer is represented as a separate row of information. Note that two of the rows are gray: they represent the boundaries of the core of the wall, which usually define each face of the structural part of the wall. They don't represent any physical component but are just a visual representation of the separation between the structural and nonstructural components of the wall. In between those two gray zones is the wall's structural core layer.

The table is divided into four columns:

Function This column provides six choices for wall functions that relate to the purpose of the material in the wall assembly. Each of those functions defines a priority that determines how it joins with other walls, floors, and roofs:

Structure [1] Defines the structural components of the wall that should support the rest of the wall layers. This function gives the highest priority to a wall layer and allows it to join with other structural layers by cutting through lower-priority layers.

Substrate [2] Forms a foundation for other layers (materials such as plywood or gypsum board).

Thermal/Air [3] Defines the wall's thermal insulation layer.

Membrane Layer A zero-thickness material that usually represents vapor prevention.


Finish 1 [4] A finish layer to use if you have only one layer of finish (gypsum wall board).

Finish 2 [5] A secondary, weaker finish layer (plaster, tiles, or brick).

With the exception of the membrane layer, which has no priority assigned, all the other layers have a priority value from 1 to 5, with 1 the highest priority. Revit uses the priorities of the layers in a wall to determine how to clean up the intersections between various layers when two or more walls meet at an intersection. The principle is simple: priority 1 is the highest in order; a layer that has a value of 1 will cut through any other layer with a lower priority value (2, 3, 4, 5). A layer with priority 2 will cut layers with priority 3, 4, or 5, and so on. Logically, the layer with priority 1 should be placed between the core limits and represents the core of the wall (the structural component); the other layers should be outside the core. Revit starts sorting out wall joins by beginning with the highest-priority components and then working down the priorities. Look at Figure 5.4, in which layers with the same priority clean up when joined.

FIGURE 5.4

Layers with the same priority clean up when joined.




Material Associating a material to a wall layer provides graphical as well as physical characteristics for the wall. With a material, you can calculate the quantity of that material used in your project and schedule this information. The material also knows how to graphically clean up when it joins with other walls, floors, and roofs that are made of the same material. Finally, a material will define the color and graphical pattern of a layer.

How does a material definition affect the cleanup? The material usage informs Revit how to treat wall layers at intersections. If the priority of the layers is the same and the material is the same, Revit cleans up the join between these two layers, creating a graphically consistent material representation. If the materials are different, even though their priority is the same, Revit separates the two layers graphically with a thin line. Figure 5.5 shows two layers with

the same priority (1) but different materials: the cleanup between the layers isn't taking place because of the different materials used.

FIGURE 5.5

Two layers with the same priority (1) but different materials. The separation between the two layers is indicated with a thin line.




Thickness This value represents the actual thickness of the material. Note that the membrane layer is the only layer that can have a zero-thickness value.

Wraps Wall layers rarely end with a straight-cut finish at wall ends or wall penetrations (windows and doors). This option allows a layer to wrap around other layers. Figure 5.6 shows layer wrapping defined within a window family in the Family Editor. You can define different settings for wrapping the end of walls or openings. Looking again at Figure 5.6, the image on the left shows wrapping applied only to the first exterior component of the wall; only that layer wraps around the window opening. On the right, the first and second exterior components have wrapping active, so they both wrap around the opening of the window.

FIGURE 5.6

Layer wrapping defined within a window family in the Family Editor.




To create a wrapping solution for openings that reflect a real-life condition, this setting probably won't be sufficient. All you can define in the Wall Editor is *if* a material layer will wrap and whether it's an exterior or interior wrap. The Wall Editor alone can only solve wrapping conditions in a generic way. To achieve more complex wraps like the one shown in Figure 5.6, you must define another set of rules in the Family Editor while creating the window or door family itself. These additional settings, combined with the wrap function of the wall layer, will produce more complex wraps at opening conditions.

To summarize, editing the wall structure means adding or deleting wall layers. Each of those layers needs to be associated with a priority, material, thickness, and wrap information. To move layers up and down in the table, or to add and remove layers, use the buttons at the bottom of the dialog box.

Once layers have been defined and positioned, you need to consider a few more properties.

Default Wrapping

Each wall layer can either wrap or not wrap at the ends of the wall or at inserts (windows, doors, openings). To make this happen in the project, you must decide whether the wrapping should occur at openings or wall ends or at both. For inserts, you can choose Do Not Wrap, Exterior, Interior, or Both. Similarly, for wall ends, the options are None, Exterior, and Interior. The default wrapping parameters appear in both the Edit Assembly dialog box (Figure 5.3) and the wall's Type Properties dialog box, as shown here:



Modify Vertical Structure (Section Preview only)

Walls are often complex and articulated in their composition. Cornices, reveals, corrugated metal finish, and other elements are used all the time. Revit can accommodate any of these types of design articulation, and this is the place where all that is handled. See Chapter 12, "Extended Modeling Techniques—Walls," for a detailed explanation of these functions.

Level of Detail

Walls have only two different styles of graphic display for the three levels of detail: one for Coarse views and another for Medium and Fine views. You will notice that changing from Medium to Fine view, and vice versa, has no effect on the graphic display of the wall, because they use the same representation.


Coarse Display This is defined as a type property for each wall family, and is typically used for 1:200 scaled drawings. You can set both Coarse Scale Fill Pattern as well as Coarse Scale Fill Color. If no Coarse Scale fill is set, then the wall category material (set in Object Styles) will be used.

Medium/Fine Display This is defined in the Type Properties dialog box in the wall assembly. The materials used for each layer establish the cut and surface patterns of the wall. These types of display will be rich in detail and show each layer of the wall.

In Figure 5.7, Coarse Scale Fill Pattern is set to a solid fill and Color to black. On the left is the Coarse view: Individual layers are not displayed; a black Coarse Fill pattern is assigned. On the right, Medium/Fine view displays all wall layers. You can see the difference in how these walls present in the same plan at different scales, and thus different levels of detail.

Rather than setting the wall fill to solid black as a coarse display option, you can also use the visibility settings of a view to override the cut value of many objects (walls, floors, roofs, ceilings, and so forth) to a solid black fill at one time. This technique will save you significant time compared to manually joining geometry between host elements during design.

FIGURE 5.7
On the left is the Coarse view: individual layers are not displayed; a black Coarse Fill pattern is assigned. On the right: Medium/Fine view displays all wall layers.



MANAGING LAYER POSITION

When you insert new wall layers, you will notice in the Layers table that the newly created wall layer is always positioned below the active wall layer (the selected layer). To position your new wall layer where you want it, either you can click the Insert button and use the Up and Down buttons to position the new wall layer, or you can select the layer you want to reposition with the mouse (place the mouse at the beginning of the line and select the entire line, as shown in Figure 5.3, and again, use the Up and Down buttons to reposition it where you need it). By default, each time you insert a new wall layer, it has a Priority value of Structure [1], a Material setting of By Category, and a Thickness value of 0. Also, Wrap is selected.

Parameter	Value
Construction	
Structure	Edit...
Wrapping at Inserts	Exterior
Wrapping at Ends	None
Width	0.2000
Wall Function	Exterior

Note that you cannot delete the wall layer between the two gray lines (the core that represents the structural portion of the wall) if it is the only layer or the last one. A structural layer must exist and have at least one layer that has a value greater than zero. If you create a wall that has only one material (like a concrete foundation wall), you must place that one concrete layer between the gray core-boundary lines.

Wall Function


Each wall assembly has a function whose value is Interior, Exterior, Foundation, Retaining, Soffit, or Core-Shaft, as specified in the Wall Type properties. Changing this parameter doesn't

affect the geometry of the wall, but setting it correctly allows you to control the visibility of walls and is useful for scheduling purposes. Another important use of this categorization is during export to DWG: you will be able to assign each functional wall type to a different CAD layer for export.


Floor and Roof Types

The process of creating floor and roof types is similar to that for walls. Editing the floor structure follows the same principles as editing the wall structure. One notable difference is that floors and roofs do not involve Wraps—in the Floor Editor, this parameter is always grayed out. On the other hand, multilayered floors have an additional parameter (that wall layers don't have) that allows the layer to vary in thickness if the floor is sloped. This appears in the Layers table as a new column named Variable (Figure 5.8). The Variable parameter is available only for Floor and Roof structures.

FIGURE 5.8
The Variable parameter is available only for Floor and Roof structures.




Revit allows you to slope floors and roofs by adding points and ridges that can then be manipulated to create creases and sloping forms. You do so using Shape Editing tools, which are available in the Shape Editing panel of the Modify Floors tab when a floor or roof is selected. The Shape Editing tools are explained in more detail in Chapter 13, “Extended Modeling Techniques—Roofs and Floors.”



Floors or roofs that have been dynamically edited with these tools will have the Variable parameter enabled. If you select the Variable property, that layer can have a nonuniform thickness, as shown in Figure 5.9.

FIGURE 5.9


The Variable property is selected, so the floor layer has a nonuniform thickness.



If the Variable property isn't selected, as in Figure 5.10, the layer in question has a uniform thickness, and the entire floor structure is going to be sloped.

FIGURE 5.10

The Variable property isn't selected, so the floor layer has uniform thickness and the entire structure slopes.




Ceiling Types

Ceilings are also system families. Revit includes two different ceilings families: a generic ceiling that has no thickness or internal layers, and a multilayered ceiling that is identical to floors and roof in terms of functionality (Figure 5.11). Ceilings don't support the variable-layer thickness functionality we just mentioned, and they don't have a wrap function. What they can do (that floors and roofs cannot) is host ceiling-mounted lighting fixtures. This is very important to know: if you need to place light fixtures, you're going to have to add a ceiling.

FIGURE 5.11

Ceilings can be generic (represented as one simple line) or compound (represented with layers).



Use the simple ceiling to model drop ceilings that are hung from the structure. These are typically only as thick as the acoustical tiles and don't need to be modeled as fully 3D forms. The multilayered ceiling is good for gypsum ceilings placed on joists.


Stair Types

Stairs are complex building elements and require a deep understanding of local standards, rules, and requirements. Check the local building code requirements (minimum width, maximum height) to confirm that you're using the correct stairwell dimensions and proper headroom. Formulas for calculating stairs are based on common codes and ergonomics. These may have slight variations in different regions, based on local conditions.

A number of parameters define the representation of stairs, including rules for risers, treads, and stringers; selection of construction techniques; and material used. All of these can be adjusted and made into types for use in your templates so that you always have the types of stairs that conform to the local building rules where you operate. Figure 5.12 illustrates different types of stairs that can be created in Revit.

FIGURE 5.12

Stair types representing different construction approaches and material selections.




Courtesy of Phil Read

PROPERTIES OF STAIRS

In the Type Properties dialog box for stairs, you can control the following properties:

Calculation rules In the stair’s Type Properties dialog box, in the Construction/Calculation rules, click the Edit button to open the calculation rules. To use the calculation functionality, select the option at the top of the Stair Calculator dialog box (see Figure 5.13). The calculation rule is based on the universal calculation formula that sets the value that should result depending on the size of the runs and risers. If this value can’t be achieved, it should at least be within the minimum and maximum range you’ve defined.

FIGURE 5.13
Stair calculation options.



Extend Below Base This field defines an offset between the base of the stair and the level where it starts. A positive value means the stair starts higher than its base level, and a negative value starts the stair below the base level. The top of the stair isn’t affected by this parameter. This option is needed for conditions where the floor material demands that the stair start a bit higher or lower than the level.

Monolithic Stair When this option is checked, it changes the stair into a monolithic form where the stringers, risers, and treads are treated as the same material. This is great for making concrete stairs.

Landing Overlap This option is active only when the Underside of Winder option is selected (see the following explanation).

Underside of Winder This option is available only with monolithic stairs and has two values: Smooth and Stepped. They represent the treatment of the underside of the stairs, as shown in Figure 5.14.

Break Symbol in Plan This parameter shows a break line in plan. If it’s selected, the break symbol appears at the cut height of the stair. The part of the stair that is beyond the break symbol (above the cut plane of the view) is shown with special subcategories of stairs: Stairs Beyond Cut Line and Stringers Beyond Cut Line. Each can be assigned a different color and line type. This setting is unique to the rest of the graphics used for the stair.

Figure 5.15 shows a stair with a visible break symbol (on the left), and the same stair with no break symbol (on the right).

FIGURE 5.14
Monolithic stairs
with Underside
of Winder set to
(A) Stepped and
(B) Smooth.





FIGURE 5.15
The same stair
with and without
the break-line
graphic enabled.



Text Size and Font When creating stairs, you can set automatic appearance of Up and Down text that indicates the direction of the stairs. The text size and font define the properties of that text.

Material You can set different materials for various components of the stairs. When the Monolithic Stair option is selected, some of the options under Material will become grayed out as only one material will be considered for the entire stair.

Minimum Tread Depth This parameter controls the depth of a tread. Once you place a stair in a project, you can set the Actual Tread Depth in the stair's instance parameters. If this value is less than the type property Minimum Tread Depth, Revit gives you an error message alerting you to the problem.

Tread Thickness This parameter controls the thickness of each tread.

Nosing Length As the name suggests, this parameter controls the length of a nosing in a stair. When this parameter has a value of 0, no nosing is applied to the stair. A positive value for this parameter results in a nosing being exposed on all treads.

Nosing Profile This is where you can set the nosing profile that is used when Nosing Length has a positive value. You can create any custom Profile family for the nosing—the Family Editor includes a Profile-Stair Nosing family template you need to use. Once you have the custom nosing family, you load it in the template (project) and associate it with a certain stair type.


Apply Nosing Profile This determines where the nosing profile is placed relative to the tread. The available values are Front Only; Front and Left; Front and Right; and Front, Left, and Right. No Back option is available.

Maximum Riser Height This field defines the maximum allowed value for a riser. Usually, this setting depends on regulations set in the local building code as well as the type of building.

Begin with a Riser, End with a Riser These settings control the start and end of the stair and the connection with the landing.


Riser Type There are three possible types: None, Straight, and Slanted. As shown in Figure 5.16, this is fairly self-explanatory for the riser. For the slanted type, you can't define the angle of the slope; that value is a result of the length of the tread and the profile of the nosing.

FIGURE 5.16
Riser types: left to right, (A) no riser, (B) straight riser, (C) slanted rise with the value 1" (2cm) for nosing, (D) slanted riser with the value 1.5" (3cm) for nosing.



Riser Thickness This value defines the thickness of the riser material.


Riser to Tread Connection There are two options: Extend Riser behind Tread, as shown on the left, and Extend Tread under Riser, as shown on the right:




Trim Stringers at Top This option controls how the stringer finishes its geometry at the top of the flight (see Figure 5.17).

FIGURE 5.17
Trim stringer options.


- Do Not Trim: The stringer continues above the level.



- Match Level: The height of the stringer is coincident with the level.



- Match Landing Stringer: The top of the stringer is cut at a height that matches the landing stringer.



Stringer Left/Right This setting provides three options for stringer geometry:

None: No stringers applied to the stair.

Closed: The stringers are placed on the sides of the stair.

Open: The stringers are placed below the stair and are cut away by risers and treads.


Note that if you have a stair with stringers and decide to change the type to Monolithic Stair, the stringer will disappear.

Middle Stringers This option allows you to add one or more stringers below the stair. When more than one is added, they're evenly spaced.

Thickness/Height of Stringers This option gives you dimensional control over the stringers.

Open Stringer Offset This option is active only if the stringers are defined as open. This parameter controls the position of the stringer relative to the stair.

Stringer Carriage Height This is the value between the stringer height and the treads. The larger the value, the deeper the stringer goes below the treads (the tread position stays the same).



Landing Carriage Height This value controls the distance between the bottom of the landing and the bottom edge of the stringer.



Door and Window Types

Doors and windows are external families (RFA files) and are loaded into a project as needed. You should include door and window families that you use most frequently in your templates, and should remove content that you do not use.

You can create initial types using the Family Editor or loading from the existing library, and there is no limit to the number of additional types you can create in the context of a project. The same principle applies to other standard families such as furniture, plumbing fixtures, lighting fixtures, and so on. As you develop doors and window families that you think will be used downstream in many projects, be sure to load them into your default templates.

Using Types and Type Catalogs

To see why type catalogs are useful, you need to understand the various ways types of families can be created.

Library elements (referred to as component or standard families) often come in different sizes and colors while maintaining the essential shape. Revit allows you to embed many variations of an element in terms of size and material in a single family by creating different types of that family. Each type corresponds to a combination of user-defined values that control the size and material. In Figure 5.18, you can see three types of the same table that come in three different sizes and three different chair configurations. They're all the same family, but each variation in table size is captured as a separate type. The geometry and number of chairs are all controlled parametrically, allowing for many types to be generated.

FIGURE 5.18
One family with
three types:
4-chairs type,
6-chairs type, and
8-chairs type.



You can create types of Revit elements in different ways and places, depending on the elements as well as the intended purpose of the types or their number:

- ◆ You can create types of families in the project environment using the duplication method
- ◆ You can set them in the family environment
- ◆ You can also use a type-catalog approach. This is used in cases where you need more than five or six types, such as 50-plus different sizes of manufactured steel columns

Keep in mind that all the family types defined in the Family Editor are loaded when the family is placed in a project, even if you only use one of the defined types. By using a type catalog, only the types that you select are loaded into the project (and you may load other types as needed as the project progresses).

Creating Family Types in the Project Environment

When you create new types in a project environment, they exist only in that project. The process for creating a new type of element involves duplicating an existing type and giving it a new name and new parameter values. For example, select a wall and open its Instance Properties

dialog box using right-click menu to access element properties. In the Instance Properties dialog box, click Edit Type and then click Duplicate. Give the wall a new name, and change its properties to reflect the new type you need. If you want to reuse that new type in another project, you can use the Transfer Project Standards tool located on the Manage tab in the Project Settings panel. This tool copies those types in another project, and they will be available for use from then on. You can create types of both standard and system families using this method.

Creating Family Types in the Family Editor

Creating family types in the Family Editor applies only to component (standard) families. You create new types using the Types tool in the Family Properties panel of the Create tab in the Family Editor. (To open the Family Editor, you'll need to open any existing RFA family, or select the Application Menu > New > Family to make a new family.) By creating the types in the Family Editor, you save time downstream by providing a collection of common sizes that will be available when loaded into any project. Creating types in the Family Editor also ensures consistent library components across projects, as they are likely shared by the whole office. If you make unintended changes in a project, you can always reload the original family file from the library and override the values you changed.

The strategy of defining types in the Family Editor isn't always applicable depending on the number of types you need per element. If you think you'll have more than five or six different types, consider using the type-catalog strategy instead of making the types in the family. Type catalogs are the best way to define many types by entering textual information that a family then uses to construct a list of possible types.

Creating Family Types with Type Catalogs

Each family type uses a certain amount of memory for its definition. When you load a family into a project, every type in that family is automatically loaded. There is no way to selectively load types of a given family created in the Family Editor. If you have lots of families with lots of types, this can consume unnecessary memory and bloat your file size, especially if you need just one type of each and many remain unused. Additionally, when you have several types defined in a family and you load them in a project, the list of available types can become long and the Type Selector becomes difficult to search through.

Think about it this way: each potential option creates a new permutation, so introducing another option causes the permutations to expand exponentially. A simple desk with three options each for length, width, and height? $3 \times 3 \times 3 = 27$ permutations. What happens if you add two hardware options? 54 permutations. Three finish options? 162 possible permutations! Things can get busy fast, making your project "heavier" than necessary.

This is where type catalogs can help. They allow you to define many different types (size combinations) of an element, which can then be selectively loaded into your project. A *type catalog* is a text-formatted list that contains all the dimensions of the family for each type variation and can include an infinite number of types. The catalog is a separate .txt file related to the family. To create a type catalog file, all you need is a simple text editor (Notepad, for example). When you load a family associated with a type catalog, you get the option to choose which types to load in.

When you're creating a type catalog, the .txt file has to have the same name as the RFA family and be located in the same folder as the family. Figure 5.19 shows a steel column that comes

Name of Parameter corresponds to the name of a parameter in the family. You have to be careful when typing, because this value is case-sensitive. For example, if you have a Width parameter in the family, it should be shown as Width in the catalog as well. This parameter must be followed by two # symbols. *Type of Parameter* also must correspond to a type parameter in the family. The supported types are Length, Area, Volume, Angle, Force, and Linear Force. If the parameter in the family doesn't correspond to any of these, type **Other**. It may not seem obvious at first, but instance parameters may not be defined in type catalogs. You'll have to define instance parameters once the family is placed in the project.

Next, enter the units. These are the valid units that will work in a type catalog:

Length Inches, feet, meters, centimeters, and millimeters

Area Square feet, square inches, square meters, square centimeters, square millimeters, acres, and hectares

Angle Decimal degrees, minutes, and seconds

Force Newtons, decanewtons, kilonewtons, meganewtons, kips, kilograms-force, tonnes-force, and pounds

Linear force Newtons per meter, decanewtons per meter, kilonewtons per meter, meganewtons per meter, kips per foot, kilograms force per meter, tonnes force per meter, and pounds per foot

Other For Other, you don't specify a value; it can be anything. This is where you might define a material option or anything that is not defined as a length, area, or angle. In our case, it's Yes/No.

In the example, Width is a length parameter defined in millimeters, Height is also a length parameter defined in millimeters, and Frame is a parameter that has Other as its value and no defined units.

After editing the first line in the catalog, key in values to define types. Here is an example showing four types. Notice that each definition consists of name, length, height, and frame:

```
900mm x 400mm - D;900 ;400 ;1
900mm x 400mm;900 ;400 ;0
1200mm x 600mm - D;1200 ;600 ;1
1200mm x 600mm;1200 ;600 ;0
```

By having set this in the type catalog, you've created four types for one family. The first type is named 900mm × 400mm – D. The width of the element is 900mm, the height is 400mm, and there is a frame (Frame is defined in a family as a Yes/No parameter; in the type catalog, this value uses 1 for Yes and 0 for No). To better understand the principle of the type catalog, it's best to see it in table form:

TYPE NAME	WIDTH	HEIGHT	FRAME
900mm × 400mm – D	900	400	1
900mm × 400mm	900	400	0
1200mm × 600mm – D	1200	600	1
1200mm × 600mm	1200	600	0


Loading from a Type Catalog

When you have a type catalog associated with a family and you load the family into a project, the Specify Types dialog box gives you the option to selectively load types from a table. This table lists type properties to help you sort and choose which types you want. Select one or many of these types (use Shift or Ctrl for multiple selections), and then click OK to load the family and selected types. Using the Ctrl key, you can select several types that aren't sequential. Figure 5.20 shows a Shift-selection, and Figure 5.21 shows a selection using the Ctrl key.

FIGURE 5.20
When you load a family with a type catalog, the Specify Types dialog box allows you to choose which types to load.

Type	Width (all)	Height (all)	Frame (all)
600mm x 200mm - D	0.6000	0.2000	1
600mm x 200mm	0.6000	0.2000	0
900mm x 400mm - D	0.9000	0.4000	1
900mm x 400mm	0.9000	0.4000	0
1200mm x 600mm - D	1.2000	0.6000	1
1200mm x 600mm	1.2000	0.6000	0
1500mm x 800mm - D	1.5000	0.8000	1

FIGURE 5.21
Using the Ctrl key, you can select several types that aren't sequential.



Customizing Project Settings in Your Template

Having a well-thought-out project template can not only save you time but can also guarantee a higher level of graphical consistency between projects. This way, you don't have to become familiar with the settings in Revit and modify them each time you start a new project; you simply have to do it once and save it to a location that is accessible by everyone.

Graphic Overrides of Host Objects

When dealing with multilayered walls, Revit uses object styles and represents the wall layers with a single cut-line style for all walls. As shown on the left in Figure 5.22, this cut line applies to the wall's outermost layer. This isn't flexible enough for some representations, where you may want to show only the core as a thick line and reduce the line weight of finish layers, as shown on the right in Figure 5.22. To add richer and more descriptive graphics to complex host structures, you need the ability to assign line thickness, type, and color to individual layers in a host structure (walls, floors, and roofs). You can do so on a per-view basis using graphical overrides; however, the settings can be stored in a view template and applied to other views.

You can change the line weight, color, and pattern of host layers. To do this, from the context menu select View Properties and open the Visibility/Graphic Overrides dialog box from a plan view. Then, choose the Overrides Host Layers option for Cut Line Styles (Figure 5.23). You need to check the Cut Line Style option to make the Edit button active.


FIGURE 5.22

(Left) The default representation of a cut line. (Right) The core layer can be made bolder and the finish layers thinner.



FIGURE 5.23


You can change the line weight, color, and pattern of host layers.



When the Host Layer Line Styles dialog box opens, you see that the wall functions are listed with options to adjust the line weight, color, and pattern. Changing these values lets you generate wall graphics. Figure 5.24 shows the effect of changing line weight, color, and pattern for walls.


FIGURE 5.24

The effect of changing line weight, color, and pattern for walls.



You can also control the line styles for *common edges*. As shown in Figure 5.25, you can override host layers in the Host Layer Line Styles dialog box.

FIGURE 5.25
Overriding host
layers in the Host
Layer Line Styles
Dialog box.



The Host Layer Line Styles dialog box also lets you define how the core layers should clean up:

Default All line weights, colors, and patterns use standard behavior.

Use Function This setting ignores the material settings (the line is never invisible) and sets the style of the separating line based on the layers’ functional priorities. The style of a separating line is determined by the layer with the higher functional priority.


Use Common Edge Style This setting ignores the functional priorities and material settings and always uses the common edge style.

No Edge This option sets the separating line to invisible whenever the layers have the same fill pattern.

Additional Global Project Settings to Consider When Making Your Templates

In addition to setting up the object styles for your templates, you should set up some other global settings in advance. In the Manage tab’s Project Settings panel (Figure 5.26), you’ll find global project settings that can be stored on a per-template basis.

FIGURE 5.26
The Project
Settings menu.



AREA AND VOLUME COMPUTATIONS SETTINGS

Area and volume calculations are based on the height of the cut plane and the layer in a wall to which the calculation is measured. The Area and Volume Computations settings are located on the Home tab, after you expand the Room and Area panel. The Area and Volume Computations

dialog box includes several predefinitions for you to consider (Figure 5.27). Here you can enable automatic calculation of Area only or Area and Volumes. We don't suggest enabling the volume calculation option at all times because it can slow down overall performance when you're working on your model. Do it only when you need the information or have to print out the documents that contain that information.

FIGURE 5.27

Area and Volume calculations are based on the height of the cut plane and the layer in a wall to which the calculation is measured.



You can also apply different rules for room calculations that relate to boundary options in walls. These include wall finish, center, core layer, and core center.

Finally, a very important factor for computation of rooms and areas is the cut height. The computation height is a property of a Level family. By default, it is set to Automatic, which is 4' (1200mm) above the base level. You can change it to any other value. Changing the computational cut height in nonvertical rooms affects the perimeter used for computation. Some users apply the strategy of creating multiple-level families that use different computation heights.


These settings affect area plans that are used to convey building usage that extends beyond the shape and size of individual rooms, such as rentable area or office space. You access area plans from the View list of the Project Browser.

UNITS

Depending on where the project is located or what country you work in, you'll use either metric or imperial units. In the Project Units dialog box (Figure 5.28), which is available from the Project Settings panel of the Manage tab, you can set the units for length, area, volume, angles, slope, and currency. Under each of these options, you can define a rounding value, rounding increment, and units suffix and decide whether you wish to show the plus symbol (+) for positive values.

Note that Revit allows for a combination of imperial and metric units within the context of the same project. For each unit type in the Project Units dialog box, you can specify the formatting that is most suitable. Also note that while the project settings establish a consistent baseline, you can override project unit settings for elements such as dimensions and schedules.

FIGURE 5.28
Set up your units
and rounding in
your templates.




IMPERIAL FEET OR INCHES?

When you're using Revit for the first time and working in imperial units, you'll notice that numeric values resolve in feet instead of inches, which is different from the way AutoCAD works. A majority of Revit users have extensive experience (and thus established habits) with AutoCAD, so this can be frustrating at first. If you want to make sure your workflow isn't inhibited by this issue, you can modify the setting here to work in inches instead of feet.

KEYNOTING SETTINGS

Keynotes are a great way to standardize on a numeric system for calling out materials and assemblies. Keynoting settings are available in the Annotate tab when you expand the Tags panel (click the little arrow in the panel). When setting up keynotes, define the following keynoting settings at the outset. First, set the keynote table path, as shown in Figure 5.29. The path defaults to the Revit library locations, but you may want to change this if you're using customized keynote files located on the office network. In this dialog box, you establish whether the numbering method for keynotes is By Keynote or By Sheet. We'll go into more detail about how to use keynoting in Revit in Chapter 19, "Annotating Your Model."

FIGURE 5.29
The Keynoting Settings dialog box.



MATERIALS

The Materials dialog can be accessed from the Manage tab (Figure 5.30). A full render appearance library ships with Revit, and you can use it to map rendering appearances to your existing Revit materials. To do so, select materials from the list on the left, and then click the Replace button to go to the Render Appearance Library (Figure 5.31).

FIGURE 5.30
Remapping concrete using the Materials toolset located in the Manage tab's Project Settings panel.





FIGURE 5.31
Use the render appearance library to select a render material.



If you were using custom texture maps previously, then use the Generic Render appearance and remap the image files. Be sure to set appropriate scale using the Sample Size control. Keep in mind that for this to work in your templates, the images need to be accessible over the network by anyone who uses the template.

SETTING UP GOOD PROJECT DEFAULTS

Whatever type of element you selected last with the Type Selector will be set in the project template as the default type during creation. Revit remembers the most recently used settings across sessions. It's therefore important that you set the types of your selected Revit elements as desirable defaults.

Default Wall

To set a default wall type, activate the Wall tool. Click the Change Element Type button to open the Type Selector. From the list, select the wall type that you wish to be the default choice. In the Element Properties dialog box or from the Options bar, select the wall height or set a top level, and select the wall location line. You never know which wall type you'll need in the next project, so we suggest setting this to a generic type. The selection of exact wall types can come later.

Default Doors and Windows


Your project template is loaded with windows and doors that are typically used in projects. Activate the window or door tools, then using the Change Element Type button to open the Type Selector, choose a default door and window family, and save your template. The last selected door and window will be default elements in the Type Selector when you place new elements. This applies to all other family elements in your template.

Default Dimension Types

To streamline your workflow, set the dimension style used most commonly in your template. You can consider presetting:

- ◆ The type of dimension (we suggest selecting Linear)
- ◆ The reference selection that will be used when dimensioning a wall (to or from). Here the choices are the usual wall references: wall center, face, core face, and core center
- ◆ The selection method, or what we call *manual* versus *automated* dimensioning. In Revit, the Pick method can be Individual, where you're asked to click each instance you wish to dimension, or Entire Walls, where you click an element and it's dimensioned automatically. With the Entire Walls option, another dialog box prompts you to further define what elements are used as auto-dimension references when you click walls (Figure 5.32)


FIGURE 5.32
Dimensions can be preset in your template to be automatic if need be.



Align Tool

Many users find this to be one of the most helpful tools in Revit, as it aligns elements to any reference target in the model. Setting its options correctly will aid in smoothing your workflow. Preset which wall layer to which you want the Align tool to default. The options available for a wall are shown in Figure 5.33.

FIGURE 5.33
Setting a default alignment preference with respect to wall references.




Levels and Plan Views

Set up levels and corresponding plan views in advance in your template to save time downstream. You can predefine the number of levels, their typical height, and naming convention (Figure 5.34).

FIGURE 5.34

Levels in the Project Browser and in section view.




Elevations

If you've started building your template from an existing Revit template, you'll already have four default exterior elevations defined. If you started from scratch with no template (which we strongly recommend against), you'll need to create all four base elevations (south, east, north, and west) by placing elevation markers. (Note that we don't recommend that you ever start Revit using the None option when making a new file, as you'll have to define a great many things to make Revit work that are already defined in the default template.) It's very important that you also set the width and depth of the elevations. To do so, select the arrow of the elevation mark that activates the current width and depth; then you can adjust them accordingly (Figure 5.35).

FIGURE 5.35

Two different settings for elevation tag depth and width.



Views

For each view that you preset in the Revit template, you can define a scale, a level of detail, the state of the crop region (visible or not), and display settings (hidden lines, shaded view, and so on). But mostly, think of view templates when you preset your views, because they're the biggest time-savers—setting them in the templates will increase productivity significantly and help you maintain graphical consistency.

View Templates

View templates let you define a desired set of view properties for any of your view typical types (plans, section, elevations, schedules, etc.). This is a great way to enforce graphic consistency across views. For example, if you want your architectural plan views to always show furniture as half-toned, you can define this in your plan view template. If someone changes the appearance of furniture to no longer be half-toned, you can reapply the view template to get the drawing back to its original configuration. To do this, right-click the view name in the Project Browser, and choose the Apply View Template option. Choose the desired template, and click OK.

Every view can have a default view template assigned to help streamline updating the view later in the process (Figure 5.36).

This doesn't automatically keep the view in sync with the view template, but it lets you select many views in the Project Browser and push their default view template back into the view. To do this, select multiple views in the Project Browser, and choose to apply the view template. Choose the option Default View Template.

FIGURE 5.36

Views can have a default view template assigned to them to help streamline updating the view later in the process.




 Real World Scenario

USE VIEW TEMPLATES

As your use of Revit on projects progresses, you'll find that you will have view settings you will use over and over again that will help quickly define many of the parameters in a new view. These can easily be for plans, details, sections, or any other view within the project. Once you've defined these view templates, add them to your project template so that you can quickly access them when you begin new projects.

All view template-related tools are available from the View tab's Graphics panel when you click the View Templates button. The last option, View Template Settings, is the place for creating, editing, and managing view templates. Look at the view templates that ship with the default template, and adjust these to suit your requirements. For example, the architectural plan scale (1:100) is set to 1/8"=1'-0", as you can see in Figure 5.37. If this is too coarse for your needs, change the value to 1/4"=1'-0" (1:50).

FIGURE 5.37
The View Template Settings dialog box lets you create, edit, and manage view templates.



Color Fill Schemes

Color fill schemes let you apply color to room and area parameter values to help graphically illustrate spatial organization. Applying a color fill scheme to a plan or section view color-codes room properties such as department, name, and usage. It's good practice to predefine different color schemes that you're likely to use. Once a color scheme is defined, it can be applied to any number of plan views. Keep in mind that color is applied only to spaces that have been populated with room or area elements. If you want to make department-usage plans, think about prepopulating your color schemes with commonly used department and usage names. This will make the value available for rooms later so you don't have to manually type them in each time. For example, if you add "Accounting" as a value to a color scheme in your template that colors by department, then when you later go to a room's element properties to assign it a department, you'll see "Accounting" as a predefined choice in the drop-down list.

The Color Scheme settings are available from the Home tab when you expand the Room and Area panel.

The Bottom Line

Create new types of system families. Incorporating common building components in your project template is fundamental to using Revit effectively.

Master It How do you add/remove wall, floor, and roof types to your template?

Use type catalogs. Revit's type catalogs are an important tool for keeping the types you create accessible in a project.

Master It What are type catalogs used for?

Customize project settings in your template. View templates allow you to tailor views according to the requirements of a project.

Master It How would you set up a new view template for plan views where the surface pattern of floors is turned off?

Chapter 6

Modeling Principles in Revit I

Creating a BIM model requires modeling in 3D. This is very different from using abstract 2D lines, arcs, and text to represent your design. To work with Revit and be able to build a BIM model, you need to understand how a building is built and how various building parts, ranging from the building mass down to furniture assemblies, are constructed at various scales. You need to know how various building elements interact with and depend on each other, what materials they are made of, and how they are constructed and assembled. To this end, Revit provides a set of tools that enable you to build your model and all the elements that go into the model. Understanding the principles of modeling in the context of Revit will be essential to your success as you move deeper into building information modeling.

This chapter is the first half of a description of the basic modeling principles that support the design process in Revit. In this chapter, you'll learn to:

- ◆ Understand the basics of modeling with Revit
- ◆ Understand sketch-based design
- ◆ Understand work planes, levels, grids, reference planes, and reference lines

Grasping the Basics of Modeling with Revit

Designers have a long tradition of modeling before building. This activity involves the use of pliable and tactile materials such as clay and wood to model designs smoothly. With these materials, form can be explored with ease, as designs iterate directly in our own hands. The use of software to model form has become a popular extension of this activity, and you only need to look so far as the latest animated film to see how far the technology has come.

Many software modeling tools are available that allow direct editing and intuitive shaping of form. Tools such as Autodesk Alias Design Studio, Autodesk Maya, Rhinoceros, Autodesk 3ds Max, Google SketchUp, and the latest release of AutoCAD allow you to create free-form conceptual shapes with relative ease. These tools are great for concept modeling, but they are not geared for a BIM approach to design and documentation. The elements created with these modelers are meshes, Non-Uniform Rational B-Spline (NURBS), ACIS solids, and other generic geometrical shapes that are used to represent walls, slabs, roofs, and windows. However, they do not have embedded intelligence or relationships among themselves or with other elements in the model. Further, they barely contain any metadata that can be quantified and analyzed. So, as it stands today, you will find great modelers that are not BIM and BIM applications that are not powerful modelers. One way that Revit approaches this problem is to allow importing of


free-form geometry into the project and family environment, where it can then be used to derive walls, floors, and roofs. And while it is not as free-form as some other applications, Revit natively supports the creation of parametric 3D forms.

The entire modeling concept in Revit is founded on some basic class modeling forms—extrusions, revolves, sweeps, blends, and swept blends—and the combinations these can produce. The only place where this is not the case is the new set of Conceptual Design tools, introduced in this 2010 release of Revit. We will discuss these in greater detail later in the book in chapters 8 and 9.

Each of the five basic modeling techniques can produce either a positive or negative shape (solid or void). These shapes can be combined to create more complex forms. Each form is derived from 2D sketches that are drawn on work planes and then given a third dimension. We'll explore sketch-based forms in more detail in the next section.

Figure 6.1 shows an example of what's possible using the modeling tools.

FIGURE 6.1
Example of expressive architecture using Revit.




Understanding Sketch-Based Design

The majority of internal modeling techniques in Revit rely on an approach called *sketch-based design*, where you draw a shape in a special Sketch mode by creating 2D lines that then generate 3D forms. When you model most Revit elements, you enter a mode in which the entire model is grayed out and not selectable, so focus is placed on the sketch, which is represented in strong magenta lines. Once you've defined your shapes by creating closed loops of lines, you click Finish Sketch, and the geometry is generated. This Sketch mode is used throughout Revit, so you should get acquainted with its behavior early on.

For example, the Floor, Roof, Ceiling, Stair, and Railing tools require you to first sketch 2D shapes and then generate the form by “finishing the sketch.” Revit then applies a thickness or other element-specific property to the sketch, based on the element type. Even walls have an underlying sketch, but in the case of walls, this is a sketch that can be edited in elevation, not plan view, as is the case with the rest of the elements (Figure 6.2). To edit the elevation of a wall, select the wall in an elevation or 3D view and click the Edit Profile button in the Modify Wall panel of the Modify tab. Note that this tool only applies to linear walls.

FIGURE 6.2

Moorish architectural example: (A) Standard straight rectangle shaped wall; (B) elevation sketch of that wall changed to the desired shape using simple lines; (C) wall shape result achieved by simple editing of the sketch in elevation; (D) the wall used in a building.



Courtesy of E. DiGiacomo

Floors and Roofs

One of the first places you'll encounter sketch-based modeling is with the Floor and Roof tools. When you initiate either of these tools, you are instantly placed in Sketch mode. The Ribbon changes, indicating the new mode (Figure 6.3), and you see a set of tools specific to the task of creating 2D sketch lines and creating lines with relationships to other model elements.

FIGURE 6.3

The Create Floor Boundary tab offers tools for sketching the floor shape.



For example, you can either draw lines freely using the Line tool in Draw panel, or use the Pick Walls tool from the same panel, which generates the floor or roof sketch lines when you pick on walls. When using the pick walls method, you create an explicit relationship between


the floor or roof sketch and the walls. As a result, when walls move, the sketch (and thus the floor or the roof made of it) adapts and updates with the walls.

There are a few important rules you must apply when creating a sketch so that it is valid:

- ◆ The sketch has to form a closed loop of lines, and the lines have to be perfectly trimmed at the ends. You cannot have gaps or overlapping lines in the sketch. Whenever a sketch is not complete or has overlaps, Revit will indicate that something is wrong with an error message and you will not be able to finish the sketch until you fix and clean it up.
- ◆ When creating certain types of elements, you are allowed to sketch more than one closed loop within or outside of the same sketch—this is fine as long as the two loops do not intersect. If one loop of lines is within the boundaries of the other, it creates an opening in the outer shape (Figure 6.4).


FIGURE 6.4

Creating a closed loop within another closed loop of lines results in an opening.



If you were to draw another loop within those openings, it would be positive and create another solid piece of floor of the same type. Here's the logic behind loops: one is positive, the next one within it is negative, and the next one within *it* is positive (Figure 6.5).

FIGURE 6.5
An additional loop of lines results in a positive shape.



Sketching Rules of Thumb

Here are some rules of thumb you will need to follow when sketching:

- ◆ To edit a sketch, you must be in a view that is parallel to the sketch or a 3D view. For example, it is not logical to edit the sketch of a wall profile in a plan view as you would not be able to see the sketch in a way that is relevant. If you attempt to do this in plan view, Revit alerts you and proposes other views in which you *can* execute the task. The same goes for a floor—only in plan or 3D will you be able to edit the sketch.
- ◆ Sketch mode cannot be activated in perspective (camera) views. If you select a wall or any other element and want to edit its shape but cannot find the Edit button on the Options bar, you are in camera view. Switch to an axonometric, 3D, or any other view in which the sketch makes sense to edit.

Understanding Work Planes, Levels, Grids, Reference Planes, and Reference Lines

Reference planes, reference lines, levels, work planes... what are they? This section delves into each of these topics. First, to master modeling techniques in Revit, you need to understand the concept of a work plane.


Work Planes

The work plane is a 3D plane that you sketch on. For example, when you are in a plan view and start sketching a floor, the work plane is set to the level associated with the plan view you are working in. The majority of views in Revit (plans, 3D views, or views set in the family templates) have predefined work planes set automatically when they are created. Views such as sections and elevations require you to manually pick a work plane in order to add 3D elements to those views. In some cases, as with placing windows or doors in an elevation view, this is done implicitly—the cursor locates planes (walls) automatically.

A work plane can be understood as a surface on which you draw or place something. Imagine you are holding a marker in your hand and have a space in front of you. Can you draw with the marker in the space? No. You need a piece of paper, glass, wall—some kind of a surface to draw on. So, a work plane defines a surface on which you can build geometry. You can define a work plane by drawing a reference plane, picking a face from an existing element, or using an existing level (datum) as a reference.

Figure 6.6 illustrates the work plane. There are a few simple rules you must follow when using a work plane:

FIGURE 6.6
Concept of work
planes.



- ◆ The work plane is set by selecting a reference plane/reference line; a datum plane (like a level or grid); or a planar face of a model element. Often it is preset and you do not need to explicitly set it.
- ◆ Many elements in Revit use the active work plane to know where to sketch or place objects. (Some objects are limited to only horizontal or vertical work planes.)
- ◆ The work plane is also used when you are modifying objects. When you drag or move an object, it is typically constrained to that plane.
- ◆ When you set the work plane to be based on other selectable elements, it creates a *dependency*, or relationship, to the underlying reference you selected. If the underlying object is moved, the work plane is moved to stay aligned to it. Any objects created on the work plane will also update.

Let's take a closer look at the types of work planes available in Revit.

Levels

Levels are horizontal work planes that define the levels in a building and can also be used to denote important horizontal references in a building (such as attic height). Levels are only created and visible in section or elevation views. The only exception to this is when creating a new Conceptual Mass in the Family Editor—there levels are represented in a 3D view. Each level typically has a corresponding floor plan view associated with it, although it is possible to make levels with no associated floor plan. For example, a level may define the Top of Steel in a building section, but there is no need to have a floor plan view of that level. For that case, you can create levels without plans by clearing the option Make Plan View on the Options bar when the Level tool is activated. This creates a level that appears black and white rather than blue, indicating that there is no hyperlinked view.

Note that when you create new levels using the Copy tool from the Modify panel, the newly created levels are black and white (unlike the levels that are drawn using the Level tool and that are represented with a blue symbol). This change in color indicates that this level has not generated a new floor plan that is associated with that level as the Level tool does usually. If you do need a corresponding floor plan associated with that level, you can use the Plan Views tool in the Create panel of the View tab. You will then be able to add a plan view associated with any existing level in the project.


When you place families, they automatically become associated with the level they are placed on. Walls, roofs, and stairs all have top and bottom constraints to levels. This guarantees that when the level changes height, so too will all the elements on that level. All sketch-based families such as floors, roofs, ceilings, and stairs are also associated with at least one level. This, however, means as well that if you delete a level, all the elements associated with that level will also be deleted! So use caution when deleting levels; it's not just a drawing that you are deleting!

Grids

Grids are vertical planes used as standard references in the construction industry for creating location grids on the site as well as a communication reference between the building participants. These construction datums are used to accurately define locations for elements such as columns and beams or positions of main structural walls or the exterior shell. You can associate elements with the grids so that when the grid system changes, it controls the position of the associated elements. A good example for that would be columns associated with grid intersections. As with a level, when a grid is moved, associated elements move with the grid (Figure 6.7). Grids and levels (datum) only show up in views that intersect the datum.

FIGURE 6.7

Grids are reference planes that can be used to control other elements such as beams and columns.



EXTENDING LEVELS AND GRIDS

If you wish to expand grids or levels to encompass a larger portion of your model, you can use the context menu of the grids and select **Propagate Extents**. This command is also available in the **Datums** panel of the **Modify** tab when you select a grid line. This extends the datum planes you have selected to the maximum extents of the model geometry.

Reference Planes

Reference planes are used to drive other geometry. They are planes that exist in 3D space that other elements can be attached to. While not visible in 3D views, they can be seen when perpendicular to plan, section, and elevations and are represented as green dashed lines. Similar to levels and grids, these lines are not view specific and will appear in all perpendicular plans, sections, and elevations. Even though reference planes look and feel like ordinary lines, they are very different. Think of them as symbolic representations of infinite planes. The ends of reference planes are selectable and you can drag them to make them longer, but you will not be able to rotate the end of a reference plane freely as you can with lines.

USING REFERENCE PLANES IN THE FAMILY EDITOR


Reference planes are the essence of parametric content creation in the Family Editor, as they are used to create the parametric skeleton to which geometry is then attached and allowed to vary. The reference planes in a family are what you dimension to when they are loaded into a project—not the geometry.

Giving the reference planes various states also affects how other elements relate to the family. A reference plane can be set as *not a reference*, *weak*, or *strong*, and it can be defined as a reference for the left, right, front, bottom, back, or center position. The selection of these options is important in the Family Editor environment, as they define references for snapping. When you have two crossing references set as **Strong**, they define the insertion point of an element when you place it in the project environment. The origin must be further defined in the instance properties of the crossing reference planes by selecting “Defines Origin.”

In Figure 6.8, the two centrally positioned strong references define the insertion point of the element. The weak references serve only as secondary snaps.

FIGURE 6.8


The insertion point of the desk is the point of the two crossing references that has been identified as “Defines Origin.”



In a project, reference planes can be used to drive geometry (see Figure 6.9).

FIGURE 6.9

Reference planes are used extensively in the Family Editor to create parametric constraints that can drive forms and define snapping references. In this example, two of the vertical reference planes define the width of the chair while the two horizontal define its height.




Reference Lines

Reference lines were designed mostly for use in the Family Editor to overcome the limitation of the reference planes and their inability to define constraints that reference a point, direction, and angle. Unlike with reference planes, the start and end points of a reference line can be referenced and used for dimensioning. A popular use of a reference line is to define door swing opening angles by creating an angular relationship between the door leaf position and the closed state of the door leaf. This will let the user set any angle of door opening later in the project. Other differences between reference lines and reference planes are that you cannot name the reference lines and you can only select them graphically.

Reference lines define four work planes—the two along the axis of the reference line and the third and fourth planes that are perpendicular to each of the line segments (see Figure 6.10).

FIGURE 6.10


Reference lines are used to control door swings and opening angle in families.



SCOPE BOXES

As previously mentioned, reference planes extend in all views. Once drawn in one view, they will appear in every view that shows the area where they are created. But that is not necessarily what you always need. Let’s say your project has a base of five floors of conference area with a 30-story hotel above (like the model shown in Figure 6.11). It’s likely you’ll have separate structural bays for each part of the building. You don’t need to see all grid lines of the conferencing base in the hotel tower, and vice versa.

FIGURE 6.11
(A) This building consists of two main volumes, a low volume with conference usage and a tower with hotel use. These two volumes use separate grid systems, and thus two different scope boxes are created to control the visibility of the separate grids. (B) Grid element properties indicate the scope box to which the grid belongs.



The Scope Box tool will help you deal with this issue and allow you to limit the range in which reference planes (grid lines, levels, and reference lines) extend and appear. In our example shown in Figure 6.11, the building has a base shape that accommodates a conference center and a tower in which a hotel is situated. They have very different configurations and need different grid systems. The thing to do is to draw two separate scope boxes around those two entities, using the Scope Box tool allocated in the Create panel of the View menu. Then the grids of each of those two parts of the building need to be assigned to the appropriate scope box (the grid of the base to the Conference scope box and the grid of the tower to the Hotel scope box). Scope boxes are visible in 3D views—although not in camera (perspective) views—and you can easily manipulate their extents at any time directly using the grip controls. Assigning

gridlines or other datums to a scope box is easy: select the gridlines, and in the Instance Properties dialog box, choose the Scope Box parameter and select the scope box where the datums should belong. Figure 6.11 shows the Instance Properties dialog box for the gridlines and the associated scope box.


VISIBILITY OF GRID LINES IN SECTIONS AND ELEVATIONS

Grid lines will show in section or elevation view and *only* if the view is cut perpendicular to the grid line. In no other case will the grid line appear. This is done to avoid confusion on the construction site due to misleading graphic description.

Work Planes in a Nutshell


Before moving on to look at using work planes in practice, let's take a moment to summarize the basic theory.

WORKING WITH WORK PLANES



When creating elements that do not necessarily fall on a standard reference plane (such as a level), you will need to select the Set button on the Work Plane panel of the Home tab to establish your work plane. This brings up the Work Plane dialog box shown in Figure 6.12. Let's review the options in the dialog box.

FIGURE 6.12
The Work Plane dialog box lets you specify the active work plane for a view.




Name This option displays available levels, grids, and named reference planes. Note that only reference planes to which you have explicitly assigned names appear in this list. To name a reference plane, use the element properties of the reference plane.

Pick a Plane This option allows you to select a plane interactively in the model. The selection is visual and you need to click on a reference plane, wall face, or faces of an element. Figure 6.13 shows how different an extruded shape will be when selecting different planes on which to sketch and create a void extrusion. The face of the element that's marked darker represents which side of the element was set as a work plane.

FIGURE 6.13


The same mass and the same 2D shape extruded as a hole. In (A) the extrusion shape is drawn on the front face of the mass; in (B) the extrusion is drawn on the back face of the mass.



Pick a Line and Use the Work Plane It Was Sketched In With this option, Revit converts the work plane on which the line was created into the active work plane. When you select a work plane that is perpendicular to your current view, Revit opens a new Go to View dialog box that gives you options to select a view in which the chosen work plane can be worked on (Figure 6.14).

FIGURE 6.14

The Go to View dialog box lists views where you can work on the active work plane.



WORK PLANE VISIBILITY



You can visually show the active work plane in your view using the Show button in the Work Plane panel of the Create tab. When visible in 3D, the work plane is shown as a semitransparent grid face (Figure 6.15). By activating work plane visibility, you'll see where you will be adding new elements. You can see the work plane change location by using the Pick Plane option in the Work Plane dialog box. Select model faces and you'll see the active work plane change.



If you are not sure where your active work plane is, click the Show button in the Work Plane panel.

OTHER WORK PLANE OPERATIONS


Revit will let you rotate a work plane grid by clicking on it and selecting Rotate from the Modify panel. This in turn affects how new elements will be placed on that work plane. You can also align elements to the work plane grid, and lines will snap to the grid (Figure 6.16).

FIGURE 6.15

Making the work plane visible helps you understand the active work plane in a 3D view.

**FIGURE 6.16**

When the work plane grid is rotated, new elements placed on the work plane will also be rotated.




To change the work plane an element is already associated with, select the element, and then click the Edit Work Plane button in the Work Plane panel of the Modify tab and select another work plane using one of the methods in the dialog box.

To dissociate an element from a work plane, first select the element. Next, click the Edit Work Plane button in the Work Plane panel to display the dialog box shown in Figure 6.17, and click the Dissociate button. The element will then be free to move anywhere in the model. Note that this option is only available for work plane–based families.

FIGURE 6.17

The Work Plane dialog box allows you to set the work plane of an element or dissociate it from its work plane.



Once you have dissociated an element from its work plane, you will notice that the value for the work plane instance parameter (located in Element Properties) will be set to <not associated>.


Most importantly, you will notice that the element is free from constraints and is free to be moved in any 3D direction.

To rehost elements from one host (wall, floor, or roof, for example) to another, you can use the Pick New Host button from the same Work Plane panel when an element is selected. This allows you to select a new host to place the element. With this tool, you can choose any new host—it does not have to be in the same plane as the original. For example, you can select a window in one wall, click the Pick New Host button, and then choose a new wall for the window.

Figure 6.18 shows an extruded shape originally created on a horizontal work plane. Using the Pick New Host tool, you can place the form on any surface in the model.

FIGURE 6.18

(A) Original condition; (B) desired repositioning of the curved element; (C) the element is rehosted and a relationship between the two elements has been created; (D) the host changed its geometry and the hosted elements follow the change.






Real World Scenario

USING WORK PLANES WITH REVIT ROOFS


Here are two versions of the same building, with roofs that use the same sketch profile but are drawn on two different work planes. Image A shows a roof by extrusion sketched on a work plane parallel to the exterior wall; B shows the same roof sketched on a work plane rotated 45 degrees with respect to the exterior wall. Notice the difference!



CREATING A ROOF BY EXTRUSION (DEFAULT WORK PLANE)

Take the following steps to see for yourself how version A was created:

1. Draw four walls in plan view in the shape of a square.
2. On the Work Plane panel of the Home tab, select the Reference Plane tool and draw a reference plane parallel to the south wall:



3. Pick the reference plane and open its instance properties. Give it the name **Front Roof Plane**.


4. On the Create panel of the Home tab, select the Roof tool and select Roof by Extrusion. You will be prompted to select a work plane.




5. From the Name list, select the named reference plane you just drew and named. You'll be asked to open a view to begin sketching. Choose the south elevation.
6. Sketch a roof in arc shape, as shown here, and finish the sketch:




7. Go to the default 3D view and, using the blue arrows, adjust the length of the roof to make sure it extends beyond the exterior walls, as shown here:




8. While still in the 3D view, select all the walls. Click the Top/Base: Attach button in the Modify Walls panel of the Modify tab and then select the roof to attach the walls to the roof. The resulting building should look something like this:



9. To cut the roof so that it ends at the edge of the exterior walls, switch to plan view (Level 2 or Site plan), select the roof, and select the option Vertical Opening in the Modify Roof panel. This allows you to cut off the extruded roof exactly at the edge of the building, regardless of its shape. In this example, draw two rectangles (the location is indicated in the following figure with Vertical opening) that cut the roof up to the face of the walls.




After applying the two sketches using the Vertical Opening tool, the final result for the first roof should look like this:




CREATING VERSION B: A ROOF USING A 45-DEGREE WORK PLANE AS A REFERENCE

To obtain the second roof (B) shown at the beginning of this section, repeat all the previous steps, but draw the reference plane at a 45-degree angle to the building, as shown here. Remember to give the reference plane a different name in its Instance Properties dialog box.



The finished roof looks like this:



The Bottom Line

Understand the basics of modeling with Revit. Modeling with software is an extension of the traditional art of modeling with the hands. Free-form 3D modeling tools are not designed with BIM workflows in mind, but it is still possible to import shapes into Revit for downstream use. At the same time, Revit provides some basic tools for 3D design, and you should familiarize yourself with these.

Master It Tools such as Autodesk Alias Design Studio, Rhinoceros, Autodesk 3ds Max, Autodesk Maya, SketchUp, and AutoCAD 2010 allow you to create free-form shapes with relative ease. How does Revit let you take advantage of such shapes?

Understand sketch-based design. Sketch-based design allows you to define some basic parameters and shapes in Sketch mode within Revit.

Master it Revit uses a 2D sketch-based approach to modeling. What modeling elements in Revit use this 2D sketch principle to generate their form?

Understand work planes, levels, grids, reference planes, and reference lines. Using these tools gives you the ability to better control your model and your design by applying and controlling parameters.

Master It In order to sketch a form, the form must reside on a work plane. How do you define and visualize the work plane in Revit?

Chapter 7

Modeling Principles in Revit II

Creating a BIM model requires modeling in 3D. This is very different from working with abstract 2D lines in order to represent your design. To work with Revit and be able to build a BIM model, you must understand how objects are constructed at various scales ranging from the building mass down to furniture assemblies. You need to know how various building elements interact and depend on each other, what materials they are made of, and how they are constructed and assembled. To this end, Revit provides a set of tools that enable you to model all the elements that go into the model. Understanding the principles of modeling in the context of Revit is essential to your success as you move deeper into building information modeling.

This chapter is the second part of a description of the basic modeling principles that support the design process in Revit. In this chapter, you'll learn to:

- ◆ Understand the principles of modeling in Revit
- ◆ Model with five basic forms
- ◆ Combine solids and voids to create complex and intriguing forms

Understanding the Principles of Modeling in Revit


Revit is much more than a 3D modeler. It was designed specifically for architects and has behavioral rules built into many of the architectural elements that make up the model. For example, walls are usually vertically oriented rectangular shapes; floors and ceilings are horizontal shapes with constant thickness. These major building elements use 2D boundary lines to generate 3D geometry, as these types of elements tend to have a consistent thickness. This is one of Revit's major differences when compared to a generic modeler that lets you model anything, any way you like. In essence, with Revit the type of element you are modeling will present a tailored set of creation tools. This approach to software tools becomes more apparent in Revit 2010, with the introduction of a new set of conceptual modeling tools designed to support free-form modeling in the early phases of design development. We'll delve into more specific methods of modeling throughout this chapter.

Revit provides specialized tools depending on the element you are creating. For example, you draw a wall by defining its start and end points, which will determine its position and length, while the width and height are determined by the instance and type properties of the wall. The wall becomes a 3D element immediately with each click of the mouse. Roofs, floors, and ceilings,

on the other hand, require you to enter a 2D drawing mode to define the boundary shape. Their thickness is defined in the type properties. To create conceptual models, you start by drawing lines, and then select them to make 3D forms. Once you've made a form, you can then modify it directly using interactive controls on edges, faces, and vertices. We'll dig into the specifics of this toolset in the next chapter.


Once the envelope of the building has been established (walls, floors, and roofs), you progressively add more elements—windows, doors, furniture, plumbing fixtures, and so on—to the model. These building components rarely depend on the context of the building and are usually manufactured offsite at a factory in real life. Somewhat similarly, in Revit many components are predefined and saved in a library for use across multiple projects. These loadable components are all created in the Family Editor using a combination of simple geometric forms that can be associated with parametrically driven dimensions and materiality. For example, a chair can be created with a combination of sweeps, blends, extrusions, and revolves. The same applies to a light fixture, a bench, a plumbing fixture—you name it. Figure 7.1 shows samples of standard “loadable” family types.

FIGURE 7.1
These windows
and doors are
standard loadable
components.




The Family Editor allows you to create components of any flavor. In some cases, the flexibility of the Family Editor modeling tools can be useful in the context of your project. When you want to create a custom design feature that is tightly related to the context of the building or the landscape around it (such as an entrance canopy or a reception desk in a welcome area), you'll need a robust set of tools that are not part of the basic wall, floor, and roof tools. To access the full range of Family Editor modeling tools in a project file, use the Model In-Place tool located in the Component drop-down on the Home tab (see Figure 7.2).

FIGURE 7.2
The Model In-Place
tool located under
the Component
tool of the
Home tab.





You can use the same features of the Family Editor to create your geometry. Figure 7.3 shows a fireplace built as an in-place model.

FIGURE 7.3
Example of an
in-place model.



Another workflow where free-form modeling comes into play is at the early stages of conceptual design, where massing studies are explored. With massing, the tools need to be flexible and not constrained to a specific use case. In Revit, these mass forms are created with the Massing tools as combinations of various geometric shapes. In Revit 2010, when making massing forms using the conceptual design tools, the interaction with form is intended to support free-form creation and direct manipulation of forms. You do not enter a “sketch mode,” but rather edit forms directly. Figure 7.4 shows a massing study using Revit’s form-making tools.

FIGURE 7.4
Example of
massing concept
studies.



Courtesy of Gensler


Modeling with the Five Basic Sketch-Based Techniques

When creating standard components, there are five basic form-making options in Revit. With these techniques you can create a variety of shapes for various scales of design. By combining forms and using forms as subtractive elements, you can model nearly anything in Revit. The five primary modeling techniques used for making components in Revit are:

- ◆ Extrusions
- ◆ Revolves
- ◆ Sweeps
- ◆ Blends
- ◆ Swept Blends


These are accessible from the Family Editor when you're creating Solid or Void forms, and are also available when you're making in-place family components within the Project environment (Figure 7.5).

FIGURE 7.5
The standard form-making types.



You can choose to create either solids or voids when making 3D forms. Selecting Solid Form or Void Form from any of these toolbars displays the options shown in Figure 7.6.

FIGURE 7.6
Solid and Void Extrusion, Blend, Revolve, Sweep, and Swept Blend options.




Extrusions

An *extrusion*, the simplest of all modeling transformations, is derived from a 2D loop (a closed chain or chains of line segments) drawn in a plane that has a thickness value. The thickness is always perpendicular to the work plane of the 2D lines (see Figure 7.7).

FIGURE 7.7

An extrusion is a 2D shape with thickness.




The element properties of an extrusion allow you to set the thickness of the extrusion as well as an offset from the work plane it was drawn on.

Extrusion Start This defines where the extrusion starts and has a default of 0, but it can have any positive or negative value. The effects of this parameter are shown in Figure 7.8.


FIGURE 7.8

(A) Extrusion start is set to 0; (B) has a positive value and starts above the work plane; (C) has a negative value and starts below the work plane.



Extrusion End This parameter defines the end of the extrusion relative to the work plane. This value can be positive or negative. The default is set to $1''-02$ (250mm). The total thickness of an extrusion is the difference between the extrusion end and extrusion start.

When an extruded element is selected, check the contextual tab and the Options bar for relevant options.




Edit Extrusion This button takes you back to the 2D editing mode so that you can make changes to the underlying shape. Once you have changed the shape, don't forget to click Finish Extrusion on the Ribbon.

Depth Depth defines the value of the extrusion thickness. This value can be positive or negative. With vertical extrusions, the depth actually is the height of the extrusion.

Visibility Settings Visibility Settings define in which view types or levels of detail the extrusion will be visible. Figure 7.9 shows that the selected extrusion will be visible only in plan and reflected ceiling plan views, and only in medium and fine levels of detail. Setting the appropriate Display and Detail Level will improve printing, exporting, and overall graphic performance.


FIGURE 7.9
Forms can be made visible or invisible in different views and at different levels of detail.



Edit Work Plane This button allows you to change the work plane of the extrusion. You can only set a new work plane if it is parallel to the existing work plane of the extrusion.

Figure 7.10 demonstrates how a furniture element can be constructed from two extrusions that create the entire shape.


FIGURE 7.10
A cozy lounge chair made of two simple extrusions.



DIRECTIONS IN A REFERENCE PLANE

The direction in which you draw a reference plane determines which way is positive and which way is negative.

These images demonstrate in plan view how the direction in which the reference plane was drawn affects the direction of the extrusion.




Because it is difficult to remember which way you drew each reference plane, we suggest that you name each reference plane you create. If you do that, you will see the name of the reference plane when it is selected, and the name is always placed at the end of the direction in which it was drawn.



When you use the face of an element as a work plane (rather than a reference plane), as shown in Figure 7.11, the direction of the extrusion will depend on whether you are making it a solid or a void shape.


FIGURE 7.11
A void extrudes
into the solid face.



When you sketch a shape that is going to be a void, the void extrudes positively toward the interior of the object that you used to define the work plane.

When you add a solid shape, the shape extrudes positively away from the exterior of the object face, as shown in Figure 7.12.

FIGURE 7.12
A solid extrudes
away from the
solid face.




Revolve

A *revolve* takes a 2D profile and rotates it around an axis. A revolve is composed of two elements: a 2D profile (think of this as a cross section) that will define the surface once it is revolved, and an axis that the profile revolves around. As with extrusions, the profile must be a closed loop of lines for the revolve to be valid. The bollard shown in Figure 7.13 is an example of a revolve form.

FIGURE 7.13


A revolve consists of a closed loop of lines and an axis of rotation.



By default, a revolve follows a full 360-degree path. In the element properties of a revolve, you can adjust this angle so that the profile will appear open, as shown in Figure 7.14. The parameters for the revolve will let you determine the start and end angles:

FIGURE 7.14

The end angle is set to 270 degrees.




End Angle The end angle positions the profile relative to the work plane of the end of the revolution. Figure 7.14 shows a revolve with an end angle set to 270 degrees.


Start Angle The start angle positions the profile relative to the work plane at the beginning of the revolution. By setting the start angle to a value other than 0, you can get shapes like that shown in Figure 7.15.

FIGURE 7.15

The start angle is set to 90 degrees and the end angle is set to 270 degrees.



When you select a revolve form, you'll see options similar to those available for an extrusion.



These are similar to the options available when selecting other modeling forms. You can change the 2D boundary that you used to execute the revolution with, set the visibility, edit the work plane, or re-host the form to another plane.

To understand how sketches create revolve shapes, we will look at three different results based on three different types of sketches. Figure 7.16 shows a standard revolve made out of one closed loop of lines; Figure 7.17 shows a revolve made out of two closed loops, where one loop is a subtractive element; and Figure 7.18 shows another revolve with two closed loops, where each loop is an additive element.

FIGURE 7.16

One closed loop of lines revolved around an axis.





FIGURE 7.17

In this example, the two closed loops of lines are placed one inside the other. Following the principle of sketch-based design, the inner loop creates a hole in the first loop.

**FIGURE 7.18**

The two loops are independent of one another and thus the resulting revolution creates two solid shapes.




A revolve can be composed of multiple closed loops to define the profile lines. Keep in mind that a profile must not intersect another profile; if it does, it will fail, and Revit will warn you when you try to finish the revolve. Depending on the positioning of the different profile loops, you can achieve different results, as shown in Figures 7.17 and 7.18.

A common example of a revolve form appears in Figure 7.19. The profile defines the cross section of a dome (cupola) roof. By rotating this profile around the center axis, we can generate a dome form.

FIGURE 7.19

The profile is revolved around the center axis, resulting in a dome form.




THE RULE OF THE AXIS

None of the shapes that are to be revolved can cross the axis of the revolution. They can, however, have an angle other than 90 degrees relative to the axis and can be offset from it.

Another example of a revolve is this doorknob (Figure 7.20), where the cross section is drawn and then revolved around an axis.

FIGURE 7.20

A revolve can be used to create elements such as doorknobs as well.




Sweeps

A *sweep* is conceptually similar to an extrusion, but you must define a path for the extrusion profile to follow. The resulting form is generated by sweeping the profile along path segments. The profile is always swept perpendicular to the path segment it follows.


A sweep is defined by two sets of lines: the *path*, and the *profile* that you sweep along the path. The path can be drawn on any work plane, and the profile will always be drawn perpendicular to the path. The first segment of the path you draw determines the default work plane for the profile lines. To change the default location of the profile sketch plane, delete the line segment of the path that hosts it; the profile plane will jump to the next available line segment in the path. Figure 7.21 shows a swept form, along with the path and profile used to create it.

FIGURE 7.21

Example of a sweep. The dashed rectangle is the profile plane, which is always perpendicular to the path.



DEFINING THE SWEEP PATH




You can make a path by either selecting existing geometric edges (imported lines, edges of other forms) to create new lines or drawing lines directly. The options shown here are available on the Mode panel when making a sweep.

When using the draw method, you'll be able to pick and draw lines. However, the path must be in the same plane. The Pick Path method allows you to create a 3D path. When you enter the Pick Path mode, click the Pick 3D Edges button, and then pick edges in the model. Note that with this method of defining the path, you will not be able to draw lines—you must pick off of existing geometry.

With this method, you create a dependency between the swept element and the object that you selected for edges to define the path. Thus, when the geometry of the referenced object changes, so too will the swept element. We strongly recommend working in a 3D view when using this method, as it will make it easier to understand the relationships and effects of changing geometry (Figure 7.22).

FIGURE 7.22
Example of a sweeping path that is created by selecting existing edges of a solid geometry (in this case a wall opening). If the opening changes its size, the sweep will also change because of the dependency established with the Pick method.




DEFINING THE PROFILE

A profile can be created using one of two methods: by drawing the profile directly or by using a loaded, predefined profile. These options are shown in the Ribbon when defining the profile for the sweep. The default, By Sketch, lets you draw the profile using standard draw tools. Click the Edit Profile button to bring up the Draw/Pick Gallery and start drawing lines. Once a profile has been loaded, it will show up in the Profile drop-down list.

This method is applicable in cases where you need to sweep the same profile on many paths. For example, you would first create a 2D profile family using the Profile (imperial) or M_Profile (metric) template. The profile has to be a closed loop of lines. Save the profile on your hard drive and then load it in your project or family.

Figure 7.23 shows the drop-down list and the Edit Profile and Load Profile buttons.


FIGURE 7.23
The default method for creating profiles is by sketching. You can also load premade profiles and use those.



If you use a loaded profile, you are given controls to position the profile relative to the X and Y axes (see Figure 7.24). These values are distances from the point of insertion of the profile (the intersection of the two reference planes in the Family Editor) and the point of reference of the profile and the path (the green cross). The values are editable in the Options bar, and will update if you move the profile interactively as well.

FIGURE 7.24


Offsetting the profile from the point of reference of the path. In this profile, the crossing of the references in the Family Editor was set to the lower-left corner of the profile. Thus, the offset values start from that point.



You can rotate the loaded profile by adding a value under the Angle option (see Figure 7.25). The Flip button mirrors the profile, if you need it. Click the Apply button on the Options bar to finish placing the profile.

FIGURE 7.25

The angle of rotation is applied to the profile that is to be swept.




Once a sweep is created, you can always change the values that are available in the Element Properties dialog box of the sweep, shown here:

Parameter	Value
Constraints	
Work Plane	Level : Niveau 0
Horizontal Profile Offset	0.1000
Vertical Profile Offset	0.0500
Angle	0.000°
Construction	
Profile	Plinth : #01

The advantage to using premade profiles is enormous. Figure 7.26 illustrates a concrete example of a sunshading family that needs to be edited.

FIGURE 7.26

Sweeps can be used to create a sunshade.



If you had drawn your profile manually and then used the Copy Multiple command to repeat the shade, you would need to change each shade separately to apply a new profile. However, if you had drawn the shape as a loadable profile family and loaded it into the family, you would only need to change the profile family once and reload it. All instances of the profile will update automatically when reloaded.



Real World Scenario

PUTTING THE SWEEP TOOL TO WORK


Here are some real-life scenarios in which the Sweep tool is very handy. We'll let the pictures do most of the talking.

First consider the modern shower fixture in the bathroom shown here:




Courtesy of Gianluca Nicholas Lange

This design was created as a simple sweep on a circular path:



The architectural example shown next demonstrates another use of sweeps: to create a highly specific wall shape. The retaining wall was created as an in-place wall using the Create function and the Sweep method.



Courtesy of E. Di Giacomo

TRAJECTORY SEGMENTATION

The Trajectory Segmentation parameter (see Figure 7.27) provides a way to segment smooth arcs into linear segments. This can be useful when you're rationalizing a form into planar, constructible elements.

FIGURE 7.27

Sweeps can be segmented using the Trajectory Segmentation parameter.


Parameter	Value
Graphics	
Visible	☒
Visibility/Graphics Overrides	Edit...
Materials and Finishes	
Material	<By Category>
Identity Data	
Subcategory	Name
Solid/Void	Solid
Other	
Trajectory Segmentation	
Maximum Segment Angle	1350.000°

When the option is checked, it makes the parameter Maximum Segment Angle active. The value you set defines the maximum value of the angle between two segments of the arc. The smaller that value, the higher the number of linear segments that will replace the arc. Figure 7.28 shows the effects of this parameter.


FIGURE 7.28

An arc path can be segmented using the Maximum Segment Angle parameter.


Trajectory before segmentation




Maximum Segment Angle = 30°



Maximum Segment Angle = 60°



Maximum Segment Angle = 90°




Blends

A blend creates a form by connecting two different 2D shapes on two different planes along a linear path (see Figure 7.29). The distance between the two shapes—the base and top—is what defines the depth of the blend. The two shapes for the top and base of the blend do not need to be the same shape or have the same number of segments. Revit can even blend arcs into linear segments.

FIGURE 7.29

A blend is created from two sketches that blend together along a linear path.



When the top and base shapes are the same, the resulting form will look exactly like an extrusion or sweep along a single, linear segment. You can think of a blend as an extrusion with two sketches—one for the base, and one for the top.

The instance properties of a blend resemble those of an extrusion. You can set the blend depth as well as the offset from the work planes on which the shapes are drawn:

First End This defines the offset of the base shape relative to its work plane. This value can be negative or positive. The default value is set to 0.

Second End This defines the offset of the top shape relative to the work plane on which the blend is drawn. This value can be positive or negative. The default is set to 1'-0" (250mm).

The total depth of the blend is the resulting value between the first end and the second end.

When a blended element is selected, look to the Modify Blend tab, where you'll be able to reedit the base and top, change the work plane, and re-host the blend:




As you can see, these are the same as the options you had for extrusions, with the addition of two other features that take you to the sketch of the base or top of the blend:

Edit Blend Base This allows you to enter boundary edit mode, where you can modify the top boundary.

Edit Blend Top This allows you to enter boundary edit mode, where you can modify the base boundary.

Whenever you select one of those two options, the Ribbon will update as shown in Figure 7.30. Click Finish Blend to complete the blend.

FIGURE 7.30
The contextual ribbon for editing a blend form (left and right sides shown).



When creating blends, the boundaries are drawn on a single work plane; this means that the two shapes will always be parallel to one another.

The Vertex Connect tool is specific to blends, and it shows up in the Ribbon when you're editing the blend boundary lines. This tool allows you to set the connection between the vertices that the two shapes have. Manipulating the vertices alters results in the final blend.

When you click the Edit Vertices tool, you see graphic controls indicating existing connections between the vertices of the blend shapes.

There are two different things you can do here:

Twisting After selecting the Edit Vertices tool, a new contextual tab will appear with the options Twist Right, Twist Left, and Reset, and the ability to edit the controls at either the base or top.



These options control the number of twists between the two shapes. In Figure 7.31, image A shows a basic blend between two 45°-oriented square shapes. Image B shows one additional twist, and image C shows yet another twist.

Editing Vertices This is another way to affect the blend in order to arrive at alternative shapes. By clicking one of the open blue circle controls that appear when you first select the Edit Vertices tool, you can change the direction of the vertices by clicking on the control. Once you change the connection point, the circle will be filled in solid blue, and a line will be drawn showing a preview of the connection from one vertex to another. Revit connects the vertices from the base shape to the top shape in an automated way with each click. But each of the vertices has an option to be connected to the top vertex that lies to the right of it, or to the left, or both. The example shown in Figure 7.32 demonstrates how the same blend with the same base, top, and depth all look different depending on the vertex connections.

TROUBLESHOOTING BLENDS

When the base shape of a blend has the same number of vertices as the top shape, the results are pretty much predictable. But often the number is not the same and you may not get the results you expect or desire. Here's a tip to consider when working with more complex blends: if one of the shapes is a circle, you might want to break it up into segments to get additional vertex points so that you arrive at a shape you need, as shown in Figures 7.33 and 7.34.

FIGURE 7.31

Various looks for the same element depending on the number of vertex connections or twists: the form shown can be either a tower shape or a table leg.




FIGURE 7.32

Changing vertex connections results in different blend forms.




FIGURE 7.33
A standard blend you will often see, with the base shape a square and the top shape a circle.






FIGURE 7.34
The same shapes with the circle split into four segments to add three more vertices. In example A, the vertex points are orthogonal; in B, they are rotated 45 degrees. Note the difference in the results.




A




B

CREATING A LAMP WITH BLENDS AND SWEEPS


A real-world application of blends and sweeps can be seen in the Revit lamp family illustrated here:



The shade is constructed using a blend between a segmented circle for the top (A) and a more complex series of arcs for the base (B).



The top boundary has been divided into many segments to match the number of vertices of the base. This file can be found in the Chapter 7 folder on the book's companion web page if you want to explore it some more on your own (PS_Lamp.rfa).



The legs of this lamp were made using sweeps. A void extrusion was used to cut the bottom of the legs horizontally so that the lamp sits flat on the floor.




EXAMPLES OF BLENDS IN PRACTICE

The shapes in Figure 7.35 are inspired by the lamps of sculptor and designer Isamu Noguchi, but as you can imagine, they could just as easily represent a lamp, a column, or the shape of an entire building. They are constructed as simple combinations of connected blends.

FIGURE 7.35


A series of blends used to create a more complex form.



The blend boundaries cannot contain more than one loop of closed lines. If your intention is to create something like the lampshade shown in Figure 7.36, you need to add a void, or use a revolve. If you try to make such a shape using multiple loops, Revit will give you a warning message telling you that “more than one loop is not allowed.”

FIGURE 7.36

This blend sketch with multiple loops is not allowed and would generate a warning message.



To obtain the result needed, you need to first create a solid blend and then a second one, done with a void that has a smaller radius, as shown in Figure 7.37.

FIGURE 7.37


A lampshade can be made by creating a void blend that is smaller than the solid blend.



Swept Blends

The swept blend is a combination of a single-segment sweep with a blend. The principles for creating a swept blend follow from the sweep and blend workflow. With a blend, you have no control over the path: it is always perpendicular to the sketch plane. With the swept blend, you can create arc paths for the profiles to blend along. Examples of this include a roof or roof segment with a shape that changes over a nonstraight path, an elbow pipe that changes diameter between the two ends, funky furniture shapes or parts, and walls beneath curved stairs. Note

that a swept blend can only contain a single line segment for the path. If you draw more than a single segment, Revit will issue this warning: “More than one curve not allowed.”



CONSIDER YOUR OPTIONS

Before making a digital model of your components, you need to analyze the basic geometric shapes that are used to create such a form. Is your object best modeled as an extrusion? A blend? A sweep? A blend with a void cut in it? Think carefully how the object is made, how it is assembled, and the tools that Revit provides to plan your modeling strategy.

Combining Solids and Voids

Many complex shapes go beyond the basic form-making techniques we just explored. Designs often require a combination of forms that are both additive and subtractive. To accommodate richer modeling, Revit approaches this problem by allowing any form to be solid or void. Solids are positive, physical elements, and voids are invisible, cutting elements that remove form from solids.

All the forms we covered (extrusion, revolve, sweep, blend, swept blend) can be made as either a solid or a void, as seen in the Create tab of the Family Editor.



NOTES ON SOLIDS AND VOIDS

Keep the following in mind:

- ◆ Voids that don't cut a solid and solids that are not joined may be switched from one to the other (from solid to void and vice versa) from the properties dialog box. Once they are joined or cut, they cannot be toggled in this way.
- ◆ Once a void is cut, it is no longer visible unless selected. However, because the void is no longer visible once it's cut, it may be helpful to model voids and solids as solids. Then switch solids to voids and use the cut geometry command as appropriate.
- ◆ All solids can be cut by the same void, but they do not have to be if you prefer not to.

Examples Showing Use of Voids


Voids can be used in many ways to arrive at some surprising geometric forms. Think of a void as a way to carve away from a solid chunk of clay. You can truly sculpt with this tool!

VAULTS

In Figure 7.38, complex vaults have been created out of a solid pentagonal extrusion and half-circle void extrusions are cutting through it.

FIGURE 7.38

Vaulted space created out of a combination of solid and void extrusions.



JOIN GEOMETRY TOOL SOLVES GEOMETRY CONNECTIONS


You will need to use the Join Geometry tool to have the void cut the solid.

VERTICAL SHAPES

The basic shape of the table legs shown in Figure 7.39 is a simple blend. A plow shape is used at the base, and a triangular shape is defined for the top (A). Then a simple curved shaped void extrusion is used to carve out the blend (B). The result is an interesting shape that is far more complex than what you'd expect to be able to do with the four basic modeling forms (C-D).

FIGURE 7.39

A blend with a void extrusion results in some very interesting forms!




COMPLEX ROOFS

A shape like the one shown in Figure 7.40 could be created using two revolved shapes and then cut off using a void square around the edges.

FIGURE 7.40


Use of a simple void to cut out geometry from a revolved shape.



Courtesy of Lillian Smith

WHERE CAN YOU GO FROM HERE?

Mastering the modeling techniques in Revit and understanding the power of parametric relationships will open doors to some powerful modeling skills. In order to construct custom components, you'll need to become familiar with the toolset, and once you do, you'll be able to model nearly anything you can imagine. We've walked through the basic form-making tools for generating components. In the next chapter, "Concept Massing Study," we'll get into the new form-making tools that were added to Revit 2010 for making building mass forms. You'll see that making complex building forms in Revit is no longer science fiction, but right at your fingertips!



Courtesy of Zach Kron

The Bottom Line


Understand the principles of modeling in Revit. Understanding how to use Revit's modeling tools is an important part of project documentation. Knowing which modeling tools to use when will aid not only in project visualization but also in documentation, scheduling, and rendering.

Master It There are many unique design elements in any project. Know when to use the appropriate modeling tools at the right times. What tool in Revit might you use to model the following elements?

- ◆ Reception counter
- ◆ Entry canopy
- ◆ A lampshade
- ◆ Custom furnishings

Model with five basic forms. These tools are at the root of practically all form modeling.

Master It Having learned the basics of Revit's form-making tools, how would you build this faucet designed by Philippe Starck?



Master It In some cases, a form uses multiple sketch lines to generate its form. What form-making tools in Revit use more than one set of 2D sketches to generate the form?

Combine solids and voids to create complex and intriguing forms. Revit's five basic forms can be expressed as either positive space (solids) or negative space (voids).

Master It To make more complex forms, both solids and voids can be used. Think of a case where the using voids as a subtractive element makes sense.

Chapter 8

Concept Massing Studies

In this chapter you'll explore the early stages of design and how to generate initial massing studies used to iterate on design concepts. We introduce you to the tools in Revit that support early conceptual design workflows where the form is not only explored but also rationalized. Revit allows you to maintain continuity in design data as you move from the massing study into real building elements, making it possible to easily transform massing studies into buildings that can be documented and eventually built. We discuss various approaches for creating massing studies and the underlying principles of creating parametric mass elements using the new conceptual design environment. We will also introduce you to a method for rationalizing massing surfaces.


In this chapter, you'll learn to:

- ◆ Understand massing workflows
- ◆ Start a conceptual massing study
- ◆ Understand form making and rationalization

Understanding Massing Workflows

There are many ways to start a new design. It often starts as a series of early sketches that convey form and function related to the project brief. These first ideas often encapsulate the essence of the design and, unless some unforeseen changes are demanded in the design, are usually easily recognizable in the final building. Many architects are known for the remarkable similarity between the first sketches of their ideas and the final outcome of the built buildings, as can be seen in drawings by architects such as Frank Gehry, Jorn Utzon, Daniel Libeskind, Frank Lloyd Wright, and countless others. Figure 8.1 shows a hand sketch using very gestural lines, tones, and hatches. The ability to sketch freely and with gestural expression is a fundamental aspect of design iteration and has been part of the architectural profession for centuries.

FIGURE 8.1
An inspiring early sketch.




Courtesy of E. Di Giacomo

Architects have long realized that the only way to make investors buy into their early ideas and designs is to make those early designs understandable to them. Many investors have difficulty reading technical drawings, so architects use creative methods to communicate the design, the space, and the experience of that space from the early stages of the design on. Perspective drawings, photo collages, and 3D physical models made of wood, Styrofoam, cardboard, balsa, Plexiglas, and metals are all used to help the client, and sometimes the public, understand the implications of a given design. Increasingly, with the pervasive use of digital tools, 3D printed models and laser cut models are being used.

In more sophisticated design studios, physical models are constructed so that the design can be evaluated by deconstructing the model into parts representing different levels or functional parts of the building. This allows people to examine individual stages of construction and integrated systems. Models can range in fidelity from very rough massing studies to highly photorealistic models, as Figure 8.2 demonstrates.

FIGURE 8.2

Models can range from very rough (A and B) to highly refined representations (C and D).



Three-dimensional physical models offer some obvious advantages for conveying design intent:

- ◆ You get an immediate feel for proportion, scale, and composition
- ◆ You get a sense of spatial volume
- ◆ Light and shadow can be easily simulated by holding a real lamp near the model and observing the shadows
- ◆ If you model the surrounding site, you can easily understand how your design relates to its context

Three-dimensional physical models also have some potential disadvantages:


- ◆ They take a lot of time and patience to create
- ◆ They require space for creation as well as storage

- ◆ They are created in one scale only
- ◆ They can't handle design options easily and thereby require building multiple models to convey each design option
- ◆ They require manual work—both in the physical modeling and in performing calculations of area and space
- ◆ They can be costly in terms of skilled personnel, materials, and equipment

As clients become more demanding, they aren't satisfied with just understanding how the future building will look but also want to know how the building will perform in terms of lifecycle costs. With sustainability now an integral part of the design process, they also need to understand how the building will function over time from an energy point of view. BIM makes this process much more viable, as you are building much more than a mere physical model. The forms you make in Revit can be used to do early sun studies, area analysis, and energy analysis. Multiple iterations can be generated for comparison. Making a final decision is not always easy, but the ability to compare and contrast multiple proposed solutions in order to arrive at an optimized design solution makes it easier for you and your clients.

To accommodate all these requirements, architects and owners need to analyze the building and experience it in the early stages of design before it's ever built. Traditional hand-built models don't provide this kind of analytical flexibility. This is where using digital models backed up by real data come into play. See Figure 8.3.

FIGURE 8.3
Early massing studies.



Courtesy of Gianluca N. Lange

Massing Study Workflows

Regardless of how a massing study is done (digitally or in a physical medium), there has always been a break in the workflow between the conceptual design phase and the next phase of more detailed analysis of how the building will behave and be constructed. In the case of a built

physical massing model, once you've built one, moving that model forward into more detailed design requires that you create a digital project from scratch, usually in a tool such as AutoCAD. The 3D model is not inherently reusable downstream.

Even when you make a study using digital tools such as Rhinoceros, SketchUp, Form-Z, Maya, or 3ds Max, in order to document those studies you still need to start from scratch because these tools are mainly modelers—not architectural documentation tools—and the data created with these tools is not reusable in any intelligent manner. In these cases, the documentation phase traditionally occurs in the form of 2D drawings produced with tools such as AutoCAD.

With the advent of building information modeling, this is all changing, as you can now carry a conceptual model through to construction documentation in one environment. Indeed, an important aspect of using BIM is the ability to move and reuse previously created data throughout the design process, from start to finish—without having to start over. Revit provides a set of tools for converting an abstract mass form into a full-fledged building information model. In Revit, a specific set of tools keeps the design process integrated. For early conceptual studies, you can create models natively within Revit using the conceptual design tools, or by importing geometric massing studies created in other applications. Regardless of how you create the concept massing studies (either within or outside of Revit), they can later be used to generate building elements such as walls, floors, and roofs.



Real World Scenario

COMMON USES FOR THE MASSING TOOLS

Here are some common scenarios where using Revit massing tools makes sense.

SITE STUDIES: USING MASSING TO QUICKLY BUILD THE CONTEXT ENVIRONMENT AROUND THE BUILDING


You can use Revit's massing tools to quickly model the surrounding context of your building to get a feel for how it fits the site. This is a standard practice used to demonstrate how your design relates to its environment. Once you have modeled the environment around your building, you can generate walkthrough cameras that move around your building so you can experience it from different points of view. You can also make solar studies to better understand how your building affects the environment and how the environment affects your design.



Courtesy of Kubik+ Nemeth+Vlkovic

MASSING STUDIES FOR TESTING DIFFERENT DESIGN OPTIONS


You can do a quick conceptual massing study to work out a functional design arrangement, make more options, and look for an optimal solution. For each design, separate masses can be made and given color to indicate their function. This allows you to see spatial relationships in simplified geometric forms but also get precise area and volume values for each mass option you explore.




Courtesy of Gensler

FEASIBILITY STUDIES AND PROGRAM VERIFICATION

You can take the massing study a step further and make feasibility studies to explore how to fit the client's program on the site and calculate the floor area ratio (FAR), mass floor area, and volume. With mode information added to the model, you can get better estimates about building cost, energy analysis, and aesthetics.




Courtesy of RMJM Hillier



Courtesy of Gensler

Three-dimensional digital massing studies allow architects to use advanced technologies and make physical prototypes for demonstration or testing purposes using the 3D printing services that are becoming more affordable. For many architects as well as owners, a physical model is still something they like to have in order to study the design.

Rapid prototyping is the automatic construction of physical objects using solid freeform fabrication. The first techniques for rapid prototyping became available in the 1980s and were used to produce models and prototype parts. Thanks to advances in technology and the increasing affordability of 3D printing, professionals in many fields now rely on rapid prototyping—architects to create models, industrial designers to make first-draft prototypes, and even artists to sculpt complex shapes for fine arts. The process of rapid prototyping takes virtual designs from a digital model, transforms them into virtual cross sections, and creates each cross section in physical space one after the next until the model is finished. This is often done by layering liquid and powdered material for each section and using glue or a laser; the material is fused together as shown here.




Courtesy of Simone Cappochin

The most common file format for sending this data is .stl. The .stl export is not natively built in Revit—you can find a prototype for an .stl exporter for Revit on the Autodesk Labs site, http://labs.autodesk.com/utilities/revit_stl/.

Figure 8.4 shows a rapid prototype model of an unbuilt Louis Kahn building.

FIGURE 8.4
Early massing
studies.



Courtesy of Simone Cappochin

Revit's Massing Tools

There are two ways to work with conceptual modeling tools in Revit—as in-place masses built directly in the project or as loadable families built using the conceptual mass family template. Each method offers slightly different behaviors, which can impact workflow. For example, building out a site context model, which is generally static, might make most sense to do in the project environment, whereas building multiple massing studies that can be swapped in and out of the site model is better handled with family instances. Anytime you have a massing shape that repeats and has some parametric variations in size, think of using a family.

In order to create, study, analyze, and later convert a massing form into a building, you need to understand the available tools first; then we'll walk through a real exercise in which you can experience the entire workflow. If you're in a project already, the massing features can be found on the Massing & Site tab (Figure 8.5). You'll use this tab to create in-place masses, place masses, and model by face (apply Revit building objects to massing surfaces). To start a new conceptual mass family, use the Application Menu ➤ New ➤ Conceptual Mass (Figure 8.6).


FIGURE 8.5

The Massing & Site tab provides tools needed to create a massing study in a project.



FIGURE 8.6

You can start a new conceptual mass family from the Application Menu.




The tools for creating masses in Revit are a bit different than those we discussed in Chapters 6 and 7, “Modeling Principles in Revit I and II.” Rather than using explicit sketch-based tools (Solid Extrusion, Solid Blend, Solid Revolve, Solid Sweep, and Solid Swept Blend), you start with lines and then “create form” by selecting those lines. You can still make extrusions, sweeps, revolves, and blends, and you can also create lofts and surfaces now—but the creation method is a bit different in 2010 for making all of these forms. Once you have made a form, you can then freely manipulate it using interactive controls, temporary dimensions, and parametric dimensions. Click on any surface, edge, or vertex of a form, and a control will appear. Use this control to adjust the form. Figure 8.7 shows an edge being dragged with the control.


Once you've made a form, you can rationalize it by either dividing the surface and applying panels to the surface or applying walls, floors, and roofs to surfaces using the Model by Face tools and Mass Floors (Figure 8.8). Dividing a surface always takes place while editing the family, and modeling by face takes place when in the project environment.

FIGURE 8.7

Use form control arrows to freely manipulate massing.


**FIGURE 8.8**

Using the Model by Face tools and Mass Floors, you can move from concept mass to building elements quickly.



Mass Creation and Visibility Tools


There are two ways to create a mass element in the project environment—by making it directly in the project or by loading it into your project. Let's look at the tools that will help you do this.



In-Place Mass



Place Mass



Show Mass


In-Place Mass tool This method allows you to create a new mass element in the project. When you start this tool, a new tab, In-Place Mass, appears on the Ribbon. (We'll discuss this later in this chapter.)

Place Mass tool This method allows you to place a mass family or load a mass family from your library. To make a mass family, use the method explained earlier, by going to the Application Menu > New > Conceptual Mass.

Show Mass tool In order to support more fluid workflows, the Massing category has a special visibility feature built in that allows all massing to be either visible or not, throughout the entire project. This is a global toggle (similar to how Thin Lines mode works) that will keep you from having to manage mass visibility independently in every view. The toggle is located on the Massing & Site tab. We'll explain this now, as you'll get a warning message as soon as you start a new massing.

Visibility of Mass Elements

When you try to place or create a mass for the first time, you'll most likely get the following message, which conveys information about the visibility of mass elements:



This message can be disconcerting at first unless you understand what is going on. Visibility of mass elements can be controlled either via the Show Mass tool or through the Visibility/Graphic Overrides dialog box. The Show Mass control is a global on/off switch for massing that affects all views temporarily.

When you click the toggle button, all masses, in all views, will become visible. This is great for early massing studies, allowing you to move from view to view and see your mass without having to turn the category on or off in each view separately. When this mode is enabled, it does not affect the Visibility/Graphic Overrides state of your views. This massing toggle is a temporary view control and doesn't affect printed output.

To see the mass elements in specific views only, you should use the Visibility/Graphic Overrides settings for view control. Even when the Show Mass button is turned off, if you activate the Mass setting in the Visibility/Graphic Overrides dialog box, it will be visible in that view.


Keep in mind that to print and/or export massing, you need to turn on the Massing category using the Visibility/Graphic Overrides dialog box.

As you develop your design further by moving from the conceptual phase into the early design development phase, you will start creating the real building components (walls, floors,


and roofs) by adding elements to the mass model. This will slowly but surely obscure the visibility of the massing form. A great way to maintain a view where only massing is visible is to create a 3D view where *all categories are turned off except the Massing category*. To do this, use the Visibility/Graphic Overrides dialog box. Be sure to duplicate a view when doing this, and name the view **Massing** or something appropriate. Figure 8.9 shows two views: one with only the Massing category visible and the other with all categories visible. This is handy when you want to make adjustments to the basic shapes that define the geometry (masses) without being distracted by the presence of the building elements.

FIGURE 8.9

The same model with two visibility states (views) showing only mass, and the full model.



View with only the massing category visible



View with all categories visible

Starting a Conceptual Massing Study

You create massing forms using tools in the conceptual modeling environment. With these tools, you can quickly generate site plans and initial building shapes for early, formal design iterations. You can also divide surfaces and apply repeating components on the divided surface to explore more articulated designs.

Creating a Mass—Basics

When you select the Model In-Place Mass tool from the Massing & Site tab, you're first prompted to name the mass you're about to create. Once you provide a name, the interface transforms and you will find yourself in a mass-creation mode, with a new set of tools (Figure 8.10). Using these tools, you proceed to create the massing form using combinations of solid and void forms.

FIGURE 8.10

The Model In-Place Mass tab.




The tools on this tab are specific to form making and surface rationalization and will be available until you click the Finish Mass button. You'll also notice that the other tabs are still available while modeling an in-place mass—click the tabs in the Ribbon to see what tools are enabled. Various other tools will be enabled or disabled depending on their relevance to massing tasks. For example, the Edit tools will still be accessible under the Modify tab, and Dimension will be available in the Annotate tab. Other tools, such as walls, floors, and roofs, will not be enabled. If you have modeled other building elements, these will not be editable while using in-place massing mode.

CREATING FORM



The tool for creating a massing form is the Create Form command. This tool requires that you first select lines, or edges of existing geometry, to generate a form. If you click the Create Form command, you'll get a warning telling you that you need to select model lines or references (Figure 8.11) in order to generate a form. This warning can seem a bit heavy-handed, but it is basically giving you a hint about how to use the tool. This means you first need to draw lines, and then create form from those lines.

FIGURE 8.11
This warning message appears if you click Create Form without first selecting an input.




Use the tools in the Draw panel to create your initial lines (Figure 8.12). These should all be familiar tools—they allow you to draw lines, rectangles, polygons, circles, arc, splines, and ellipses. Note that there are two types of lines you can make: lines and references. Two differences between the two should be noted: first, lines will be “consumed” into a form when used to make a form, while reference lines will not. Second, reference lines can be used to host other elements, whereas lines cannot. For example, a family can be loaded into a conceptual mass and placed on a reference line, and if that reference line rotates or moves, the family will go along for the ride.

FIGURE 8.12
The Draw panel of line-creation methods.




To get acquainted with this environment, start by drawing a simple rectangle, and click on the Create Form button in the ribbon to make a box. Note that if you de-select the lines before making the box, you simply re-select the lines and then click the Create Form button. You'll notice that selection in this environment will prefer chains of lines over individual lines when lines are connected. In other words, you will not need to press Tab to select a chain. When lines are selected, the contextual tab changes to Modify Lines. Clicking the Create Form button will then create a solid box, as shown in Figure 8.13.

FIGURE 8.13
Lines are used to create a form using the Create Form command.



You can make as many forms as you see fit for any given mass element. Everything you add in the mass editing session will create a single mass instance when you finish. Your decision to make each shape as a separate mass element will depend on what you need it to represent and how you intend to interact with it. For example, one mass element could have five boxes representing five buildings. Or, you could make five separate mass elements for each building. Do you want to move each building independently? Or, will you likely want to move all the buildings together as a single element? Let these kinds of questions guide your decision-making process.

When you've finished modeling, click the Finish Mass button in the Ribbon. After clicking Finish Mass, everything you modeled becomes one mass element. To re-edit the mass, select it and click the Edit In-Place button on the contextual tab.



Direct Manipulation of Mass

Once you've made a form some controls will show up when a mass is selected. These controls will allow for some direct editing by dragging the triangular control grips on the form. You will get different controls depending on whether you are editing the form from the project context or the conceptual design mode. When you're in the project, you'll see blue triangles appear on masses when selected. These controls do not provide temporary dimensions, and the dragging will result in hard-to-predict numeric values (Figure 8.14). Rather than deal with these grips, it is easier to simply select the form and edit it in place. You'll get better interaction and more precise control with the arrow controls (Figure 8.15).

FIGURE 8.14

When a mass is selected, grips appear on the form. You can drag these and change the form.





FIGURE 8.15

For more precise editing and less visual noise, edit the form in place by selecting the surface, edge, or vertex you want to edit.




When you have a surface, edge, or vertex selected, you'll be able to use this control. Press the spacebar to change the orientation of the control to align with local geometry. This is useful if the geometry you are working on is not aligned to the global XYZ coordinates. Note that if the local geometry is aligned with the global XYZ axis, the control will not change appearance with the spacebar.

Boolean Operations


The conceptual tools support essential Boolean operations—such as cutting and joining of intersecting forms. It is important to note that massing forms can be solids or surfaces—something new to the 2010 release (Figure 8.16); however, surfaces cannot be used to cut into solids. We'll explore the range for form topologies later in the chapter.


FIGURE 8.16
Surfaces, such as this loft, can be created in the conceptual massing environment; however, they cannot be joined to solids.



Any form can be either solid or void and can be changed from one state into another state at any time with the Create Form tool (Figure 8.17). Try making two boxes—one void and one solid—using the options in the Create Form pull-down. If the two forms intersect, the void will cut away geometry from the solid.

FIGURE 8.17
You can make a solid or void form with the Create Form tool.







Voids, as the name suggests, create negative volumes that carve away from solid forms, as shown in Figure 8.18. A void will autocut a solid when they intersect, and it can be made to not cut using the Don't Cut tool in the Modify tab.

FIGURE 8.18

A void form intersecting a solid form creates a different form.




Multiple forms can be joined to one another to create connected forms. The Join and Unjoin Geometry tools are available on the Modify tab.

Join Geometry

This tool joins solids to form one connected element. (Note that voids can't be joined together.) It merges the shapes (masses) into one, both graphically and as data (Figure 8.19). To use this tool, select the tool, and then select solids you want to join. Multiple solids can be joined together.

FIGURE 8.19


Joining two masses together creates a single, seamless element.



If you edit the position of one of the joined forms (by pressing the Tab key twice when over a joined geometry), the intersection (called the *Boolean*) instantly updates. If you move one of the joined forms outside the boundary of the other joined form so they no longer intersect, they will still maintain their Boolean relationship. You can see this by pressing the Tab key when your hover over an apparently disconnected form. Both forms will become selected (Figure 8.20). To remove the Boolean, use the Unjoin Geometry command in the Modify tab.

FIGURE 8.20

Joined masses—the first selection in tab order—show that apparently disconnected elements are still one connected form element.



Creating a New Mass Family


You can create your own mass families using the new Conceptual Massing Family Editor and load them later in any project. To create a mass family, you use a special family template called *Mass.rft*. Later in this chapter, we'll guide you through the creation of various mass forms.

CREATING PARAMETRIC FORMS

At any point when making a massing form, you can add dimensions and make them parametric variables. This allows you to control the form precisely via the Element Properties dialog box for obvious values such as height, length, width, and radius.

In the next section, "Understanding Form Making and Rationalization," we'll add parameters as we build forms. A feature unique to the new conceptual design environments is called


“loose labeled dimensions.” This sounds complicated, but it just means that the interaction with parametric dimensions has been loosened to allow more bidirectional behavior. Unlike in the standard Family Editor where a labeled dimension will prevent you from directly manipulating a form, in this environment, you are free to drag a form, and the labeled dimensions update on the fly. You will not be confronted with “Constraints Are Not Satisfied” warnings by dragging something with a labeled dimension, as you might see in the standard Family Editor.



Understanding Form Making and Rationalization

We’ve talked about how to get started on a massing form and some likely workflows you’ll encounter. Now we’ll dig into how to actually create forms, and then we’ll rationalize form using a surface division tool. In the following exercise we’ll guide you through the creation of several types of forms that you can make in the conceptual modeling environment, including extrusions, lofts, sweeps, and revolves. (In the next chapter, “From Conceptual Mass to a Real Building,” we’ll explore creation of special panel components that can be hosted on a surface.) The result will be the mass shapes similar to those shown in Figure 8.21.

FIGURE 8.21
Basic forms that
can be generated
include lofted
surfaces, sweeps,
revolves, and
extrusions.




Making a Parametric Extrusion

First, when you're creating a new mass, it's essential to select the correct family template. In this case, you want to be sure to select **Mass.rft** or **Metric Mass.rft**—the default template if you use **New > Conceptual Mass**. Follow these steps:


1. Choose **Application Menu > New > Conceptual Mass**. In the New dialog box, select the template **Mass.rft** or **Metric Mass.rft** and click the **Open** button.

The Family Editor opens with a 3D view. You'll see a base level and two reference planes in the view. The level sets a starting elevation plane, and the intersection of the reference planes define the origin of the family.

2. Using the **Rectangle** tool from the **Draw** panel, draw a rectangle on **Level 1**. This will be the default work plane, and it will highlight as you draw the rectangle.




3. Click the **Create Form** tool. A box will appear, with a temporary dimension to the top of the box. Type in **100'** to set the height.







- To make the height parametric, click the Make this Temporary Dimension Permanent icon next to the vertical temporary dimension. This will create a dimension.
- Using the Label dropdown list in the Options bar, add a parameter to the dimension—making it parametric.




- In the Parameter Properties dialog box that opens, name the parameter **Height**, group it under Dimensions, make it an Instance parameter, and click OK.




- Now, reselect the top face of the box and drag it up and down. Note how the parameter updates with the direct edit. You'll notice that dragging a face results in overly sensitive precise dimension values—numbers that round to nearest 256th of an inch, for example. To overcome this, click on the Types button in the Family Properties panel to open the Family Types dialog box, and set the value there.




8. Set Height to 120' and click OK. As you can see, the height can be whatever you want in the family environment, but without the parametric dimension, you'll have no way to change the height parametrically once the box is loaded into a project.
9. Open a new project using the Application Menu ➤ New ➤ Project. This will open a blank project. Press Ctrl+Tab to go back to the box you were making.
10. Click the Load into Project button in the Ribbon to load the box into the project. You will be put into component placement mode, in the default plan view. Note that your cursor will show as a banned symbol, indicating that you cannot place the component. This is because the Placement Editor is looking for a face to place your massing box onto. Not a problem—change the placement method to Place on Work Plane in the Placement panel on the Place Mass tab—this will allow you to place the mass family on Level 1 (or any level in your project using the Placement Plane drop-down list in the Options bar).



11. Click to place the mass family, and then hit the Esc key twice to cancel the placement mode.
12. Using the 3D View tool in the Quick Access toolbar, open the default 3D view to see the placed mass. Change the view display to Shaded with Edges, and you'll see a semitransparent box.



13. Select the mass and open the Instance Properties dialog box. Change the Height value to 200' and click OK—you'll see the form update to the new height. Your mass box is now working parametrically.




MAKING A PARAMETRIC MATERIAL

You'll notice the material appears slightly transparent. This is because the material in the project has the same name as in the Conceptual Mass template, and materials in the project always trump those created in the Family Editor that have the same name. The reason for the semitransparent material is so you can visualize mass floors when they are added to a massing form, as shown in Figure 8.22.


To make the material parametric, follow these steps:

1. Go back to the box massing family.
2. Select any part of the form and open the Instance Properties dialog box. Next to the Material parameter, click the small button at the far right. In the Associate Family Parameter dialog box that opens, click the button at the bottom, Add Parameter.


FIGURE 8.22
The transparent material allows you to visualize mass floors.





- 3. Create a new parameter named **Box Material**, group it under Materials and Finishes, and make it an Instance parameter.



4. Load the family back into your project. You'll get a warning that the family already exists. Choose Overwrite the Existing Version.



5. Select the massing element, and open its Instance properties—you should see the new material parameter, Box Material. With this parameter you can now assign any material you want to the mass instance. In this example, we gave the mass a Chipboard material.



Now that you have made a parametric box with height and material parameters, let's see what other forms you can quickly generate with Revit's conceptual modeling tools.


Making a Revolve

A revolve form (Figure 8.23) takes curves and revolves them around an axis. To make a revolve, you simply draw a line for your axis, draw lines to revolve around that axis, select the lines, and


use the Create Form command. Revolves can be made from open or closed profiles. Let's try making one now.

FIGURE 8.23


A revolve form.




1. Create a new conceptual mass family.
2. In the view draw a single straight-line segment—this will become the axis of rotation.
3. Draw an arc offset from the line segment—this is what will revolve around the axis.
4. Select the arc, and then make the radius dimension permanent using the Make Dimension Permanent toggle on the temporary dimension.
5. Add a parameter to the dimension named **Radius**.
6. From the Create tab, choose Aligned Dimension and dimension to the ends of the arc. Make this dimension parametric by adding a parameter to it named **Length**.




7. Select the arc and line, and then click the Create Form button. You will see a preview to two possible forms appear below the form: a revolve and a surface. Hover the cursor over the revolve preview and click on it—this will create a revolved form.



8. Select the top face of the form, and go to the Instance Parameters dialog box. Change End Angle to **180**, and click OK. This will give you a half-revolve form.



9. Select any edge of the form and experiment with dragging the control arrows. You'll notice that the parameters update as you manipulate the form. At any point, you can open the Types dialog box on the Ribbon and enter exact numbers.




Making a Loft

A lofted form (Figure 8.24) is a surface or solid that blends between two or more open or closed curves. For example, if you draw a series of splines on different levels, you can loft between the lines and create a surface. Likewise, you can loft between closed loops and even loft from a closed loop to a single line segment.


FIGURE 8.24

A lofted surface form.




Let's make a lofted form now:


1. Open a new conceptual mass template.
2. Draw an ellipse on Level 1.




3. Select Level 1 and drag it up with the Ctrl key pressed—this will create a Level-2 copy. Set the height of the level to be 80' using the temporary dimensions.



4. Select Level 2 and Ctrl+drag it to make a third level—set the height to be 80' above Level 2.




5. Select the ellipse on Level 1 and press Ctrl+C to copy it to the clipboard.
6. Using the Paste Aligned option from the Clipboard panel, choose Select Levels, and choose Level 2 and Level 3 by holding down the Ctrl key when selecting the levels.




7. Select the top ellipse and rotate it 90 degrees.
8. Select the middle ellipse and rotate it 45 degrees. Use the Options bar for quick numeric entry.
9. Select the three ellipses and then click Create Form. A lofted form will be generated.

Angle: 45




10. Use the View Cube to see the form from the top.





11. Select the form and click the X-Ray command on the Modify Form panel. This will allow you to see the skeleton geometry of the form.




X-RAY MODE

In X-Ray mode, it is easier to select the individual ellipses and make further modifications, such as move, rotate, and scale. X-Ray is a temporary, per element override, and only one element can be shown in X-Ray at a time.

Making a Sweep

Sweeps are composed of a path and a profile that follows that path (Figure 8.25). A path can have multiple segments, so long as they are connected end to end. Profiles can be open or closed; however, if the path contains multiple segments, the profile must be closed.


FIGURE 8.25
A swept form.




Here's how to make a sweep.




1. Open a new conceptual mass family.
2. Start by drawing a spline through points from the Draw panel, on Level 1, that creates a swooping path.




3. Place a reference point on the spline—this will serve as the plane on which we will draw a shape to be swept along the spline.
4. Select the reference point—this will set the active work plane to that of the point, which is perpendicular to the spline.




5. Draw another spline through points on the point you placed on the spline.



6. You can drag the reference point and see that it follows the spine it is hosted on, and by extension the spline you sketched on the point also follows. Select both splines and then click the Create Form button; a swept surface will be created.



7. Select the form and click the X-Ray tool to reveal the path and profile that are being swept:




Rationalization of Surfaces

Once a form has been generated, it is often necessary to divide the form into regular intervals to better understand how a complex surface can actually be rationalized into buildable form (Figure 8.26). Once a surface has been divided, you can then begin to place real building components on that surface. These components begin to suggest an architectural articulation that goes beyond mere massing studies and also begin to suggest fenestration patterns, surface modulation, and surface variations.

FIGURE 8.26

A divided surface with a component family applied.



DIVIDE SURFACE TOOL




To divide a surface, select any surface and then click the Divide Surface tool in the contextual tab.

The default division is a two-dimensional pattern that divides the surface evenly into 12 divisions in both U and V directions. U and V represent a way to show a surface as a mesh that follows the natural contours of a surface. You are probably familiar with XYZ coordinates; well, *U* and *V* are simply the letters in the alphabet directly before that. Start with a simple box, and select a surface to divide—click the Divide Surface button, and you will see the surface disappear and a UV grid appear. You can see a UV division on nonplanar surfaces, as shown in Figure 8.27.

FIGURE 8.27


UV surface divisions.



Changing the UV division of the surface can be done a number of ways: using the Options bar, using the Instance Properties dialog box, or using the Configure UV Layout mode—accessible by clicking the icon that appears on the center of a divided surface when selected (Figure 8.28).

FIGURE 8.28


Click the UV Layout icon to get access to in-context controls.



Divisions can be established using a fixed number or a fixed distance. If you want to start dividing a surface using more concrete sizes, change your division to fixed values. The fixed number will result in nonstandard numbers that change based on the surface. To change the division to use fixed distances, use the Options bar, as shown in Figure 8.29.

FIGURE 8.29

Use the Options bar to change how the U and V division is computed.




APPLYING A PATTERN TO THE SURFACE

Once a surface has been divided, you can apply patterns to the surface. Revit ships with a fixed set of predefined patterns (Figure 8.30) that range from simple rectangles and triangles to more complex hex patterns and brick layouts. To apply a pattern, select the divided surface and use the type selector.

FIGURE 8.30

Use the predefined patterns to create some interesting surface rationalizations.



Patterns are two dimensional by default but can be swapped with 3D components on the fly. We will look at how to make a custom component family and get it onto a surface in the next chapter. Note that you cannot make custom patterns—you must choose a pattern from the preset list.


Importing 3D Conceptual Models Created in Other Applications

We walked through some examples of conceptual forms that can be created directly in Revit. Of course, Revit is not the only 3D modeler out there, and many people have become experts with tools such as AutoCAD, SketchUp, Rhinoceros, Maya, and 3ds Max, among others. All of these tools can still be used, and the geometry you create can be leveraged inside a mass instance or mass family. Importing CAD formats is supported in the conceptual design environment, and you can even divide surfaces from these files. You may want to use imported geometry in several scenarios:

- ◆ You have users who are comfortable with 3D modeling tools such as those listed. They prefer to do the massing there and then use Revit's conceptual analysis capabilities as well as the Model by Face tools to turn the mass into a building
- ◆ There are shapes and NURBS forms that Revit doesn't do easily (or at all), so you need to create the shape in another application. You need not import a whole building shape, as shown in Figure 8.31—it may be just a face of a shape that you'll need later to design a specific portion of a complex-shaped building, such as its roof

FIGURE 8.31

A NURBS shape can be imported into Revit and used as a basis for making building elements.



Courtesy of Matt Jczyk

You can import individual masses (a complex shape, for example) or a fully developed massing study model. Regardless of what the import represents, the strategy is to never import it directly into the project file but to go through a family import:

- ◆ If the geometry is an individual element that you're likely to reuse, open the Family Editor by opening a mass template, and create a new mass by importing the geometry
- ◆ If you have a full study model, it's advisable to import it as an in-place mass family in the project (use the Create Mass tool and then choose Insert ➤ CAD Formats to import the 3D geometry created elsewhere)

We'll talk more in Chapter 9, "From Conceptual Mass to a Real Building," about how the behavior of the imported items depends on how they're imported, whether directly into the project, in a mass family, or in an in-place mass.

The Bottom Line

Understand massing workflows. Using generic forms, you can create early conceptual models and then use the mass to create the walls, floors, and roofs.

Master It You need to explore a design idea early on, in 3D, using abstract forms. How would you do this with Revit?

Start a conceptual massing study. In the project environment, you can make massing forms at any time. For generic forms that might appear in multiple projects, consider using the conceptual mass template and creating mass families.

Master It You've imported a 2D site plan, and now you need to start building a massing study model in the project. How would you approach this with Revit?

Understand form making and rationalization. You can make many types of form using Revit's form-making tools. You can then rationalize your form using the Divide Surface tool. Get familiar with how to go about creating forms, as it's different from in the standard Family Editor.

Master It You have made a form and want to edit it further. What tools can you use to make changes to the form?

Chapter 9

From Conceptual Mass to a Real Building

In this chapter, we describe the use of an early conceptual mass model to help you understand program fit and the creation of early feasibility studies. You'll see how easy it is to convert a massing study—whether done within Revit or imported from another application—into building elements such as walls, floors, and roofs. The premise of a BIM approach to design is that a fluid workflow can be maintained as you move from early concept models into design development and eventual construction documentation, all the while maintaining the same underlying geometry and design intent. Revit provides specific tools that accommodate early massing model studies for program validation and feasibility studies, which can then be quickly converted to real building elements.

In this chapter, you'll learn to:

- ◆ Make conceptual designs and early studies in Revit
- ◆ Build a real building out of a 3D concept mass
- ◆ Use imported geometry from other applications for massing
- ◆ Use smart relationships between the building mass and the underlying mass


Understanding Conceptual Design and Early Studies

A project usually starts with a rough conceptualization of first ideas in which the architect's mind wanders between the creativity of fantasy and the reality of customer needs, merged with the influence of the context, the *genius loci*.

Conceptual designs are the first graphical words an architect exchanges with a client to get approval for the architect's first thoughts and sense the client's taste. When the initial idea is approved, the architect continues in the next stage of development and makes more detailed studies supported by concrete measurements and numbers that prove the applicability and feasibility of the design.

We'll review how this process of initial conceptualization and form finding can be done using Revit. Figure 9.1 shows an example of an early massing study made in Revit. Let's walk through how this workflow is supported.

FIGURE 9.1
Massing study
model.



Courtesy of ADD Inc., USA

Getting Site Data and Building the Context

A project usually starts with a client's wishes, vision, and expectations that are described in initial conversations with the architect. A list of program requirements is compiled, listing the types of spaces the building will have and its rough area. The architect then starts gathering information and data about the site—aerial photos, photos of the site and context, site-survey files with land information, and building footprints and blocks. Using site analysis, program requirements, and creativity, the architect proceeds to study what shape and size building fits best. Variations of the design are studied, analyzed, critiqued, and presented to the client.

Getting site data into the digital model is the first step in moving from loose napkin sketches to a real project. By importing DWG or DGN site information into Revit or using a CSV points files, you'll have a real-world underlay from which to work. (For small projects, this can also be a scanned image of a hand-drawn site situation.)

CAD drawings with site information usually come with a rich amount of information that needs to be culled. Using the Visibility/Graphic Overrides dialog box, after having imported the DWG or DGN file, you can hide unnecessary layers to make the drawings more legible. Setting the correct scale and orientation of the site relative to the building will be the most critical initial steps, and they should be carefully considered during the import.

SCALE

In the Import CAD Formats dialog box, setting the Import units to Auto-Detect usually works well if the CAD file was drawn correctly, that is, at 1:1 scale. If the drawing was scaled, you may find that the scale of the imported file is incorrect. If this is the case, you can rescale the image using Element Properties, in the Instance Properties dialog box.

ORIENTATION

The next step is to deal with the orientation of the imported site plan. Maps are usually created so that north is always at the top, and that is how site information should be displayed in final documents. However, when you're working on developing a site plan, you'll probably prefer to


work in a way that is most comfortable for you, in a way that the site is oriented parallel to your computer screen (meaning you don't have work under some strange angles)—not to true north.



Real World Scenario

ORIENTING A SITE PLAN TO FIT YOUR SCREEN

Suppose you're starting your design study and you open a site plan view to import the CAD file with the site. An imported CAD drawing usually comes in its original coordinates' orientation, with north and south in the vertical axis.




If you open the view's properties, you'll notice that the Orientation parameter indicates Project North.

Underlay Orientation	Plan
Orientation	Project North
Wall Join Display	Clean all wall joins
Discipline	Architectural

By default, the orientation of a view is set to Project North. By changing the Orientation parameter to True North and rotating the True North setting, you can work in a comfortably oriented plan relative to your screen.

In the View Properties dialog box of a plan view, change the Orientation parameter to True North, and rotate true north using Manage > Project Settings > Position > Rotate True North. A rotation control appears in the view. Rotate to an angle best suited to work on. Note that this does not mean you've rotated the project, but rather you've rotated the world.



This procedure is more than enough if you don't intend to send information back to the person you received the file from. However, if you're collaborating with a civil engineer and need to send back the building footprint or an early mass study, you need to establish a connection between the two files so they have the same coordinates. This can be achieved using Linking (an option during the import) as well as the Acquire Coordinates functionality.

Positioning Imported Files Relative to the Revit Project

You can choose an automated or manual placement of the imported file in your Revit project. With Automatically Place (under the Positioning drop-down in the Import dialog box) you have the following options:

- Auto - Center to Center** Aligns the 3D center points of both models.
- Auto - Origin to Origin** Places the world origin of the linked file at the Revit model's origin point. If the linked model was created far from the origin point, linking with this option may put the linked file far away from the main model.
- Auto - By Shared Coordinates** Places a linked Revit file according to the shared coordinate system created between the two files (this is available only if you're linking files). If no shared coordinate exist between the two files, Revit alerts you and uses the Auto - Center to

Center positioning. The Shared Coordinates settings can be found in the Tools drop-down menu; you have the following options:

Acquire Coordinates Allows you to take the coordinates of the linked file into the host model. There is no change to the host model's internal coordinates; however, the host model acquires the true north of the linked model and its Origin setting.

Publish Coordinates Allows you to publish the Origin and True North settings to your linked model. Revit understands that there may be other things in your linked file, and you may not want this to be a global change to the linked file. An additional dialog box appears that gives you the option to name separate locations for each set of coordinates.

Specify Coordinates at a Point Allows you to manually key in X, Y, and Z coordinates relative to the origin or define where you want your (0,0,0) point to be.

Report Shared Coordinates Shows the E/W (east–west) (X), N/S (north–south) (Y), and elevation (Z) coordinates of any point in the model.

Manual - Origin The imported document's origin is centered on the cursor.

Manual - Base Point The imported document's base point is centered on the cursor. Use this option only for AutoCAD 2009 or later files that have a defined base point.

Manual - Center Sets the cursor at the center of the imported geometry. You can drag the imported geometry to its location.

You can import a CAD file so that it appears in all views of your project, or you can import it so that it is visible only in the current view in which you are importing it. You will find these options at the left side of the dialog box.

Remember that for topography files, as an exception to the rule, you should *not* select the Current View Only option because you will not be able to convert the imported file into topography. This might be slightly counterintuitive because this is exactly a case where you would logically import it only in site view because you don't need the topography in any other view (and thus the Current View Only option would have rather been the logical way to proceed). However, because of some settings concerning the site in Revit, you will need to remember this exception. In any other case, if you need to see an imported file just in one view, select the Current View Only option.

If you forget this rule during the import and import the site plan using the Current View Only option, we advise that you delete the import and re-import the file, making sure that the Current View Only option is *not* checked. As you will probably not want the site file to be visible in all other views, you can turn its visibility off in the other views later.

Building the 3D Context

After positioning an imported CAD file in your site plan and reorienting it to true north, you can start building a 3D environment using the massing tools. The base shapes of buildings in the CAD file can be used to generate a massing model of the surrounding site quickly. Figures 9.2 through 9.5 show examples of generic massing of context buildings. Use photos or actual data to establish building heights.

To make a 3D study of the surrounding site, use the In-Place Massing features and begin developing solids out of the existing geometry:

1. From the Massing & Site tab, select Create In-Place Mass. Give the mass a name, such as **context buildings**.
2. Select the Pick Lines tool in the Draw panel (the last icon in the gallery) and the pick lines from the imported file to use as a base for generating 3D masses using the Create Form tool.
3. Select chains of lines individually, and then click the Create Form tool. Use the temporary dimensions and the form control arrow to set exact heights.




FIGURE 9.2
Massing used to
add surrounding
context buildings.




Courtesy of Kubik+Memeth+Vlkovic

FIGURE 9.3
Massing used for
abstract contextual
representation.



Courtesy of Felipe Manrique Diaz, Uruguay

FIGURE 9.4
Massing used to
model existing
buildings on site.



Courtesy of Felipe Manrique Diaz, Uruguay

Program Check and Feasibility

Many of the activities in early design revolve around exploring the commercial viability of the site and figuring out the right mix of uses (for example, residential versus office versus retail). All these uses have different economic returns. Zoning regulations can be complicated in how they allow different amounts of total development based on the mix ratio. In essence, two numbers govern almost all urban properties: floor area ratio (FAR) and lot coverage ratio (LCR). FAR is a number that says how many multiples of the site area the building area can be. LCR specifies the percentage area of the site that can be covered by the building footprint. Usually the architect is required to maximize the FAR by determining the right mix of uses placed at the right location on the site.

At this stage, the problem is not only about forms or shapes but also about the program, construction costs, rents, and the functional distribution on the site horizontally and vertically. The architect usually attempts to determine what physical forms, in what location, and with what use will provide the best economic return to the owner. This study then needs to be consolidated and documented. While studying this problem, the architect may generate tens if not hundreds of slightly different alternatives for numerical comparative purposes. A few of the most promising are then developed further for client and authority presentation purposes.


At early stages in design, you need to check the program and how well your proposed design fits into it. A program can be less or more precise, depending on the client and the task in question. It can be as bold as 15,000 sq. ft. (4,570 sq. meters) offices, 40,000 sq. ft. (12,200 sq. meters)

hotel space, and 20,000 sq. ft. (6,100 sq. meters) retail space for a bigger complex, or it can be an exact number of rooms and spaces when working on one building. Figure 9.5 shows an early massing study annotated to show usage and areas.

The next step is to propose multiple solutions to the client, so proposals with different mixes of functions and spatial solutions can be reviewed and analyzed. This is where the Design Options tools you'll learn about in Chapter 10, "Working with Design Options," come in handy.

FIGURE 9.5

Early study documenting maximum allowed heights and total square footage of a proposed solution.




Courtesy of Kubik+Nemeth+Vlkovic

Architects are constantly thinking about architectural expression, fitting in the site, and accommodating the program. They're also evaluating whether the client's requirements can fit the allowed buildable area and height of the site, zoning regulations, land uses, traffic requirements (they usually always want more), and information about the number of parking spaces and other support functionalities. This phase of the project can also involve shadow studies and energy modeling, as discussed in Chapter 18, "Evaluating Your Preliminary Design: Sustainability."


CREATING MULTIPLE MASSING STUDY DESIGN OPTIONS

Here is a suggested workflow based on a real-world use case.


The architectural firm Gensler created an option set with three options, each with a distinct name. They duplicated the 3D views, made three different variations of the design and schedules to document project information of the three design options early on. In each view, the Visibility/Graphic Overrides were set to display only one option at the time (one set to Option 1, another to Option 2, and the third to Option 3). Doing so not only visually described the new option but also presented the data behind each design.



Courtesy of Gensler



Courtesy of Gensler



Modeling by Face to Make a Building

After a series of iterations and tweaking, the client makes up their mind. One of the solutions is selected, and you're ready to move early massing studies into a real building project. Here is where the Model by Face tools comes into play. With these tools, you can use the mass as a basis for actual building elements and move to the next stage of design, attaching walls, floors, and roofs to the massing surfaces.

This approach has two major advantages over traditional 3D systems:


- ◆ The need to re-create the digital data from scratch is eliminated. Instead of building a new project with walls, floors, and the like, you simply use the created mass as a reference
- ◆ A connection between the building elements made by referencing the mass and the mass itself is established, so that the massing design can change later, and this will automatically update the building elements made out of its faces or floor slices

The nice thing about this workflow is that it also supports the import of massing elements or studies from other tools, such as AutoCAD 2010, Maya, Rhino, 3ds Max, Inventor, or SketchUp, and converts them into Revit mass elements, to which you can then attach walls, floors, and roofs and thus convert the mass into a real building.

Chapter 8, "Concept Massing Studies," discussed the principles of conceptual form making and rationalization, so by now you should have a good understanding of how to create a mass element or an entire massing study using in-place massing or loaded mass families.

In this chapter we'll focus on how to apply building components to your massing—in the conceptual design environment and in the project. The tools for placing mass floors, roofs,

curtain systems, walls, and floors are under the Model by Face drop-down in the Conceptual Mass tab on the Massing & Site tab.



Let's get an overview of the available tools and then examine their real-life application.

MASS FLOORS



The first tool you should know about isn't visible in the Massing & Site tab, but it will show up when a massing instance is selected in the Modify Mass contextual tab. The tool is the Mass Floors tool, which is designed to get early square footage take-offs from your massing model.

Assuming you've created a mass study in which you defined the basic volumes and shapes that will form your building or complex of buildings, you're ready to start setting up levels. Depending on the type of building you're making, code regulations, and functional usage, you can begin to lay out levels for the building. Let's say the maximum allowed regulated height for your building is 70' (22m), and your building is a hotel, which will usually have a 10' (3m) floor-to-floor height. In that case, you can get approximately seven levels.

Switch to any elevation view, and using the Level tool, start adding as many levels as your building needs to have. It's obviously much easier to copy a level graphically using the Multiple Copy or Array command than to manually draw a level seven, eight, or as many times as you need it. However, if you use the Copy or Array method for level creation, you won't create actual floor plan views associated with each of the levels, something that would automatically be done when you manually draw levels. (The difference between drawing and copying a level was covered in Chapter 3.) If that's okay with you, and you don't need floor plan views for each of the levels, then all is well and you can go ahead. If not, and you do wish to have a relevant floor plan generated for each level you are creating, you can either use the Level tool and draw each level or use the Copy method to create levels but then additionally create floor plans from those levels by using the View/Floor Plan tool and selecting which levels should have a floor plan view associated with them.


Once you have established the number of levels your building will have, select the mass and click the Mass Floor button from the Modify Mass tab. (It is good to do this in a 3D view, as you will instantly understand what that tool does.) Upon clicking the Mass Floor button, a dialog box will appear with a list of all available levels in the project. Click the checkbox next to each of the levels you want to generate floor areas for. If you check all levels, a *mass floor* will be created for each level that can be calculated for area. If you want to skip a level because of double room height, for example, don't check that level. You can do this for all masses at the same time or separately for each one. You can also add or remove levels later: anything in Revit can be changed at any time.

Select the levels that intersect your mass and that you want to get area information from, and click OK. You will see the mass sliced by all the levels you selected, and mass floors are indicated on the mass.

Figure 9.6 shows Mass Floors being applied to the main building only. In Figure 9.7, all other masses representing other buildings have also been sliced by the Mass Floors tool.

FIGURE 9.6


Mass Floors tool applied to one of the masses.



Courtesy of Kubik+ Nemeth+Vlkovic

FIGURE 9.7

The different masses can be sliced using a different level selection.



Courtesy of Kubik+ Nemeth+Vlkovic

ASSIGNING LEVELS FOR MASS FLOORS

In cases where you have multiple individual mass bodies representing different buildings, you can have them all use the same levels for the floor slicing, or you can select them individually and have each one use different levels. Imagine you have set up levels at a distance of 3m and have seven levels. You have a hotel building and a conference center building. The conference building might have a floor-to-floor height of 6m, and thus you'd select only Level 1 and Level 3 as floor area slicers—as opposed to the hotel rooms that will need a floor sliced each 3m.


Revit is fantastic because you can add, delete, and reshuffle levels at any moment in your project development without needing to redo work or losing any invested work.

The *slicing* of masses done by the Mass Floors tool doesn't just visually help you understand the number of floors and divisions—it also provides numerical information essential for early conceptual analysis. With the help of this tool, you can find out the following:

- ◆ Floor area
- ◆ Exterior surface area
- ◆ Floor perimeter
- ◆ Floor volume
- ◆ Usage


The Mass Floor Area parameter can be added to schedules, so that you can call out and schedule all parameters associated with mass floors (Figure 9.8).

FIGURE 9.8
Mass floor can
report areas in
schedules.



An additional improvement allows you to get information about the floor perimeter and the exterior surface area (Figure 9.9).

FIGURE 9.9
Floor perimeter
and exterior
surface in Revit
schedules.



- ◆ You can calculate gross floor area, surface area, and volume, and for that you make a schedule of the Mass category
- ◆ You can also calculate and schedule floor area, exterior surface area, floor perimeter, floor volume, usage, and some additional parameters inherited from the mass, all per individual level—and to do that you schedule the Mass Floor category

This provides data that can help you easily create a conceptual analysis and validate the program fit. By scheduling, sorting, and filtering the data of mass floors, you can find out the exterior skin material for each usage on each floor and calculate its percentage against the entire exterior surface of the building. You can do similar calculations for the floor area to determine the total usage of various functions and their percentage relative to the total usable area of the building.

Even though the floor area faces calculate volumetric slices of the mass, they will not show up as 3D volumes. Only the floor area surface geometry becomes a new element in the model.

VERIFYING YOUR DESIGN AND ITS FIT WITHIN THE DEFINED PROGRAM


You can schedule the parameters and values of the masses like you can for any other Revit element. In the earliest phase of the project, you'll probably want to schedule the functional zones. To create an understandable schedule, it's a good idea to give the mass elements you created names according to their function—Hotel, Conference Hall, Parking, Restaurants, and so on—and assign them different colors (materials) so it's easy to visually represent the data. If you need to rename the mass element once it is created, you can do that from the Project Browser—find the mass element in question and rename it using the context menu. You can also add project parameters to the mass elements, such as Public or Private Space, Department, and so on. If you wish to tag those new parameters so that they are shown in a mass tag, you must make them shared parameters and add them in the Massing Tag family. See Chapter 19 to learn about shared parameters and their applicability.

Out of the box, the Mass category in Revit can report the following numeric properties:

- ◆ Gross floor area
- ◆ Gross surface
- ◆ Gross volume


If you create an initial mass study and schedule the mass elements, the schedule reports the gross surface area and gross volume of the entire shape, as shown in Figure 9.10. Note that the Gross Floor Area field is blank: the reason for that is that you can't schedule the gross floor area without first adding levels and creating mass floors, as explained at the beginning of the chapter.

FIGURE 9.10
Example of a mass element without mass floors applied (no floor area faces generated as of yet).



By defining levels and creating floor area faces using the Mass Floor tool, the floor area slices will show in the mass, and the missing information about the gross floor area will be automatically filled in the schedule (Figure 9.11).

FIGURE 9.11
The mass is sliced into floor area faces.



The gross floor area of the mass is the sum of all the mass floor slices related to any given mass element. Periodically, you need to get separate data about the floor area per floor, sorted and grouped by use or function. This is possible by creating a schedule for the Mass Floor category (Figure 9.12).


FIGURE 9.12
Scheduling new parameters can help you make a more accurate conceptual analysis about the usage of space and materials.

Mass Floor Schedule					
Usage	Level	Floor Area	Floor Perimet	Exterior Surfa	Floor Volume
hotel lobby	Level 1	1979 SF	211' - 7 13/32"	1101 SF	19700.02 CF
restaurants	Level 2	1979 SF	211' - 7 13/32"	1101 SF	19788.02 CF
conference rooms	Level 3	1979 SF	211' - 7 13/32"	1101 SF	19788.02 CF
hotel rooms	Level 4	1979 SF	211' - 7 13/32"	1359 SF	22377.30 CF
hotel rooms	Level 5	2468 SF	249' - 8 9/32"		
hotel rooms	Level 6			5836 SF	54346.62 CF
hotel lobby	Level 7	2944 SF	265' - 0 25/32"	2102 SF	30392.79 CF
hotel rooms	Level 8	3128 SF	271' - 7 11/16"	2148 SF	32031.56 CF
hotel rooms	Level 9	3272 SF	278' - 2 1/32"	2183 SF	33261.66 CF
hotel rooms	Level 10	3374 SF	279' - 4 1/32"	2205 SF	34067.64 CF
restaurants	Level 11	3433 SF	281' - 1 25/32"	6131 SF	30055.76 CF

The reported values are useful for further conceptual analysis, as you can apply different cost factors for different exterior skins. For example, you can get a good idea about the cost of making the last five floors of your building using glass skin versus having them all be solid walls.

The massing tools in Revit have been extensively used by many architects. Figure 9.13 shows a project of the firm HOK in which they used the massing tools to produce colored diagrams that are great for explaining to the client the spatial organization of the project. This book is black and white, so you will need to apply your imagination as to how such a color diagram looks. Know that investors love this simple but informative way of understanding functional distribution.


FIGURE 9.13
Transparency and color in massing studies used as a language to explain programming.



Courtesy HOK

Because you can quickly generate metrics and graphics showing the functional distribution of program elements, you should be able to get feedback on the fitness of the design early on. This will in turn allow you to fine-tune the design and make sure you're keeping pace with the client's requirements. Once you've built a parametric massing model, the elements are all adjustable in size and shape, and any change you make will instantly be reflected in the visual and schedule data (Figure 9.14).

FIGURE 9.14
Conceptual mass
analysis.



After you've reviewed a couple of design options with the client, a decision is made and you need to move forward into the real project. Moving to the next stage is simple: you can use the mass to generate building components using specially designed tools. Let's look at these tools now.

MODEL BY FACE: WALLS

You can start using the mass to generate real building elements such as walls. For that you will use the Model by Face ➤ Wall tool on the Massing & Site tab. Note that you can create walls by face only on vertical and inclined faces or arc faces of a mass. Walls cannot be applied to horizontal faces. You can begin applying generic walls that you will later swap out with the exact wall types you'll be using; or, if you want to make early renderings that convey color and texture, you can apply the types of walls that you believe best represent your concept about and texture, material, and color.

Many of the rules and principles behind standard wall creation should be followed here as well. It's important to correctly set your wall location prior to applying it in order to minimize

rework later. Of course, if you make a mistake, you can always fix that later. How you build the mass—to represent the outermost envelope or to represent the interior envelope—will determine how you want to set the location line for your walls. Use the exterior face if you modeled the massing to the exterior envelope of construction. Keep these limitations in mind:

- ◆ Any wall in Revit can be converted into a curtain wall. Unfortunately, this isn't the case with walls created with the Wall by Face option. To make curtain walls, you need to use the Curtain System tool in the Model by Face drop-down list
- ◆ You can't edit the profile of a wall by face (using the Edit Profile tool available to standard walls)—meaning you will not be able to freely carve out shapes from a wall. To do that, you must change the shape of the underlying mass first


MODEL BY FACE: FLOORS

Only after you've used the Mass Floor tool to generate mass floor area faces can you apply real floor elements. Select Model by Face ➤ Floor and start selecting the mass floor area faces to which you want to assign a floor. To create the floors, you will need to click the Create Floors button in the Ribbon or nothing will happen.

To accommodate floor creation in a tower with many floors, for example, you can check the Select Multiple option on the Options bar. You can then begin selecting all the floor area faces to which you wish to apply floors and finish with the Create Floors tool.

The Mass Floor tool slices the mass horizontally, creating horizontal floor plates by default. If you need floors to be sloped (such as ramps), you can always slope them later after applying Floors and the Shape Editing tools available when a floor is selected, or you can edit the sketch of the floor and add a slope arrow when in Sketch mode of the floor (Figure 9.15).

FIGURE 9.15
Click a grip
control to change
the floor slope.




It's worth mentioning that when you create a floor by face, the Options bar includes an Offset parameter.

Offset: 0' 0" ☒ Select Multiple

This isn't the vertical offset of the floor from the level you can find in the Floor properties; it's an offset of the floor sketch from the current floor area boundary. If you add a positive value to the offset, the floor plate becomes smaller than the actual floor area (Figure 9.16).

FIGURE 9.16
Use Offset to make a slab smaller or larger than the floor area face.



MODEL BY FACE: ROOFS

You've learned how easy it is to apply walls and floors to massing faces. Roofs follow the same basic principles but are more flexible. You can create roofs by face on planar faces, arcs, or other shapes created by extrusions, revolves, sweeps, and blends.

Note these limitations:

- ◆ You can't select a vertical face to create a roof
- ◆ Once a roof is created using the Model by Face: Roofs method, you can't edit its sketch to change its shape in plan. If you created a roof by face and need to change its sketch, you must change the shape of the underlying mass from which the roof has been derived; only in that way can you affect the shape of the created roof

MODEL BY FACE: CURTAIN SYSTEM

Curtain systems are a handy tool for dividing a façade into regular intervals of panels and mullions. With one click, you can convert the face of a mass into a curtain system with predefined parameters to match your needs. Curtain systems can be applied to any face and are composed of grids, panels, and mullions. Make sure the curtain system type you choose has a predefined Curtain Grid layout.


Keep these limitations in mind:

- ◆ You can't edit curtain system sketches. A curtain system made by face requires editing the shape of the underlying mass
- ◆ You can't always predict the XY coordinate system applied to the face. You may have to make new types in order to meet your requirements
- ◆ Only masses that are planar or curved in one direction can host custom curtain panels. Compound curved systems have to use the default system panel

Technical Details You Should Be Aware of When Scheduling Mass Elements


It's important that your mass model be modeled properly from a geometrical point of view in order to support accurate area reporting and downstream applications of walls, floor, and roofs. Look at the towers shown in Figure 9.17. If you simply draw the two towers and schedule them, the schedule reports the values for the individual towers.

FIGURE 9.17
Unconnected mass forms and their schedule.




If you move the position of the towers so that they intersect, the schedule reports the same calculated values: Revit doesn't join the geometries and eliminate the overlapping areas automatically (Figure 9.18). If you place different masses that aren't joined and overlap, when you use the Floor by Face tool the intersecting portions of floor slabs overlap and cause duplicate area calculations. To resolve this issue, you need to join geometry.

FIGURE 9.18
Mass forms inter-
sect but are still
not joined; the
schedule still
reports the sum
of the area and
volume.



To get the correct schedule that represents the actual volume, surface, and floor area values, use the Join Geometry tool on the Modify tab. Whichever mass you used first is the one that penetrates into the other mass. The schedule now reflects the values of the joined, merged geometries (Figure 9.19).


FIGURE 9.19
Mass forms are
joined. The sched-
ule reports the
correct surface and
volume.



Joining the masses creates a relationship between the two masses. This means that if you move the location or edit the shape of one, the joined geometry (Boolean) automatically updates. Only in cases where you move one mass completely away from the other mass will you get an error message that the two masses don't intersect anymore, and you will need to use the Unjoin Geometry option to fix the error.

Once the masses have been joined, you can begin to apply elements to the mass surfaces (Figure 9.20).

FIGURE 9.20
Mass with applied
walls by face.




Applying 3D Components to a Divided Surface

The Curtain System by Face method is great if you only need to lay out equal-spaced lines in two directions, but what if you want to create more complex surface patterns and give 3D articulation to that pattern? This is where the new pattern-based curtain panel family comes into play. As we mentioned in the previous chapter, any surface in the conceptual design environment can be divided and patterned with any of the precooked patterns provided. These patterns are 2D by default, but they can be made 3D very easily. Once you have a 3D pattern family, you simply load it into the massing family, and it will be available in the type selector when any divided surface is selected. We'll take you through an example.

Before jumping in, keep in mind that a surface has four levels of representation: the original surface, the UV division of the surface, a pattern that is "stitched" onto the UV division, and components that can fill in a pattern. Figure 9.21 shows the progression, from left to right. The most important thing to keep in mind is that a pattern is always made of straight segments that span from node to node along a surface—it is not made of segments that follow the curvature of a surface. This fact is important, as this is what truly makes a surface rational and eventually buildable.

FIGURE 9.21

From left to right: original surface, divided surface, patterned surface, component on patterned surface.




To start, from the application menu, choose New > Family > Curtain Panel Pattern Based.rft. This will open the template for creating dynamically adjusting panels. The principle of these families is based on the idea that points can be used to register 3D coordinates—every point in the panel template will correspond to a node on a divided surface. As the surface changes shape, the panel will follow along.

Figure 9.22 shows an example of the default rectangular pattern family with the reference lines selected. The reference points can be clearly seen.

FIGURE 9.22

The default pattern-based curtain panel family template.




The grid represents an abstract version of a divided surface. If you select it and open the Instance properties, you can adjust the UV spacing. You can also swap the pattern type using the type selector.


Figure 9.23 shows a hexagon pattern. The reference lines are important features of these families—these are the linear elements that span between points as the points adapt to surfaces. Using the reference lines to create form will cause the form to adapt to surfaces as well. Let's try one out.

FIGURE 9.23


A hexagonal pattern—note how the pattern spans multiple tiles on the UV grid.




1. Open a new Curtain Panel Pattern Based.rft file.
2. Select the grid and change the type to Triangle using the type selector.
3. Place a reference point on one of the reference lines—this will be the host for a swept profile.



4. Select the point to set it as the active work plane; then sketch a circle with a 3" radius around the middle of the reference line.
5. Select the circle and the chain of reference lines that make up the triangle, and then click the Create Form button. You should end up with a sweep along the triangle.




6. Create a new conceptual mass family and create a simple form. Divide a surface of the form, and then apply a triangle pattern to the form.
7. Go back to the triangle family and load it into the mass family.
8. Select the divided surface, and use the type selector to change the triangle pattern to use your custom panel—you should see the name of your family at the bottom of the list.



As you can see from Figure 9.24, this feature is very powerful way to propagate a family across a façade. The patterns available offer flexibility of formal expression, and you should feel inspired to give them a try.

FIGURE 9.24
Triangle component family applied to a surface.



Using Imported Geometry from Other Applications for Massing

You can use various applications to create geometry to be imported into Revit for massing. This section looks at using SketchUp, Autodesk Maya, Rhinoceros, Autodesk 3ds Max, Autodesk Inventor, AutoCAD 2010, and many more.

SketchUp

SketchUp is a fantastic piece of software. It's considered by many to be a great concept modeling and visualization tool that is easy to use, produces great results, and really feels architectural. Many architects adore SketchUp for conceptual studies or early images of design ideas. Revit users use SketchUp to make initial massing and conceptual studies to produce nice graphic outputs for their clients. They can then move the model into Revit for the documentation phase.

SketchUp files can be imported in either of two file formats, which are tied to different workflows and expectations:

SKP Use this format if you've created a complex geometric element in SketchUp that is pretty much final, and you just need to import it into Revit using the direct import of the SKP file. An example is a building with a complex shape or roof that you couldn't easily do in Revit.

DWG If you expect a dynamic workflow where the models need to move back and forth and maintain some intelligence, use file linking and link in the DWG files. This way, if the DWG changes, the model will update to show the latest version of the DWG.

IMPORT THE SKETCHUP MODEL IN A PROJECT ENVIRONMENT TO LEVERAGE LINKING


You can leverage the linking functionality only if you import the SketchUp model within the project environment. If you import it as a mass, the reload link functionality will not work.

Here is how we suggest working with a SketchUp file:

1. In SketchUp, make a quick and easy initial concept design like the one shown in Figure 9.25, and save it.

FIGURE 9.25


Massing created in SketchUp.



2. Start a new massing by using the In-Place Mass tool in the Massing & Site tab, and then import the file from the Insert tab, using the Import CAD button. This will open the Import CAD Formats dialog box (Figure 9.26).

FIGURE 9.26


The Import/Link CAD Formats dialog box.



3. Finish the family.
4. Switch to 3D view, and switch the model graphics of the view to Shaded with Edges. The SketchUp model appears in Revit. You can also activate shadows to see the model better (Figure 9.27).

FIGURE 9.27

Imported SketchUp
file with shadows
turned on.



Often, when you finish the mass family after importing the SKP file, you'll get a warning message. It's important to read this message in order to understand the future expectations for the import. If a mass family imports only nonvolumetric geometry, you can't create floor area faces in Revit. This is the case with any imports that come from surface or polymesh modeling applications. When imported into Revit, NURBS surfaces and solids can to be fully understood by Revit, and you can use them to generate the mass floor area faces and all future reporting needed for conceptual studies. Maya and Rhinoceros deliver good NURBS surfaces for this workflow.

Rhinoceros


Rhinoceros (known popularly as Rhino) is a neat application that many architects love for the powerful shapes it can create and its relative ease of use. Rhinoceros produces NURBS surfaces that can be easily imported and used as a reference to create a building out of the Rhino massing concept.

You can use Rhino to create concept studies or a complex-shaped building element. As an example, a draped form was created using Rhino and then imported into a Revit massing element (see Figure 9.28), just as you'd do with a SketchUp import. The form was then used as a reference and a curtain system by face was applied to it to generate the roof in Revit.

Rhino models are imported in Revit as SAT files. To import a SAT file from Rhino into Revit, the best approach is to make a mass family in the project environment and import the SAT file while in mass editing mode. This allows Revit to use the imported geometry for mass floor area faces and to perform other calculations and cuts in section and plan.

FIGURE 9.28

NURBS surfaces turned into curtain systems using the Curtain System by Face tool.




This warning can safely be ignored. Finish the family; then, from the Massing & Site tab, select the Model by Face ➤ Curtain System tool. You can select a different type from the type selector. Click the imported file geometry, and click the Create Roof tool on the Options bar.

The new object—a curtain system—is generated from the underlying geometry (Figure 9.29). It's important to understand that glass panels don't conform to the surface—the panels remain planar and attempt to fit the surface as best they can. So, as the panel cell size gets smaller, deviation decreases. You can always change the type later, just as you can for any element in Revit. Once you're happy with the type and the size of the panels, you can apply mullions. Depending on the complexity of the imported file, this can take up to a few minutes—but don't worry, it's a one-time action! Note that tighter grids give better results but also increase the processing time.

FIGURE 9.29

You can apply a curtain system to a NURBS imported geometry.



Autodesk Maya

As technologies become more powerful, they have the ability to influence trends in many industries, including architecture. Organic, free-form, generative buildings are all over the architectural magazines: this in a way is provoked by the fact that building technologies have become more sophisticated but also because modeling tools to create such forms have become better and easier to use. And while no software can make something beautiful unless it is in the hands of a creative person, these inspiring tools certainly capture the creative mind of talented architects.

In the myriad of available modeling tools today, the question is not only if you can make a shape or inspiring design but *how*. Maya is considered one of the best tools with a most artistic approach to form finding. No wonder that it started to capture the mindshare of many famous architects and is being implemented in the curricula of the most advanced architectural schools that teach generative techniques and methodologies of computational modeling.

Maya not only helps artists explore forms that are approximations or alternatives to creative visions but in itself sparks ideas and forms not previously explored or considered in a creative process.

Maya can create the most amazing shapes (Figure 9.30) and supports three major types of geometry: polymeshes, NURBS surfaces, and subdivision surfaces. You can import any of those into Revit, but if you want to leverage the full power of Revit to get area, volume, and skin calculations from the Maya model, you'll get best results by using NURBS in Maya.

The workflow from Maya to Revit is either via DWG directly to Revit or via AutoCAD where the DWG is converted into a SAT file and then imported into Revit. As a general rule, use the latter only in cases where you have trouble importing the DWG created with the plug-in.

The DWG export from Maya is not native in Maya but is a separate plug-in and can be found at the Autodesk Labs website: http://labs.autodesk.com/utilities/maya_export_dwg/.

FIGURE 9.30

There is no limit to your fantasy when modeling with Maya.



Courtesy of Marcel de Jong


Autodesk Inventor

Autodesk Inventor is a software solution for the manufacturing industry, but it starts to provoke a growing interest among architects for its parametric rules-based form generation as well as for its fabrication capabilities. Using rule-based techniques, you can create a complex conceptual mass in Inventor and then use them in Revit to make initial conceptual analysis, mass floor areas,

volumes, and so on and then move the concept to a real building by creating elements by faces, just as you can from the other modelers (Figure 9.31). You should export the conceptual mass done in Inventor in SAT file format to be able to import it in Revit.


Inventor can serve later in the stage of creation of implementation documentation and fabrication details (Figure 9.32). You can design, for example, your curtain wall layout in Revit but can make fabrication exact drawings of each of the elements using Inventor.

FIGURE 9.31
Conceptual mass
created in Inven-
tor, imported as a
Revit mass, turned
into a building,
and rendered.



Courtesy of David Light, Excitech

FIGURE 9.32
Detailed design and fabrication documentation can be easily done with Autodesk Inventor.



Courtesy of David Light, Excitech

AutoCAD 2010

New to the 2010 release of AutoCAD are some new free-form modeling tools that allow you to rapidly convert boxy shapes into smooth subdivision surfaces. These forms can be imported into Revit and work well with the Model by Face tools.

The new Mesh Modeler in AutoCAD is based on subdivision surfaces, and it allows you to make free-form shapes that would otherwise be difficult to model with NURBS, polygons, or solids. These tools provide a simple and intuitive set of modeling techniques, based on pushing and pulling vertices, edges, or faces of a mesh. This is done through direct manipulation of the mesh, which is quite nice. The modeler then has the ability to smooth the mesh, making an approximation of a curve with different levels of complexity. This can then be used in a Revit massing family (Figure 9.33).

FIGURE 9.33
Creation of organic concept models using Mesh modeling in AutoCAD 2010.



When you import a mesh into Revit from Rhino, Max, Maya, SketchUp, or a similar application, you can only use the surface of the imported object to apply faces, and you cannot get floor area calculations. With irregular or complex geometries, where walls may not be vertical, or where the concepts of wall, floor, and roof become blurry, generating a floor without a mass may become unfeasible. AutoCAD 2010 introduced a new topology that replaces the old mesh and can be directly manipulated and smoothed with a very simple set of commands. These meshes can be converted into solids or surfaces within AutoCAD and then imported into Revit as .dwg files and used to host walls, floors, and roofs using the Model by Face tools.


Using Smart Relationships between Building Mass and the Underlying Mass



The idea behind attaching building elements to massing surfaces is that you can come back to the massing and make large gestural edits to the underlying form and have the walls, floors, and roofs update to meet that design change. When you're working in the conceptual design phase, you experiment a lot during the form-finding and creative-thinking stage. In Revit, the change of the underlying mass form will not automatically update Revit building elements related to mass surfaces, as this would present regeneration slowdowns and impede a fluid workflow. That said, it's easy to keep your model in sync. You might first play with the shape, and then when you're happy with it, choose to update Model by Face elements. To do so, select a mass, and then click the Show Related Hosts button in the Modify Mass tab. This will select all face-based elements related to the mass. Click the Update to Face button to bring the building elements into sync with the mass faces. So how does that work? When elements that are tied to a massing are selected, an Update to Face button appears in the contextual tab on the Ribbon. Clicking that button updates the element to match the newly edited shape of the underlying mass form, as shown in Figure 9.34.

FIGURE 9.34

A: The starting form. B: The mass is made larger.
C: The wall is remade to match the mass. D: The roof and other walls are remade to match the mass.



The Bottom Line

Make conceptual designs and early studies in Revit. You can use massing studies to validate a design against the program requirements.

Master It Conceptual modeling is used early in the design process to explore the building shape and building program. How do you approach schematic design using Revit and perform feasibility studies?

Build a real building out of a 3D concept mass. Moving from massing to actual building components is easily done with Revit.

Master It You have the basic massing nailed down, and now you need to study more details such as wall and window fenestrations. How do you approach this with Revit?

Use imported geometry from other applications for massing. Make your own conceptual massing forms using the new Revit conceptual design tools.

Master It How can you reuse conceptual models created in other modeling applications and turn them into a measurable and documentable building in Revit?

Use smart relationships between the building mass and the underlying mass. Use the update tools to re-sync building elements with changes to the underlying mass surfaces. With Revit, you can change the mass and know that most objects can be recomputed to match the form.

Master It Change your massing model to explore design alternatives.

Chapter 10

Working with Design Options

Revit supports workflows where multiple design options need to be explored, evaluated, and presented. This type of workflow is an integral part of developing and iterating a design solution. With Revit's design options, you can use the same integrated building model to create a range of variations on a design at scales that range from entire façade studies down to kitchen layouts.

In this chapter you'll learn to:

- ◆ Use Revit design options
- ◆ Decide on a design solution
- ◆ Use design options with parametric design

Using Revit Design Options

Revit provides a set of tools for developing multiple design iterations in the context of one project. You can use these tools to explore alternative designs without having to keep saving multiple independent versions of your model as you move in different directions. With Revit's design options, you create, evaluate, and mock up a wide range of options in the context of your project file. You're free to investigate multiple roof configurations or different entry canopies, explore various furniture and office layouts and stairs—quite literally anything that can be modeled. Figure 10.1 shows an example of the same building model with two different entry canopies. Each canopy belongs to a separate design option that can be displayed or hidden in any view. This lets you create views that show each option so the two designs can be evaluated against each other.

FIGURE 10.1
Revit design options used to explore alternative design solutions for an entry canopy.




Design options work in the following manner. First, you have a *main model*, which includes all the elements you've modeled that are fixed and not affected by the options you want to explore. The main model can be thought of as a backdrop or stage on which different options play. Elements in the main model are always visible by default whereas design options—such

as different furnishings for the interior or different canopies over an entrance—come and go, appearing and disappearing depending on what you’re editing. Put another way, the main model includes everything else that’s *not* in the options.

You can make as many options as you need—there is no limit. You can create views for each option that only show that option displayed against the main model, and thus be able to place these views on a sheet in order to compare and contrast your designs. You can then present them to a client, to the project architect, or to other stakeholders in the design process. Once a design option has been settled on, you *accept* it as the primary design solution going forward by adding it back to the main model. Doing so deletes all elements in the design option that you won’t use going forward. That is, some elements become embedded in the architecture, while others disappear forever.

Design Option Tools

To access the design option toolset, switch to the Manage tab and select Design Options from the Design Options panel.



In a new file that has no design options yet, by default only one button (Design Options) is enabled. That button launches the Design Options dialog box, where you create, manage, and edit all the design options in a project. We’ll cover the other buttons in the next few sections.

Creating a design option doesn’t create anything at first—it simply sets up the work environment so you can begin making various designs using the feature.

Design Option Sets

In Revit, every design option belongs to a *design option set*, which is a way of structuring the design options into clusters to aid your workflow. For example, a project may have three design options for an exterior façade, two options for a bathroom configuration, and three options for room and furniture layout. Revit allows you to have several sets—one for each major type of option you’re exploring. You may have a design option set called Exterior Façades, one called Bathrooms, and another called Room Layout. In each set, you can have as many options as you need for the design in question. This hierarchy is structured as a tree interface in the Design Options dialog box, as shown in Figure 10.2. Each option set is shown in a top-level node of the tree, and each design option is shown as a child of a set.

As you can see in Figure 10.2, there is always a *primary* option in each set. It is designated by the “(primary)” suffix. This makes that option always visible by default in any view unless overridden. You can change the default primary option by selecting any other option in that Design Set in the Design Options dialog box and clicking the Make Primary button. In the views, the new primary option will then be visible by default, hiding the previously defined primary option.

When you reach a point in your design where you’d like to explore multiple design solutions, it’s time to start creating option sets. Think about how you’d describe the option—Façade

Studies, for example—and name your option set accordingly. Add at least two options to the set—more, if you think you’ll be exploring more than two options. You don’t have to define all the options in the beginning; you can always come back and add or remove options if needed.

FIGURE 10.2
Design Options
dialog box showing
some option sets
and options.



Creating new design option sets is straightforward. Click the New button in the Option Set zone in the Design Options dialog box, and a new set is created. To give the set a unique name, select it in the tree and click the Rename button from the Option Set zone. Adding new options within the set follows the same pattern: use the New button in the Options zone, and then give the set a name.


You can delete design sets and options at any time. Deleting a design option effectively deletes any elements added to a design variation you’ve made using that design option. Deleting a design options set deletes all options in that set. These are drastic decisions, so be wary of deleting anything before you’re sure you are ready to do so. Deleting a design option will also delete any views that you have set up specific to those design options. In both cases, Revit will warn you before the views and option sets are removed. The same effect is achieved when you click the Accept Primary button—all other options in that set are deleted.

Adding Elements to a Design Option

Once you’ve formally established design option sets and design options, you can do a number of things depending on the scope of your options. You can add elements from the main model into each option if you want to experiment with variations of the element. This way, you can explore different expressions of the same object without adding new elements. For example, if you want to show two roofs with the same footprint but different slopes, this method of adding the roof into each design option will work nicely. Once the roof is added to each option, you edit the option first, then edit the roof slope. The roof is essentially a copy and can be edited independently in each option (Figure 10.3).


FIGURE 10.3

Two design options of a roof can be done within the same Revit model.



Another way to work with options is to start editing the option directly, without first adding elements to the option. This approach works well if you have a design idea but don't want to add it to the main model just yet. When you begin editing an option, the main model grays out, and any new element you add is added to the active design option. For example, let's say you haven't yet designed the entry canopy for your model, and you want to experiment with some different ideas. Start editing the option, and you can then model whatever you want. The main model is still visible for reference, but it won't be editable.


You can use both methods in combination as well. For example, you might add a wall from the main model to two options and in each option add new, but different, window types to the wall. You'd use the Add to Set button to put the wall into both options, and then you'd edit each option to add the new windows.



To add elements to an option, first select them, and then add them to the appropriate design options by clicking the Add to Set button on the Design Options panel in the Manage Tab. Select only the elements you wish to make variations of—you don't need to add elements that you won't be editing. Once you click the Add to Set button, a dialog box appears that allows you to copy the elements into the desired design option or options. Again, this method is best if you know the elements will be essentially the same in each option and will vary only in type, material, or arrangement. Figure 10.4 shows the same walls in two options with different windows and wall material types.

FIGURE 10.4

Add walls to multiple options in order to experiment with different window placements.



To edit a design option, expand the list of available options from the Design Options panel and choose the option you want to edit. That option will become active and you will enter a special edit mode in which anything you create will be added to the active design option automatically. Use this method if you're starting from a blank slate and laying out several options for furniture layout or exterior shading devices, like those shown in Figure 10.5.

FIGURE 10.5

Use this dialog box to choose the design options into which you want to add elements.



When you're adding elements to design options, keep the following basic rules in mind:

- ◆ Host-based elements that cut the host (such as windows or doors) need to be included with the host when you make design options, meaning both the host and the insert have to be a part of the same option. You cannot have the host be a main model but make the inserts an option.
- ◆ Inserts are automatically copied with the host when you add hosts to design options. Using our example of a wall with a window in it, if you add the wall into a design option the window is automatically added as well.
- ◆ By the same token, if you're editing an option and try to place a window or door into a wall that's not included in the option, you'll get a warning:



You need to add that wall to your design option if you want to place inserts in the wall. Host-based elements that *do not* cut their hosts *can* reside in different design options without the host. For example, a wall-hosted sink can reside in a different design option than the wall on which it's mounted (which resides in the main model), but a window that cuts a wall can't.

- ◆ When you're adding curtain walls from the main model to a design option, the grids, mullions, and panels are automatically added for you.

- ◆ When you're adding a roof to a design option, you should include all walls that attach to that roof. Otherwise, you won't be able to attach walls to the roofs in your design options.
- ◆ When you create groups or arrays within a design option, selected elements must be in the active option.

☒ Active Only


Once an element has been added to a design option, by default it will no longer be selectable when you work on the main model. You can override this behavior by deselecting the Active Only option check box located on the bottom of the application frame near the right corner.

Because the elements in a design option can't be selected from the main model, you'll need to use this feature to edit elements belonging to an option or activate a design option. For example, if you add all your exterior walls to design options in the Exterior Façades option set, the walls won't highlight or be selectable unless you're editing one of the design options. If you add elements to a secondary option, they won't be visible by default in the main model.

Editing a Design Option

To start experimenting with design variations, after you create your design options you can edit them. To do so, use the drop-down menu in the Design Options panel and choose the option you want to edit (Figure 10.6). Alternatively, open the Design Option dialog box by clicking the Design Options button, select an option in the zone on the left, and click the Edit Selected button in the Edit zone on the right side of the dialog box.

FIGURE 10.6
List of available
design options.



The moment you select an option to edit, the main model grays out and becomes unselectable. This allows you to modify the elements in the design option without worrying that you'll mess up other parts of the model. Any element created while in the design option's Edit mode is automatically added to that option. For example, if you're editing Option 2 of an Exterior Façade set and you insert new windows in a wall in that option, the windows are added to the design option—they aren't added to the main model.

WHERE'S THE WALL?

Remember that the wall must be in the design option in order for you to place the window.



Real World Scenario

MAKING DIFFERENT EXTERIOR SKINS

Using design options, we added the exterior skin of a building to two options in an option set. By creating a new wall type with different materials, we easily exchanged one wall type for another in each option. Once the wall types were swapped in each option, we duplicated the perspective view showing the exterior skin and changed it to show each of the options (spandrel glass in the one on the left, wood in the one on the right) using the Visibility/Graphic Overrides dialog box. To make the northeast perspectives easy to find in any list, we assigned the views meaningful names: Glass NE and Wood NE.



EDITING AN OPTION BY SELECTING AN ELEMENT



If you want to start editing an element in a design option directly, click the Pick to Edit button. Hover the cursor over the model. Elements in design options will highlight. Now you can begin editing an element as soon as you select it. This shortcut lets you edit elements in a more direct manner. You can open the desired option automatically without having to know its name.


Take the example in Figure 10.4 of two views showing different roof options. In each view, to start editing the option choose Pick to Edit, select the roof, and start editing the roof. You don't have to think about the name of the option.

Displaying Design Options

To visualize different design options and have them represented in separate views that you can drop on a sheet, you need to create a new view that displays the desired option. These usually are duplicated views of the same view for which you want to show different options. To do this, right-click any view in the Project Browser, choose Duplicate, and give the view a name that indicates which design option it represents. Then adjust the visibility/graphic overrides settings of that view to show the desired design option.


As you can see in Figure 10.7, once you've created option sets and design options, a new Design Option tab appears in the Visibility/Graphic Overrides dialog box of all views. The default visibility setting is Automatic, which means that the option displayed will be the primary option and the main model. However, using the drop-down menu under Design Option, you can override this setting and show any of your other options.

FIGURE 10.7
By default, views are set to show the primary design options and the main model.



In Figure 10.8, three options are shown for a building façade: Option 1 has no canopy over the third-floor deck, Option 2 has a solid canopy, and Option 3 has a louvered canopy. All three options exist in the same model and can be visualized next to one another by duplicating the view and changing the design option in the visibility/graphic overrides of the view. By duplicating views and changing the default design option visibility, it's easy to compare options and even place the views on sheets for printing.

FIGURE 10.8
Visualizing three
options within one
model.




Deciding on a Design Solution

After many meetings and discussions, there will be a moment when you will decide which option is the final one—the one to build. Keeping unused and out-of-date options in the project needlessly inflates the file size and adds unwanted complexity. Revit will let you, with one click, choose the option that will become a part of the main model and get rid of all other options and information and views related to them.

1. First, decide which option you intend to keep. Make sure you're ready to implement your decision, because it will be irreversible after closing the project!
2. Designate it as the primary option by clicking the Make Primary button in the Design Options dialog.
3. Select the option set, and click the Accept Primary button. Doing so brings up a warning dialog asking if you're sure you want to do this.


As the message shown in Figure 10.9 suggests, if you proceed *all* secondary options will be deleted, and whatever is in the primary option will be pushed into the main model. The elements belonging to the chosen option will now become a part of the main model and thus you will be able to select them without having to edit a design option.

FIGURE 10.9
Delete Option
Set warning
dialog box.



You cannot keep any views that were set to show secondary options that no longer exist. Therefore, Revit will display a dialog box asking you to delete any views that were set up to display options that you're deleting (Figure 10.10). Click Delete to continue, and the views will be removed from your project.


FIGURE 10.10
Delete Dedicated
Option Views
dialog box.



Putting Design Options into Practice

In the following exercise, you'll make three different office layouts, shown in Figure 10.11, using design options. Option 1 is a hybrid design of open space and closed offices, Option 2 is an open office with cubicles, and Option 3 has only enclosed offices.

FIGURE 10.11
The three office
layouts you'll
create as design
options.



Once created, all the options will exist in one file and can be separately displayed in different views or dropped on one sheet for comparison. Follow these steps:


1. Open the Foundation_chapter_10 model in the Chapter 10 folder of the book's companion web page (www.sybex.com/go/masteringrevit2010).
2. Open the Level 1 Presentation plan view.
3. From the Manage tab, select the Design Options button.
4. Create a new Design option set called **Interior Fitout**.
5. Create three options, and set Option 1 to be primary by clicking the Make Primary button, as shown in Figure 10.12 (this should be set by default).

FIGURE 10.12
Create a design option set and three design options.




6. Close the dialog box.
7. Choose to edit Option 1, using the drop-down list from the Design Options panel.
8. While editing Option 1, place a series of workstation families (workstation.rfa) located in the Project Browser, under Families | Furniture Systems. Also add interior partitions and offices to create a layout similar to the one shown in Figure 10.13.
9. Finish editing the options either by selecting the Design Options button and clicking the Finish Editing button or by simply switching to the Main model in the drop-down list of the available options in the Design panel.
10. Choose Option 2 from the drop-down list to start editing that option.

FIGURE 10.13
Add workstations
to Option 1.



11. For Option 2, create an open floor plan layout similar to the one shown in Figure 10.14. You can simply draw this option layout. Alternatively, to speed up the process, you can choose to edit Option 1, copy the row of cubicle desks to the clipboard using Ctrl+C, choose to edit the Option 2 from the drop-down list, and paste the desks in using the Paste Aligned > Same Place option from the Clipboard panel of the Modify tab. Don't be thrown off by Same Place; this pastes the workstations only into the active design option.

FIGURE 10.14
Add cubicles to
Option 2.




12. When you've finished, select Main Model from the drop-down list in the Design Options panel to return to the main model. This finishes editing any particular option.

The elements in Option 2 will disappear from the view. The primary option (Option 1) is set to be visible by default, and as mentioned earlier, you can't view more than one option per view.

13. To make a third option that has enclosed offices and no cubicles, again you can either draw everything in that option from zero or you can choose to edit Option 1, select all the offices in the top half of the space, and copy them to the clipboard using Ctrl+C or the Copy command from the Clipboard panel.
14. Choose Option 3 from the drop-down list of available options in the Design Options panel.
15. From the Clipboard panel of the Modify tab, choose Paste Aligned ➤ Same Place (Figure 10.15).


FIGURE 10.15
Use the Paste Aligned feature to copy elements from one design option to another.



The workstations are copied into Option 3.

16. Continue to fill the space with offices, drawing the partition walls as shown in Figure 10.16. You can use the Mirror command to speed up the process.

FIGURE 10.16
Design Option 3 contains offices.




Next, you need to place each option on a sheet so you can show the options to your client and get feedback about the various layout options. To do that you will first need to create duplicated views, assign different design options to them, and finally place them on a sheet. Follow these steps:

1. Duplicate the Level 1 plan view from the Project Browser and rename the copy **Level 1 - Option 1**.
2. Duplicate the Level 1 plan view two more times, and give each view a unique name: **Level 1 - Option 2** and **Level 1 - Option 3**.
3. Open the Level 1 - Option 3 view, open the Visibility/Graphic Overrides dialog box, and select the Design Options tab. Change the Design Option value from Automatic to Option 3.
4. Open Level 1 - Option 2, and repeat step 3, but make sure Design Option is set to Option 2. For Option 1 you can repeat the process, but you don't need to do anything for the Level 1 - Option 1 view as it will be, as it's a primary option automatically assigned to be visible with the Main model. You have thus created three views of the same floor plan, each showing a different design option.
5. Create a new sheet view, and drag each of the plans onto the sheet, as shown in Figure 10.17.
6. You're now ready to present your alternatives. By associating schedules to design options, you can further illustrate the implications of various design decisions for your client.

FIGURE 10.17

All three options can be placed on a sheet at the same time by duplicating the plan views and adjusting the settings in the Visibility/Graphic Overrides dialog box.



Using Design Options with Parametric Design

Now that we have discussed the ability to have different design options within Revit and how to show these various solutions, let's dig into a little more detail and talk about other ways to consider the various solutions. As any designer knows, multiple factors come into play with any design solution—beauty, functionality, cost, and sustainability, to name a few.

Showing Quantities and Cost Schedules for Multiple Options

When presenting design options to a client, schedules allow you to compare the cost of adding particular features to different design options. A schedule, like any view, can be tailored to show specific design options. Here's how to create a schedule of elements in a design option.


1. Switch to the View tab.



2. From the Create panel, click the Schedules button and select the Schedule/Quantities tool. Choose the category you'd like to schedule and the appropriate parameters.
3. Right click on the newly created schedule in the project browser and select Properties. From the Instance Properties dialog box (Figure 10.18), you can access the Visibility/Graphic Overrides dialog box and change the design option. The properties of the schedule include a parameter for Visibility/Graphics Overrides.

FIGURE 10.18

The Element Properties dialog box.




- 4. Click the Edit button. This brings you to the Design Options tab (in this case, the only tab in the dialog box), where you can choose a design option to schedule. Here is this feature's real power: only elements belonging to the selected category in the selected design option are included in the schedule.

Working with Rooms and Design Options

You can create rooms in design options to compare areas and create color schemes for various options. Revit allows you to create multiple independent room layouts in the same model. For example, you can create two office layouts with different sizes and number of offices in each option and then add rooms to the offices. You can then create views of each option that are color-coded to provide a nice visual comparison. To get a feel for how this works, consider this simple example.


Start with a corridor and rooms on either side. You need to create two design options that show different room configurations. Follow these steps:

- 1. Draw a simple layout of walls, as shown here in plan view.



- 2. Open the Design Options dialog box from the the Design Options button on the Manage Tab, and create an option set named **Office Configurations**. Add two design options to the set, as shown in Figure 10.19.


FIGURE 10.19
Adding the design options.



3. Back in the plan view, duplicate the view from the Project Browser. Name the view **Level 1 Plan View - Option 2**. In the Visibility/Graphic Overrides dialog box for that new view, select the Options tab and set Option to Option 2.
4. Go back to your original Level 1 view and change the Options Visibility/Graphic Overrides setting to Option 1.
5. In the Option 1 plan view, choose to edit the option. Draw walls to create 12 offices, as shown here.




6. Add rooms to each office using the Room tool from the Room and Area panel of the Home tab. Your design should resemble this graphic.




These rooms are added to the primary option.

7. Open Plan View - Option 2, and click to edit Option 2 from the drop-down list of Design Options in the Design Options pane of the Manage tab. Place walls so that you make 10 offices rather than 12, and place rooms in each office space, as shown here.



- 8. To create a schedule of the rooms in each option, select the Visibility/Graphics Overrides parameter in the Instance Properties of the room schedule, and set the design option to the desired option (Figure 10.20).

FIGURE 10.20
A room schedule set to schedule the rooms of a chosen option.



- 9. Make a schedule for each design option showing rooms, areas, and count. Be sure to name each schedule so that it corresponds to your design options. You can then place each schedule and plan view on a sheet for comparison (Figure 10.21). Don't be confused if the total areas of two options differ, even though the overall space is the same. This results from the spaces being measured to other than the center of each wall, such as the wall finish. More spaces require more partitions, resulting in different area totals. And with less usable space, you begin to understand why open-space offices are more common than partitioned offices.

FIGURE 10.21
The design options in schedule form.

Room Schedule - Option 1			Room Schedule - Option 2		
Name	Count	Area	Name	Count	Area
Office	1	254 SF	Office	1	323 SF
Office	1	254 SF	Office	1	323 SF
Office	1	254 SF	Office	1	323 SF
Office	1	254 SF	Office	1	323 SF
Office	1	299 SF	Office	1	323 SF
Office	1	299 SF	Office	1	381 SF
Office	1	299 SF	Office	1	381 SF
Office	1	299 SF	Office	1	381 SF
Office	1	316 SF	Office	1	381 SF
Office	1	267 SF	Office	1	381 SF
Office	1	323 SF	Office	1	381 SF
Office	1	381 SF	Office	1	381 SF
Grand total: 12			Grand total: 10		

The Bottom Line

Use Revit design options. Design options provide a means to maintain two or more alternative designs for the same project or component.


Master It What are design options in Revit?

Decide on a design solution. The end result of exploring multiple options is to choose one alternative and implement that choice.

Master It You've explored a number of design options for an entry scheme. Your client has selected one, and you need to incorporate it into the rest of the model and remove the unwanted alternates.

Use design options with parametric design. Making quantitative differences visible is an essential part of presenting multiple alternatives.

Master It You need to look at some seating layout options for an auditorium space based on different-sized seating and show the seating counts.



Chapter 11

Creating Custom 3D Content

In this chapter we explore how to build your own designed library elements (families) for use in a project. We'll look at how parametric constraints and parameters can be used to build flexible, time-saving, beautiful, and smart content. By learning a few simple rules in addition to the form-making principles that we covered in Chapters 6 ("Modeling Principles in Revit, Part 1") and 7 ("Modeling Principles in Revit, Part 2"), you can build just about any element and assign it a behavior that you wish it to have—all without writing one line of code or knowing a programming language.

Building intelligent content is a key feature of Revit and deserves an entire book in its own right, but we will introduce you to some useful concepts and get you going. This chapter will take you through fundamental principles and some compelling use cases using the Family Editor.

In this chapter, you'll learn to:

- ◆ Model parametric 3D families
- ◆ Nest one family into another
- ◆ Build relationships between parameters with formulas

Modeling Parametric 3D Families

As a design progresses from generic to more refined, you'll need to add more detail and realism to your model. This process involves more faithfully representing what will be built and requires you to start building your own families. Although many types of families are provided out of the box, additional families can be downloaded from websites such as seek.autodesk.com, www.revitcity.com, or www.arcat.com. You'll inevitably reach a point where your design intent isn't matched by any of those, and you'll need to create new elements yourself. This is when you'll need to dig into the Family Editor and create new building components (Figure 11.1).

Up to now we've covered many of the basic principles of families, including understanding the different family categories, the principles of modeling, form making, and constraints—but we haven't put all this into practice beyond some simple shapes. In the following sections, we'll look at more advanced techniques used to create parametric families with embedded intelligent behaviors.


FIGURE 11.1
Custom design
for a sunshading
element.



Choosing the Right Family Template

Every family belongs to a category, and it is essential to categorize new families correctly so they can be controlled and scheduled logically when you load them and use them in a project. Choosing the correct family template when making new families will set the appropriate category. Revit provides templates (see Figure 11.2) for most families. These are hard-coded, and you cannot create a new template from scratch. Don't regard this as a limitation, since there is a template for all major necessary architectural elements, and those few rare elements for which you might not find a corresponding template can be created using the generic template.

FIGURE 11.2
Family templates.




When you decide to create an element on your own, you need to select the correct template. These templates are time-savers, because they already have the right category assigned, provide the most important reference planes that drive the behavior and geometry, and in some cases

include text notes to help explain how the family will work in the context of a project. Figure 11.3 shows a window template file, which includes text indicating the exterior and interior of the wall; parametric dimensions for width, sill height, and opening height, and a sample host wall. This is the template to start with when you've designed a new custom-shaped window, for example.

FIGURE 11.3

Plan, elevation, and 3D views of a template for windows. Text notes, reference planes, and dimensions have been preset.



The reference planes that appear in the family environment are the essential “bones” of any family. They establish the critical dimensional rules for the family, define the origin, and provide references that can be dimensioned to when loaded into a project. Without reference planes, you can’t make parametric content or dimension it in the project. Fortunately, all templates provide at least two reference planes to start with.

Types of Families

At the highest level, families occupy two categories: those that will appear in one view only (drafting, annotation, 2D families) and those that, when placed in a model, will appear in any view (model-based).

For model-based families, there are two high-level types: 2D families are used for making 2D details of the model, and 3D families are for making 3D geometric representations.

For 2D families, you can make standard detail components and line-based (2-pick) detail components. Three-dimensional family types include various host-based types (floor, wall, roof, and ceiling), profiles, line-based, work plane-based, and generic model. Note that 3D families can contain nested 2D elements as a way to embed more detailed information about that element directly into the families. Two new templates were added to 2010 that provide a custom set of tools for making conceptual masses. These are the Mass and Curtain Panel Pattern Based templates.

Choosing the correct template is essential to getting the desired family categorization and behavior of the element you are creating. To better understand what that means, let's drill deeper into family types.

HOST-BASED FAMILIES


Windows, doors, skylights, and lighting fixtures are all discretely manufactured objects, but they have something in common: they're installed into something else. Without the wall, ceiling, or any other mounting surface, the object has no place to ground itself in a typical building project. In other words, these types of elements require a host in which they can be placed or by which they can be supported. For these types of elements, Revit provides host-based families and templates.

When you need content to have an explicit relationship with a wall, floor, or roof, then a host-based family is absolutely the way to go. This is the most common type of family used in Revit. A host-based family includes components such as doors, windows, skylights, solar panels, light fixtures, and balusters. If you are reading this, you've probably placed some windows and doors in a Revit project, so we will not cover the benefits and behaviors of host-based families in detail here. If you are new to Revit, or need a refresher, don't worry. The basic principles are quite simple: once a host-based element is placed in or on a host, a dependency arises between the element that requires a host and the host in which it is placed. In an example of a wall (host) and window (host-based family), if you move the host, the hosted element will move as well; if you delete the host, the hosted element, too, will be deleted. Bear this in mind going forward in developing your model. Figure 11.4 shows several examples of such host-based families.

The golden rule when making a new family is to first consider it from a category point of view. What am I making? How does it need to behave (in a view or schedule, 2D or 3D, parametric, limited parameters, etc.)? Once it's made, how might it need to change, if at all? Then you can use an appropriate template as a starting point. For example, if you need to make a new window, start with the `Window.rft` template. Similarly, if you are making a table, the `Furniture.rft` template is the way to go.

Windows and doors don't exist in the model in isolated, abstract form, but are always hosted by a wall. This is why when you start creating or editing a window family, you will see a sample host element (a small wall, roof, or floor). The sample host in the family is there just to help you construct the family so it behaves properly in the model. It gives you a context in order to build the family so it correctly relates to wall thickness.

FIGURE 11.4
Examples of host-
based families.




WHERE'S THE HOST?

Note that the host that exists in the family template (such as the wall in the window template) isn't loaded in the project when you load the window. It's present in the Family Editor only as a reference to help you understand how the window will work when loaded into a project. Only the geometry, symbolic lines, and reference planes that you create will end up in your project. This is a very important concept to understand.

PROFILE FAMILIES

Many architectural details have distinct cross sections that run in a closed, linear fashion. Revit constructs these details by extruding that profile along a path, a process that is similar to how

many of these elements are physically manufactured. Baseboards, cornices, handrails, and mullions are all good examples of profile-based elements:



Revit provides special templates designed for elements like these. To create one of these elements, you need to create a Profile family. You will notice that there are a few different profile family templates to choose among: Hosted, Mullion, Rail, Reveal, and Stair Nosing. Make sure you pick the correct one when creating a profile family. Once you select a template, you can start sketching with 2D lines, defining the shape of the profile cross section. Like many sketches in Revit, the profile must be made of a *single closed loop* of lines. Multiple loops will lead to errors downstream. For example, if you created a mullion profile like that shown in Figure 11.5 and then tried to load it and use it in a mullion family, you'd get a warning message. Delete the inner loop of lines to get the mullion to work properly.

FIGURE 11.5
This profile is invalid because profiles with more than one loop won't work in a project.



If this is true, you must be asking yourself how you can make something like the shape shown in Figure 11.5. Although you can't have multiple loops in the profile family, you *can* import a detail component into the profile family that will mimic the representation you need; this is possible because there is no penalty for having multiple loops of lines in the detail component. The detail family showing the rest of the content within the outer profile adds much more detailed information about that element. It can be visible in a section of that element in the model (think plan and section views), and you can decide in which levels of detail you want that detail component to be visible.


To control when this level of detail will be visible in the model, set the visibility of the detail component so it appears only at fine levels of detail. Continuing with the mullion example, take these steps:

1. Start a new family using the Profile Mullion.rft family template.
2. Load a complex detail component done by a manufacturer into the mullion profile family. You will find a myriad of them on the Web, usually offered in DWG format, although with every passing day more manufacturers offer their content in .rfa format as well.

- Trace the loaded component with a single loop of lines to get the outer shape of the profile (see Figure 11.6).

FIGURE 11.6


On the left is the profile sketch, and on the right is a detail component.



- As you probably don't need to see such complexity at the coarse or medium level of detail (it will probably just print as black blobs in your drawings in small scales), set the options in the Visibility Settings dialog box to show the detail only in fine views.
- Load the Profile Mullion family into the project by using the Load into Project button.
- From the Project Browser, under the Curtain Wall Mullions node, locate the Rectangular Mullion family. Right-click to duplicate it and give it a specific name. Open the Type Properties dialog box of that new mullion, and under Construction on the Profile line, choose the 'Curtain Wall Mullion-Rectangular-Center : 2 1/2" x 10 1/2"' in the project to the mullion family (see Figure 11.7).


FIGURE 11.7

Choose the profile from the mullion's type properties.



Once a profile is loaded into Revit, it doesn't take 3D form until it's assigned to system families such as mullions, rails, wall sweeps, and gutters. To do this, open the Type Properties dialog box of any of these families and assign the profile to the family. You can use a 2D profile in the definition of a wall as a precast parapet cap, as shown in Figure 11.8.

FIGURE 11.8
Assigning a profile to a system family.



Many companies that sell finish molding provide 2D CAD drawings that you can import directly into a Revit profile family. This is a great time-saver and will keep you from having to draw complex profiles from scratch.

Profiles can be used for many different purposes. To accommodate more specific behavior as well as categorization, six profile family templates are available: Profile.rft, Profile-Hosted.rft, Profile-Mullion.rft, Profile-Rail.rft, Profile-Reveal.rft, and Profile-Stair Nosing. Be careful to select the correct one, because Revit looks only for specific profiles depending on what you're making. For example, a mullion family won't let you choose a wall-sweep profile; only mullion profiles will show up in the list.

NOTES ON USING PROFILES

Keep in mind that simple-looking profiles can quickly weigh down a project if overused, and if you export for rendering purposes they can be more tessellated than necessary. When creating profiles, don't use a spline when an arc (or series of tangent arcs) will suffice. And don't use an arc when a line will suffice.

2D LINE-BASED FAMILIES

Working on a 3D model does not mean that all elements need to be modeled in 3D; some are represented using 2D detail drawings. Most details can be drawn using lines and filled regions,

but these are inherently difficult to maintain and reuse. For details that are likely to be used in other drawings or projects, you should create detail families. With Revit, you can make stand-alone detail components or line-based families. The line-based family type is great for making elements where length is the primary variable and for making 2D repeating components.


The 2D line-based template (Detail Component line based.rft) allows you to draw a detail element as if you're drawing lines with two picks, but the component can contain as many lines and filled regions as you want. For example, you can draw a detail component that represents plywood (lines plus wood hatch) with two clicks of the mouse.




Real World Scenario

MAKING A PLYWOOD LINE-BASED FAMILY

When we had to make a plywood detail element, we went to the line-based detail family. With this detail template, we created a filled region between the left and right reference planes and assigned a plywood fill pattern to the region. As long as the left and right lines of the filled region are coincident with the reference planes, they will follow the planes when the family is placed in a project and drawn. The cross-sectional dimension of the filled region can be driven by a Thickness parameter, which is set to $\frac{3}{4}$ " and can later be modified if you need new types:



When the plywood family is loaded into the project, we were able to make a symbolic 2D plywood representation with two clicks that defines the length. Once the plywood was placed, we could reselect it and drag either end using the blue grips to stretch the detail. Compared to using a filled region in the project, this method provided parametric constraints, reusability, and incredible ease of use.




3D LINE-BASED FAMILIES

Just like the 2D drafting line-based families, you can make 3D line-based families. For these families, use the template *Generic Model line based.rft*. Examples where you need such 3D line-based families are molding details, sunshades, grating, and any other elements that have length as their primary variable and repeating 3D components. Figure 11.9 shows a 3D chair


family that adds chairs as the family elongates. If you want to count the number of chairs, you'll need to read about nested families and shared values, covered later in this book in Chapter 19.

FIGURE 11.9
3D line-based
chair family.



With two clicks of the mouse, you can quickly add rich 3D content to your model. Figure 11.10 shows a sunshade example. (Figure 11.1 showed this same sunshade in 3D.) The brackets at the left and right side were modeled in the family using solid extrusions and constrained to the left and right reference planes. The blades were modeled as sweeps between the two horizontal reference planes, using a profile. When placed in the model, the sunshade can be stretched dynamically.

FIGURE 11.10
3D line-based Sun
Shade family.



FACE-BASED AND WORK PLANE-BASED FAMILIES


For elements that need the flexibility to be placed on any model face, such as electrical outlets, signage, or coffee pots, there are work plane and face-based families. Not only do these families attach to any surface of the model during placement, but you can also re-host them at any point later to any other surface if need be. Any time you have a component that needs to be installed on multiple types of hosts, think of making the family face-based.

Face-Based Families

To create face-based families, use the template *Generic Model face based.rft*. When you open the template, you'll see an abstract host surface on which you can model your family. When you load your family into your project, the host surface in the family maps to whatever face you choose in the project, and your family reorients to be placed on that face automatically. The face you choose can be anything from another family to geometry of a linked file. An example of a face-based family is an HVAC supply register, which you need to be able to place on walls, ceilings, or even floors. Figure 11.11 shows another application of a face-based component, where the curved surface doesn't have a work plane.

FIGURE 11.11

A sign created as a face-based family can be placed on a curved wall.



Work Plane–Based Families

Work plane–based families are placed on the active work plane of the current view. Every view has an active work plane that you can manipulate using the Work Plane tool (see Chapter 6, “Modeling Principles in Revit, Part 1”).

Be sure to give the family an appropriate category before loading it so you can control its visibility and graphics.

RICH PHOTOREALISTIC CONTENT (RPC) FAMILIES

When you’re rendering a view, it’s possible to substitute real model geometry (the family) with highly photorealistic images (such as ArchVision content, available at <http://www.archvision.com/>). For example, a simplified stick figure can turn into a real-looking person when the view is rendered (see Figure 11.12).

FIGURE 11.12

Left: Entourage family, non-rendered. Right: same family when rendered.



This can be a cool feature when you’re rendering, and it makes rendering faster because there is no complex geometry to render. You can create plants, cars, and people using these families.

ASSIGNING A RENDERING APPEARANCE

RPC families are specialized and have specific behavior when rendered. In addition to the 3D and 2D representation that you normally add to a family, you can assign a rendering appearance to the family. This appearance shows up only when you render a 3D view.

You create RPC families using the template RPC Family.rft. RPC appearances can only be added to the Entourage and Planting families. When the family is set to either of these categories, a Rendering Type parameter is enabled in the dialog box that opens when you select Category and Parameters from the Create ribbon. RPC families in these categories have additional type parameters (located in the Family Types dialog box; see Figure 11.13) to control the associated RPC file used when the family is rendered in a project, along with specific properties.

FIGURE 11.13
RPC parameters in
the Family Types
dialog box.





Figure 11.14 shows the Render Appearance library and some of the people/characters that come with Revit.

FIGURE 11.14
Render Appearance
library for
RPC content.




Once you’ve selected an RPC object, you can further refine the properties of the object by clicking on the first Render Appearance parameter. Figure 11.15 shows the properties of a Steelcase Think chair, with options to change the back and seat fabric. You’ll also notice that RPC content supplies you with 3D model geometry.

FIGURE 11.15
Editing the render
appearance prop-
erties for a chair.



DETAIL COMPONENT FAMILIES

As you'll see in Chapters 20 and 21 ("Developing the Design with Smart Workflows" and "Moving from Design to Detailed Documentation"), a typical workflow to complete a construction document set involves enriching the model with 2D details in detail views. These detail elements typically depict cross sections or elevation views of elements that don't need to be modeled in full 3D (to do so would only bog down the model and not add much value). For this use case, you can use detail component families to add detail to model or drafting views; these details are visible only in the view in which they're placed. Examples include blocking, studs, steel sections, bolts, flashing, and so on:



Detail components can contain lines, filled regions, masking regions, symbols, and other detail components. Detail components are meant to represent real building components and assemblies, so they scale with the model when the view scale is changed. To create a new detail component family, use `Detail Component line based.rft` or `Detail Component.rft`.


3D FAMILIES

To accommodate fast and easy creation of architectural content, many templates have been made for you with the appropriate category selected. Examples include `Furniture.rft`, `Furniture Systems.rft`, `Mechanical Equipment.rft`, and `Plumbing fixture.rft`, to name a few. Use these templates to make content when starting from scratch.

CURTAIN PANEL FAMILIES


Curtain walls and aluminum storefront systems are composed of mullions, panels, operable windows, and doorways. In Revit, the Curtain Wall tool organizes all these components into an integrated system of parts. For panels, the default solid and glazed options are usually sufficient. Adding doors and windows to a curtain wall requires you to make custom windows and doors made with a special template in the Family Editor. Figure 11.16 shows a curtain wall door family in the Family Editor. (These templates don't contain host walls as other door family templates do.)

FIGURE 11.16
Double-panel curtain wall door.



Keep this in mind: to add doors to a curtain wall, you must use one of the special *curtain wall doors*; you can't place a standard door into a curtain wall. Use the `Door - Curtain Wall.rft` template to create these families. They resemble regular door families, but the width and height are dynamically tied to the size of the curtain wall cell in which the door is placed. As the curtain grid spacing changes, so does the size of doors placed in the wall. As you can see in Figure 11.17, the door family adapts to the size of the curtain grid spacing.


FIGURE 11.17
The curtain wall door adjusts its width and height to the size of the cell in which it is placed.



Family Categories and Parameters


In every Revit family, settings control specific behavior of the family and set the category. Depending on what category you assign the family, you can get a different set of type parameters and category-based parameters. For example, in a window family template, preset parameters for sill height, width, and height are hard-coded into the family (see Figure 11.18). In a furniture family template, you don't see these parameters.

FIGURE 11.18
Family parameters for windows.



Another set of parameters affects the entire family based on the category it belongs to. You can access these settings by choosing Category and Parameters on the Create tab. In the resulting dialog box (Figure 11.19), you can set or change the category and also adjust other parameters that affect how the family will behave when placed in a model.

FIGURE 11.19
The Family
Category and
Parameters
dialog box.



In the figure, the Entourage category has four family parameters listed: Work Plane–Based, Always Vertical, Rendering Appearance Source, and Shared. Remember that changing the active category at the top of the dialog box may enable or remove family parameters displayed in the bottom of this dialog box. Let’s briefly review what these parameters do.

Work Plane–Based Enabling this option allows the family to be hosted by the active work plane when placed in the project or nested into another family. Any nonhosted family can be set to be work plane–based. Any family using the generic template (furniture, site, casework, and so on) can be set to work plane–based, as such families aren’t required to be hosted by another component (like doors or windows).

Always Vertical This parameter keeps a family oriented in the positive Z direction when placed in a project. In most cases this is desired, because levels are always horizontal. But when you have sloped floors or sloped site conditions, you may want the component to be oriented perpendicular to the surface it’s placed upon. Parking stripes and cars placed on a sloped slab of a parking structure are examples where making the family *not* always vertical can make sense (see Figure 11.20).


As another example, the Always Vertical parameter comes into play with trees placed on a toposurface. As the site changes slope, you want to keep the trees vertical and not have them look like they’re falling over.

Rendering Appearance Source This only applies to the categories Planting and Entourage. There are two options here: Third-Party or Family Geometry. Choosing Third-Party automatically imports 3D geometry from RPC content. Choosing Family Geometry does not use RPC geometry but rather the geometry you construct yourself in the Family Editor.

Shared This parameter controls whether or not a nested family will be scheduled in a project of a family that is nested in another family component. You may choose to nest families

to create assemblies or save time modeling components that repeat. Nesting has implications when you need to tag or schedule the family. For example, consider a window assembly with a main light and two side lights—one on each side. If the design intent is that the window is to be tagged and scheduled as a unit, then the families will be nested into a host family and the Shared parameter will remain unchecked. In this situation, only the host family (the family containing all nested windows) will schedule. If the intent is that the assembly be constructed from separately purchased units and assembled on site, then the nested families should have the Shared parameter checked. This allows each nested window to appear on the schedule as if placed separately.

FIGURE 11.20
Family set to not
be always vertical.



ADDITIONAL FAMILY PARAMETERS FOR STRUCTURAL CONTENT

When you choose some structural categories, you'll see additional options show up that are specific to structural framing, foundations, and columns. We will not go into detail here on each of these, but structural engineers should be aware that special functionality has been built into family templates depending on the type of family you are creating.

Nesting One Family into Another

When you open a family in the Family Editor, you can load another family and place instances of it into your host family much as you would in a project. This powerful feature allows you to manage your content and reuse existing work. For example, consider the workstation family illustrated in Figure 11.21.

This family is composed of loaded filing cabinets, a desktop, partitions, and a chair. This makes building the family much more manageable and also makes it much easier to place and manipulate the family as a unit when placed in a project. In this example, you'd want to make sure that the filing cabinets were set not to display in plan views, since they're obscured by the working surface.

One common example of family nesting is the combination window. Rather than model the entire unit from scratch, you can load and insert existing window components into a base window family. You place the windows just as you would in a project. For example, you can place a fixed-window family in the center and two double-hung windows on either side (see Figure 11.22). You can then save the family and load it into a project. The entire assembly acts as one element when placed in the model.

FIGURE 11.21
Nested families
used to create a
workstation.






FIGURE 11.22
Combination win-
dow: one family,
created from two
nested families.



Choosing to use nested families not only saves modeling time but can also simplify your work in the Family Editor. It's often easier to manipulate and constrain an assembly of extrusions as a nested family than to model the same geometry in the host family. In another example, a bracket for a sunshade is modeled separately and nested into the host sunshade family (Figure 11.23). Two instances of the bracket can now be placed and constrained in the family much more easily than modeling the same elements as separate extrusions. Later in the chapter, we review some powerful features that you can use via family nesting.

FIGURE 11.23
Nesting a bracket
into a Sun Shade
family (host).



Finally, nesting of one family in others allows for centralized change management: if you create a handle, you can nest it in doors, windows, or curtain wall doors and windows. If any change is made to the handle, it will propagate to all other families where it has been nested.

Scheduling Nested Families

When a family is nested in another family, by default it doesn't appear in project schedules and isn't taggable. For the most part, this is the desired behavior because it avoids overburdening your schedules with unneeded subassembly elements. A nested family's geometry displays, but is treated as part of the host family.

In some cases, you may want to schedule nested families—for example, if you've nested chairs within a table family. To expose nested families to tagging and scheduling, you need to enable a parameter called *Shared*, as we detailed earlier. To do so, follow these steps:

1. Open the nested family.
2. Choose Categories and Parameters.
3. Select the *Shared* option in the Family Parameters group.
4. Reload the family into all its host families, and then reload those host families into your project.

Once all your nested families have sharing enabled, they will be schedulable and can also be tagged in your project. Keep in mind that once a family is shared and placed in the project, it's not possible to "unshare" the family and reload it into the model.

Linking Parameters


When families are nested, the parameters of the nested family *aren't visible in your project* by default. Only the parameters of the host family are visible, and they can be modified in the project environment. If the element you're nesting is unlikely to change parametrically, this may be desirable.

However, if you want to control the nested element's parameters as well, you must explicitly link them to parameters in the host family.

In our example, the support bracket of the sunshade is a nested family, and you need to be able to drive its dimension from the context of the project.

In Figure 11.24, the depth of the nested bracket family is associated with the depth of the host Sun Shade family. Changing the Depth parameter of the sunshade causes the depth of all support brackets to also change to the same value.

FIGURE 11.24
Linking a parameter in a nested family to the host.



You can link any kind of parameter, from dimensions to materials to text. For example, the Sun Shade family has two material parameters: Material Supports and Material Blades. By selecting one of the nested brackets and opening its type properties, you can assign its Finish Material parameter to the sunshade (host) material parameter Material Supports. When this is done, you can control the bracket material from the project by assigning a material to the sunshade's Material Supports property.


Parameters in many nested families can be linked to a single parameter in a host family to provide powerful control over size, quantity, and even display of family subassemblies from within a project. This is a great way to limit exposing a family's internal complexity when the family is loaded into a project.

Linking Parameters (Conditional Visibility)

Every nested family or piece of solid geometry has a Visible parameter. This parameter allows you to control the visibility of nested families by creating a Yes/No parameter in the host family and then linking the nested family to that parameter. Checking or clearing this check box controls the element's visibility in the host family when viewed in a project. Keep in mind the Visibility option only controls visibility! If the nested element is shared, it will still schedule.

For example, let's look at a window family that has a shutter family nested in it and two instances placed on either side of the window. You can create a Yes/No parameter called **DisplayShutters** in the window family and link the Visible parameter of the shutter family to this parameter (Figure 11.25).

FIGURE 11.25
Linking a Yes/No parameter to the Visible parameter allows the same window to be shown with and without shutters.



Two types are then created: Window w Shutters and Window w/o Shutters. The former has DisplayShutters selected and the latter has it deselected. When they are loaded into the project, you can use the two types to control whether or not the shutters are visible (Figure 11.26).

FIGURE 11.26
Two types of a single family—conditional geometry display.




Building Relationships between Parameters with Formulas

There are many examples of building components that have repetitive subcomponents built into them: evenly spaced shelves, brackets, structural members, nested chairs, or other components—the list goes on. Figure 11.27 shows a perfect example where using an array to place vertical and horizontal shelves makes sense.

FIGURE 11.27

Arrays can help maintain element spacing in a family and allow you to control the number of grouped element instances.



In the Family Editor, you can use arrays on any geometry you’ve created or on any nested families you’re using. The Array tool in the Family Editor works the same as it does in the project, but in the Family Editor, it can also be driven parametrically.


Making a Parametric Array

To make a parametric array in the Family Editor, you need to use the Group and Associate option in the Options bar. This allows you to parameterize the number of instances of the element in the array. When you select the array, a number appears that corresponds to the total number of groups in the array. If you change this number, the number of groups in the array updates. If the array was created with the option Move to: Last, elements are added or removed between the start and end of the array as defined when it was created. If the array was created with the option Move to: 2nd, elements are added or removed after the end of the array.

You can turn the array number into a parameter by selecting the array and labeling it as a parameter (see Figure 11.28). Once the number is selected, the Options bar displays a Label drop-down menu. Select <Add Parameter...> to create a new number parameter.

FIGURE 11.28

Assigning an array number to a parameter.



Once you make the assignment of the array number to a type parameter, the number of elements in the array can be controlled from the Family Types dialog box. In Figure 11.29, the number parameter Chairs controls the number of chairs in the radial array. Changing the number automatically changes the number of elements in the array.

FIGURE 11.29

Array of
chairs in
Table-Dining
Round w
Chairs.rfa.

Chairs = 6



Chairs = 5




Encoding Design Rules

Proportion has been an important consideration in the design of objects for centuries. Relating width, height, and depth to a design rule informed the design of architecture dating back to early Greek and Egyptian times. The dimensional size of one element often drives the size of other related elements. Think, for example, of a window with muntins; the number of muntins often grows in proportion to the size of the window (see Figure 11.30). To this end, Revit provides ways to relate parameters to one another using formulas. By changing one dimension of a component, you can effectively change many other dimensions and thereby maintain design intent. Often, your family will have parameters that determine its dimensions, and it's the relationship between these dimensions that you want to maintain.

FIGURE 11.30

Window with
muntins added as
function of height.



EXAMPLE: USING A FORMULA TO CONTROL DIMENSIONS

In a simple case, you can imagine using a formula to set the width of a shutter in a window family. The window family may already have types that control its width and height. Knowing that the shutters should always be equal to the window height and half the width, you can use a formula and let Revit do the calculation for you. Follow these steps:

- 1. Load the shutter family into your window family, and place an instance on either side of the window.
- 2. In the window Family Types dialog box, create a new parameter by clicking the Add button:



- 3. In the Parameter Properties dialog box (see Figure 11.31), give the parameter the name **Half Width**, and set Type of Parameter to Length. You can group the parameter under Dimensions to make it easier to find.
- 4. Back in the Family Types dialog box, in the parameter's formula field, enter **=Width / 2** (see Figure 11.32). This ensures that the parameter is always half the window's width. The Value field displays the calculated value; when the family is loaded into your project, the parameter will display but won't be editable.
- 5. Select the nested shutter in your family, and link its dimensions to the window so they change together. To do so, in the Associate Parameter dialog box (accessed from the small button at the far right of the parameter row), click the button in the correct row of the Shutter element properties. Associating the shutter's Width parameter with the window's Half Width parameter and its Height to the window's Height connects the two objects.

The shutter will now adapt its dimensions to the window whenever its shape is adjusted.

FIGURE 11.31
Use the Parameter Properties window to give the new parameter a name and type.






FIGURE 11.32
A simple formula
for half width.



USING A FORMULA TO CONTROL AN ARRAY

In the next example, you'll see how you can use a formula to control the number of elements in an array used to construct a sun-shading family (Figure 11.33). (You'll find this file, *Sunshade.rfa*, on the book's companion web page, www.sybex.com/go/masteringrevit2010.)

FIGURE 11.33
A sunshade family
can be parametrically
defined with
a formula.



This family is constructed of a support bracket and blades that make up the shade. The design calls for supports to be added dynamically as a function of length. In this example, both the brackets and the shades are arrayed so that their quantity is determined by the size of the family when placed in the project. The number of brackets is controlled by the Support Quantity parameter, and the number of blades in the shade is controlled by Blade Quantity. Both of these can be driven by formulas. The calculated value of a formula is always displayed in the Value column. Let's look deeper at this design problem and see how it can be solved.


Support Quantity uses a conditional statement to guarantee that there are always at least two support brackets in the family. A conditional statement takes this general form:

If (*condition*, do this, else do this)

In the support case, if Support Minimum is true, then the number of supports is set to Length / 60. If it's false, then the value is 2.

Support Minimum is a Yes/No parameter that's also set to a formula. In this case, if Length (the length of the family) is greater than 135", Support Minimum is Yes (true); otherwise, it's No (false). In Figure 11.34, you see the default Length value is 110". So Support Minimum is false, and Support Quantity is set to 2. When the length exceeds 180", Support Quantity equals 3, and an additional support bracket is introduced via the array.


FIGURE 11.34
Formulas used to control arrays.



Blade Quantity is simpler. The conditional statement determines whether the depth is greater than 15.75". When the depth is larger (shown as 37"), the number of blades is one more than $\text{Depth} - 10" / 6$. When the depth is less than 15.75", there are only two blades.

Figure 11.35 shows how changing the length to 180" causes a new bracket to be added based on the formula.

FIGURE 11.35
Different shade sizes evaluated via the formula. On the left, two supports are added. On the right, three supports are added.






Real World Scenario

MAKING A PARAMETRIC SUNSHADE

We constructed an advanced line-based family to model an exterior shading element. The family uses arrays with a formula to capture the design intent regarding the number of blades, proper support spacing, and blade angle. The resulting family can be quickly placed with two clicks, and the correct number of supports are placed. Note that the way this family is constructed, it must be placed in a plan view of the model. Once you place the family, you can experiment with different blade angles and numbers of blades in the system by changing a few properties:




Building a Parametric 3D Family

In this exercise, you'll assemble a furniture ensemble consisting of a round table surrounded by chairs (see Figure 11.36). To accomplish this, you'll do the following:

- ◆ Nest families
- ◆ Create an array
- ◆ Use a formula to lock in design intent
- ◆ Use parameter linking to control element visibility

FIGURE 11.36
Table family with
nested chairs.




NESTING THE CHAIR

To nest a chair into the table family so the whole family works as a unit, follow these steps:

1. Open Table Round.rfa from the Chapter 11 folder of the book's companion web page (www.sybex.com/go/masteringrevit2010).
2. Open the Ref. Level plan view using the Project Browser, and fit the view to the screen.
3. Choose Load Family from the Insert ribbon and load Chair-Breuer.rfa from the Chapter 11 folder.
4. Activate the Component tool on the Create ribbon. The active component in the Type Selector should be Chair-Breuer.
5. Place a single instance of the chair, as shown in Figure 11.37. Use the spacebar to rotate the chair to face the table, and type **SI** to use the intersection snap override to snap the chair origin to the reference-plane intersection.

FIGURE 11.37
Place an instance of chair in the table family.



CREATING A PARAMETRIC ARRAY

Next, you'll make the chair array become parametrically driven. Follow these steps:

1. Click the Types command on the Create ribbon to launch the Family Types dialog box.
2. In the Parameters group, click Add.

3. In the Parameter Properties dialog box, enter the information shown in Figure 11.38 for the parameter, and click OK.
4. Add a Radius parameter (Figure 11.39), and click OK.
5. For the Radius parameter, enter the following in the Formula column: **Diameter / 2**. This ensures that the radius is half the diameter.
6. For the Chairs parameter, enter the following in the Formula column:

$$(\text{Diameter} * 3.14) / 2'6''$$

This formula sets the desired number of chairs relative to the circumference of the table.

FIGURE 11.38
Adding a new
Chairs parameter.





FIGURE 11.39
New Radius
parameter added.



7. Select the chair instance you placed earlier, and select the Array tool. Change the array type in the Options bar from linear to radial. A red box appears around the chair, with a blue rotate control in the center. Drag the blue control to the intersection of the two reference planes at the center of the table to set the center of the array.

8. Define the start of the array by clicking at the origin of the chair, and then move your mouse into the Options bar area. Set the Move To radio button to Last, and enter 360 in the Angle field.
9. Press the Enter key twice. Revit creates three chairs.
10. To constrain the array to the radius of the table, activate the Dimension tool, and choose the Radial placement method from the Options bar:




11. Hold the tool over the table edge, and press Tab until the status bar reads *Array : Array*. Click in any whitespace to finish the dimension.

Array : Array

12. Select the dimension. In the Options bar, set the Label drop-down menu to the Radius parameter. This sets the radius of the array to match the radius of the table.
13. Select a chair group, and then the array reference (the line that connects the chair groups and displays the array number). You may need to press Tab until you see the status bar read *Array: Array*.
14. Once you make this selection, the number of chairs should change to match the value of the formula-driven Chairs parameter (Figure 11.40).

FIGURE 11.40
Assign the array
reference to the
Chairs parameter.




CONTROLLING VISIBILITY

To modify the family so that chairs can be made visible (or not visible) as part of the family definition, follow these steps:

1. Click Types on the Create tab to open the Family Types dialog box.
2. In the Parameters group, click Add.
3. In the Parameter Properties dialog box, enter the data shown in Figure 11.41.
4. Click OK.
5. Select one of the chair groups, and choose Edit Group from the Group panel.
6. Select the chair, and edit its element properties, either by right-clicking and using the context menu or by clicking the Element Properties from the Element panel.
7. Under the Graphics group, find the Visible parameter. At the far right end of the row, click the small button to launch the Associate Family Parameter dialog box.

FIGURE 11.41
Fill out the Parameter Properties dialog box as shown here.




8. In the dialog box, choose the displaysChairs parameter you created earlier.
9. Click OK twice to dismiss the Associate Family Parameter and Element Properties dialog boxes; then, click Finish Group.
10. Click the Types command to launch the Family Types dialog box.
11. Choose the type 36" Diameter in the Type drop-down list at the top of the dialog box.
12. At the right, in the Family Types group, choose New.
13. Type in the name **36" Diameter no Chairs**, and then click OK.
14. In the Graphics group, select the displaysChairs parameter, and then Click OK to close the Family Types dialog box.

15. Save the family. Choose Load into Project from the Create ribbon to view the completed family.
16. You should have four types of families available. Place an instance of each to see the results (see Figure 11.42).

FIGURE 11.42

Finished family types placed in a project. All four types are displayed, illustrating the use of the array with the formula and the conditional display of the chairs.



The Bottom Line

Model parametric 3D families. When you're making a new family, consider how it will be used in the model, and choose an appropriate template.

Master It You found a ceiling-mounted lighting fixture that you want to use in your existing project, but you can't find a Revit family for it in any libraries or online communities. How would you start?

Nest one family into another. The ability to nest families in other families lets you create content that's easier to manage and improves your workflow.

Master It Building components are often composed of a series of subcomponents that form an overall assembly. Think of some common examples and what strategies you could use to build such content in Revit.

Build relationships between parameters with formulas. Create smart connections between geometry and dimensions to create efficient and parametric content.

Master It You can use dimensional relationships to tie the size of one object to the size of another. How do you do this in the context of a family?

Chapter 12

Extended Modeling Techniques—Walls

In the previous chapters, we covered basic modeling techniques for constructing a simple building. We skipped over many additional features to give you a handle on essential workflow, the user interface, and modifications to the model. In this and the following two chapters, we'll cover advanced features that are available any time you're modeling in Revit. As you'll see, with a little refinement and creativity, you can create a wide range of building components with the standard tools.

In this chapter, you'll learn to:

- ◆ Use advanced modeling techniques for standard walls
- ◆ Use advanced modeling techniques to create stacked walls
- ◆ Use advanced modeling techniques for curtain walls

Using Advanced Modeling Techniques for Standard Walls

Walls are made from layers of materials that represent the construction assemblies used to build real walls. In Revit, these layers can be assigned functions that allow them to join and react to other similar layers, so that when walls, floors, and roofs meet you get the expected representation. The wall core is one of these special layers, and understanding its behavior will help you when designing and editing your walls.


Wall Core

Revit has a unique ability to identify a *wall core*. As you will see, this core is much more than a layer of material. Every wall type in Revit has a core material with a boundary on either side of it. The core (the layers between the two boundary lines) defines the structural part of the wall and influences the behavior of the wall and how it interacts with other elements in the model. The core of a wall creates references to which you can dimension, designating the location of structural wall components as separate from the finish materials. The core boundary can also be used as the location definition when drawing host elements (walls, floors, ceilings, roofs). For example, you can constrain a floor sketch to the structural stud layer of walls by using the wall-core boundary to create the sketch. If walls change size or types are swapped, the floor sketch maintains its relationship to the core boundary and will automatically adjust to the new wall.

To access and edit wall-core boundaries and material layers, select a wall and choose **Element Properties** ➤ **Edit Type**. In the **Type Properties** dialog box, select **Structure** as the parameter to

edit. This will open a new Edit Assembly dialog box. From here you can add or delete wall layers, define their materials, move layers in and out of the core boundary, and assign functions to each layer (see Figure 12.1).

FIGURE 12.1
The Edit Assembly dialog box of a wall type lets you define the construction layers of a wall.



To get a feel for how core layers are used in relation to a floor, start a new session of Revit and follow these steps:


1. Open a new project, select the Wall tool from the Basic tab in the Design bar, and draw a simple rectangular floor plan. Prior to drawing it, from the Type Selector select a multilayered wall type in order to understand the value of the exercise—the Brick on CMU wall type works well. Draw at least four connected walls that represent a simple floor plan.
2. Use the View Control bar to switch to fine or medium detail view so you can see the wall layers. (In coarse views, wall layers are never displayed.)
3. On the Home tab, select the Floor tool, and from the Draw panel keep the default Pick Walls option, and on the Options bar, check the Extend into Wall (to Core) option.

Offset: 0.0 ☒ Extend into wall (to core)

4. Position your cursor over an edge of the wall (do not click yet), press Tab to highlight all connected walls, and then click to select, and then zoom in. A boundary line indicating the shape of the floor will be created. This line indicates the position of the floor boundary relative to the wall—it's drawn at the exterior edge of the wall core. Make sure you've selected all walls as a reference to create the floor and click Finish Floor.

- 5. Create a section through the wall and open the section view. Again, make sure your view level of detail is set to medium or fine. You'll see the edge of the floor and how it aligns with the wall construction. Figure 12.2 shows the sketch in plan and how the floor looks when finished in section.

FIGURE 12.2
Floor sketch indicated in plan view (left), and section through the floor and the wall (right).



If you change the wall type later on or move its position, the floor will update to maintain its position relative to the wall's new core position.

Layer Join Cleanup

Having clean and legible drawings is important when representing construction design intent. To this end, Revit provides a wall layer priority system that intelligently manages the cleanup of wall layers between touching and/or intersecting multilayered walls. Revit provides six functions (levels of priority), with *Structure* having the highest priority (Figure 12.3).

FIGURE 12.3
Each wall layer has a function.

	Function	Material	Thickness	Wraps
1	Finish 1 [4]	Masonry - Brick	90.0	☒
2	Structure [1]	Air Layers - Air	76.0	☒
3	Substrate [2]	Insulation / Thermal	76.0	☒
4	Thermal/Air Layer [3]	Dr / Moisture Barriers -	0.0	☒
5	Finish 1 [4]	Layers Above Wrap	0.0	☒
6	Finish 2 [5]	Brick - Concrete Mason	100.0	☒
7	Membrane Layer	Layers Below Wrap	0.0	☒
8	Substrate [2]	Metal - Furring	42.0	☒
9	Finish 2 [5]	Finishes - Interior - Gypsum	16.0	☒

When you create a new wall type and begin defining and adding layers to the wall, you need to assign a material, thickness, and priority to those layers. When you're assigning a priority, think about the function of the layer in the wall—is it finish? Substrate? Structure? This decision will help Revit understand your intent and help clean up your wall joins down the road.


Editing Wall Joins

If you encounter situations in which the automated wall cleanup doesn't correspond to your expectations, a tool is provided that allows you to cycle through a range of possible layer configurations using the Wall Joins tool, located on the Modify tab.



With the Wall Joins tool, you can edit wall join configurations. The default wall join is set to butt join (see Figure 12.4). Activate the Wall Joins tool, and place your cursor over a wall join. (This can be a corner where two walls meet.) The Options bar shows some alternative configuration options: Miter and Square. A miter join is also shown in Figure 12.4.


FIGURE 12.4
A butt wall join
(left) and a miter
wall join (right).



Disjoining Walls

In some cases, you will want to override the intelligent wall cleanup that Revit provides. For example, a nonrated partition should not interrupt the gypsum board in a fire-rated wall. The Disallow Join option lets you create this condition. To access this command, right-click the blue control dot at the end of any wall and select Disallow Join from the context menu. Doing so breaks the auto-join cleanup. Figure 12.5 shows the default cleanup (left) and the same join after disallowing the join and adjusting the wall end (right).


FIGURE 12.5
The Disallow Join
option provides
extra flexibility
in controlling the
wall joins.



A wall on which Disallow Join has been applied displays an Allow Join symbol upon selection (Figure 12.6). This is to give you a visual aid so you know when a wall has been explicitly set to not join. Note that the symbol only appears when a single wall has been selected.

FIGURE 12.6

The Allow Join option indicates a wall that has Disallow Join applied to it.




Stacked Walls

Walls in a building, especially exterior walls, are often composed of different wall types, made out of different material combinations and with different widths that stack one on top of another over the height of the façade. At the very least, most walls sit on top of a foundation wall. You can create such walls by creating individual walls of different types at different heights, but if you want an intelligent relationship among all different wall types that make up one wall and that act together as one wall (for example, the foundation wall moves and you expect walls on top of the foundation to also move), a *stacked wall* might be a good way to go.


Stacked walls allow you to create a single wall entity composed of different wall types stacked on top of each other. In order for you to construct stacked walls, some basic wall types need to already be defined in your project. To understand how stacked walls work and how to modify one, follow these steps:

1. Open a new session of Revit, and make sure three levels are defined. (If you don't have three levels defined, switch to an elevation view, add a few new levels, and then go back to your floor plan view.)
2. Pick the Wall tool on the Home tab and select Stacked Wall: Exterior - Brick Over CMU w Metal Stud located at the bottom of the list in the Type Selector, as shown here:



3. In the Element Properties dialog box, click the Edit Type button and then duplicate the wall type to create a new stacked wall.
4. Edit the structure parameter and click the Preview button to see the wall in section (Figure 12.7). When you're editing the Stacked wall type, you'll notice that the user interface is slightly different from when you're working with a basic wall. Rather than editing individual wall layers, in this dialog box you are editing Stacked wall types.

FIGURE 12.7
Section preview of
stacked wall type.




5. Click the Insert button to add a new wall. A new row appears in the list and allows you to define a new wall. Select the Generic wall type from the Name list, and set the Height value. With a new row selected, click the Variable button. This will allow the wall to vary in height to adjust with level heights. Click OK in each dialog box to return to drawing the wall.
6. Go back to your level 1 plan view and draw the new wall, setting its top constraint to Level 3 using the Options bar.
7. Cut a section through the model and change the heights of Level 1 and Level 3 to see the effect this has on the wall. (Make sure the level of detail is set to medium or fine so you can see the wall layers.) You'll see that changing Level 2 does not change the bottom walls because they are fixed in height. However, changing the height of Level 3 changes the height of the variable wall (Figure 12.8).

Adding Wall Articulation

Walls are often complex and articulated in their composition. Cornices, reveals, corrugated metal finish, and other projections are used all the time. Some wall finishes have more than one material on them, and they can be flush or of different thickness. Revit can accommodate any of these types of design articulation in smart wall assemblies. Some examples of such walls, called "compound walls" by many Revit users, are shown in Figure 12.9.

FIGURE 12.8

The middle section of this stacked wall varies on a per-instance basis.



From the Edit Assembly dialog box of any basic wall type, you can enable a preview of the wall. This preview allows you to view the wall in either plan or section. When the section preview is active, additional tools also become active and allow you to place geometric sweep and reveal components on the wall (Figure 12.10).

FIGURE 12.9

Compound vertical walls: (A) brick wall with horizontal sweeps, reveals, and a top finish; (B) compound wall with aluminum corrugated finish, trapeze-shaped; (C) compound wall with aluminum corrugated finish curved; (D) compound wall with slanting wall finish.





FIGURE 12.10
With section view active, tools for modifying the vertical structure become active.



EXAMPLE: ASSIGNING TWO DIFFERENT MATERIALS ON THE FINAL FINISH OF A WALL

Now, imagine a case where you need to create a wall that has two different material finishes that are flush aligned, as seen in Figure 12.11.

- 1. Select a multilayered wall as a base and duplicate it to create a new wall type.
- 2. In the wall’s Edit Assembly dialog box, switch the view to show a section view of the wall.






FIGURE 12.11
Exterior wall layer built of two different materials arranged vertically.



In this exercise, the exterior wall layer is plaster, but what you need is the lower 4" (120cm) to be brick and to keep the walls flush with one another.

- 3. Place your cursor at the beginning of the exterior finish layer. This highlights the wall component in the section preview. Select the Split Region tool and split the layer at the 4" (120cm) height (Figure 12.12).

FIGURE 12.12
The Split Region tool applied to the exterior layer.




- 4. The moment you split the layer, you will notice that the Finish layer reports a thickness of 0.00, meaning that it is variable.



EXTERIOR SIDE				
Function	Material	Thickness	Wraps	
1 Finish 1 [4]	Plasterboard	Variable	☒	☒
2 Thermal/Air Layer	Misc. Air Layers -	76.0	☒	☒
3 Membrane Layer	Air Barrier - Air In	0.0	☒	☒
4 Substrate [2]	Wood - Sheathing	19.0	☒	☒
5 Core Boundary	Layers Above Wr	0.0	☒	☒
6 Structure [1]	Metal - Stud Layer	152.0	☒	☒
7 Core Boundary	Layers Below Wra	0.0	☒	☒
8 Membrane Layer	<By Category>	0.0	☒	☒
9 Finish 2 [5]	Plasterboard	13.0	☒	☒
INTERIOR SIDE				
Insert Delete Up Down				


- 5. Add one more layer. Use the Insert button and add that layer right after the first exterior finish layer. Change its function to Finish 1, its material to Brick, and its thickness to 0.



EXTERIOR SIDE				
Function	Material	Thickness	Wraps	
1 Finish 1 [4]	Plasterboard	90.0	☒	☒
2 Finish 1 [5]	Masonry - Brick	0.0	☒	☒
3 Thermal/Air Layer	Misc. Air Layers -	76.0	☒	☒
4 Membrane Layer	Air Barrier - Air In	0.0	☒	☒
5 Substrate [2]	Wood - Sheathing	19.0	☒	☒
6 Core Boundary	Layers Above Wr	0.0	☒	☒
7 Structure [1]	Metal - Stud Layer	152.0	☒	☒
8 Core Boundary	Layers Below Wra	0.0	☒	☒
9 Membrane Layer	<By Category>	0.0	☒	☒
10 Finish 2 [5]	Plasterboard	13.0	☒	☒
INTERIOR SIDE				
Insert Delete Up Down				

- 6. Place the cursor at the front of the row of the new material and select it. This highlights the material and shows a thin red line in the section view (Figure 12.13).

FIGURE 12.13
Highlight the lower portion of the split wall layer to assign a new material to it.




- 7. After adding that layer, click the Assign Layer button and select the portion of the wall that you wish to assign the zero thickness layer to (in this example, the lower portion).

The result is that the selected portion of the wall has the new layer assigned and your wall exterior face shows two different materials.

While working on a complex compound wall, you might have a situation where you need to merge horizontal or vertical wall layers that already exist in the wall. For that, use the Merge button and select the line between two layers. Once the cursor is over a line between two layers, an arrow indicating which layer will override the other one during the merge shows up, as shown in Figure 12.14.


FIGURE 12.14
(A) Merge layers vertically;
(B) merge layers horizontally.



Wall Wrapping

Materials are detailed at insert conditions (where doors, windows, and openings are placed in walls) depending on the construction type, building conventions, and aesthetics. For this purpose, Revit provides Layer wrapping options in the wall Edit Assembly dialog box; however, they aren't sufficient to accommodate a complex wrapping situation specific to a particular door or window. To achieve more control over these construction conditions, you need to set parameters in the window or door family itself.

In the Family Editor, you can assign a *Wall Closure* property to reference planes. This parameter defines a plane in the wall family to which wall layers can wrap to.



In a door or window family, check the option *Wall Closure* in the Element Properties dialog box for the reference plane. This means that the exterior wall layers that have wraps assigned will terminate at this reference plane. The effect can be seen in Figure 12.15.

FIGURE 12.15

(A) The reference plane in the Family Editor, and (B) its effect when set to *Wall Closure*.



Sweeps and Reveals

Many walls have linear embellishments that are attached or embedded in the construction. Cornices, brick soldier courses, and reveals are all examples. Using basic walls, you can add these elements directly into wall types.

Clicking the Sweeps or Reveals button in the Edit Assembly dialog box opens a new dialog box where you can define profile families to use as sweeps or reveals.



These are 2D shapes made out of simple lines and then swept along the length of the wall at a specified height. Many profiles representing cornices, skirting, and chair rails ship with Revit, but if you need to create a custom profile, you can use the Profile Family template. Open the Application Menu and choose **New > Family** to access the Revit Family Editor templates. Choose a default Profile template. From here, you draw a single closed loop of lines at the desired real-world scale and load the profile back into your project. Be sure to use dimensions to verify the size of your profile. Follow these steps to get a feel for the workflow.

1. Click the wall tool from the Home tab, then click the Type Properties button in the Element Types dropdown menu, and then duplicate the type.
2. Open the Wall Assembly dialog box.

FIGURE 12.17
Profiles attached to
wall top and base.





FIGURE 12.18
Wall with cor-
rugated siding
created with inte-
grated wall sweep.



REVEALS

Reveals can be added to a wall using the same workflow you use with sweeps; the only difference is that the profile is subtractive rather than additive.

WALL SWEEP RETURNS

When you're working on traditional architectural projects, the wall sweeps usually wrap around door openings in thick walls. Revit can accommodate that using the Change Sweep Return command. To understand this feature, follow this simple exercise:

1. Open a new session of Revit and place a generic wall. Switch to the default 3D view.
2. Rather than placing a sweep in the wall type (as we just did), you can use another method for placing sweeps: the Wall Sweep tool located in the Wall drop-down list.



These sweeps can be placed either vertically or horizontally using the contextual ribbon.




3. Add a horizontal sweep to the middle of the wall. Use the temporary dimensions to place the sweep at the desired height.
4. Choose the Wall Opening tool, located on the Modify tab.



Select Wall Opening, and using this tool, draw an opening that intersects the sweep (Figure 12.19).

FIGURE 12.19


A manually placed wall sweep intersected by a wall opening shown in (A) perspective and (B) elevation.



5. Select the sweep—it will display a blue grip at the end (the edge of the opening). Click the Modify Returns button in the Modify Sweeps contextual tab. Also take notice of the Options bar, where you can also set the angle of the return or decide to make a straight cut. The cursor turns into a knife symbol, and when you click somewhere on the profile it creates a new segment that can be wrapped around the edge of the opening. Press Esc or use the Modify tool to exit the command. You will need to zoom in close to the end of the sweep to really see the effect. (If you zoom very closely, the lines might become thick and ugly. In that case, click the Thin Lines Mode button on the View tab.)
6. Select the sweep again, and drag the control to adjust the length of the sweep. Figure 12.20 shows how the return can be modified.

FIGURE 12.20

Wall sweep returns.




EXTENDING WALL LAYERS BEYOND THEIR BASE

In many construction scenarios, you need layers of materials to extend beyond the base of the wall. A typical example is the extension of sheathing and siding on an exterior wall (Figure 12.21). Letting layers extend requires you to unlock the bottom edges of the wall from the sectional preview in the Edit Assembly dialog box. Once the layers have been unlocked, an instance parameter of the wall becomes enabled, either Base Extension Distance or Top Extension Distance (depending on which edges you unlocked). This value can be entered directly in the Element Properties dialog box or adjusted graphically when you select the wall by dragging the small blue triangle control at the bottom of the unlocked layer.

FIGURE 12.21


Example of wall layers extending past the base of the wall.



Follow these steps to enable the Base Extension parameter of a wall:


1. From the Home tab, create a new Wall. Select it and duplicate it by editing the type. Name it **Exterior wood siding**.
2. Select the structure parameter to open the Edit Assembly dialog box.
3. Add a new layer to the exterior of wall, set its function to Finish (4), use the material *siding - clapboard*, and give it $\frac{3}{4}$ " thickness.
4. Open the preview and look at the section view. Zoom into the bottom of the wall.
5. Select the Modify button located in the dialog box, and then click on the bottom edge of the exterior siding layer. Click the padlock icon to unlock the layer (Figure 12.22). Note that if you wanted to unlock additional layers, they all need to be adjacent—you cannot, for example, extend layers on either side of the core.

FIGURE 12.22
Use the padlock icon to unlock layers.



6. The layer is now unlocked. Click OK twice to get back to the Instance Properties dialog box. You'll see that the Base Extension Distance parameter is now enabled. Type in **-10"** for this parameter, and check the wall in 3D. You'll see that the wood siding layer is now extending 10" below the level shown in Figure 12.23.

FIGURE 12.23
Modifying the wall layers to have a base extension.




Creating Custom In-Place Walls

When you're working on traditional architecture or restoration of historic buildings, you often need to create walls that are irregular in shape. The Model In-Place tool, found in the Component drop-down on the Home tab, lets you address such wall styles. Figure 12.24 shows an example. This tool allows you to draw solid geometry using one of four modeling methods. Each created form is assigned a specific category that is later used to control visibility and behavior in the model. For example, assigning a sweep to the category Wall allows the wall to host inserts such as windows and doors.

FIGURE 12.24

Manually constructed wall used to create nonvertical wall surfaces.



USING BLENDS TO MAKE NONSTANDARD WALL SURFACES

The wall in Figure 12.24 was created using a series of blends assigned to the category Wall using the In-Place modeling method located in the Component tool on the Home tab. It still behaves like a wall: you can insert doors and windows into it; they will cut through the geometry and create openings. If you are making a wall schedule, you will also be able to schedule these walls and get correct documentation—very slick!

Various wall types can be created using this method. Consider the modeling tools we've covered previously and how you can use them to generate unique wall profiles.


Using Advanced Modeling Design Techniques for Curtain Walls

Curtain walls in Revit are unique wall types that allow you to embed divisions, mullions, and panels directly into the wall. They have a distinct set of properties, but still share many characteristics of basic walls.

The curtain wall A curtain wall is drawn like a basic wall and is available in the Type Selector when the Wall tool is active. It has top and bottom constraints, can be attached to roofs, can have its elevation profile sketch-edited, and is scheduled as a wall type.


Curtain grids These are used to lay out a grid that defines the physical divisions of the curtain wall. The layout grid can be designed freely as a combination of horizontal and vertical segments or can be a type with embedded rules that specify regular divisions. Figure 12.25 shows a typical grid division and expressive curtain panels in between.

FIGURE 12.25
Curtain wall with regular orthogonal grids and expressive curtain panels.



Mullions These represent the metal profiles on a glass façade, and in Revit they follow the geometry of the grid. They can have any shape that is based on a mullion profile family. Mullions can be vertical or horizontal. If you have a playful spirit, however, you can make curved mullions as shown on Figure 12.26.

FIGURE 12.26
With a little bit of
inventive spirit,
you can have
curved mullions
as well!



Curtain panels These fill in the space between gridlines and are always one of the following:

Empty panels No panel is placed between the grids.

Glazed panels These can be made out of different types of glass that can have any color or transparency.

Solid panels and panels with wall types These can take on any geometry you wish and thus create the most interesting structures, like the one shown in Figure 12.26.

Wall types as infill You can also choose from the Type Selector a wall type to fill the space between the gridlines (mullions). All wall types in the project will be available for your selection. Adding a wall type is usually a typical case in office partitions where the lower portion is a parapet wall and glass fills the upper portion of the metal stud wall.


Designing a Curtain Wall

In this exercise, we'll walk through the creation of a simple curtain wall. To draw a curtain wall, you can either draw a standard wall and then change its type to Curtain Wall or select a Curtain Wall type from the Wall Type Selector first. Follow these steps:

1. From the Home tab, select the Wall tool.
2. From the Type Selector, select Curtain Wall 1.
3. In the Level 1 plan view, draw a simple curtain wall (Figure 12.27). Use the wall type Curtain Wall 1.

FIGURE 12.27


A generic curtain wall before adding any grids or mullions looks like a simple glass wall.



4. Toggle the view to see the result in 3D.
5. Divide the wall into panels using the Curtain Grid tool on the Home tab. Position your cursor over the edges of the wall to get a preview of where the grid will be placed. (Selecting a vertical edge places a horizontal grid, and selecting a horizontal edge allows a vertical grid.) Revit has some intelligent snapping built into grid placement that looks for midpoints and points that will divide the panel into thirds. Place the grid so that you get something like Figure 12.28.


FIGURE 12.28

Curtain wall with a few added grids.




6. Place mullions on the wall. You can place one mullion at a time by selecting separate grid segments. If you want to apply the same mullion on all segments, hold the Ctrl key and click a gridline to select all segments and apply the mullions. With mullions placed, your wall should look like Figure 12.29.


FIGURE 12.29
Mullions applied
to the grids on a
curtain wall.



7. Let's say you want to add more mullions, but this time you don't want them to extend the entire height of the curtain wall. Select the Curtain Grid Line tool on the Home tab, and place new grids (Figure 12.30).

FIGURE 12.30
To add more mul-
lions, you will
need to add
another grid.






8. Before applying a mullion to the new gridline, delete the segments of the gridline where you don't wish the mullion to occur. (You can also add grid segments that don't span the entire panel. This may be faster than creating a long grid and then deleting the segments you don't want.) Close the Curtain Grid tool, and select the newly created gridline. Click the Add or Remove Segments button in the contextual tab and click the segment you want removed.

Remove the top and bottom segments, and then add mullions (Figure 12.31).

FIGURE 12.31
Removing portions
of the grid and
applying a mullion
on the remaining
segment of the grid.



Curtain Panels

Curtain panels fill the space between the curtain grids and mullions. These elements are created in the Family Editor using the Curtain Panels family template. Access them by choosing Application Menu ➤ New ➤ Family ➤ Curtain Wall Panel.rft. The Revit default template has a couple of curtain panels preloaded: System Panel Glazed and System Panel Solid. You can duplicate different types of these families and change the material, thickness, and offset to customize the appearance.

Figure 12.26, earlier in this chapter, shows some very creative curtain panels.

SELECTING THE ELEMENTS WITHIN THE CURTAIN WALL

Revit provides specially tailored selection options in the context menu to aid with workflow and interaction when you're working with curtain walls.



When you hover the mouse over or select an element in a curtain wall, take note of the status bar in the lower-left corner of the screen: it tells you exactly the type of element you're about to select or have already selected. Depending on what the mouse is hovering over, various selection options are available. The elements you can select include the following:

- ◆ The entire curtain wall entity (indicated by a green dashed line surrounding the curtain wall)
- ◆ A gridline
- ◆ A mullion
- ◆ A curtain panel


To select the element you want, use the Tab key until that element is highlighted.

Curtain Wall Doors and Windows

Curtain walls can host specially designed doors and windows. Keep in mind that standard doors and windows cannot be hosted by a curtain wall. These specially designed elements are recognizable in the library by a name that indicates they are curtain wall doors or windows. Revit schedules them as doors and windows, but their behavior is dependent on the curtain wall. Curtain wall doors and windows adapt their width and height to fill in grid cells. Essentially, they behave exactly like panels—they've just been made to appear and schedule as doors or windows. To insert a door within a curtain wall, choose Component ➤ Load from Library ➤ Load Family. Navigate to the Doors folder, and select a curtain wall door (single or double). Figure 12.32 shows a curtain door panel that has been swapped with a glazing panel. To make your own doors, select the Application Menu ➤ New ➤ Family ➤ Door - Curtain Wall.rft.

FIGURE 12.32

A special curtain wall door family is used to represent a door within a curtain wall.



Complex Curtain Wall Panels

Look at the complex-shaped curtain panels in Figure 12.33. You may think, “Oh, I can *never* do that!” Well, Revit can help you do it—and do it easily. The creation principle behind any of these types of curtain walls is the same as you learned in Chapter 10. By being smart about nesting and linking parameters, it is possible to build sophisticated curtain panel families.

FIGURE 12.33
Complex curtain
wall panel example
using a series
of nested
components.



The Bottom Line

Use advanced modeling techniques for standard walls. Many design situations require more than just the basic wall features; learn to use the more advanced Revit tools.

Master It A design calls for a horizontal soldier course in a brick wall every 12" on the façade. Using Revit, how would you build this into a wall element?

Use advanced modeling techniques to create stacked walls. Walls along a building façade usually have different construction layers from foundations to the top of the building. Stacked walls allow for a single wall to be constructed with varying wall types along its height.

Master It You have a building project where you are still experimenting with a number of floors but have already defined the wall types for the foundation, typical floor, and the attic and have combined them in a stacked wall type. How do you define the stacked wall so that it will accommodate middle floors with varying heights?

Use advanced modeling techniques for curtain walls. Curtain walls find their way into many architectural projects and designs. Knowing how to manipulate curtain walls in Revit is a key piece of the software for many design solutions.

Master It You've got to add a doorway to a storefront façade you've made. How would you go about doing this?

Chapter 13

Extended Modeling Techniques— Roofs and Floors

In the previous chapters we covered basic modeling techniques for constructing a simple building. We skipped over many additional features to give you a handle on essential workflow, the user interface, and making modifications to the model. In this chapter we cover more advanced features that are available any time you're modeling in Revit. As you'll see, with a little refinement and creativity, you can create a wide range of building components using the standard tools.

In this chapter, you'll learn to:

- ◆ Understand the various roof creation methods
- ◆ Create all kinds of roofs
- ◆ Work with advanced roof and floor shape editing

Understanding the Various Roof Creation Methods

In real life, roofs can come in many shapes, sizes, and degrees of complexity. They can be as simple as a single-pitch shed roof, or they can involve complex sine curves or intersecting vaults. Once you understand Revit's primary concepts, logic, and tools, you will be able to design just about any roof shape.

In general, roofs in Revit can be constructed in four different ways:

Roof by footprint Use this method to create any standard roof that more or less follows the shape of the building footprint and is a simple combination of roof pitches.

Roof by extrusion This method is best applied for roof shapes that are geometrically generated by extrusion of a profile, such as sawtooth roofs, barrel vaults, and waveform roofs.

In-place roof This technique is used to accommodate roof shapes that cannot be achieved with either the footprint or extrusion methods. They are either done by using the general modeling techniques and applying a roof category to that geometry, or by using an underlying mass form.


Roof by face In this technique, you select faces of massing forms to create standard thickness roofs. You can create those underlying massing forms within Revit, or import geometry created in other modeling applications into a mass family and use it as an underlay to create the roof by face. This technique is discussed in more detail in Chapter 8, “Concept Massing Study: Early Design Phase.”

The following sections provide a close look at these approaches and review their application to real-world scenarios.

Roof by Footprint

Use the roof by footprint method to create any standard roof that more or less follows the shape of the footprint of the building and is a simple combination of roof pitches (Figure 13.1).

FIGURE 13.1
Simple roof
created using the
roof by footprint
method.




These roofs are based on a sketched shape that you define in plan view at the soffit level and that can be edited at any time during the development of a project from plan and axonometric 3D views. The shape can be drawn as a simple loop of lines using the Line tool, or can be created using the Pick Walls method, which also should result in a clean closed loop of lines. The latter means that the exterior walls are used to define the shape of the roof.

The best way to conceptualize the roof by footprint method is to understand that the sketched shape defining the main shape of the roof is just a simple, closed loop of lines—nothing more than that, regardless of whether it’s drawn or picked.

The Pick Walls method provides an intelligent selection method, so if you select walls as references to generate the sketch lines, with or without an offset to the walls, the lines will maintain a smart relationship with the walls. The Pick Walls method is the suggested approach for creating roofs by footprint. By selecting the walls to generate the sketch for the roof, you are creating an exclusive relationship between the walls and the roof so that if the design of your building later changes (wall position, level height, wall height, etc.), the roof will follow that change and adjust to the new wall position without any intervention from you (Figure 13.2). Like any change in Revit, this happens everywhere in all views, and thus not only the model but also its entire documentation and related quantities will be updated. This will not automatically occur if you just drew the roof lines and did not explicitly create a relationship between them and the underlying walls.

FIGURE 13.2

Examples of using the Pick method:
 (A) original roof;
 (B) entrance wall position has changed and roof has been updated automatically;
 (C) angle of wall to right of the entrance has changed and roof has changed to a new shape.




To guide you through the creation of roof by footprint and explain some of the main principles and tools, here is a brief exercise demonstrating the steps:

1. In a new project, open a Level 2 plan view and create a building footprint similar to Figure 13.3.

FIGURE 13.3

Draw a simple set of walls.





2. From the Build panel in the Home tab, select the Roof tool. The default setting for the Roof tool when you click on the Roof button is Roof by Footprint. The other roof creation options as well some other roof-related tools are available when you expand the Roof button using the little arrow in the icon.
3. From the Draw panel in the Create Roof Footprint tab, select the Pick Walls tool (this should be the default).
4. When you've chosen to create a roof by footprint, the Options bar makes the tools shown here available.




To define whether you want a sloped or flat roof, use the Defines Slope check box in the Options bar. The Overhang parameter allows you to define the value of the roof overhang beyond the wall. When the Extend into Wall (to Core) option is checked, the overhang is measured from the wall core. If the option is deselected, the overhang is measured from the exterior face of the wall.

5. After defining these settings, place your cursor over one of the walls (don't click). Press the Tab key. This will result in both automatic selection of all walls and automatic indication of the roof overhang around those walls. Once you see the entire roof overhang indicated around all walls, click with the mouse over the wall. The dashed lines indicating the overhang will turn into solid lines, confirming that the roof sketch is created. The lines will be offset from the walls by the value of the overhang that you defined in the Options bar. Your display should look like Figure 13.4.

FIGURE 13.4

Roof sketch lines are automatically drawn offset from the walls by the value of the overhang as defined in the Options bar.



6. Click the Finish Roof button at the top right of the ribbon menu.

If at any time the shape of the roof doesn't meet your expectations, you can select the roof and select Edit Footprint from the Edit panel in the Modify Roofs tab to return to sketch mode, where you can edit lines or sketch lines or the slope.

To change the slope definition or angle of individual portions of the roof, select the roof, and then from the Edit panel, click Edit Footprint. This brings you back to Sketch mode; select the sketch line of the roof portion for which you wish to change the slope and either toggle (check) the Defines Slope button in the Options bar to remove or add a slope, or click the slope value that is displayed when you select the sketch line to change the slope angle. If you mistakenly made all roof sides with slope but wanted to make a flat roof, you can Tab-select all sketch lines that form the roof shape and clear the Defines Slope box in the Options bar.

Roof slope can be measured in different ways: it can be set as an angle or percentage rise. You can find all slope measuring options on the Manage tab by selecting the Project Units in the Project Settings panel and then selecting Slope (see Figure 13.5). If the current slope value is not expressed in the units you want to use (such as percentage when you want it to display an angle), you'll need to change the slope units in the Format dialog box. (You will not be able to do this while editing the roof slope.) Setting it here means specifying the way you measure slopes for the entire project.

FIGURE 13.5
Format dialog box
for slopes.



Here are some of the important instance properties you should be aware of and know how to set properly. All are found in the dialog box shown in Figure 13.6:

Base Level As in other Revit elements, this is the level at which the roof is placed. The roof moves with this level if the level changes height.

Room Bounding When this is checked, the roof geometry has an effect on calculating room area and volume.

Related to Mass This property is active only if a roof has been created with the roof by face method (Conceptual Mass tools).

Base Offset from Level This option lowers or elevates the base of the roof relative to the base level.

Cutoff Level Many roof shapes require a combination of several roofs on top of each other. To do this, you need to cut off the top of a lower roof to accommodate the creation of the next roof in the sequence. Figure 13.7—in which the cutoff level is applied to the main roof and a secondary roof is built on top of the main roof using the cutoff level as a base—is an excellent example of this technique.

FIGURE 13.6
Roof Properties
dialog box.





FIGURE 13.7
The cutoff level is
applied to the main
roof, and a second-
ary roof is built
on top of the main
roof using the cut-
off level as a base.




Cutoff Offset When the Cutoff tool is applied, the Cutoff Offset value also becomes active and allows you to set the cutoff distance from the level indicated in the Cutoff Level parameter.

Rafter Cut This defines the eave shape. You can select from Plumb Cut, Two Plumb Cut, or Two Plumb Square. When Two Plumb Square is selected, the Fascia Depth parameter is activated and you can set the value for the depth.

Rafter or Truss With Rafter, the offset of the base is measured from the inside of the wall. If you choose Truss, the plate offset from the base is measured from the outside of the wall. Figure 13.8 is a typical example of a roof by rafter cut.


FIGURE 13.8
Construction
drawing of a
rafter detail.



Roof by Extrusion

The roof by extrusion method is best applied to roof shapes that are generated by extrusion of a profile, such as sawtooth roofs, barrel vaults, and waveform roofs. Like the roof by footprint method, it is based on a sketch; however, the sketch that defines the shape of the roof is drawn in elevation or section view (not in plan view) and is then extruded along the plan of the building (see Figure 13.9).

FIGURE 13.9
A barrel-shaped
roof extended
with sunshades.
The main roof is
an extruded arch
sketch.



The Roof by Extrusion tool offers additional settings in the Options bar when selected.




Roofs by extrusion do not have an option to follow the building footprint, but that is often needed to complete the design. To accommodate this, a special tool called Vertical Opening is provided. This tool is available when you select Roof by Extrusion from the Modify Roof panel on the Modify tab.

Here's a brief explanation of how the tool works. First you create your roof by extrusion by defining a profile in elevation that is then extruded above the building. The extrusion follows a straight path, which probably is not the same as the building footprint (unless your building footprint is also a straight rectangle in shape). If the shape of the building is nonrectangular in footprint or the shape of the roof you want to create is not to be rectangular, this tool will let you carve geometry from the roof to match the footprint of the building or get any plan shape you need using a plan sketch.

You will recall that with sketch-based design, any closed loop of lines creates a positive shape, every next loop inside it is negative, the next one inside that negative one is positive, and so on. In Figure 13.10, a roof by extrusion was drawn at an angle to the underlying walls, but the final state should not extend beyond those walls. To clip the roof to meet the walls, the Vertical Opening tool was used to draw, in plan view of the roof, a negative shape that will remove the portions of the roof that extend beyond the walls.

FIGURE 13.10
The Vertical Opening tool applied in plan view to an extruded roof to follow the exterior shape of the building.




Roof-in-Place

The roof-in-place technique accommodates roof shapes that cannot be achieved with either of the previously mentioned methods. It is the usual way to model historic roof shapes or challenging roof geometries such as domes and onion-domed roofs (see Figure 13.11).

FIGURE 13.11

Manually constructed in-place roofs.




Here's the concept: you create a geometry using the Component tool found in the Home tab and select Model In-Place; then you can assign a roof category to it, and go wild with your creativity.

To start an in-place roof family, click the Component tool in Build panel of the Home tab. Select Roofs from the Family Category list (Figure 13.12), and click OK. This list allows Revit to assign a specific category (Roof in this case) to your in-place model and thus later schedule the new element as a roof.


You can create any roof shape using Solids and Voids and the modeling techniques of Extrusion, Blend, Revolve, Sweep, Swept Blend, or any combination of them (see Figure 13.13). There is a lot more information about some advanced shape-editing techniques later in this chapter, in the section "Working with Advanced Roofs and Floor Shape Editing."

FIGURE 13.12

Set the category for an in-place roof.

**FIGURE 13.13**

Organic-shaped roof created using the Swept Blend modeling technique.




SLOPED GLAZING

You saw earlier that a curtain wall is just another wall type made out of panels and mullions organized in a grid system. Similarly, sloped glazing is just another type of roof that has glass as material and mullions for divisions. Using sloped glazing, you can make roof lights and shed lights, and use them to design simple framing structures.

To create sloped glazing, make a simple pitched roof, select it, and use the Type selector available upon selection of the Change Element Type tool to change the type to Sloped Glazing. Once you have done that, switch to a 3D view and use the Curtain Grid tool to start applying horizontal or vertical grids that define the panel sizes; then you can apply mullions. Figure 13.14 demonstrates the process of converting a standard roof into sloped glazing.

FIGURE 13.14

(A) Standard roof.
(B) Convert a standard roof into sloped glazing.
(C) Divide with curtain grid.
(D) Add mullions to the grid.
(E) Finish applying all mullions to the grid.
(F) Change curtain panel from glass to empty.
(G) Finished rafters.






Real World Scenario

CREATING A RIDGE SKYLIGHT ROOF

Suppose we are planning a factory whose roof needs to be a ridge skylight on a pitch.




Here's how to make this roof:

1. In Level 1, draw the floor plan of the building. For the sake of simplicity, we will assume that the floor plan is a rectangle.
2. Switch to any elevation view and define two new levels in the drawing: Level 2 at 12' (4m), and Level 3 at 18' (6m).
3. Switch to Level 2 and from the Home tab on the Build panel, expand the Roof tool.
4. Select Roof by Footprint.




5. Click the Pick Walls tool from the Draw panel.
6. In the Options bar, define an Overhang setting of 1'6" (50cm), and check the Defines Slope option.
7. Click Finish Roof (at the far right of the Create Roof Footprint tab).

Once you complete these steps, this is how the resulting roof should look:



We now need to cut the top of this roof at Level 3.

1. Select the roof and, in its instance properties, select Level 3 under Cutoff Level and -1'8" (-57cm) for Cutoff Offset (the roof thickness value); then click Finish Roof. The result looks like this:




Next, we'll create the second roof and use the opening in the first roof as a reference for the sketch lines defining the new roof:

1. Switch to Level 3 and select the Roof by Footprint tool. Instead of selecting the Pick Walls option from the Draw panel, select the Pick Lines tool, right next to it.




2. You will notice a Lock option in the Options bar. When checked, this option will lock the newly generated lines to the lines of the lower roof that you use as a reference. Check the Lock option.
3. Now select the four edges of the opening of the first roof: this results in the creation of four new rooflines for the upper roof that have a relationship with the lower roof sketch lines indicated by the four closed padlocks.
4. Click Finish Roof.



You just created the upper roof but also a relationship between the two roofs. That way, if you later change the cutoff level or the geometry, the second roof will change to match the new cutoff level.


5. Select the newly created roof, and select the Change Element Type tool to open the Type Selector. From there, pick Sloped Glazing to get the following configuration:



If the slope of the upper roof isn't what you desire, you can change it at any time. Select the roof, click Edit Footprint in the Edit panel of the Modify Roofs tab, click each of the sketch lines, and type in a new value over the slope value displayed. In this example, we have set 9° for the upper roof (the skylight).

6. Divide the sloped glazing into segments and apply mullions. For that, use the Curtain Grid tool located in the Build panel of the Home tab and start dividing the glazing.

7. Add mullions by selecting the Mullion tool from the same Build panel and picking the gridlines on the glazing. The final outcome should be similar to this:




SLOPED ARROWS

Another way to slope a roof is by manually adding slope arrows to a sketch of flat roof slabs. This can be useful for unusual shapes, especially if the roof edges are not straight.

First create the sketch lines to define the shape of a roof, and do not check Defines Slope on the Options bar. Instead, choose the Slope Arrow tool from the Draw panel of the Modify tab. Draw the slope arrow in the direction you want your roof to pitch and at the intended height between the base of the roof and sloped end (see Figure 13.15).


FIGURE 13.15

A slope-defining arrow is added to the sketch in Roof by Footprint.



Once you've drawn the slope arrow, you can select it, and click on the Properties button in the Draw panel to open the Instance properties dialog box and set any of the parameters shown in Figure 13.16. The most critical parameter to check is Height Offset at Head. This defines the height of the roof slab from the base to the top of its slope.

FIGURE 13.16
Slope arrow
properties.



To create a shed roof, you can draw a roof without any slope-defining sides and then apply a slope arrow that defines the exact sloping (see Figures 13.17 and 13.18).

FIGURE 13.17
A shed roof defined
using the Slope
Arrow tool.





FIGURE 13.18
The same roof,
with the slope
arrow shortened.
Note that the roof
became much
steeper.





Creating All Kinds of Roofs

The following section demonstrates a series of typical roof conditions and the appropriate strategy to use in Revit to create these roofs. For any roof, there can be many ways to solve it geometrically. You can use this section as a guide and to shore up your skills with the roof tools and methods described previously in this chapter.

Each roof in the typology is represented with the roof plan view, sketch plan, and 3D view of the roof.


Flat Roof

We created this flat roof using Roof by Footprint and the Pick Walls tool; we also unchecked Defines Slope on the Options bar.





Gable Roof with Asymmetric Slopes

We also created this roof using Roof by Footprint and the Pick Walls tool. But in this example we checked Defines Slope for the shorter sides of the roof, and the slope angles are not identical.



Shed Roof

We created this Roof by Footprint by using the Pick Walls tool and checked Defines Slope for only one of the short sides of the roof.




Note that you could also make this same roof by adding a Slope arrow to a flat roof:




Hipped Roof

We created this Roof by Footprint by using the Pick Walls tool, and Defines Slope was checked for all sides of the roof.





Hip Roof Following Recessed Walls

We created this Roof by Footprint by using the Pick Walls tool. Defines Slope was checked for all sides of the roof except the three walls that recess toward the inside.






Gable Roof

We created this Roof by Footprint by using the Pick Walls tool and checking Defines Slope for all sides of the roof but not for the one that recesses toward the interior of the building.




Gable Roof with Extending Pergola

This Roof by Footprint was created over a rectangular floor plan using the Pick Walls tool. We then edited its sketch and included additional sketch lines to shape the extension. We checked Defines Slope only for the sides indicated in the sketch.




Hip and Gable Hybrid Roof

We created this Roof by Footprint by using the Pick Walls tool with Defines Slope checked for all sides.




Notice that we split the sketch lines of the shorter sides in thirds and checked Defines Slope *only* for the middle portion of the line, as shown here







Gambrel Roof

We created this Roof by Footprint by using the Pick Walls tool. We checked Defines Slope for the two long sides of the roof only. We cut the roof off at a certain height (cutoff level), and created a second roof using as a sketch the cutoff shape of the first roof. For the second roof, we checked the Defines Slope option for its two longer sides.





Dutch Gable with Glazed Roof

We created this Roof by Footprint by using the Pick Walls tool and checking Defines Slope for all sides of the roof. We cut the roof off at a certain height (cutoff level), and created a second roof using as a sketch the cutoff shape of the first roof. We set the Type value of the second roof to Sloped Glazing. For the second roof we also checked Defines Slope for all sides of the roof, but the slope of the second roof is slightly steeper than that of the first roof. We applied curtain grid and mullions to the sloped glazing. (See “Real World Scenario: Creating a Ridge Skylight Roof” earlier in this chapter for a full step-by-step procedure for this example.)




Dutch Gable

We created this Roof by Footprint by using the Pick Walls tool and checking Defines Slope for all sides of the roof. We cut the roof off at a certain height (cutoff level), and we created a second roof using as a sketch the cutoff shape of the first roof. We checked Defines Slope for all sides of the second roof; the slope of the second roof is slightly steeper than the slope of the first roof.






Hipped Roof with Sloped Arrow Dormer

We created this Roof by Footprint by using the Pick Walls tool and checking Defines Slope for all sides of the roof. We split the sketch line on the south of the building into four segments to allow for the dormer creation. We added sloped arrows facing each other and meeting in one point to the middle two segments of the split sketch line.






Hipped Roof with Two Dormers

We created this Roof by Footprint by using the Pick Walls tool and checking Defines Slope for all sides of the roof. The two dormers are also separate roofs created by the footprint of the walls defining the sides of the dormer. We then joined the roofs. The opening in the roof slab is made up of two simple closed loops of lines (this can be done directly in Sketch mode or later, using the Openings tool from the Modify tab).






Four-Sided Gable

We created this Roof by Footprint by using the Line tool from the Draw panel in the shape indicated in the sketch. Defines Slope is checked for all four corners (see the blowups of the corner and middle roof edge).



Hipped Roof with Extruded Roof Dormer


We created this Roof by Footprint by using the Pick Walls tool with Defines Slope checked for all sides of the roof. We created the dormer roof as a roof by extrusion by using the wall face as a work plane, and then joined with the other roof in the sketch (you could also use the Openings tool later).



Cone Roof


We created this in-place roof by using the Component tool and selecting Model In-Place from the Build panel of the Home tab, with Roof as the assigned category. A simple closed loop of sketched line is revolving around an axis.

This roof can also be created as a footprint roof that is sketched as a circle while Revit is in sketch mode. Make sure that the number of full segments is set to 0. Adding three or more segments created even faceting.




Dome

This dome was also created as an in-place roof using the Revolve modeling technique. To replicate it, you will first need to draw a reference line in plan view that crosses the center of the circle describing the exterior walls, and then, in section view, draw the revolving shape as well as the axis of rotation.




Barrel Roof

We created this example with the Roof by Extrusion method. A simple line in arc shape defines the main shape of the roof extruded over the building footprint. In this example we included an additional roof by extrusion and converted it into sloped glazing. The edges of the roof have been rounded using the Vertical Opening tool. The sloped glazing curtain panel type is set to Empty Glazing, which allows the mullion structure to create a sunshade.



Multipitch Roof

We created this Roof by Footprint by using the Pick Walls tool with Defines Slope checked for all sides of the roof. Regardless of how complicated the underlying footprint, Revit correctly calculates the ridges as long as the eaves are aligned.






Real World Scenario


CREATING A DORMER

Roofs with dormers generally cause grief for architects, so we'll guide you through the creation of one.


1. Create the base of a building, set up three levels, and create a Roof by Footprint with Defines Slope checked for all sides.
2. Approximately in the position indicated in the following graphic, on Level 2 create the four walls of a dormer using the Wall tool. Set their height to such a value that they extend above the roof. (For easier verification, create a cross section through the dormer to check the height of the dormer walls, and if necessary, modify their height in the element properties so that they extend above the roof.)




3. Using the Roof by Footprint tool, create a pitched roof on top of the dormer walls.
4. If you switch to a side elevation view, you will notice that the dormer roof probably does not extend to meet the main roof. Therefore, you will need to use the Join/Unjoin Roof tool, located on the Modify tab in the Edit Geometry panel, to join the main roof and the dormer. Select the Join/Unjoin Roof tool, select the main roof as the target, and then select the edge of the dormer roof to extend.





5. From the Edit Geometry panel on the Modify tab, expand the Openings tools and select Dormer Opening. Now pick first the main roof, then the dormer roof, and then the sides of the walls that define the dormer. Select the *inside* faces of the walls. Unlike with most sketches, in this case you will not need to provide a closed loop of lines. Finish the dormer opening.




6. Go back to the section view you previously created and edit the elevation profile of the walls to make sure they don't extend below or above the roofs. Note that you should *not* use the Top/Base Attach tool; instead use the Edit Profile tool available in the Edit panel on the Modify Walls tab to edit its elevation profile. Then manually change the base sketch line of the walls to get the triangular elevation profile as shown here:




Your dormer opening is now correct and you will see that it has cut the roof in two directions, as a true dormer needs to.






As a final touch, you can convert the front wall of the dormer to a storefront wall type or add a window.



Working with Advanced Roof and Floor Shape Editing

No flat roof is ever really flat! And Revit is equipped with smart tools that allow for tapered insulation over a flat roof and similar conditions. A rich set of shape editing tools for roofs and floors help create and modify such conditions in no time. These powerful tools are modifiers that are applicable to roofs and floors and will allow you to model concrete slabs with multiple slopes, often referred to as warped slabs (see Figure 13.19).

FIGURE 13.19
Sloped roof with drainage.



The set of tools available for editing floor and roof shapes are called Modification tools and appear in the Shape Editing panel of the Modify tab when a roof is selected. Here is what each tool is meant to do (left to right):



Modify Sub Elements This tool allows you to direct edit element geometry using selection and modification of points (vertices) and edges.

Add Point This tool allows you to add points on the top face of a roof or floor. Points can be added on edges or surfaces.

Add Split Line This tool allows you to sketch directly on the top face of the element, which adds split lines to the floor and roof so that hips and valleys can be created.

Pick Supports This tool allows you to pick linear beams and walls to create new split edges at the correct elevation automatically.

As you will see, once any of these modifiers are applied to a floor or roof, a new Reset Shape button appears on the tab when the roof is selected. Select this button to remove all modifiers applied to the floor or roof that you have selected.




Sloped Roofs

Let's do a short exercise that shows how to make a sloped roof like the one in Figure 13.20 (shown in plan view).

FIGURE 13.20

A roof plan showing a roof divided into segments, with drainage points.




Follow these steps:

1. Open **Modifying Roof Shape start.rvt** from the book's companion web page (www.sybex.com/go/masteringrevit2010).
2. Select the roof that has already been prepared for you.
3. From the **Shape Editing** panel, activate the **Add Split Line** tool (note that the color of the rest of the model grays out while the roof lines are dashed green).
4. Draw ridge lines to divide the roof into areas that will be independently drained. The ridge lines will be drawn in blue color.
5. Using the same tool, draw diagonal lines within those areas to create the valleys. Make sure you zoom in closely when drawing the diagonal lines, so to be sure that you are snapping in the exact same diving points. (Should you notice that you have not snapped well, select the **Modify Sub Elements** tool, delete the incorrect segments, and try again.)

You have split the roof surfaces into many subfloors, but they are still all at the same height and inclination. You should have a roof that looks like Figure 13.21. Take care when sloping structures using this method; the structural thickness decreases with changes in slope. Press **Esc** to exit editing mode.

FIGURE 13.21


Using the **Add Split Line** tool, you can create ridges and valleys.



6. Switch to a 3D view.
7. To add a slope, you need to edit the height of the drainage points. Tab-select the crossing point of the diagonals. New controls that allow you to edit the text appear, and you can either move the arrows up and down or type a value for the point height. As shown in Figure 13.22, type -0'5" (-13cm).

FIGURE 13.22

Drag the drainage points to change their height or type a new value in the numerical field.



8. Repeat steps 1–7 for all three drainage points.
9. If you need to move the point to another position (perhaps to accommodate what's happening in the room below the roof), select the point and drag it.
10. Make a section through the roof—if possible, somewhere through the drainage point. Open the section; change the detail level to Fine to see all layers. The entire roof structure is now sloped toward the drainage point.




What if you wanted the insulation to be tapered but not the structure? For that, the layers of the roofs can now have variable thickness. Let's see how to apply a variable thickness to a layer.

1. Select the roof, and navigate to its type properties to edit its structure.
2. Activate the preview. You will notice that in the roof-structure preview, you do not see any slopes. That is correct and will not change. This preview is just a schematic preview of the structure and does not show the exact sloping. Look for the Variable column under Layers (see Figure 13.23). This allows layers of the roof to vary in thickness when slopes are present. Check Variable for the insulation material.
3. Go back to the section view and take a look at the difference that this change provoked. As you can see, only the insulation is tapered now, while the structure remains flat.




FIGURE 13.23
The Edit Roof
Structure
dialog box.



Warped Surfaces

Warped surfaces can also be created using this tool. Using the Roof by Footprint method, draw a flat roof, uncheck Defines Slopes, and then select the roof. Using the Modify Sub Elements tool, you can start moving edge points up and down (Figure 13.24).

FIGURE 13.24
Warped roof.



The Bottom Line

Understand the various roof creation methods. There are multiple methods for creating roof forms in Revit, and you should become familiar with each.

Master it When would you use a Roof by Extrusion method?

Create all kinds of roofs. Roofs are an integral part of any building. Knowing how to create them in a variety of shapes and sizes is critical to the success of a project.

Master It In the early design phases of a project, you are exploring a variety of roof forms for your building. Create the base building form and explore different roof options and shapes. How would you go about exploring a variety of roof shapes?

Work with advanced roof and floor shape editing. Roofs are another seemingly simple element that presents architectural challenges, and Revit has tools for them.

Master It You are working on a flat roof retail project, but the roof is not really flat and will need to drain. Using Revit roof tools, how would you go about modeling this?

Chapter 14

Extended Modeling Techniques— Railings and Fences

In the previous chapters, we covered some advanced modeling techniques for making complex walls and curtain walls and for accommodating various specific conditions with roofs and floors. In this chapter, we explore some advanced stair and railing features that enable you to make some quite creative and smart designs. As you'll see, with a little refinement and creativity, you can create a wide range of railings and fences with a simple set of standard tools.

In this chapter, you'll learn to:


- ◆ Work with railings and fences
- ◆ Use balusters and rails to construct railings
- ◆ Adjust additional settings

Working with Railings and Fences

Railings and fences can range from very simple shapes to quite complex ones. A small selection of the possible variety of railings and fences can be found in the examples of the Revit help system (Figure 14.1). Railings and fences can be represented as simple walls that follow the sides of a stair or balcony, or the boundaries of your garden; you can also create glass frameless railings or complex combinations of balusters and posts in different materials (wood, metal, glass panels). Revit allows most combinations of railings to be built, but this does require a thorough understanding of the Railing tools, recognized as one of the more complicated tools in Revit.

FIGURE 14.1

From the Revit help system, a variety of possible railings and fences that can be created with Revit.




In the following sections, we will cover some of the main principles used to create different types of railings in Revit.

Railings

When you need to create a railing in your model, Revit provides a customized tool to accomplish this. From the Circulation panel of the Home tab, choose Railing. You'll enter a Sketch mode where you have to first draw the path of your railing (Figure 14.2). You define the position and length of a railing by drawing a base line in Sketch mode. You can draw the base line of the railing wherever you please: in the center of the stair or on the side. The actual geometry of the railing is defined in the type properties, where you set up rail and baluster placement rules.

FIGURE 14.2

Defining the position and length of a railing by drawing a base line in Sketch mode.



Like many elements in Revit, railings must be placed on a host object. A valid host for a railing can be a floor, a stair, a ramp, or a level. If you draw a railing sketch line without first defining a host, it is drawn on the active level of the view you are in and you will create a horizontal railing. If you want to add a railing to a stair, select the Railing tool and, before or after drawing the railing path but definitely before selecting Finish Railing, use the Set Railing Host button


available in the Tools panel of the Create Railing Path tab to select the stair as the host for the railing.

If you do not set a host prior to finishing drawing the railing, the railing will be placed below the stair, on the active floor or level. If you forget to do that and need to re-host the railing to a stair after sketching the railing, this is not a problem; you can re-host it later. To re-host, select the created railing, select the Edit Path tool available in the Edit panel of the Modify Railings tab, select Set Railing Host, and pick the stair as a host. Finish the sketch, and the railing will jump from the level to the stair.

Since a railing is based on a sketch line that defines its path, you can have your railing follow just about any path by drawing an appropriate line shape (Figure 14.3).

FIGURE 14.3

A freestanding railing and a railing hosted by a stair, both following the sketch line shape.




Subelements of the Railing Element and Principles of Railing Structure

A railing element consists of the subelements shown in Figure 14.4: posts, rails, and balusters.


FIGURE 14.4

Railing components.




Balusters These can be any shape or form. A baluster repeats itself in a railing based on spacing rules. To place balusters, you first need to load existing baluster families into your project. These could be baluster families provided by Revit or your own custom content. To create your own designed baluster families, use one of three available family templates: *Baluster.rft*, *Baluster-Panel.rft*, or *Baluster Post.rft*. Using the basic modeling tools explained in Chapter 6, “Modeling Principles in Revit I,” you can make balusters such as those shown in Figure 14.5.

FIGURE 14.5
Balusters can be
any shape or size.



Posts Posts can also have any shape, as shown in Figure 14.6. They are created using the *Baluster-Post.rft* template in the Family Editor.

FIGURE 14.6
Various post types
created using
Baluster-Post.rft.




Rails Rails are horizontal elements that can either connect posts (should there be any) or represent handrails attached to a wall. The geometry of the rails is defined by profile families that you create in the Family Editor using the *Profile-Rail.rft* family template. Figure 14.7 shows some examples of typical rail profiles.

FIGURE 14.7
Typical rail profiles.



A rail can appear attached to a wall as a handrail, as shown in Figure 14.8. In this case, no posts are used and the wall-mount brackets are custom-designed balusters. The rail is following the stair and is given an appropriate offset from the wall.


FIGURE 14.8
Handrail attached to wall.



Railing Construction

The order and combination of subelements of the railing element can create unlimited variations of railings. In the type properties dialog box of the railing, under the Rail Structure and Baluster Placement parameters (Figure 14.9), you can define any combination of rails and balusters.

FIGURE 14.9
Type properties of a railing element with embedded editors for rail and baluster placement.



Setting Up Rail Structure

From the type properties of a railing, selecting Rail Structure ➤ Edit. That displays the Edit Rails dialog box shown in Figure 14.10, where you define the number, shape, and position of the rails in your railing.

FIGURE 14.10
The Edit Rails
dialog box.




Figure 14.11 shows a railing with two rails: one set to 1' (30cm) height and the upper one set at 3'-6" (1m). Both of them use the profile Rectangular Handrail. The rails are placed with an offset to the mid-axis of the rail sketch line. (The balusters have no offset.) The 1" (2.5cm) offset pushes the rail away from the sketch line, as you can see in the front elevation.

FIGURE 14.11
Front and side ele-
vations of a railing
with two rails.



To define post and baluster patterns, click the Edit button for Baluster Placement in the type properties of the railing. You'll see the dialog box shown in Figure 14.12.

OPTIONS FOR POSTS

Depending on their position in the railing, posts can be placed at the Start, Corner, or End condition of the railing. You can choose to have different families for the three positions and thus select a different baluster-post family for each, or you can keep it simple and use the same family. You also don't have to have them at all—you can set the post placement to None for any of them (for example, you can have start and end but no corner). Figure 14.13 shows various possibilities for the placement of posts. On the railing at left, the start, corner, and end posts use the same post family. The railing at right was created with the corner post set to None and uses different post families for start and end posts.

FIGURE 14.12
The Edit Baluster Placement dialog box.






FIGURE 14.13
Various possibilities for the placement of posts.



The Corner Posts At dialog box allows you to define corner posts to be dependent on the angle of the railing or to only appear under certain conditions, or choose to not place them at all. The option Angles Greater Than allows for inclusion of the element dependent on the set angle. This means that if the individual segments of sketch lines of a railing turn into angles greater than the parameter you set, a corner post will be placed (Figure 14.14). If the angles are less than the parameter, none will be placed.

FIGURE 14.14
When the sketch lines of a railing meet at an angle greater than the angle defined for corner posts, a corner post will be placed.




As mentioned, railings can be hosted only on a slab, stair, ramp, or level. Thus, their placement is usually defined as an offset from the host. In the Edit Baluster Placement dialog box, you will find that you can also define the position of a rail as an offset from another rail that exists in the structure (Figure 14.15).

FIGURE 14.15
Offset a rail from another rail.

	Name	Baluster Family	Base	Base offset	Top	Top offset	Space	Offset
1	Steel Post	Baluster - Round : 2"	Host	0' 0"	Rail 1	0' 0"	0' 0.3/8"	0' 0"
2	Current Rail	Baluster - Square : 3/4"	Host	0' 0"	Rail 1	0' 0"	0' 0"	0' 0"
3	Fixed Post	Baluster - Square : 3/4"	Host	0' 0"	Rail 1	0' 0"	0' 0.3/8"	0' 0"

The Top parameter is where you can either select the host of the entire railing or choose from a list of existing rails in the railing as a top reference. The top offset can be a positive or negative value. The Space parameter defines the distance of the post centerline to the railing viewed in a longitudinal direction, as shown in Figure 14.16. This value can be positive or negative.


FIGURE 14.16
Space parameters define the longitudinal position of the rail.



DEFINING THE MAIN PATTERN

The Main Pattern section of the Edit Baluster Placement dialog is where you define the pattern of the railing between the posts to generate a complex railing, as in Figure 14.17.

FIGURE 14.17
Baluster main pattern.



The options (Figure 14.18) are similar to those just discussed for the rails.

FIGURE 14.18
The Main Pattern options.

	Name	Baluster Family	Base	Base offset	Top	Top offset	Dist. from previous	Offset
1	Pattern	N/A	N/A	N/A	N/A	N/A	N/A	N/A
2	Regular bal	Baluster - Square : 3/4"	Host	0' 0"	Rail 1	0' 0"	0' 8"	0' 0"
3	Pattern end	N/A	N/A	N/A	N/A	N/A	0' 0"	N/A

Break Pattern at

Each Segment End

Angle

0.000°

Pattern Length

0' 8"

Justify:

Beginning

Excess Length Fill:

None

Spacing

0' 0"

Delete

Duplicate

Up


Down

Note that all parameters that define position (such as Dist. [distance] from Previous or Offset) are calculated from the center reference planes of the baluster families.

The Dist. from Previous setting allows placement of balusters at a specific set distance from one another. To keep balusters from running into one another, you should know the actual dimensions of your different balusters prior to defining this parameter (Figure 14.19).

FIGURE 14.19

The baluster position is always measured to the mid-axis for all positioning parameters.




As you can imagine, the railing length will not always fit an even number of panels or balusters based on the pattern length. How do you deal with that?

Revit provides four different justifications for the pattern fit: Beginning, End, Center, and Spread Pattern to Fit. Their names explain the usage, but Figure 14.20 shows the different justifications and their implications for a design.

The justification you select obviously depends on your design, but you may also be using prefab standard railing patterns that come only in certain dimensions.

BALUSTERS PER TREAD


Revit allows you to set a specific number of balusters per tread on stairs.



If you want to control the number of balusters per tread, check the first option: Use Baluster per Tread on Stairs. This makes the next option active and you can then type in the number of balusters you want to have per tread. You can also change the baluster family by clicking the Baluster Family option, which displays a list of all loaded baluster families available in the project.

FIGURE 14.20


Using different pattern options for seven defined panels results in different distribution of the panel along the railing length.



The top and middle images in Figure 14.21 show railings for spiral stairs created with two different settings: (A) two balusters per tread, and (B) one baluster per tread setting. When the bottom image (C) was created, the Use Baluster per Tread on Stairs option was not activated, so the railing follows the main pattern.

FIGURE 14.21

Spiral stairs with different settings: (A) two balusters per tread; (B) one baluster per tread; (C) Use Baluster per Tread on Stairs option not activated.



As you can see, the moment you use the Use Baluster per Tread on Stairs option, the Baluster Family selection overrides the one set in the Main Pattern section.

ADDITIONAL CONTROLS


Landings can be difficult to work with when designing railings. Revit has a set of additional tools to control landings located in its Type parameters (Figure 14.22). By default, each railing in Revit follows the stair flight and the landing and creates the most logical solution. Often, however, the height of the railing on a landing is not calculated according to your design intent. With the Use Landing Height Adjustment parameter, you can change the railing at the landing to a specific height.

FIGURE 14.22
Landing parameters: Use Landing Height Adjustment.

Type Parameters:	
Parameter	Value
Construction	
Railing Height	5' 0"
Rail Structure	edit...
Baluster Placement	edit...
Baluster Offset	0' 1"
Use Landing Height Adjustment	No
Landing Height Adjustment	0' 0"
Angled Joins	Add Vertical/Horizontal Segments
Tangent Joins	Extend Rails to Meet
Rail Connections	Trim

Landings can also generate unresolved situations where segments of the railing meet. By default, the joins at the angles are unresolved and the segments are not connected. You can fix that by adding vertical or horizontal segments and refine it further by setting the rail connections to Trim or Weld (see Figure 14.23). All these settings are also part of the type properties for the railing.

FIGURE 14.23
Angled joins: (A) no connector; (B) add vertical or horizontal segments; (C) with rail parameter set to Trim/Weld.




The Tangent Joins tool does a similar job but affects connections of different segments of the railing that are on a continuous tangent. The options are located in the type properties of a rail.

Tangent Joins	Extend Rails to Meet
Rail Connections	Add Vertical/Horizontal Segments
Identity Data	No Connector
Keynote	Extend Rails to Meet

The effects can be seen in Figure 14.24.

FIGURE 14.24
Mid-landing railing segments cleanup: (A) No Connector; (B) Add Vertical Segments; (C) Extend Rails to Meet.




Finally, there are a few more adjustment tools needed to refine the railing and bring it closer to your design goals. These last tools are available in Sketch mode of the Railing tool only.

Use the Edit Rail Joins tool to clean up segment joints while in the railing sketch. Once you're in a Sketch mode, this option appears in the Tools panel of the Modify Railings tab.

After selecting the Railing tool, click the Edit Rail Joins button located in the Tools panel, hover the cursor over the sketch line joins, and then click the join (Figure 14.25) to activate options in the Options bar. These provide the same controls you saw in the previous example.



FIGURE 14.25
Edit joins by clicking on the end join of sketch lines.



In Sketch mode, after you select one of the railing sketch lines, the Options bar tools shown in Figure 14.26 appear. These tools let you manipulate the sketch lines in order to adjust the slope of the railing or correct the height connection.

FIGURE 14.26
The Slope tool.



The Slope tool offers you three possibilities:

By Host This option follows the slope of the host, which is what you would need in the majority of cases.



Flat This option keeps the railing flat, regardless of the slope of the host.



Sloped This option defines a custom slope for your railing that ensures uninterrupted connection between adjacent segments.



Similar to what we have shown about the height adjustment on the landing, there is an additional adjustment of the height of a railing that is useful for controlling the extension of a railing (Figure 14.27).

FIGURE 14.27
The Height Correction option.



This is also available when in Sketch mode only and offers two options:

By Type The railing height for the selected segment depends on the properties of the railing type.

Custom The railing height for the selected segment can be forced to a different custom value. Figure 14.28 demonstrates both situations.

FIGURE 14.28
Railing height adjusted By Type or forced to a new height value (Custom).






Real World Scenario

ADDING A RAIL ONTO A WALL

Adding a rail to stairs is easy, but adding a rail on top of a wall is more difficult the way Revit elements are set up today. Shown here is a railing design consisting of a base wall and a railing element on top of it. This is a common type of railing in institutional buildings or outdoor stairs, so let's see how it is made.




The challenge we face is that a wall is not considered a host for a railing element in Revit, so we have to find a workaround for how to place a railing that will follow the stair angle and is based on the wall.

Start by creating a stair without any railings (or if you already created a stair with default railings, delete the railings later) and create a wall next to the stair with an edited elevation profile, as shown in the previous graphic.

Then create a very thin floor on top of the wall that will play the role of a host for the railing (a floor is a valid host for railings):


1. Create a floor type that is very thin.
2. Switch to elevation view. Using the Dimension tool, measure or dimension the height of the top of the wall at the beginning and end of the stair. You will need these values when you slope the floor to match the stair.




3. Define the floor shape by switching to plan view and drawing a floor. Use the Pick method and select the four lines representing the top of the wall.
4. While still in floor Sketch mode, click the Slope Arrow tool and set the properties as shown:
 - ◆ For Specify, choose Height at Tail
 - ◆ For Height Offset at Tail, set the value of the lower height of the wall to 3'-0" (97cm)
 - ◆ For Height Offset at Head, set the higher value of 12'-0" (405cm)



Draw the slope arrow in the middle of the floor starting at the beginning of the stair and finishing toward the end of the stair. By doing this, you have added a slope to the floor that matches the slope of the wall.



5. Select the Railing tool from the Circulation panel on the Home tab, then click on the Set Railing Host button on the Tools panel of the Create Railing Path tab, and select the floor, and draw the railing in the middle of the floor.



This workaround can be quite practical when dealing with railings in big auditoriums. Auditoriums are rarely done using huge stairs; rather, they tend to feature stairs divided into many floors. As a railing can only have one host, it isn't possible to host the railing on many floors at the same time. Using this workaround, however, you will be able to create a railing that runs through many auditorium levels and is still hosted.

The Bottom Line

Work with railings and fences. Railings are a bread-and-butter architectural element whose design can be streamlined with Revit.

Master It You've found some nice-looking railing panels and balusters while scouring the Web for interesting rail designs. How do you go about building the railing in Revit?

Use balusters and rails to construct railings. A railing is a complex set of subelements that Revit lets you organize and control with rules and settings.

Master It You want to make a railing where the balusters are glass panels with fixed width. You wish to add a railing that contains the maximum number of those panels and you wish them to be spread symmetrically. How do you do that?

Adjust additional settings. Stair railing details are particularly difficult to design and plan at landings. Revit helps you fine-tune the details using additional settings.

Master It After designing the stair railing, you notice that there is a gap between the rails following the stair flight and the horizontal rail on the landing. What options do you have to resolve this situation?

Chapter 15

Presentation Techniques for Plans, Sections, and Elevations

As design professionals, we are deeply rooted in the art of representation and expression. Our drawings are powerful communication devices and tools for personal expression. We manipulate color, contrast, light, and shadow to give a drawing life and dramatic poise. From the loose napkin sketch to the photorealistic rendering, we imbue our designs with a sense of purpose and intent. This intent is a driving force in architecture and critical to its progression. Without models and drawings that challenge the senses, where would we be today? Consider the drawings of Piranesi, Boullée, Wright, Woods, and Hadid. Each is distinct, thoughtful, evocative—at times utopian.

Consider your role in shaping the built environment. Think about how your drawings are interpreted, received, and understood. How do they shape the evolution of a design? How have digital tools changed the way you present and evaluate a design? Keep these questions in mind as we move through the next two chapters. Consider how the techniques can help you, and also think of how you might push some boundaries and extend your creativity using the tools in Revit

You've seen with Revit that many traditional documentation drawing types are generated with little effort. With a few clicks of the mouse, you can generate entire building sections and elevations. Likewise, a perspective view now takes only a few seconds to generate. Revit does a fairly good job of producing these drawings, but it can't fully replace the skill and decision-making process of an artist. Design intent and message still need to be considered by the designer. Because of this, Revit provides some tools to help you make your drawings more legible and expressive. If need be, you can also export a drawing as vector lines or as pixels and further refine it to meet your design requirements.

In this chapter, you'll learn to:

- ◆ Use shadows for presentation purposes
- ◆ Create presentation-quality plans and sections
- ◆ Create elevation drawings that convey depth

Using Shadows for Presentation Purposes

Shadows tend to be used for two purposes: analysis (Figure 15.1) and expression (Figure 15.2). For analysis, shadows are used to see how a building will be affected by its environment and real-world sun angles based on the location of the site. This analytic use is explored in depth in

Chapter 18, “Evaluating Your Preliminary Design: Sustainability,” and is covered here primarily to introduce the shadowing tools for presentation purposes. The expressive use of shadow, our focus in this discussion of presentation issues, conveys depth in drawings and gives them more character; it may or may not be tied to real-world sun positions. Revit provides a tool for each of these use cases, and this book will show you how to use both tools. The nice thing about shadows in Revit is that it’s easy to enable them, and voilà!—shadows are there.

FIGURE 15.1

Analytical use of shadows in a site plan shows the effect of buildings on their environment.





FIGURE 15.2

A more expressive view using shadows in a shaded view without edges.




Courtesy of Felipe Manrique Diaz

Analytical Drawings: Sun and Shadow Studies

Using shadows analytically allows you to see (and demonstrate) the effect of a building on its environment and, likewise, the effect of the environment on your building. Using real-world sun and building positions, you can evaluate the design impact on its surroundings. You need to know whether the building will have a negative impact and make sure building codes are satisfied. You'll also want to see the effect of the sun on the building itself so you can study light penetration and how other buildings will affect light and shadow. Figure 15.1 shows a site plan view with shadows turned on.


To get accurate sun shadows, you must establish where the building is on the planet, the building's orientation relative to north, and the date and time that you wish to analyze. For example, it's common practice all over the world to represent the extreme sun angles at both the summer and winter solstices. Both of these are provided in the default templates. These angles vary based on latitude and longitude. In Revit, every project has a location that is defined in the Manage Place and Locations dialog box that is accessible from the Manage tab, in the Project Location tab; this location has a direct influence on sun position. In the Place tab (shown in Figure 15.3), when you choose from a list of cities, the latitude and longitude are set for you automatically. If you don't find your city in the list, choose a nearby city, and then edit the latitude and longitude to match your location. If you're still not sure, you can use a tool like Google Earth to accurately locate your latitude and longitude.

FIGURE 15.3
Set your building location using the Manage Place and Locations dialog box.



You need to set your location only once per project; this will affect all sun angle calculations based on the selected location.

To turn on shadows and see the effect of date, time, and location, choose the Shadows On option from the view controls at the bottom of any view.




ENABLING SHADOWS

Shadows are enabled on a view-by-view basis. This means that for each view in which you wish to display the shadows, you need to activate them independently. The downside of this is that if you have activated the shadows in many views, there is no one global button to turn them all off; you might well have to do that throughout the course of the project, as shadows can slow down the performance of the project significantly. Alternatively, you can just close the views that have the shadows turned on.

To understand how shadows are being cast, click the Graphic Display Options button to open the dialog box shown in Figure 15.4, where all the shadow settings are defined. From this dialog box, you can access the Sun and Shadows Settings dialog box, play with the brightness and darkness of the sun and shadows, override silhouette edges, and enable gradient backgrounds.


FIGURE 15.4
Graphic Display
Options dialog box.



SUN AND SHADOW SETTINGS

Clicking the ellipsis button next to the Sun Position field opens a dialog box where you set the angle of the sun. For analytical views, choose meaningful times and dates. Revit ships with the presets shown in Figure 15.5.


FIGURE 15.5
The Sun and
Shadows Settings
dialog box for
still images.



There are two methods for setting the sun angle: By Date, Time and Place; and Directly. Making any changes to them could cause serious problems later. For example, if you manually set Summer Solstice to an azimuth and altitude that aren't accurate, you can create misleading settings. If you need to create a unique setting, the best practice is to duplicate an existing setting and go from there, rather than editing the preset options. Or, if you really intend to change a preset setting permanently, go ahead and rename it with an appropriate and meaningful name.

INTENSITY

To get different graphic results using the same geographical settings, try experimenting with the Sun and Shadows intensities in the Graphic Display Options dialog box by sliding the two sliders between the brightness and darkness extremes.



If you give the sun 100 percent intensity (Brighter), the model will appear brightly lit, and shadows appear more subdued. Figure 15.6 shows the different effects that can be achieved by adjusting the intensity values. Keep in mind that the sun and thus shadows affect only views set to Shading or Shading with Edges model graphic styles. In other words, for Hidden Line views, you can change only the darkness of the shadows but not the intensity of the sun.

FIGURE 15.6
Adjust intensity
to get different
graphic results.



Sun = 20%
Shadow = 100%




Sun = 100%
Shadow = 20%

To create several graphic versions of the same view, you must duplicate the view and apply different sun and shadow settings using the Advanced Model Graphics Settings dialog box.

Create Expressive Drawings with Shadows

When you use shadows expressively, the need for accurate lighting conditions is not as important as the need to define consistent angles so that your drawings express depth. Without shadows, a façade appears flat and difficult to interpret. By adding shadows and setting them to be Relative to View, you can create an image that discloses information about the depth in that flat image, allowing it to be much better understood. To do that, you establish a shadow angle that suits your needs and reuse the settings for multiple views. The default template includes two presets for this in the Sun and Shadows Settings dialog box: Sunlight from Top Right and Sunlight from Top Left (see Figure 15.7).

FIGURE 15.7
Sun locations
in the default
template.




The combination of Azimuth and Altitude with these presets produces 45° shadows on an elevation.

HIGH-CONTRAST BLACK AND WHITE EFFECTS

Using hidden line display and increasing the shadows to 80–90 percent produces nice, high-contrast elevations. As you can see in Figure 15.8, this is a great way to create visuals that will read from far away.

FIGURE 15.8
High-contrast
black and white
elevation.




Courtesy of Felipe Manrique Diaz

SOFT SHADOWS

If you prefer to give an image a softer appearance, try using a shading view (shading without edges) and setting shadows to 30 percent and sun to 70 percent. You'll get a very even-colored, washed-out feel, as shown in Figure 15.9. Because the book is printed in black and white, you might not be able to appreciate the finesse in these, so make sure you try them out yourself!

FIGURE 15.9

Soft edges and low-contrast shadows.




Performance Considerations

As you'll discover when working in views with shadows enabled, the speed of panning and zooming in the model degrades when shadows are on. So, as you start to use shadows, keep this in mind: *turning off shadows is always two clicks away*. If you want to start panning and zooming around the view, turn off the shadows for a while. When you've finished zooming about, turn them back on. Remember that the settings are persistent, and turning off shadows is just a simple way to improve performance while working with your model. But don't worry—your work will be saved and you will not need to remake them again the next time you turn them on.

Color-Coded Plans and Sections

Colors, when associated with a legend, are an effective way to signify meaning. In the context of architectural drawing, the colors are often applied to convey how space is used or intended to be used. With Revit, you can use color to differentiate one room from another or to communicate ideas about usage, size, importance, and cost. By assigning parameter values to colors and patterns, you can quickly make views that show how a building is spatially organized (Figure 15.10). For example, you can create a department floor plan by assigning department values (names) to all your rooms and then apply a color fill scheme to the view that changes the color of rooms based on what department they're assigned to.

FIGURE 15.10
Use color and parameters to generate color fill plans.



To make a color-coded plan, first duplicate an existing plan view and give it a unique name. Then add rooms (if they have not been added already). The reason for adding rooms is that the color-coding is based on the properties of room elements and will have no effect unless room elements exist in the project. You can also create new area plans and use area separation lines to divide space at a more macro scale. You can then assign values to each area that can then be colored with a color fill scheme. Once rooms and areas have been placed, you can access their Element properties.

All of the properties grouped under the Identity Data parameter group can be color-coded. Using project parameters, located in the Manage tab, you can also add custom parameters to the room and area categories.

From the View properties of a plan, area plan, or section view, you can assign a color fill scheme to the view. Clicking that parameter takes you to the Color Fill Schemes dialog box, where you set up and assign various schemes. Whatever is selected in that dialog box is applied to the view, and the rooms will become colored.



You can also create a color scheme using the Legend tool in the Home tab, in the Room & Area panel. The moment you place the legend, you will be prompted to select the space type (Rooms or Areas) and a color fill scheme.

COLOR FILL SCHEMES

Color fill schemes are applied to views on a per-view basis (in other words, they appear only in the view where you created them) and are exposed as an Instance property of floor plan, area plan, and section views. To access and create color fill schemes, click to expand the Room & Area panel on the Home tab, and click Color Fill Schemes to open the dialog box in Figure 15.11 (you can get to the same dialog box from the View Properties dialog box). In the Edit Color Scheme dialog box, you'll see a list of schemes on the left and all the rules and colors for those schemes

on the right. Each scheme colors one parameter and all its values. For each unique value, a unique color or hatch pattern is assigned. For example, if you choose to color by name, the table fills with all the room names in the project and assigns a color to each unique name. Clicking the button in the Color column allows you to choose your own colors. While Revit will create new colors for you automatically with each new value, you are free to change those to your own colors and can even save these into a template for use in other projects.


FIGURE 15.11
The Edit Color
Scheme dialog box.



Information in this dialog box is also used to fill out color fill legends, which are essentially graphical tags of the color scheme and are placed next to the plans to explain the color-coding. The legend shows the title, values, and color swatches for the scheme applied to a view. To place a legend in a view, use the Color Scheme Legend tool in the Drafting tab of the Design bar.

The color-scheme legend allows you to edit its Type properties to control the visibility of the title, swatch size, fonts, and color (Figure 15.12).


FIGURE 15.12
Color Scheme
Legend properties.



Note that the order of the values in the legend coincides with the order set up in the Edit Color Scheme dialog box. The default behavior lists each entry alphabetically, but you're free to change that by using the Move Up and Move Down buttons when a row is selected. Doing so simultaneously updates the color-scheme legend.

	Value	Visible	Color	Fill Pattern	Preview	In Use
1	Circulation	☒	RGB: 209-203	Solid fill		Yes
2	Equipment	☒	RGB: 139-166	Solid fill		No
3	Lab	☒	RGB: 096-175	Solid fill		Yes
4	Merch	☒	PANTONE: 63	Solid fill		Yes
5	Office	☒	PANTONE: 32	Solid fill		Yes
6	Meeting	☒	RGB: 173-118	Solid fill		Yes
7	Sto.	☒	RGB: 196-183	Solid fill		Yes
8	W/C	☒	PANTONE: 62	Solid fill		Yes

Another important graphical control of the legend is the Values Displayed parameter. This gives you the option to show only values in the legend that are also in the view (By View). In a project where the number of departments and room names can be large, and they aren't used in all floor plans, this is a great way to focus the legend on what is important to that view instead of listing all possible colors that might not be applied in that view and are thus irrelevant. Many designers do not want to display all the color swatches, but this is ultimately up to your own personal taste and what the drawings are intended to convey. Revit allows you to do both, so it's really up to you. Choosing the All option shows all values used in the project, whether used in the view or not.



CREATING PREDEFINED COLOR SCHEMES

If you've created a list of room names, departments, and a carefully chosen palette of colors that are likely to be reused in future projects, you can transfer the color scheme from one project to another or reuse it in your office template. This transfers all the values and colors, even if the project you're transferring to doesn't contain that value.




Real World Scenario

TRANSFERRING COLOR FILL SCHEMES BETWEEN PROJECTS OR TEMPLATES


Imagine you have invested quite a bit of time setting up a color scheme in your current project, adding room names and departments and assigning them colors in the Color Fill Scheme dialog box. If you want to reuse the same values and colors in other projects so that you maintain your graphical language, use the following strategy:

1. Open the source project, and then open the project into which you want to transfer. You need to have two projects open to transfer from one to another. If you have only one project open, Revit will inform you that there are no open projects to transfer project standards from. Remember, the project in which you invoke the Transfer project standard is the one you wish to import the standards to.

2. Open the Manage tab, and then select Transfer Project Standards. Select Color Fill Schemes in the Select Items to Copy dialog box.



3. Values are transferred into the project. You can then access the list of values from the room's Element Properties dialog box.



This saves you from having to manually retype all these commonly used values, and the colors will be consistent from project to project.


COLORED SECTIONS

In architectural practice, section views as well as floor plans are often color-coded, showing the stacking of various functional zones (Figure 15.13). You can get automated coloring of the rooms in section view just as you can in plan view:

1. Open a section view.
2. From the context menu, under View Properties, open the Visibility/Graphics Overrides dialog box (type **VG**) and make sure the Rooms category in the view is checked as visible.
3. Open the View Properties dialog box and assign a Color Scheme setting to the view. Use Name as the parameter to color if you have not assigned any departments (departments are the default setting, which comes from the fact that the selection is alphabetical). You're likely to get an image where the rooms do not fill the entire space being cut by the section, similar to Figure 15.13. (Since this book is printed in black and white, use your imagination: purple is used on the first two floors and gray on the third.)

FIGURE 15.13

Use the grip controls when a room in section view is selected—or the Limit Offset parameter in the room properties—to change the height of the room.



4. You can see that the rooms are not extending up to the next floor and roof. To fix this, select a room and drag the blue arrow controls at the top, or change the Limit Offset parameter from the element properties of the room.
5. To change how the color is drawn relative to the model geometry, you can set the color to be drawn in either the foreground or the background. This parameter is called Color Scheme Location and is a property of the view you are working in. Figure 15.14 shows the color in the background; the result is that you see walls and doors *not* colored by the color fill. Figure 15.15 shows the color in the foreground; now doors and walls appear filled in.

FIGURE 15.14

Color fill drawn in the background.

**FIGURE 15.15**

Color fill drawn in the foreground.




Creating Presentation-Quality Plans and Sections

Not all plans and sections end up as drawings full of dimensions, tags, notes, and layers of construction information. Easy-to-read, graphically clean drawings are used all the time in marketing collateral, on project websites, in print magazines, for competition boards, and for client presentations. A great way to create presentation-quality plans and sections is to clear out most of the textual information and fill in walls, floor, and roofs with a solid fill when they're cut. This creates views that are easier to read and that convey solid and void effectively (Figure 15.16). With Revit, this kind of representation is a few clicks away, and the fill hatch is tied directly to the element. You don't need a paint-bucket tool or special hatch tool to get results.


There are two strategies for dealing with solid fill for elements that are cut: as a property of the element or as a property of the view. Each strategy has its own merits. Let's review the options.

FIGURE 15.16
Plan view with
walls and columns
filled with solid
black.



Coarse Scale Fill Patterns

Walls, floors, roofs, ceilings, and columns all have a Coarse Scale Fill type parameter. This allows you to define how the element will appear when cut in the view if the view detail level is set to Coarse.




The downside is that the property is stored with each type, so making all walls have the same hatch requires you to edit every wall type. The same goes for floors and roofs. And if you decide to change the color of the fill, you have to again edit every type.

Also, not all elements have this property. For example, in-place family walls, floors, and roofs don't have this parameter, so you'd have to go a separate route to get correct graphics if you chose to use this type of element.

Graphic Overrides and View Templates

The other way to think of this problem isn't as a property of the element but as a property of the view that can be reused in other views. Think of a view as a multidimensional lens through which you look at the model. Once you've set up the right lens, you can apply it to any number of views and get the right results using view templates. We recommend this direction for graphic overrides, as it makes for an easier way to deal with entire categories of elements. For example, most Revit categories can have their cut pattern overridden with a hatch or solid fill. If you go to the Visibility/Graphic Overrides dialog box and select the Walls, Floors, Roofs, and Columns categories (by holding Ctrl with each row selection), you can then click the Fill Override button and apply a solid fill hatch (Figure 15.17). This applies to elements in your active view but isn't stored with the element. These overrides are stored on a per-view basis and are distinct from the project-wide object styles.

FIGURE 15.17
Use pattern overrides to apply a solid fill to categories.




This view setting is great—but what if you want to apply the same graphics to other views? Follow these steps:

1. Once you have the overrides set up, go to the Graphics panel on the View tab, and choose Create template from current view from the View Templates drop-down list.
2. Name the view **Cut Overrides**.

3. If you only want to store the cut pattern values and not affect scale or any other graphic settings when applying this view template, clear all other view properties except for the properties under the V/G Overrides Model (Figure 15.18).
4. Right-click the view name you want to apply the overrides to in the Project Browser, and choose Apply View Template. Choose the view template you just created.

FIGURE 15.18

You can selectively choose which view properties are stored in a view template.




Creating Elevations That Convey Depth

Revit applies the same line style to all edges based on the cut or projection settings in the Object Styles dialog box. This can lead to elevations that appear flat and lack depth. Strategies for dealing with this issue range from using a highly parametric approach to using lines and drafting right on the view. In Figure 15.19, the Linework tool and some graphic overrides were used to punch out the building elements in the foreground and halftone elements in the background.

FIGURE 15.19

Edges can be made thicker with the Linework tool.



Linework




The Linework tool, located in the Modify tab under the Edit... panel, is a parametric approach that allows you to select a line style and then apply it to edges of the model as an override. Any edge can be overridden by this tool in order to change the line's graphic appearance. The override is applied to the element, so if the element moves, the line style override will move with it. When activated, the type selector displays a list of available line styles in your project. You can add additional Line Styles under the Object Properties dialog box.



The cursor changes to a pencil and highlights edges of the model as you move the mouse around the view. With each click, the override is applied to the edge. This override is associated with the element: if you move the element, the linework moves with it. The line style applies to the entire edge of an element by default, but this can be adjusted. For example, if you need to make the diagonal line of this wall with a thicker line style, you select the Linework tool, choose the Wide line style, and then select the edge of the wall. The line goes the entire length of the wall (Figure 15.20A). While still in the Linework command, click and drag the blue control dot to adjust the length of the linework override (Figures 15.20B–C). Note that if you have your view set to thin line display, you will not see the effects of using linework.

FIGURE 15.20
(A) Initial condition; (B) linework applied; (C) cleaning up the line by dragging the control at the end of the line.



To reedit the length of linework, you need to activate the tool and then again select the edge you're concerned with. The same blue controls appear, allowing you to adjust the length of the line.

If you need to remove a linework override, the same principle applies: activate the Linework tool, choose <By Category> in the type selector, and then select edges in the model that you don't want overridden.


Drafting Lines

The other way to punch out the elevation is to use drafting lines and draw directly over the model in the view. This means you are not changing the appearance of a line in a view but instead are adding new lines on top of the model. With this method, you also choose a line style, and you can even use the Pick tool to get the same behavior you would with the Linework tool. The only difference is that the lines aren't automatically associated with the element you draw on. Depending on your workflow and where you are in the process, this may be the best way to create a final elevation drawing. A nice benefit to this method is that you have access to all Revit's familiar timesaving tools such as Trim, Align, and Multi-select.

True-Color Elevations

Every material in Revit has a shading color and transparency. This is the color you see when the display mode is set to Shading or Shading with Edges. Be aware that the transparency is graphically visible only in 3D view. In elevations, a glass window will not appear as transparent; this helps keep drawings clear of unwanted visual noise. After all, who wants to see interior furniture showing through the glass of a hotel façade in an elevation? The color you select in the Materials dialog box will be an RGB or Pantone color (see Figure 15.21), but it often won't look like that color in shaded elevation views. That has confused many users, so here is the explanation: shaded views use a hidden fixed light source to light the scene, which causes the color to appear washed out or brighter in different views.


FIGURE 15.21
Every material has a shading color, transparency, and options for cut and surface patterns.



To overcome this limitation, you can control where the light comes from by using the Sun and Shadows Settings dialog box. You can also force the light to come from directly above the model so it doesn't affect any vertical surfaces. To do this, follow these steps:

1. Open the Sun and Shadows Settings dialog box, and duplicate the Sun from Top Right setting—give it a name like **True Color Shading**.
2. Change Azimuth to 0 and Altitude to 90 (see Figure 15.22).

FIGURE 15.22
Use these settings
to get accurate RGB
colors in elevation.



3. Open an elevation view, and go to the Graphic Display Options dialog box from the view frame. Set the Sun Position to True Color Shading. Set Shadow Intensity to 0. Set Sun Intensity to 80.

Be sure to enable shadows in the view. The effect should be immediately obvious.

Elevations with Transparent Materials

Using the standard Revit elevation views, transparent surfaces are always rendered as opaque surfaces. This generally produces the right quality and meets most expectations, but it can also seem limiting. Luckily, creating an elevation view with enabled transparency is easy using the 3D views and orienting them to display an elevation view. Here is how you can do that.

1. Open the default 3D view.

2. Right-click the View Cube and choose Orientate to View ➤ Elevation ➤ South.



3. The camera swings around so it's lined up with the elevation view, and transparent surfaces appear transparent.



Using Images in Elevation Views

You can import image files (click Image from the Import panel on the Insert tab) into a Revit view to create effects such as gradient fills, add a backdrop to the view, or add a photo-style entourage to a nonrendered view. By taking advantage of the draw-order options for images when placed in a view, you can position the image either in front of or behind the model. When you select an image, the Options bar gives you the ability to position the image in the foreground or background.

To add a gradient fill to the background of an elevation, follow these steps:

1. Import a gradient image file into an elevation view.
2. Select the image, and send it to the background using the Options bar.
3. Stretch the image to fit using the grip controls. You can unlock the proportional scaling using the Options bar (see Figure 15.23). If you tend to use the same image or entourage from project to project, keep in mind that you can keep a “library” of image elements in a drafting view.

FIGURE 15.23

Elevation with the gradient JPEG import set to Background.



Another great technique is to use the transparency channel available in PNG-formatted images. By making a color transparent and pushing images to the foreground and background, you can add trees, people, and cars, and the image won't mask the model. In Figure 15.24, the tree image was imported into an elevation view and then copied and scaled. The copy on the right is set to Foreground, and the copy on the left is set to Background.

FIGURE 15.24

Imported PNG file of one tree set to Foreground and another to Background—note that the transparency channel is preserved.



The Bottom Line

Use shadows for presentation purposes. Presenting your design to stakeholders is a critical part of your workflow and allows you to sell your ideas. Having tools that make this process easier without compromising your creativity is essential to being successful.

Master It You've been asked to show the effect of your building's shadow on its surrounding site during the winter solstice. How would you do this with Revit?

Create presentation-quality plans and sections. Creating clean, easy-to-read plan and section views using Revit is a huge timesaver.

Master It Your latest design is all the rage, and you've been asked to publish the plans and sections in a magazine. How do you make these?

Create elevation drawings that convey depth. Two-dimensional drawings can be hard for clients to read, which makes shadows a useful mechanism for illustrating recesses and projections.

Master It You need to give your elevation view more variation in line weight to convey depth beyond the default line styles established in the Object Styles dialog box. How do you do this?

Chapter 16

Presenting Perspective Views

One of the many advantages of working with BIM models is that you can produce perspective views of your model as often as you wish—and it takes only a few mouse clicks to do it. Think about how tedious the process of creating 3D axonometric or perspective drawings was, whether you did so manually or used CAD drafting tools. Perspective views are greatly appreciated by owners as they visually communicate the intent of the design better than any other representation.

If you open a Revit project that has been in development for a while, you'll find dozens of perspective views. Although most of these views will never make it onto sheets, it's becoming standard practice to include one or two exterior perspectives on the cover sheet. Sheets aside, these views are critical for understanding your design from a human point of view and are used consistently for client meetings and internally when fleshing out a design. In many cases, a hidden line perspective view with shadows turned on provides an excellent graphical representation of your model. You can also take the visualization up a notch and produce photorealistic renderings without having to be a rendering guru.

In this chapter, you'll learn to:


- ◆ Create perspective views
- ◆ Create photorealistic renderings
- ◆ Create animated walkthroughs
- ◆ Export the 3D model for use in other applications

Creating Perspective Views



Use the Camera tool to create perspective views in Revit. This tool can be found in the Create panel of the View tab. For perspective views, a good exterior shot typically shows a corner of the building from a human vantage point (Figure 16.1).

FIGURE 16.1
Street-level
perspective view.



For exterior views, start by placing the camera approximately 100' (30m) from where you intend to aim the camera. Placing the camera too close to the model will often put you right up against a wall, and you'll have to readjust the camera to see more of the model.

When you activate the Camera tool, you first establish the eye position and then set the target. It's a simple two-click operation, and the next thing you know, you're taken directly to the camera view, looking at a perspective of your model. Revit puts the camera at eye level by default when you place a new camera in a plan view. This is usually fine, but you're free to adjust the camera dynamically or by manipulating the elevation of the eye and target levels through the element properties of the camera.


To adjust your camera dynamically, enable the SteeringWheel from the Navigation bar located next to the ViewCube, and use the options to orbit, zoom, pan, and move through the view.



The walkthrough options allow you to walk, look, and move the camera up and down. To adjust the focal length of the camera (zoom the camera in or out without moving the camera), click the small arrow at the bottom right of the SteeringWheel, and choose Increase/Decrease Focal Length (Figure 16.2). It acts as if you're zooming your lens in and out, while keeping the camera stationary. (Don't confuse this with walking the camera closer to the building.)

FIGURE 16.2

Focal length controls are accessed from the SteeringWheel.




Showing the Camera

To see a camera from the context of 2D or 3D axonometric views, right-click the 3D view name in the Project Browser and choose Show Camera. The camera appears in all views as a camera icon with the view extents shows as red lines (Figure 16.3), so you can visualize where the camera is relative to your model. At this point, the camera is selected, so you can move it to a new location, and the view updates automatically to reflect the change. You can also adjust the target position in this mode. Just be careful where you click—clicking anything else (including nothing) deselects the camera, which causes it to disappear.

FIGURE 16.3

When a camera is shown, the view extents appear in all views.




PERSPECTIVE VIEWS ARE FOR VISUALIZATION

Currently, perspective views are used only for visualization. You can select elements and change their properties (or delete them) from a perspective view, but you cannot edit any of the model using grips nor edit commands within these views.

Silhouetted Edge Display


As you saw when we discussed elevations, overriding the edges of elements can help make a drawing more legible and graphically clear. In addition to using the Linework tool, you can use a more dynamic feature built into Revit, which accounts for the fact that perspective views are likely to be spun around and reoriented. From the shadow icon in the view frame control tools you can access the Graphic Display Options dialog box. Toward the bottom is a control that lets you set a line style called Silhouette Style.



By choosing a line style with a thicker line weight, you'll see the effect of this feature. The line style isn't applied to specific edges of the model but instead is dynamically redrawn depending on the camera's point of view. Revit applies the line style to the outer edges of elements visible in the view, giving the model a bold outline. The effect can be subtle but elegant, as shown in Figure 16.4. If the effect is too subtle, try making the view larger (the default is a 6" × 4.5" view) and making a new line style with a heavier line weight.

FIGURE 16.4

Top: No silhouette edges applied;
bottom: silhouette edges applied with
a line style using a
line weight of 6.



Creating Photorealistic Renderings

Revit provides an integrated rendering workflow that delivers stunning photorealistic renderings. The rendering engine works hand in hand with a library of rendering materials custom-designed for architectural visualizations. With Revit's rendering features, you can assign some materials, set up a camera, click Render, and get some great results right out of the box (Figure 16.5).

FIGURE 16.5

Example of rendering.



The Rendering Dialog Box

To render a perspective view, click the teapot icon in the view frame controls at bottom of the view. This launches the Rendering dialog box (Figure 16.6), where you set all the parameters for the rendering, such as quality, output, lighting, background, and exposure settings.

Let's look at this dialog box in more detail, as each setting will affect how the rendering looks.

FIGURE 16.6

The Rendering dialog box.




QUALITY

The first set of rendering options is the Quality settings (Figure 16.7). These affect the overall quality and, perhaps more important, the time it takes to render the view. The higher you go in quality, the longer the rendering time will be. We recommend rendering at draft or low quality initially


and going to higher quality only after you have validated the material and scene selection assigned to the model.

FIGURE 16.7
Quality setting
options range from
Draft to Best.



The settings have been tuned for optimal results, but if you want to tinker under the hood, so to speak, you can select the Edit... option located at the bottom of the dropdown list. This opens the Render Quality Settings dialog box (shown in Figure 16.8), where you can see all the variables that affect the rendering quality. Any change you make to these settings is stored in the file as a Custom (view specific) setting. This prevents your changing any of the factory presets but at the same time gives you total flexibility to go beyond what has been preset.

FIGURE 16.8
To see all the
parameters that
affect quality
settings, open
the Render
Quality Settings
dialog box.



The images on the right and left sides of each setting are visual cues to help you understand the effect of the setting. To see what each factory preset does, use the Setting drop-down list at the top of the dialog box. To edit these settings, click the Copy to Custom button. This copies all the settings into the editable custom setting and allows you to refine the settings.

OUTPUT

The Output Settings area allows you to set the resolution of the image being rendered. The default is Screen; the size of the image (width and height) is measured in pixels, as shown in Figure 16.9A. Choosing Printer allows you to select from some standard DPI settings. The Width and Height values update automatically for you, giving you an idea of the final output size and the Uncompressed Image Size, which is the size of the file if saved as an uncompressed TIFF (see Figure 16.9B).

FIGURE 16.9
Select Screen or
Printer to set the
output size for
the rendering.




Unless you are ready to send the rendering off for printing (150 dpi draft or 300 dpi finished print quality is recommended), keep the resolution at Screen (72 dpi). This will improve the speed of the renderings without compromising overall quality.

LIGHTING

The Lighting options (Figure 16.10) set exposure levels, let you select what kind of lighting to use, and establish the sun position. The options are self-explanatory: just match the setting with the kind of camera you’ve set up. Are you outside? Inside? Do you want to see the effect of sun, just artificial lights, or both?

FIGURE 16.10
Lighting options.



Sunlight

The sun position is enabled for any scheme that includes the sun as a light source. The list includes sun settings. To access and edit these settings, click the Edit option at the bottom of the list. You can also access this same list by choosing Settings ➤ Sun and Shadows Settings from the Manage tab. The resulting dialog box (Figure 16.11) lets you edit the sun position by adjusting time, date, and place. Be careful not to edit a setting without changing its name. You don’t want to change carefully prepared and geographically correct settings. Always duplicate an existing one, give it a new name, and only then set your desired values.

FIGURE 16.11
Sun and Shadows
Settings dialog box.




FIGURE 16.13
Grouping lights
that are visible in
the view.






FIGURE 16.14
When a fixture
is selected, the
option to add it to
a group is available
in the Options bar.



You can also choose to edit the group (if the light is in a group) by clicking the Edit button. This changes the model to halftone and shows all lights in the group as green. A floating toolbar appears that allows you to select light fixtures and either add or remove them from the group (see Figure 16.15).

FIGURE 16.15
When editing a
light group, you
can add or remove
fixtures from the
group using a float-
ing toolbar.



BACKGROUND

The Background settings (Figure 16.16) help give your model some context by using a sky, a sky with cloud cover, or color. The sky in Revit is tied directly to the Sun and Shadows settings and will accurately color the sky based on time, date, and place. As you get toward dawn or dusk, the sky will change color to reflect this. You won't need to manually specify any color gradients. If you intend to use images in your background with a tool like Photoshop, you'll be glad to know that the background is saved as its own channel when images are exported as PNG files. This means you can use whatever background image you want and get a clean, perfectly blended look. This also allows you to position and edit your background graphics in Photoshop, where you have total control.

FIGURE 16.16
Background
options.




To add some clouds to the background, choose from the options available in the Style drop-down menu. Clouds will appear wispy and subtle when using these options. If you want strong, high-contrast clouds, add them in postprocessing by doctoring your images in an image-editing program—just be sure to export to PNG. You can also use a single color for a background.


RENDERING THE VIEW

Once you’ve chosen the quality, output, and lighting scheme, you’re ready to render the view. Click the Render button and Revit will start the rendering process. Actually, a new process starts that is independent of Revit, so if the rendering were to get stuck or crash, you could stop the rendering process without having to stop Revit. You can see this in Windows Task Manager as fbxoopsrender.exe (see Figure 16.17).

FIGURE 16.17
Rendering is
managed as a
separate process
by the CPU.



A progress dialog box will also appear.



Here you will see how long the rendering is taking, how many artificial lights and daylight portals are being calculated, and if any warnings are encountered during the rendering process. An example of a warning would be if the path to images used for rendering were no longer intact. To cancel the rendering at any time, just click the Cancel button, and confirm you want to stop.




You can also decide to render just a portion of a view. This will save time but still give you an idea of the results to be achieved. To render only a portion of the view, use the Region check box next to the Render button. This enables a box in the view that you can adjust by selecting it and then dragging the grips to resize it. Use this option if you want to render only portions of the model to check materials, rather than rendering the entire view.

ADJUSTING EXPOSURE

When you choose a lighting scheme, Revit automatically determines some exposure settings for you. You can adjust these either before or after running a rendering. Click the Adjust Exposure button to open the Exposure Control dialog box, shown in Figure 16.18.

FIGURE 16.18
The Exposure Control dialog box gives you a series of settings for adjusting the exposure.



After the rendering is complete, you can change the values of these options. Click Apply to change the appearance of the image after the rendering is complete. For example, if the rendering seems too dark, try decreasing the Exposure Value setting. To return settings to factory defaults, click the Reset to Default button at top of the dialog box.

SAVING RENDERINGS AS IMAGES

Once you've produced a rendering that you're happy with and want to keep, the Rendering dialog box gives you two options. You can either save the image in the project or export the image to disk. When saving to the project, the rendering is saved in the Rendering branch of the Project Browser and can be dragged onto sheets like any other view. When exporting, the image will be exported and not stored in the project environment. If you need to do some postprocessing with Photoshop, click the Export button. You can save the rendering in standard image formats (BMP, GIF, JPG, PNG, or TIF).


Materials

Revit's rendering materials are designed to convey characteristics of texture, color, reflectivity, and transparency that you'd expect to see in reality. An entire library of materials (branded as ProMaterials) was designed specifically for architectural visualizations. In this section you will learn about how to use the material library and how to create custom render appearances.

EDITING A RENDERING APPEARANCE

The Revit materials have an associated tab that contains information about how each material will look when rendered. This information is located in the Render Appearance tab in the Materials dialog box, shown in Figure 16.19.


FIGURE 16.19
The Render
Appearance tab
in the Materials
dialog box.



REPLACING MATERIALS

If you're not satisfied with the default render appearances and need to manually assign new materials, the Replace button should be your first stop. Click that button to bring up the Render Appearance Library (Figure 16.20), where you can search for and assign render appearances.

FIGURE 16.20
The Render
Appearance
Library.



In this dialog box, you can search for materials by typing in the search field, or you can sort the materials using the Class drop-down list. Selecting a render appearance and clicking OK closes the dialog box and replaces your active material with a new render appearance. Consider using this library before making your own customized materials, as they have been carefully tuned to work well in Revit models.

CUSTOM RENDERING IMAGES

Many good-looking materials use digital images that are scaled to match the building model. These images are often professionally produced and edited so as to not tile in an obvious manner when repeated over a surface in the model.




Real World Scenario

SOURCING TEXTURE MAPS

A hallmark of a bad image map is that you can see where each image begins to repeat. We don't recommend making your own texture maps, because the tiling effect is difficult to manipulate on your own. Go to a website such as www.turbosquid.com or do image searches for materials.

If you have your own high-quality images that you'd like to use when rendering, this is not a problem. Locate your material in the Materials list. To remap your image, choose the Color parameter and select Image File (Figure 16.21). This takes you to a dialog box where you can browse to your own image file.


FIGURE 16.21
Assigning an image file to a generic render appearance.



You'll then need to set the scale and change the preview to something more appropriate. Change the scale by typing in a value next to the image preview. This value sets up the repetition module for the image—relating a pixel-dimensioned image to a real-world scale. You can play with other parameters available in the generic render appearance, but for the most part, getting scale correct will be the most important task.

To change the preview, use the drop-down menu next to the preview swatch scene at the top (Figure 16.22). In this example, we are using a custom brick image and changing the preview to use the Flat Surface setting.

FIGURE 16.22
Changing the
Scene preview.



ADDING ENTOURAGE FOR RENDERING

Adding people, cars, and trees to a rendering will give it a sense of scale and context. This technique is usually applied to give a rendered image a more realistic and human effect. This can be achieved by placing entourage and planting families into your model. When rendering a view, this content takes advantage of Rich Photorealistic Content (RPC) technology to show photographic images in the context of the rendering.

Note that any trees created pre-2009 Revit will not render. You'll need to load new trees and replace the old ones manually. To do so, load from the planting folder and select an RPC tree. Doing so will load many types, and you can choose from a list of RPC trees (Figure 16.23).


To replace trees quickly, use the Select All Instances option in the context menu when a tree is selected. This selects all instances of the tree and allows you to change the type to an RPC type. Be aware that the graphics will change, as the new RPC trees use a different mode of representation than previous versions of Revit. To see what RPC file is associated with a type, select the tree, open Instance Properties, select Edit Type, and click the Render Appearance parameter

in the Type Properties dialog that opens. This opens a Render Appearance Library with all of the available RPC trees (Figure 16.24).

FIGURE 16.23
Some RPC tree types provided in Revit planting content.



FIGURE 16.24
Render appearances for trees are accessed via the Type Properties dialog box.



Once you have placed your trees, render the view, and you'll see the results (Figure 16.25).

Rendering Tips

Here are some guidelines for rendering efficiently.

- ◆ Don't set the Quality settings to Best when iterating through material selections; doing so only slows down the time it takes to render. Keep Quality at Low or Medium until you're ready for a final pass.
- ◆ Use a low screen resolution until you're ready to export a final image for printing.

- ◆ Turn off lights that aren't visible in your view using the Artificial Lights dialog box. Group lights by floor if you are doing interior renderings of various floors in your model. This will speed up your renderings.
- ◆ Adjust quality settings only if you absolutely have to. Changing one value could inadvertently slow down your renderings and return unnoticeable effects. All of Revit's presets were carefully calibrated and should do the trick.
- ◆ Export rendered images to PNG in order to composite the image with background imagery.

FIGURE 16.25
Example of
RPC trees
rendered in a
perspective view.



Creating Animated Walkthroughs


Moving through a building in a virtual manner is a great way to experience a design before it gets built. Static images are nice, but it's becoming a common method to create animation sequences that showcase key aspects of the design. Revit provides tools for creating walk-through sequences for the model, which you can then export as an AVI file.

To make a walkthrough in Revit, the process is as follows:


1. In a plan view, create a path through the model by starting the Walkthrough tool located in the Create panel of the View tab. The Walkthrough tool is located in the 3D View drop-down list.

Once you've clicked the tool, you're put into a Sketch mode where each click creates a keyframe that lets you change the direction of the camera. Think about how a camera would move through or around a building. When you've finished sketching, click the Finish Walkthrough button on the Ribbon.

2. Edit the keyframes along the path, so the camera looks in the proper direction, by clicking the Edit Walkthrough button on the Ribbon.




In this mode, you can edit the camera and path. The default setting allows you to step through each keyframe using the VCR-style controls located in the Modify Cameras contextual tab and adjust the camera direction in the view. You can edit the camera direction only at keyframes. To see what the camera sees, click the Open Walkthrough button. Keep stepping through keyframes and adjusting the camera. In the camera view, you can enable the SteeringWheel and change the direction the camera is looking just as you can in a 3D perspective view.



- 3. With the walkthrough view open, export the walkthrough to .avi format by using the Application Menu and choosing Export > Images and Animations > Walkthrough. Figure 16.26 shows the resulting Length/Format dialog box.

FIGURE 16.26
The Length/
Format dialog box
lets you set out-
put values for the
length and size of
the animation.



Exporting the 3D Model for Use in Other Applications

If you have established ways of working with vector or pixel-based artwork, you can always export Revit views and use them as backdrops for your artistry. From the application menu, choose Export. You'll find options to export CAD formats for DWG, DXF, DGN, and SAT. You can also export any view as an image file using the Export > Images and Animations option. Supported formats include BMP, JPEG, PNG, TARGA, and TIF.

Once you've made edits to the exports in applications such as Photoshop, Illustrator, or Piranesi, you can always re-import the artwork into Revit and place it on sheets with your other views.

For rendering purposes, you can export a Revit file to FBX format (Figure 16.27) and open it in 3ds Max (2009 or later). Even though Revit can create compelling renderings on its own, the ability to batch render as well as utilize render farms means that you'll be able to create

renderings in minutes rather than hours when using 3ds Max. In addition to the geometry, the FBX file contains information about the materials in the model (Figure 16.28) and to which elements the materials are applied. This information is available only if you open the file with 3ds Max or 3ds Max Design 2009 or later.

FIGURE 16.27

On the Export menu you'll find the option to export to FBX.



FIGURE 16.28

Rendered model using 3ds Max.



Courtesy of Andrea Sader and Ines Magri

The Bottom Line

Create perspective views. Design visualization is a key benefit to using Revit as a documentation solution. Being able to snap quick perspectives of your spaces and building forms can be critical to making good design decisions.

Master It Create a new perspective view showcasing a critical design feature. Use the Rendering dialog, lighting, and the materials dialog to complete the rendering.

Create photorealistic renderings. You know those signs that are put up at a site before and during construction—the ones with the nice rendering showing the final product? Well, you can generate those directly in Revit!

Master It You've been asked to produce an exterior rendering of a building. Can you do this in Revit? Can you tweak the results in Photoshop?

Create animated walkthroughs. Creating animated walkthroughs is an excellent way to visualize the spaces within the project, as walkthroughs are more dynamic than still renderings.

Master It You want to create a compelling animation showing an entry approach to the building. How would you do that with Revit?

Export the 3D model for use in other applications. Revit is an excellent application, but a variety of other tools are available that you might want to use for rendering, modeling, or other BIM features such as 3D printing.

Master It You've modeled your project in Revit and assigned materials, and now want to make an animation sequence with 3ds Max. What should you do?

Chapter 17

Fine-Tuning Your Preliminary Design

The next step we'll explore is taking a preliminary building design and doing spatial analysis of the Revit model. You'll see how creating simple schedules of building and room areas can verify program information and start to generate preliminary cost analysis. We'll show you how to verify program data and evaluate a project's initial feasibility.

In this chapter, you'll learn to:

- ◆ Quantify your preliminary designs
- ◆ Create schedules
- ◆ Use schedules for preliminary cost estimates

Quantifying Your Preliminary Designs

In this chapter we're introducing a scenario that we'll build on in the next several chapters. As this is a Mastering book, we won't go into significant detail about how to perform some of the more basic techniques in Revit, such as how to make simple walls, floors, and roofs. Instead, you'll work from an existing, more developed design and build skills by adding and extracting information to and from this base model. You will move the design from a preliminary level through a set of design documents based on common architectural requirements that occur in a typical project workflow. We will also explore some sustainable design strategies.

The Foundation Model

The model we'll be using for the next several chapters can be downloaded from the book's companion web page, www.sybex.com/go/masteringrevit2010. Called "The Foundation ch17," it was part of a design competition for a university alumni facility and was created by BNIM Architects. The building is approximately 46,000 square feet and comprises office space, meeting areas, and multipurpose space spread out over three floors. It is located at a major university in the Midwestern United States (see Figures 17.1 and 17.2). Under a leaseback agreement, the building will be owned by its builder rather than the university—hence you will need to calculate rentable area.

FIGURE 17.1
Perspective view
of the Foundation
model.



FIGURE 17.2
Another view of
the Foundation
model.



We recommend doing a few things to familiarize yourself with this model:

- ◆ Open the project, and in the Project Browser, choose View ➤ All. This will give you a list of all the views in the model and provide you with an opportunity to browse through them and see what has been given focus and importance
- ◆ Take a look at the generic 3D view. Using the ViewCube, spin it around a bit and kick the tires, so to speak. Take a look at the overall building form and geometry to help acclimate yourself to the overall design. That will give you a sense of direction within the building
- ◆ Browse through any sheets that have been set up. Not only will this give you an idea of what the building looks like, but it will also tell you what stage the project is in and what the focus has been so far



In this Foundation model you will find many preestablished 3D views, as well as some sections and generic plan views. Sheets have been started and views placed on those sheets. A structural grid, elevations, and the primary building materials have all been defined. Based on the plans, you can get a clear idea of what the building program is and how the spaces are organized. At this stage in a project workflow, you'll often need to take a short timeout from design work and do some program verification and evaluation, with the goal of creating an initial cost per square foot assessment. To do that, you will first create area plans for the Foundation's total and rentable areas and then create schedules of materials so you can check costs against some square foot assumptions. This is where we'll begin with this model.


Calculating Area Plans

For the purpose of program verification, you need to establish how area values are calculated and represented. The simplest method is to use room tags, which can report room area, but you'll quickly see the limitations of that approach. Room tags only report the carpet area of the room and the calculated room surface does not take into account walls. For the feasibility study in this chapter's example, you'll need to create area plans for both total area and rentable area. Then we'll show you how to add areas and area tags manually.

Rooms and Room Tags

The room tag shown in Figure 17.3 has been placed in the model and is tagging a room. This is used to label the room and its surface. The surface value or the value expressed in square feet (SF) on the room tag is the usable area within the room, sometimes referred to as the *carpet area*.

FIGURE 17.3
Room area as a
property reported
in the room tag.



Revit calculates this area by finding all of the entities that touch the floor bounding a space. As you can see from the thick outline of the room in Figure 17.3, it does not include things like the area below the column (at the upper left) or other objects that penetrate the space, giving you a truly usable floor area. Later in this chapter, we will discuss how to schedule those areas so you can report them in a way that they are all visible at the same time.

While this is certainly a useful feature, it does not accommodate calculation of the precise areas you will need to verify your program or perform any cost take-offs.

Area Plans

Area plans are views of the model used to calculate the areas of your model according to various calculation standards. Some of the standards for area calculations are as follows:

Gross area This is the overall area of a floor or footprint of the building.

Rentable area Different developers and leasing companies have different standards for rentable area. For example, it may include all the spaces in a building except egress corridors, vertical transportation, and mechanical spaces. However, this includes the floor area taken up by columns and some walls.


Usable area This area defines only the usable space in a plan. It doesn't count areas taken up by columns, walls, mechanical rooms, and shafts or other unusable space.

BOMA area BOMA is the Building Owners and Managers Association. Widely used in the United States by architects, developers, and facilities managers alike, it was created to help standardize office building development. BOMA has its own set of standards for calculating areas. More information on BOMA standards can be found at www.boma.org.

Revit allows you to choose from two predefined area schemes, or it gives you the option to create your own scheme based on standard area calculation variables.

All area- and room-related tools are available on the Home tab (Figure 17.4).

FIGURE 17.4
Room and Area
tools panel located
on the Home tab.



To add or modify the area settings, on the Home tab click the arrow in the Room and Area panel to expand it. From the expanded menu, select Area and Volume Computations. The Area and Volume Computations dialog box shown in Figure 17.5 will appear.

FIGURE 17.5
The Area and Volume Computations
dialog box, with
the Computations
tab displayed.




The Computations tab allows you to change how the areas and volumes are calculated in the model. Here you can set how areas are calculated relative to the wall geometry (wall finish versus wall core, for example).

The Area Schemes tab, shown in Figure 17.6, lets you add different schemes to calculate room areas, allowing you to calculate multiple area types.

In the sample Foundation model, you first need to establish the gross area per floor of the building. To do this, begin by adding an area plan to the model.

FIGURE 17.6
The Area Schemes
tab of the Area and
Volume Computa-
tions dialog box.




CREATING A GROSS AREA PLAN


Take the following steps to begin creating a gross area plan:

1. Open the 'Foundation ch17' model.
2. Select the Area button from the Room and Area panel on the Home tab and click Area Plan (see Figure 17.7). This opens the New Area Plan dialog box, where you will select the area scheme, levels, and scale. Select Gross Building from the drop-down menu at the top. Using Shift-click, select the floor plans for Level 1, Level 2, and Level 3. Leave the scale at the default setting, $\frac{1}{8}" = 1'-0"$ (1:100), and click OK. You will then be presented with a dialog box asking you if you would like to 'Automatically create boundary lines associated with external walls and gross building areas?' Click Yes to continue. You'll have to do this once for each floor plan selected.

FIGURE 17.7
Creating area
plan views.




3. Revit automatically adds a new node called 'Area Plans (Gross Building)' to the Project Browser and adds plans for each level you selected. Open the Level 2 area plan.




4. In the View window, you'll see a duplicate of the Level 2 plan view you selected. The difference between the original Level 2 and this one is that it has purple lines defining the area boundaries (see Figure 17.8). This might be a challenge to notice in this black and white image, but you will get the idea if you open the project and follow the steps we indicated. These purple lines are placed on the walls according to the type of area plan computation you selected, which in this case was Gross Building Area. You can make manual adjustments to these lines, move them, or delete them if they don't appear where you want them. In our instance, you'll note that Revit didn't draw all of the lines around the building. This is easy enough to remedy. Using the Trim command from the Modify tab, simply trim the remaining lines to complete the area.

FIGURE 17.8
Area boundary lines for gross area are indicated by the gray color.



5. Revit has generated Gross Building Area plans for each floor, and you can start adding area tags to get an idea of what your floor areas are for this project. From the Home tab, in the Room and Area panel, expand Tag Room and select Tag Area. You can do that by selecting


the area tag is located. As you can see, you have about 21,192 square feet (~ 7,000 m²) of area for the first floor.



The area boundaries that Revit applies automatically are not set in stone. Should you need to manually change them and add new boundaries, you can do that using the Area Boundary tool, also available under the Area button. When adding new boundaries, note that they must form closed loops of lines in order for Revit to calculate areas. Any breaks or gaps between the area lines, or lines that don't intersect, will result in Revit returning a "Not Enclosed" value for the area. If you get that message, inspect all your lines, and close gaps using the Trim tool or by extending the boundary lines. It is not possible to add Area Boundary lines to anything but an area plan. That option will be grayed out in all other views.

CREATING A RENTABLE AREA PLAN

Now that you have defined the Gross Area and have a good idea of what the floor plate sizes are, you can move on to getting a better understanding of the building program. For the program verification, you need to figure out the rentable area for each of the spaces so you can see how well you fared against the program supplied by the client for this project. Using the same process described earlier for the gross building areas, you can make rentable area plans for the building. Repeating the technique described earlier but selecting the Rentable option, you'll create a new view in the Project Browser: Area Plans (Rentable).



You'll notice that in displaying rentable areas, Revit draws the area boundary on the *inside* of the exterior walls (unlike with the gross area, where the lines were drawn on the *outside* of the exterior walls), but it also draws boundaries down the *centerline* of the interior walls. All of this happens automatically—all that is left for you to do is to verify the lines and make sure you have them where you need them.


For this exercise, you'll want to modify the results slightly from what Revit provides by default. For the program and client on this project, you're not going to calculate core areas (areas around the elevator and stair cores) as part of the rentable area, so you'll need to adjust the area boundary lines around the core walls to reflect this and turn the many spaces into one area.

AUTOMATING AREA CALCULATIONS DURING DESIGN

When Revit creates area boundary lines, those lines by default are locked to the walls on which they are created. This is a helpful feature: when your design changes and walls are relocated, the area boundaries automatically update as well, keeping your area plans always up to date.

In the case of the restroom core, start by deleting the lines that separate the restrooms from the janitorial closet (see Figure 17.9).

FIGURE 17.9
Modifying an area plan.



As you delete area lines, you'll more than likely get the warning message shown in Figure 17.10. This message tells you that you have removed the boundary between two areas, and Revit is asking what to do with them. Before answering this question, let's discuss what "areas" means in Revit.

FIGURE 17.10
Area warning message.



In the context of Revit, *areas* are elements, just like walls, doors, and furniture. They are selectable, have properties, and can be scheduled. When selected, they will highlight in yellow and appear within the space as a box with an X through it, as shown in Figure 17.11.

Because areas are elements, you can tag them. An area tag reflects the properties of the element it is tagging. The tag itself is only an annotation.

FIGURE 17.11
Areas are select-
able elements with
properties.




At this point, you might be asking yourself, “Where did those areas come from? I didn’t insert them.” The answer is that Revit generated them automatically when you created the area plans. This is the essential difference between rooms and areas. By default, when you create a new area plan, it creates an area element within all of the closed area boundaries, so as long as there are no adjustments for you to make, it is only necessary for you to tag and label the areas.

In this case, you needed to make some changes to what Revit provided by default and now have more areas than you have spaces. So let’s jump back to the warning dialog box. You’ve been given two choices: delete all but one of the areas or click OK and accept having multiple areas in the space. Both of these options have viable workflows. If, as in our case, you do not plan to subdivide the room again, you can click Delete Area(s) to delete the extra areas and continue with your work. If you had deleted these lines with the intent of drawing new ones in a different location within this boundary, you could click OK, knowing you would have redundant areas for a short time until you finish this part of the model.

Clicking Delete Area(s) deletes the redundant areas and gives you a single core area for the restrooms shown in Figure 17.12.


FIGURE 17.12
One area is used for
the restroom core.



Since you don't want to count any of the core areas, you'll need to move the boundary lines from the centerlines of the walls to the inside face of those walls. Because the area boundaries surrounding the restrooms are locked to the walls themselves, you need to delete these lines and redraw them in desired locations. By now, you'll be used to the warning message about redundant areas, and in this case you know that you want to keep the areas and click OK instead of the Delete Area(s) button.

To draw the new area boundary lines, use the Area Boundary Line tool described earlier to add the new area lines to surround the core. If you choose the default Pick option, Revit will automatically choose the line location based on the rules established for that area plan type. Since we specifically want the area lines on the outside of the core, it is best to draw them manually. So, instead of the Pick tool, select the Line tool from the Draw panel on the Place Area Boundary tab. Very quickly, our new core boundary will look like Figure 17.13.

FIGURE 17.13
Use the Area Boundary Line tool to revise the core boundary.




CREATING COMPLEX AREA PLANS

In some cases, such as General Services Administration (GSA) projects, there is a need to create and maintain a series of possible area plans. All these additional calculations can slow file performance, depending on the complexity of the building. One way around this is to make a separate project file for the area plans. By linking the building model to a separate file with area plans, you cannot improve model performance, but you can create the area plans quickly without interfering with other workflows.

Adding Areas and Tags



As we mentioned earlier, areas are actually elements within the model. When we made the area plans, Revit automatically populated the plan with area boundaries. However, you might want to create your own areas or area boundaries to provide for area types that Revit cannot automatically generate. You might want to add units to a condominium building, for example. To add boundaries manually, click the Area button and use the Area Boundary Line tool. This adds an area and a tag (provided Tag on Placement is checked in the Options bar) at the same time to your area plan.



To tag an existing area element that was created without a tag, on the Area and Room panel, expand the Tag button and use the Tag Area button.

DON'T DRAW MORE THAN NECESSARY

When designing office buildings, you will probably have your building cores as a repeating element on each floor of the building. In many cases, these cores will be identical. If that is the case, there is no need to redraw your area lines. You can simply group the area lines and then copy those elements between floors. This way, if you edit one group the change will be propagated to all other groups.

To copy area boundaries between floors, select them and copy them to the clipboard using the following steps.

1. Select area boundaries using one of the following options:
 - ◆ Ctrl-click each line individually
 - ◆ Highlight one line by mousing over it (don't click) and press the Tab key. This will highlight the chain of all the connected lines, and you can then click to select them
 - ◆ Drag a selection window around all of the elements, and using the Filter tool in the Multi Select tab, filter out all but the <Area Boundary> lines, as shown in Figure 17.14. This is probably the best method





FIGURE 17.14

Filtering your selection.




2. Once the Area Boundaries are selected, you can use Ctrl+C or the Copy command from the Clipboard panel to copy them to the clipboard. Now, choose Paste Aligned from the same panel and from the expanded menu, select the option Select Views (see Figure 17.15) to paste your copied area boundaries directly into the same location on other floors, ensuring consistency in your area calculations.

FIGURE 17.15
Pasting the copied
Area Boundaries
into selected views.



3. Now that you have all the areas defined, you can present them by printing the individual views to see graphically how the spaces are assembled (see Figure 17.16).

FIGURE 17.16
Area and tag
graphics.



But what happens if you want to show this information in a tabular, spreadsheet format? Often you'll need to share information of this kind in a table format. Because Revit is based on a bidirectional information model, it can do all of these calculations and update tasks for you in real time. All you need to do is set up a view type in the model that allows you to look at the data in a list format instead of showing the information graphically. For this, use schedules.

Creating Schedules

Schedules are lists of elements within the model. They enumerate items, including building objects such as walls, doors, and windows; calculate material quantities or areas and volumes; and list the number of sheets, text notes, keynotes, and so on. The ability to dynamically create and update schedules is a core aspect of both BIM and Revit.

Creating schedules of objects, areas, or material quantities in a project is usually one of the most painful (if not boring) but necessary tasks for architects. Needless to say, performing a

manual calculation takes a long time and can result in errors. Using CAD tools can partly automate this process, but when it comes to calculating numbers of objects, the calculation can only count the number of blocks that are predefined in a file. In Revit, all elements have information about their physical properties, and you can add information to individual elements. For example, doors can have properties such as size as well as material, color, fire rating, and whether they are exterior or interior.

Revit lets you schedule any element based on properties of the element. In effect, this means that almost anything placed in a Revit model can be scheduled and quantified. Additionally, because the schedule is linked to the objects in the model, you can use the schedule to locate objects within the model or to change their types and properties. This ensures that in any view, regardless of type, the count and properties of all elements are always synchronized. As we often state, the view in which you add or change something doesn't matter; the changes will be reflected in all the views.

If you're unfamiliar with database concepts, don't worry; we'll explain the options in the New Schedule dialog box. The following types of elements can be scheduled:

Areas	Gutters	Rooms
Casework	Lighting fixtures	Site
Ceilings	Mass	Slab edges
Curtain panels	Mass floors	Specialty equipment
Curtain systems	Mechanical equipment	Stairs
Curtain wall mullions	Parking	Structural columns
Doors	Planting	Structural foundations
Electrical equipment	Plumbing fixtures	Structural framing
Electrical fixtures	Property line segment	Structural trusses
Fascias	Property lines	Topography
Floors	Railings	Wall sweeps
Furniture	Ramps	Walls
Furniture systems	Roofs	Windows


There are also some other schedules you can create that are not limited to specific types of elements:

Multicategory This type of schedule is for objects that span across Revit category organization. For example, you may want to create a list of windows and doors in the same schedule. You may also want a schedule showing all the casework and furniture in a project. A multicategory schedule allows you to combine a number of different categories into one schedule. It is also the only way to schedule generic model elements. The one limitation of a multicategory schedule is that you can't schedule host elements (walls, floors, roofs), only their materials and family components.

Area (gross building) This schedule lists the gross building areas created with the area plans.

Areas (rentable) This type can be created with a rentable plans schedule. Later in this chapter, we'll walk through an exercise demonstrating how to create a simple schedule showing the program areas we created in our area plans.

Although we've listed quite a few, we haven't included all the schedules available in Revit. There are still a few more worth mentioning. These schedules can be accessed only from the View tab. To see them, expand the Schedules button on the Create tab.



Material take-off This type of schedule can list all the materials and subcomponents of any Revit family and allow an enhanced level of detail for each assembly. You can use a material take-off to schedule any material that is placed in a component. For example, you might want to know the cubic yardage of concrete within the model. Regardless of whether the concrete is in a wall or floor or column, you can tell the schedule to report the total amount of that material in the project. As we will show later, you can use this schedule type to make some preliminary calculations regarding the use of recycled materials in the project to support sustainable design goals.

Drawing list This schedule shows a list of all the sheets in the project, sorted alphabetically.


Note block This schedule lists the notes that are applied to elements and assemblies in your project. You can also use a note block to list the annotation symbols (centerlines, north arrows) used in a project.

View list This schedule shows a list of all the views and their properties in the Project Browser.

These schedules are separated from the main list of schedules because they aren't commonly used in building documentation. They are primarily for data coordination that happens outside the project documentation.

The Keynote Legend is located under the Legends button on the Create panel of the View menu.


The Revision Schedule is available in the Family Editor environment. You use this schedule when creating a Titleblock family.



STANDARDIZE YOUR SCHEDULES

You will find yourself making the same schedules for each and every project. Take the ones you find the most universal and make them a part of your default template. As you add content to the model, these will start to autopopulate.

Making a Simple Schedule (Rentable Area)



You can begin making a new schedule by selecting the View tab, and in the Create panel, expanding the Schedules button. There you select Schedule/Quantities. When you begin a new schedule, you will have a number of format and selection options. These will help you set the font style and text alignment as well as organize and filter the data shown in the schedule. Remember that Revit is a database at its core, so many of the same functionalities that are available in database queries are also available in Revit.

SORTING YOUR DRAWING LIST


The drawing list can also be used as a sheet index to the documents. By default, Revit sorts sheets alphabetically. It is traditionally desirable to prepare the sheet index with civil sheets first, then architectural, structural, and so on. One way to customize sheet sorting is to add a Discipline field to the schedule and number the sheets so civil is 1, architectural 2, and so on. You can then sort by that numbered column.

The process of creating a new area schedule is best demonstrated with an example. Take the following steps to create a new rentable area schedule for the Foundation model:

1. Open the Foundation.rvt file from the book's companion web page (www.sybex.com/go/masteringrevit2010).
2. Navigate to the View tab, and click Schedules ➤ Schedule/Quantities.
3. Choose Areas (Rentable) from the Category area, name the schedule **Rentable Area Schedule**, and confirm by clicking OK.

You will see a series of tabs that allow you to specify the schedule's graphic appearance and choose exactly what data you would like to show. Figure 17.17 shows the dialog box for the rentable area schedule. As each grouping of elements within Revit is unique, the list of possible schedule values changes accordingly.

FIGURE 17.17
Rentable area
scheduling options.



Each tab controls different ways to sort and view the data within a schedule. Here is a basic explanation of their functions:

Fields The Fields tab lets you select the data that will appear in your schedule. For the wall schedule, it shows all the properties available in the wall family.

Filter On the Filter tab, you can filter out the data you don't wish to show. You'll use this tab, for example, to restrict displayed data so that only information about the concrete walls in the project appears in the schedule.

Sorting/Grouping This tab lets you control the order in which information is displayed. You can also decide whether you want to show every instance of an item or only the totals for a given family.

Formatting The Formatting tab controls the display heading for each field and whether the field is visible on the schedule. It's possible to add fields that are necessary for calculations or sorting but don't show on the printed copy of the schedule. Additionally, this tab can tell Revit to calculate the totals for certain fields.

Appearance The Appearance tab controls the graphical aspects of the schedule, including the font size and type of text for each of the columns and headers in the schedule. It also allows you to turn the grids on and off or modify the line thickness for the grid and boundary lines.

The following example walks through the different options in the New Schedule dialog box while you create a new wall schedule.

In this example, you'll create the schedule, filter out all but the concrete walls, and calculate the volume of recycled content in the walls based on the assumption that you're using 15 percent recycled content in all the concrete you pour on this project.

1. For your schedule, choose the following fields from the Fields tab and sort them in this order:
 Level
 Name
 Area
2. Select the Sorting/Grouping tab to give the schedule some parameters to sort by. First, sort by level, so you can see which floors you have the areas on, and then sort by area name. You will also want to see a total of the areas by floor, so include a footer showing totals only for the levels. Also check the Header check box so you can tell which floor you're on in each grouping. Finally, you'll want to see a grand total of all the areas in the building. Your dialog box should look like Figure 17.18.
3. Select the Formatting tab, as you'll also want to make a couple of changes here. Select the Level parameter and select the Hidden Field check box. You don't need to see a level heading for each item in the list, especially since you have one established already as a header for each floor. You'll also want to select the Area field and make two changes: first, right-justify the areas so they align properly, and then check the box to have the schedule calculate totals, as shown in Figure 17.19.
4. Clicking OK at this point will give you a schedule broken out by level and totaling each floor's areas. Your schedule should look something like Figure 17.20.

FIGURE 17.18
Set the Sorting/
Grouping tab to
match this.




FIGURE 17.19
Set up the Format-
ting tab to look
like this.





FIGURE 17.20
The area schedule.

Storage	252 SF
Telefund	000 SF
Vestibule 1	237 SF
Vestibule 2	70 SF
	19829 SF
Level 2	
Conference Rm	000 SF
Core 1	460 SF
Core 2	377 SF
Office	125 SF
Office	125 SF
Office	125 SF
Office	125 SF
Open Office	17989 SF
Restroom Core	513 SF
	20447 SF

5. For areas, you are concerned only with the rentable spaces and don't need to see how much area the cores take up in the building. By right-clicking on the schedule, you can view its properties and make some modifications. Choose the Filter tab this time, filter out any name that does not contain the word *Core* (with a capital C), as shown in Figure 17.21, and click OK.

FIGURE 17.21
Filter out areas
that do not include
the word *Core*.



- 6. Pan down to the bottom of the list and you will notice that you still have the name *Restroom core* in the list (see Figure 17.22).

FIGURE 17.22
Check the schedule
to see the effect of
the filter.

Level 2	
Conference Rm	600 SF
Office	125 SF
Office	125 SF
Office	125 SF
Open Office	17989 SF
19097 SF	
Level 3	
Open Office	16215 SF
Restroom core	513 SF
16728 SF	
54350 SF	

- 7. The name *Restroom core* is still in the list because the filter and fields in the schedules and families within Revit are case-sensitive. The fields need to match exactly. However, there is an easy fix. By clicking within the cell itself, as you would do in Excel, you can modify the word *core* so it has a capital C and the name will then be filtered from the list. The finished schedule should look like Figure 17.23.

FIGURE 17.23
The finished area
schedule.

Rentable Area Schedule	
Name	Area
Conference	250 SF
Conference	250 SF
Dwycare	2054 SF
Electrical	233 SF
Entry	214 SF
Mechanical	674 SF
Multi-purpose space	2695 SF
Office	104 SF
Office	163 SF
Office	128 SF
Open Office	120 SF
Open Office	6872 SF
Restroom	48 SF
Restroom	40 SF
Restroom	48 SF
Restroom	40 SF
Storage	252 SF
Telefund	838 SF
Vestibule 1	237 SF
Vestibule 2	70 SF
10525 SF	
Level 2	
Conference Rm	600 SF
Office	125 SF
Office	125 SF
Office	125 SF
Open Office	17989 SF
19097 SF	
Level 3	
Open Office	16215 SF
16215 SF	
53637 SF	


Placing the Schedule on a Sheet

Now that you've created the schedule for the program, you need to put it on a sheet. As you've figured out by now, schedules work like any other view: to place the schedule on a sheet, drag and drop it from the Project Browser onto the sheet you wish to place it on. One of the nice things about schedules is that you can actually place them on multiple sheets and they will always provide the most current information.

We want to create a set of sheets you could provide to the client that demonstrates the program for each floor in both graphic and list format. When finished, you should have an 11×17 presentation sheet that looks like Figure 17.24, with a floor plan and schedule for each floor.

1. Expand the sheets in the Project Browser and find the sheet 01 – First Floor Program.

FIGURE 17.24
Finished presentation sheet with area plan and schedule.




2. Expand the rentable area plans and drag and drop the Level 1 Rentable Plan onto the sheet.
3. You will notice that the plan is much larger than the sheet, since we made the area plan at 1/8" scale originally. Right-click on the plan and choose Activate View from the context menu. In this view, you want to do two things: change the scale, and turn off some of the unnecessary annotations. So, first, adjust the scale of the drawing to be 1/16" = 1'-0" (1:200). Second, open the Visibility Graphics dialog box (by typing **VG** or choosing the View tab and in the Graphics panel, clicking Visibility/Graphics). On the Annotations tab in the Visibility/Graphic Overrides dialog box, turn off visibility for the following categories:
 - ◆ Elevation tags
 - ◆ Grids
 - ◆ Reference planes
 - ◆ Section tags


Once the view is resized and the display reconfigured, place the plan at the upper portion of the sheet.

- 4. Drag and drop the rentable area schedule onto the same sheet. When it first appears, it will look something like Figure 17.25. You'll need to do a bit of rearranging to get the schedule to fit the sheet properly.

FIGURE 17.25
Unformatted
schedule placed
on sheet.



Now, there are two different ways to modify the shape of the schedule directly from the sheet. The first one way is by dragging the triangles that appear on the upper portion of the schedule header. Note that there is one blue triangle for each column. By dragging the triangle left or right, you can resize the width of each column. You will notice some of our longer room names have wrapped to the next line. Grab the left triangle and drag it to the right to lengthen the Name field. Note that this also shortens the schedule by removing the wrapped lines.



The other way to modify how the schedule fits on the sheet is to use the squiggle, located in the center of the schedule. Clicking the squiggle splits the schedule into two columns. It is important to note that you cannot choose where this split occurs. However, you end up with two separate columns that you can now drag independently of each other. Now that the columns fit within the space you have remaining, you can relocate them on the right-hand portion of the sheet. The sections of the schedules can be subdivided as many times as you need, and each section will subdivide independently of the others. Your final sheet will look like Figure 17.24.



Real World Scenario

KEEPING BUILDING AREA SCHEDULES UPDATED

To most clients, building areas are a critical part of the development pro forma. (The *pro forma* is a document, typically a spreadsheet, that outlines the financial goals of the project or development.) In practice, you will create area plans that coincide with how the owner needs areas computed for its calculations. You keep these in a schedule, allowing owners to make regular updates to the building areas so they can compare them to the current pro forma. Since you can keep the schedules dynamically updated, you can set this up once and know that the areas will always be up to date.

Additional Schedule Capabilities

Now that you've generated a schedule of spaces, let's look at some of the other advantages of using schedules in the design process. Since Revit is a parametric modeler, all parameters are linked to elements within the model. You might notice that at the top of your schedule, the label is simply labeled Area. This is easy to change.

Rentable Area Schedule		
Name		Area
Level 1		
Area	377	SF
Area	48	SF
Area	813	SF
Transition Room	120	SF


If we were not using BIM as a modeler, it would become tedious to locate these areas so they could be properly labeled. In Revit, there are two ways to rename these spaces. First, if you know what the areas are supposed to be, you can either type the name in or select it from the list of already used names. However, what happens when you need to locate the room on the plan before making changes to it? This is easy to do within Revit. By selecting the area name in the schedule, you'll get useful tools in the Quantities tab of the Modify Schedule tab.

The Highlight in Model button repeatedly cycles through all of the existing views within Revit and zooms into the one that would best show the area in question. Clicking the button gives you a view similar to what you see in Figure 17.26. As you can see, the restroom does not have a descriptive name and is shown highlighted in the view.



FIGURE 17.26

Use the Highlight in Model option to point to the location of elements highlighted in the schedule.



This is a powerful tool because it can be used to locate any of the elements within the Revit model directly from any schedule. Not only do Revit schedules report information about elements in the project, but they can also be used to control elements. If you decide to exchange one wall type for another, you can do so by clicking in the schedule—under wall types, for example. A drop-down menu appears, listing all available types currently in the model, so you can choose the type you want. Again, this automatically changes the instance of the wall to another wall type in all views in which the wall is present.

Using Schedules for Preliminary Cost Estimates


At this stage, we're still in preliminary design for this project, and have not gone through the rigor of cost estimating the project yet. Nonetheless, you can use some of the scheduling tools to help calculate a rough cost of the building based on a cost per square foot assessment. The disclaimer here is that Revit is not a cost-estimating package. It is a database that can count, total, and tally the number of items, areas, or other properties within the model. Cost estimating itself is part counting and part experience; we can work on the counting part with the BIM model.

Since you already created gross area plans earlier, go ahead and create a new schedule to analyze the area plans to create a rudimentary cost estimate based on the building square footage. This time, only include the Level and Area fields in the Fields tab. Next, add a parameter for cost. That parameter is *not* a standard property of the areas, so you'll need to add it to the list. Here's how to do that.

Add Parameter

1. To add a custom parameter such as the Cost parameter, use the Add Parameter button on the Fields tab in the Schedule Properties dialog box. This allows you to add a new custom parameter to the Areas field. You need to add one for Cost and you need the parameter type to be a number so we can get a cost per square foot. See Figure 17.27 for the dialog box properties.

FIGURE 17.27
Adding a new parameter.





2. Use the Calculated Value button to add a new field to the schedule. The button displays a new dialog box (Figure 17.28) where you can create new fields that are basically custom formulas defined by combining numerical values with other fields.

FIGURE 17.28
Calculated Value
dialog box.

The dialog box is titled "Calculated Value". It has a "Name" field with the text "Cost per sq ft". Below it are two radio buttons: "Formula" (selected) and "Percentage". There is a "Description" dropdown menu with "Parameter" selected. Below that is a "Type" dropdown menu with "Area" selected. At the bottom is a "Formula" field with the text "Area * Cost". There are three buttons at the bottom: "OK", "Cancel", and "Help".

In our example, we want Revit to calculate a total cost for the project based on a cost per square foot we consider close to accurate based on previous experience.

1. For our Type setting we made the type a Number. In Revit, you need to make sure the types of fields are compatible so you are not multiplying length times something like material. Also, as we mentioned before, the fields are case-sensitive. In the formula line, you will need to type **Area * Cost** to get the total project cost. Click OK to exit the dialog box.
2. Finally, on the Sorting tab, check the box for Grand Totals, and on the Formatting tab, highlight the Cost per Sq Ft field you just created and check the box to calculate totals. Once you enter an estimated cost of \$169.00 for each floor, the final schedule will look like Figure 17.29.

FIGURE 17.29
Building cost per
square foot.

Area Schedule (Gross Building)			
Level	Area	Cost	Cost per sq ft
Level 1	20312 SF	169	3432808 SF
Level 2	22767 SF	169	3847562 SF
Level 3	17839 SF	169	3014813 SF
Grand total: 3			10295104 SF


Now you have a constantly updated area of each floor of the building multiplied by our estimated cost per square foot for a continuously accurate total, based on those metrics. However, the costs are being reported as SF values and not dollar amounts. You can fix that problem using the Schedule Properties dialog box.

Editing the Graphic Appearance of a Schedule

When you create a new schedule, you're presented with a number of format and selection options on the Appearance tab of the Schedule Properties dialog box. These let you set the font style and text alignment and decide how to organize and filter the data for display in the schedule. Let's explore the options in the Schedule Properties dialog box.

On the Appearance tab (see Figure 17.30), you'll see the options to change the font styles, gridline visibility, and other variables for header and body text of the schedule.

FIGURE 17.30
On the Appearance tab, you can control font, size, and header visibility.




However, the change you need to make to the appearance of the data in the schedule is found on the Formatting tab of Schedule Properties dialog box. For our purposes in our cost per square foot schedule, select Cost per Sq Ft and make the following adjustments:

1. Change the alignment to right justified, which is conventional for money totals.
2. Select the Field Format button and uncheck the option Use Project Settings. Here is where you can choose to change the Unit suffix and remove SF from the cost per square foot values (see Figure 17.31). Click OK to close all the dialog boxes and return to our schedule.



FIGURE 17.31
The Format dialog box.



You also have the ability to add headers to your schedule. By selecting the Headers check box, you can group them under another title.


1. Select Level and Area by clicking in one of them and dragging the mouse to the other one (see Figure 17.32). They will show as highlighted. While Level does not look selected, it currently is.

FIGURE 17.32
Selecting headers.

The image shows a screenshot of a schedule table titled 'Area Schedule (Gross Building)'. The table has four columns: 'Level', 'Area', 'Cost', and 'Cost per sq ft'. The 'Level' and 'Area' columns are highlighted. The table contains data for three levels and a grand total.

Level	Area	Cost	Cost per sq ft
Level 1	20012 SF	109	3422009
Level 2	22767 SF	169	3947562
Level 3	17839 SF	169	3014813
Grand total:	3		10205194

2. Doing this activates some of the different tools on the Schedule panel on the Modify Schedule/Quantities tab. You'll now have the option to group (or ungroup) these headers. Choose the Group button.



3. You now have a header that spans the two headers selected, and we can add some more descriptive information to help clarify the schedule. In this example, we have added the text "Preliminary Design Plan" to the header (see Figure 17.33).

FIGURE 17.33
Grouped headers.


Preliminary Design Plan		Cost	Cost per sq ft
Level	Area		
Level 1	20312 SF	169	3432809
Level 2	22767 SF	169	3847562
Level 3	17830 SF	169	3014813
Grand total: 3			10285104

NOT ALL SCHEDULES NEED TO APPEAR ON SHEETS

You can use schedules to document objects used in your project (number of doors or windows, furniture pieces, material quantity, areas of rooms, etc.), but you can also use them to locate elements in the model or look for inconsistencies. For instance, you can keep a schedule of text notes only within a model and not use them on sheets. This schedule can then be used to look for odd items inserted into the model. In essence, you can schedule the text note name and the number of times it appears in the model. Perhaps the schedule indicates that a particular note is used only one or two times in the model. You can then decide if the note was inserted incorrectly into the project and determine whether it's inconsistent with the other notes in the model. The same thing can be done for wall types or anything else in the model.

NEW OPTIONS IN REVIT 2010

When you are creating a schedule of elements that need naming and you click on any name in the schedule (as example open the Gross Area BOMA schedule) you will notice three new options on the Modify Schedule/Quantities tab.



The three options are as follows:

Show In the room schedule, includes rooms that are not placed or enclosed in the building model. Those rooms will be marked as Not Placed in the schedule and the model.

Hide Filters the schedule so that it only includes rooms that are placed or enclosed in the building model.

Isolate Filters the schedule to list only rooms that are not placed or enclosed in the building model.

The Bottom Line

Quantify your preliminary designs. Once your plans are established, create your own area plans to dynamically track changes in the project.

Master It Establish your preliminary design, and then create area plans so you can keep up to date with space sizes, allocations, and your project program.

Create schedules. One of the benefits of Revit is the ability to manage not only your drawings, but also other information about the project. Create schedules for your project templates to manage the materials within the project.

Master It Schedules have a multitude of uses and value at all levels of the project. Explore a variety of schedules to optimize your workflow and maximize what you can get from the model.

Use schedules for preliminary cost estimates. Create a schedule that tracks project costs based on an estimated cost per square foot.

Master It Many developers and facilities managers use BOMA calculations for figuring rentable area, gross area, and R/U (rentable/usable) ratios. Establishing area plans and schedules can help you find these numbers much quicker than a legacy CAD system would have allowed.

Chapter 18

Evaluating Your Preliminary Design: Sustainability

In this chapter, we will take our preliminary building model and investigate sustainable design strategies using the building information model geometry.

Revit does a number of things to support a sustainable design process and workflow, ranging from accurate material take-offs to energy analysis with third-party software. As you move to Revit from a more traditional drafting approach, you will begin to see more opportunities to engage in model-based simulation. This represents a shift in office workflow and culture. Revit changes how teams communicate, since everyone works with one centralized model that can aggregate linked structural and MEP models. Such close integration allows team members to understand better the overall direction of the project from many vantage points. This ability to see the model from different points of view also makes a BIM project perfect for exploring sustainable design strategies. We will explore how Revit can help support those strategies.

In this chapter, you'll learn to:

- ◆ Incorporate a sustainable approach from the very beginning of project development
- ◆ Use Revit to create sun studies
- ◆ Track recycled materials and other sustainability strategies using schedules
- ◆ Analyze daylighting

Incorporating a Sustainable Approach from the Beginning

Sustainable design has been a long-standing practice in the construction industry, but it has recently received mainstream recognition and grown in popularity. Sustainable design can address many issues, such as energy use, access to natural light, human health and productivity, water conservation, use of recycled materials—the list goes on. One of the primary goals of sustainable design is to reduce a building's *carbon footprint* (the net amount of carbon dioxide emitted by a building through its energy use) to zero. This means the finished building uses no more energy than it can produce or offset. At the same time, sustainability means creating better conditions for the people who work, live, or play in the buildings.

An important factor in sustainable design is the huge effect that construction has on the environment. The United States, as an example, uses 25 percent of the world's energy, and the U.S. building industry uses 40 percent of global energy. Buildings, taken together, are the largest single resource consumer in the world. To solve the problem of global warming, we in the

architecture, engineering, and construction (AEC) industry must work toward a more efficient, more sustainable building practice. And even if this sounds like alarmist propaganda, we should embrace sustainability because it saves time, materials, labor, money... in other words, it leads to better buildings.

Preliminary Design Tools

In the previous chapter, “Fine-Tuning Your Preliminary Design,” we introduced the Foundation model by working with the preliminary design, and we discussed verifying program and area information by creating area plans and schedules. We will be building on the same model in this chapter to investigate sustainable strategies.

Since we have a digital building model, we can also rapidly iterate different variations of the design using sustainable strategies. When designing for sustainability, the important thing is to understand which questions to ask—and to ask them early enough in the process that you can make appropriate changes. There are five simple things you can do to help make any project more sustainable:

- ◆ Optimize the building mass
- ◆ Create good site orientation by maximizing north–south exposure and minimizing east–west exposure (in the northern hemisphere)
- ◆ Optimize the use of daylight and sun shading
- ◆ Optimize the building envelope assembly
- ◆ Optimize the use of carbon-free resources such as sunlight, wind, and rain

Although it was not created primarily as a sustainable design tool, Revit does provide an integrated 3D model that can be used as input by other applications for the purpose of running analyses. This saves you the time of having to remodel geometry in these applications and thus reduces the amount of time and money spent on analytical modeling. With Revit, you are building a 3D model by default, so testing a number of simple but effective sustainability strategies early on makes sense and does not require you to remodel anything.

The LEED Rating System

One widely used tool for measurement and rating of sustainability in the building industry in the United States is the LEED rating system. Created by the U.S. Green Building Council (USGBC), the Leadership in Energy and Environmental Design (LEED) system is a nationally recognized benchmark for high-efficiency design and construction. The LEED rating system consists of five key areas:

- ◆ Sustainable site development
- ◆ Water savings
- ◆ Energy efficiency
- ◆ Material selection
- ◆ Indoor environmental quality

Each of these areas assigns point values to a variety of methods and processes of sustainable design. The goal of the ranking system is to determine and rank a building's sustainability. For more information on the USGBC and LEED, visit www.usgbc.org/leed.



Real World Scenario

TAKE ADVANTAGE OF THE DESIGN CYCLE

As any designer can attest, design is an iterative process. The process of design—especially sustainable design—can involve a series of intuitive and creative movements followed by periods of research, testing, and validating the design decisions. This is in turn followed by some manner of redesign to adapt to any changes that are needed due to the new information or direction.

Use the energy and sun tools in a similar fashion. If you wait until the end of the design process to begin using these tools, they will be of little value to mold and inform your process. Begin your investigations and testing right away to see how the energy and sun tools can shape the form and design of your project.


Using Revit to Create Sun Studies

Chapter 15, “Presentation Techniques for Plans, Sections, and Elevations,” introduced Revit’s tools for applying physically accurate shadows for presentation purposes and showed how to enable and control them. Here we take a closer look at using these features analytically.

Good sustainable design optimizes the use of natural daylight within a building and thereby minimizes the need for heavy use of electrical (artificial) lighting. The design should take into account the direction the daylight is coming from because this dictates the amount of solar gain the building takes in during the course of the day. East and west daylight are the hardest types to control. In the Northern Hemisphere, north elevations get a great amount of indirect lighting, while south elevations get a great deal of direct exposure. This can be mediated with the proper use of sun shading devices (see Figure 18.1).

FIGURE 18.1

Sunshades and natural ventilation.




Sunshading devices are specific to the local climatic conditions; however, there are some fairly typical rules of thumb. North and south sunlight are the easiest to control since the angles of exposure are not nearly as dramatic as the east and west façades. Because of this, sunshading on the south side is typically horizontal, to allow more sun exposure to the interiors during winter months when the sun is lower in the sky and less exposure in the summer months when the sun is higher. Sunlight affecting the east and west façades is more difficult to control, and sunshading is typically vertical.

Working directly and early on with a mechanical engineer who is knowledgeable about sustainable principles and approaches can help direct and maximize the use of natural light and heat in your design. However, even without an expert, a simple daylighting view can help a design team make good decisions regarding daylighting.

Sun studies are views (they can be still or animated) that you can generate to reflect the solar conditions during specific times of the year to visually gauge light and shadow conditions. By creating camera views at key locations within the model, you can see the resulting shadows based on the location of the model on the planet and the date and time. In Figure 18.2, you can see the effect of sun on the Foundation model during four peak times of the year: the summer solstice (June 21), the spring and fall equinoxes (March 21 and September 21), and the winter solstice (December 21). We will be using these same dates as we study the model from other angles. Note that because the spring and fall equinoxes replicate the same solar condition, only one image needs to be shown.

Remember, once we establish these views, they will be constantly updated as we make modifications or design changes to the model.

FIGURE 18.2
Sun studies at
various times of
the year.




Making a Solar Study

Open the Foundation model in the Chapter 18 folder on the book's companion web page (www.sybex.com/go/masteringrevit2010), and let's establish a few views from different locations. We'd like a better understanding of the play of sun and shadow within the model from these locations. To do this, we are going to set up some sun studies in these spaces.

1. Set up the following camera views:
 - A. From the second floor, place a camera from the View tab looking at the southern elevation of the building, eastern half (because of the building's length, we will not be able to see sufficient detail if we look at the entire façade at once). Name it **Sun Study-South E Facade** (Figure 18.3).

FIGURE 18.3


Exterior camera placement looking at south façade.



- B. From the second floor, place a camera looking at the western elevation of the building, east half. Name it **Sun Study-West Facade** (Figure 18.4).


FIGURE 18.4

Exterior camera placement looking at west façade.



- C. From the interior third-floor office space, place a camera looking to the southwest. Name it **Sun Study-3rd Floor Interior** (Figure 18.5).

FIGURE 18.5
Exterior camera
placement looking
at the third-floor
interior.



2. Now if you go back to the first view, the *Sun Study-South E Facade*, the view by default will look like a colorless perspective of the south façade (see Figure 18.6). You can either choose to accept the way this view looks or choose Shading or Shading with Edges from the View Control bar at the bottom of the view window.



You need to turn on the sun and cast some shadows.

3. In the View Control bar, the third button from the left is the Shadows button. Clicking this button toggles the shadows on and off. It also gives you the option to go to the Graphic Display Option dialog box, where you can then set the parameters for what time of day to show the shadows. Choose Graphic Display Option from the menu. Note that you can save these settings in a view template to quickly be applied to other views.





FIGURE 18.6
Default appearance of a perspective view.




4. In the Graphic Display Options dialog box, select the Cast Shadows check box (Figure 18.7).



This activates the browse button for the Sun and Shadows Settings dialog box. Click it to access that dialog box.

FIGURE 18.7
The Graphic Display Options dialog box.



5. In the Sun and Shadows Settings dialog box, you have three options:


Still casts the sun at a specific time of day based on the parameters you choose.

Single-Day allows you to animate the sun and export the animation to an AVI file to show it over the course of a single day.

Multi-Day casts the sun in the same position (same time of day) over the course of multiple days.

For this exercise, choose Still (see Figure 18.8).

FIGURE 18.8
Sun and Shadows
Settings dialog box.



6. Here you need to start by setting the location of the building as well as the Date and Time of the year for which you wish to analyze the effect of the sun and thus shadows. Choosing the By Date, Time and Place option, we can give our building a geographical location.
7. Click the browse button to open the Manage Place and Location dialog box. Here you'll find a long list of choices available. Choose Kansas City, Missouri, and click OK. For the date, choose June 21, because we want to see the sun during the summer solstice. Set the time to 10:30 A.M. Finally, make sure Ground Plane at Level is selected and set to Level 1. This will allow Revit to cast shadows against the ground.
8. Before you click OK and let Revit calculate the effect of the sun for the location you have selected, you need to name your settings. Choose Rename from the buttons on the left of this dialog box and rename Sun and Shadows Settings to **6/21, 10:30 am**.
9. Click OK twice to exit the dialog boxes. It will take a moment for Revit to calculate all the shadows. The finished view should look like Figure 18.9. It looks like the sun canopy extends far enough to reach all the floors at this time of day in the summer, and it will give us an interesting play of light on the façade.


FIGURE 18.9
How the sun
affects the
south façade on a
summer day.



In Figure 18.9, you can see the results of the sunshades on the southern façade. Both solar studies were done at the same time of day, but there is an obvious impact of the shading devices on the second elevation over the first. Later in this chapter, we will discuss different energy modeling strategies that are designed to report the actual load differences the building will have with or without the shades.

SUN STUDIES THROUGHOUT THE YEAR

By going back to the Sun and Shadows Settings dialog box, you can duplicate the settings and modify only the date or time of day to include a sun study for the equinoxes and the winter solstice. You can then export each view using the Export Image option. From the Application Menu choose Export > Images and Animations > Images and export each view to keep a record of the sun at different times of the year. Here are some examples of how shadows are cast on the building: the upper image reflects the sun on the building in the winter; the middle, spring and fall; and the bottom summer.




Animated Sun Studies

A great feature in Revit is the ability to create animated solar studies. You can see the effect of sun and shadow over time. For example, it is possible to animate the sun over the course of an entire year to see the extent of light penetration and shadow cast by your building and other buildings in its context. This is an excellent communication tool for explaining the impact of your building on the site and can be used very early on in massing studies to make adjustments to orientation, placement, and form.

Any view can be animated to show the effects of the sun. To access this feature, use the Graphic Display Options dialog box and navigate to the Sun and Shadows Settings dialog box.

There you will find three tabs: Still, Single-Day, and Multi-Day. The default tab is Still, and the settings on this tab affect static views. The other two tabs are specifically designed for creating multi-image representations of the model over time (Figure 18.10).


FIGURE 18.10
Use the Single-Day and Multi-Day tabs to define time and time intervals for the animation.




Single-day studies Create single-day studies with the settings on the Single-Day tab. These settings will show the effect of sun on a specific day at various intervals (15, 30, 45, or 60 minutes). By setting the date and checking the Sunrise to Sunset box, you'll be able to animate the effect of sun on your model.

Multi-day studies The settings on the Multi-Day tab (Figure 18.11) are just like the settings on the Single-Day tab, but the interval is days, weeks, or months, and you can see the effect of sun over the course of an entire year.

FIGURE 18.11
Sun and shadows settings for a multi-day sun study.




Once you select either a single-day or multi-day setting, a new control will become available in the View Shadow flyout menu to help facilitate visualizing and generating the animation.



PREVIEWING A SOLAR STUDY

To preview the solar study, click the Animated Solar Study option; the following controls will appear on the Options bar:




You can use the controls to step through the frames of the animation and access the Sun and Shadows Settings dialog box. The animation will play slowly because the frames have to be redrawn one by one to recalculate the shadows. We do not recommend playing the animation using these controls, as it is very time consuming for Revit to redraw all these views. To get a feel for the final output, you need to export the view and see it play back at real-time speed in a video viewer.

EXPORTING THE ANIMATION

Once you've set the correct values for the solar study, you can export it and play it in a media player. To do so, go to the Application Menu and choose Export > Images and Animations > Solar Study. The Length/Format dialog box includes options to set file type, duration, size, and model graphics style (Figure 18.12). For better performance, drop the image size to something reasonable for a monitor (800 600, for example). As with the interactive preview, it will take Revit some time to process all the frames. The more frames, the longer the export will take, but the final result makes for compelling demonstration media. Revit also gives you the option to compress the video upon export.

FIGURE 18.12
Set the values for
your animation.




ANIMATED SOLAR STUDIES


Animated solar studies can track the course of the sun over the period of a day or at one time of day over a period of many days or months in an animated video format. These studies help us to better understand the impact of the sun on a building and of the building on the surrounding context. To set up an animated solar study, follow these steps:

1. Open the second perspective, Sun Study-West Facade.
2. Using the View Control bar at the bottom of the screen, open the Sun and Shadows Settings dialog box. Alternatively, you can choose the View tab and click the Settings button to reach the same dialog box.


- Choose the Multi-Day tab. You will notice that since you have set our location previously for the still study we did earlier, you don't need to set a new location for the project. Set the start date to **1/2/2009**, the end date to **12/28/2009**, the time interval to one day, and the time of day to 3:30 P.M. The dialog box should look like this:




- Clicking OK to exit the dialog box will give you a perspective with the sun located in a position to support the first date (1/2/2009) at the 3:30 time. If you go to the View Control bar and click the Shadow button again, you will notice a new option: Preview Solar Study.



- Choosing this tool highlights the view window and gives you a new set of tools in the Options bar, as shown here:



- The controls work the same as they do on your DVD player. Clicking the time and date button will take you back to the Sun and Shadows Settings dialog box. The other controls are there to set the frame rate and initiate playback. Playback time will vary depending on the size and complexity of your model and your processor speed.
- You also have the ability to export this animation to an AVI file. Go to the Application Menu and choose **Export > Images and Animations > Solar Study**, and you can set the dimensions of the image, the model graphic style, and the frame rate for your AVI. You can play around with the settings until you get the right proportion of size and time for each slide.
- Once you have begun the export, you can view the progress of the AVI at the bottom of the view window.



These types of sun and shadow studies are not designed to provide you with quantifiable metrics for the amount of daylight in a given space. However, they are a good, quick tool during the earliest design decision phase to help check your design assumptions regarding where, when, and how the daylight enters the space.

Tracking Recycled Materials and Other Sustainability Strategies Using Schedules

In this section, we will be reviewing how to leverage schedules to track sustainable design strategies. Including recycled content in your building design is only part of the solution. To document credits for LEED points, it is important to know how much recycled content is in the building.


Recycled Materials

In Chapter 17, we discussed maximizing the power of schedules by adding custom variables to the calculations. We did this by doing a basic cost analysis on the Revit model and calculating a square foot cost against the gross square footage of the building. It is possible to use this same method to track the amount of recycled materials used in the project.

In our project, we have decided to substitute a percentage of Portland cement with fly ash in all of the cast-in-place concrete. As a by-product of burning coal, fly ash will help count toward the recycled materials points we need for LEED accreditation. Based on a number of concerns, we have chosen to use 21 percent fly ash in our concrete. We can calculate this very quickly using a simple schedule:


1. Navigate to the View tab, click the Schedule button in the Create panel, and choose Material Takeoff from the flyout. Now, choose Multi-Category from the list of schedule types provided.
2. In the next dialog box, you will be asked to choose fields for the schedule. Choose the following fields and place them in this order:
Material: Name
Material: Volume
3. Clicking OK at this point would give you a list of all the materials in the project. Since we want only the concrete, select the Filter tab. Choose Material: Name and then Contains from the Filter By drop-down menu, and type **Concrete** in the Filter field (see Figure 18.13).
4. Now, you'll need to add another calculated value to tabulate the percentage of fly ash in the project. Click the Calculated Value button. Name the field **Volume of Fly Ash**. Change Type to Volume and enter the following formula: **Material: Volume * 0.21**. Another option is to create a separate parameter called Percent Recycled, and then multiply this value by Material Volume. This will allow the user to see the calculated value in the schedule, rather than hiding it inside the formula.

FIGURE 18.13
Filter the model materials for Fly Ash.



Remember, it is all case-sensitive, so make sure you type the formula properly. The finished dialog box should look like Figure 18.14. Click OK.

FIGURE 18.14
Use a formula to calculate the volume of fly ash.



- 5. On the Sorting/Grouping tab, check the Grand Totals check box.
- 6. Finally, on the Formatting tab, select Volume and change the alignment to Right. Select Volume of Fly Ash and change the alignment to Right. Also, check the Calculate Totals box. Click OK.

When the schedule is complete, you will get an up-to-date list containing all the instances of concrete in the building and a calculation showing how many cubic feet of fly ash each contains. This will all be totaled at the bottom of the schedule. As you can see, there are 6,898 cubic feet (CF) of fly ash so far in the project if we are using 21 percent recycled content (Figure 18.15).

Each of these schedules can be added to a template. Even if the percent of fly ash varies from project to project, you will have the basis for the schedule already created.

FINDING “CONCRETE” IN THE MODEL

Remember, by scheduling things within Revit, you can easily use the schedule to locate them. Simply select the element within the schedule view. In the Modify Schedules/Quantities tab, you’ll see a button to Highlight in Model; clicking this button will cycle you through all of the relevant views showing the element selected. This is true for any schedule.

FIGURE 18.15

You can see the total amount of fly ash in the schedule.


Multi-Category Material Takeoff		
Material Name	Material Volume	Volume of Fly Ash
Concrete - Cast-in-Place Concrete	258.04 CF	54.10 CF
Concrete - Cast-in-Place Concrete	210.20 CF	44.10 CF
Concrete - Cast-in-Place Concrete	239.44 CF	50.28 CF
Concrete - Cast-in-Place Concrete	86.89 CF	14.05 CF
Concrete - Cast-in-Place Concrete	604.91 CF	169.00 CF
Concrete - Cast-in-Place Concrete	230.04 CF	48.31 CF
Concrete - Cast-in-Place Concrete	600.80 CF	146.06 CF
Concrete - Cast-in-Place Concrete	86.00 CF	18.06 CF
Concrete - Cast in Place Concrete	272.33 CF	57.19 CF
Concrete - Cast-in-Place Concrete	4286.33 CF	900.13 CF
Concrete - Cast-in-Place Concrete	476.81 CF	100.13 CF
Concrete - Cast in Place Concrete	230.70 CF	49.45 CF
Concrete - Cast-in-Place Concrete	191.17 CF	40.14 CF
Concrete - Cast-in-Place Concrete	258.04 CF	54.19 CF
Concrete - Cast in Place Concrete	5109.22 CF	1072.94 CF
Concrete - Cast-in-Place Concrete	537.35 CF	112.04 CF
Concrete - Cast-in-Place Concrete	13.70 CF	2.88 CF
Concrete - Cast in Place Concrete	13.88 CF	2.91 CF
Concrete - Cast-in-Place Concrete	13.00 CF	2.91 CF
Concrete - Cast-in-Place Concrete	12.33 CF	2.59 CF
Concrete - Cast-in-Place Concrete	211.37 CF	44.30 CF
Concrete - Cast-in-Place Concrete	19.07 CF	4.17 CF
Concrete - Cast-in-Place Concrete	12.89 CF	2.71 CF
Concrete - Cast-in-Place Concrete	10.06 CF	2.30 CF
Concrete - Cast-in-Place Concrete	10.48 CF	2.30 CF
Concrete - Cast in Place Concrete	10.96 CF	2.30 CF
Concrete - Cast-in-Place Concrete	10.06 CF	2.30 CF
Concrete - Cast-in-Place Concrete	10.96 CF	2.30 CF
Concrete - Cast in Place Concrete	10.96 CF	2.30 CF
Concrete - Cast-in-Place Concrete	10527.22 CF	3080.72 CF
Grand total: 31		6898.13 CF

Window Surface Percentage vs. Room Area

We discussed concepts of sustainability earlier in this chapter and specifically the use of sun-shading devices to allow natural daylight into spaces but minimize the effects of solar gain at unwanted times of the day or year. Another way to keep out the sun is to simply minimize the amount of glazing on a given façade. There is a delicate balance between the amount of glazing on a façade and the amount of daylight that enters a space. In the ideal design, we want to maximize daylight but still be efficient with glazing. Again, north and south light is easier to control, the north particularly because it includes no direct sunlight. East and west light can be more challenging. One way to work toward the most efficient amount of glazing is to work directly with your mechanical engineer or energy modeler to calculate the ideal percentages of glazing for a given façade or cardinal direction. Once you have these goals, you will want to quickly calculate the percent of glazing versus wall area or room area. Revit can help you do this with the Room/Area Report (Figure 18.16).

One of the export commands available within Revit is Room/Area Report (go to the Application Menu and choose Export ➤ Reports ➤ Room/Area Report). If all the room objects are placed in a given floor in the model, this report creates an HTML file detailing how the areas for the rooms were calculated. The report lists in graphic and table format each room, its perimeter, and the triangulated areas within the room that generate the areas. If you choose the Settings option before you export the table, you can check a box to also report window area as a percentage of the room. This gives you the square footage of window area within the room as a percentage of the overall area of the room. This square footage percentage can also assist in the documentation you will need for LEED credit EQ 8.1 (for more information, see www.usgbc.org/leed).

FIGURE 18.16
Analytical views
of room area and
window area.



Energy Analysis

Energy analysis is a useful tool in estimating building life-cycle costs and is becoming more and more important to facility managers and owners early in the design process. The tool gives you the ability to predict building energy use. By making design changes to the model and running a series of energy analyses based on the various design iterations, you are able to estimate the building's loads based on the design schemes, thereby helping to minimize energy use and overall life-cycle costs.

In its current incarnation, Revit does not provide energy analysis. The software is primarily created for architects to model and document their designs; you'll need to use one of the third-party applications discussed in the following pages. At the same time, the design of a building involves not only its function but also its aesthetic and social implications and its environmental impact. Today, the focus on energy efficiency is becoming increasingly important to stakeholders involved with architecture. Owners and facilities managers alike are looking to get up-front data on predicted energy footprint and short-term and long-term costs and other information at the early stages of design.

Energy modeling can involve a complex set of analytical calculations, and entire careers are based on deriving accurate and predictable results. This type of analysis can encompass building energy use, daylighting, alternative power sources, computational fluid dynamics (CFDs), thermal gain, and carbon footprint, to name a few. Essentially, energy modeling allows you to understand the building from a more holistic, ecological point of view.

It is important to keep in mind that any value you get out of the Revit model with respect to energy analysis is only as useful as the information you put into the model. Good input will lead to good output.


There are a couple of applications that can be used in conjunction with the Revit architectural model for additional energy analysis data.

IES <VE>

IES <Virtual Environment>, or IES <VE>, (www.iesve.com) is advanced simulation software that provides analytical tools for energy, daylighting, computational fluid dynamics (CFDs), and a variety of other analysis features. Opening a Revit Architecture model in Revit, in the Modify Schedules/Quantities tab you'll see a button to Highlight in Model; you can link to Integrated

Environmental Solutions (IES) and get an estimation of the building's energy consumption based on rooms, location, and construction type (Figure 18.17). Revit allows you to export the whole model to IES so that a full-blown analysis can be performed.

FIGURE 18.17
A model as seen
in the Revit MEP
heating and cool-
ing interface.



In Revit 2010, you can install an IES plug-in for Revit Architecture. This allows you to get peak energy loads in the form of reports.

gbXML

gbXML, or Green Building XML (www.gbxml.org), was designed as a neutral file format to transfer the data required for an energy model into various analysis applications from a Revit model. This file format, while not quite an industry standard, has been quickly adopted by a number of leading CAD vendors and is one way to transfer design intent into an energy modeler without having to re-create the building form in another application. IES <VE>, for example, will import a gbXML file, but it will not have all the geometric and spatial data that you will have if you imported directly from Revit.

Exporting to gbXML

Exporting to gbXML is a simple, fluid process; one of the primary benefits of using this file format as a basis for your energy analysis is that it is easy to create. To begin, you need to set a few variables before you start the export.


1. There is a location in the Revit file to set some energy data parameters of the project specifically for the energy analysis. Navigate to the Manage tab and click the Project Information button. Then click the Energy Data button. In this simple dialog box (Figure 18.18), define the following project variables:

Building Type Such as office, residential, museum.

Postal Code The five-digit postal code of the project. This variable defines the building's global location for sunlight.

- Ground Plane** Where the ground level will be calculated.
- Shading Surfaces** This is a simple check box. Shading allows you to take into account sunshades and other exterior features in the gbXML model.
- Project Phase** Based on any phasing you have in your project.
- Sliver Space Tolerance** By default, this value is set to 1'-0". This specifies the tolerance for areas that Revit considers sliver spaces.
- Export Complexity** By default, this value is set to 'Simple with Shading Surfaces' but can be expanded based on the complexity of your model's geometry and inclusion (or not) of curtain wall and storefront wall types.

FIGURE 18.18 Set basic variables to establish some assumptions about the energy requirements for your building.



For our Foundation project, let's declare it as an office building with a 64105 zip code (Kansas City). The ground plane is at Level 1, Shading Surfaces is turned on, and we can leave the other variables at their defaults.

- Next, we will need to turn on the volume calculations within the model. By default, these are left turned off; turning them on and leaving them on can lead to a lot of overhead within the model. We recommend turning them on for the gbXML export, then turning them back off after the export has completed successfully. To turn on the volumes, choose the flyout under the Room & Area panel on the Home tab and click Area and Volume Computations. Choose Areas and Volumes in the dialog box.



- Now that you have set those variables, exporting is a simple process. Go to the Application Menu and choose Export ➤ gbXML. Revit will automatically begin calculating the export before you are given the option to save the file. The export will take a little time, depending on the speed of your computer. Once it's created, you'll have a small, compact file you can easily share with your mechanical consultant or upload directly into your energy analysis application.

Green Building Studio

The Autodesk Green Building Studio (www.greenbuildingstudio.com) is an online service that provides a simple energy analysis based on your gbXML file and some basic energy demand assumptions you provide. The results are reported in an easy-to-interpret web format with a lot of visual cues and graphics. The report takes into account TMY2 (Typical Meteorological Year 2) data, which is historical data of sunny versus overcast days; regional utility demands and costs; and climatic data. It will return information such as the predicted annual utility costs, building life-cycle costs, and carbon footprint (see Figure 18.19).

FIGURE 18.19
Example from
Green Building
Studio showing the
estimated energy
cost of the building.

General Information		Location Information	
Project Title: Foundation		Building: KANSAS CITY, MO 64105	
Run Title: Foundation-13.xml		Electric Cost: \$0.057/kWh	
Building Type: Office		Fuel Cost: \$1.286/Therm	
Floor Area: 52,697 ft ²		Weather: TMY2 weather for Kansascity, MO	
Estimated Energy & Cost Summary		Electric Power Plant Sources†	
Annual Energy Cost	\$35,642	Fossil:	80%
Lifecycle* Cost	\$485,441	Nuclear:	19%
Annual CO ₂ Emissions		Hydroelectric:	0%
		Renewable:	1%
		Other:	0%
		† BASED ON US EPA EGRID 2006 DATA (2004 PLANT LEVEL DATA).	
Electric†	743,613 lbs		
Onsite Fuel	167,846 lbs		
H3 Hummer Equivalent	41.4 hummers		

This is a service for basic energy calculations, and there is a nominal charge for more developed results. You must download a small client application that will help coordinate the upload and calculations of the gbXML files. You can download it from <http://usa.autodesk.com/adsk/servlet/index?siteID=123112&id=11261770>.

Even if you do not understand the results from an energy analysis application such as this, it can always be used as a comparative tool. Take, for example, the large sunshading device on this project. At some point during the design, we will undoubtedly find it necessary to discuss with our client how much energy something like this can save the project. Within Revit, this element can be set to a design option and we can run an energy simulation using Green Building Studio (GBS) with and without the sunshade. Figure 18.20 shows the building model with and without the shades.

By comparing the annual energy costs from the GBS analysis, we can quickly see a 68 percent increase in energy savings over the course of a single year (Figure 18.21). Over the lifetime of this building, that can lead to a substantial energy savings for the client and more than offset the initial costs of the shading device.

FIGURE 18.20
The Foundation
model with
and without
the sunshades.




FIGURE 18.21
The energy
analysis for both
designs shown in
Figure 18.20.

General Information Project Title: Foundation Run Title: Foundation.xml Building Type: Office Floor Area: 52,957 ft²	Location Information Building: KANSAS CITY, MO 64108 Electric Cost: \$0.057/kWh Fuel Cost: \$1.295/Therm Weather: Kansascity, MO (TMY2)
Estimated Energy & Cost Summary Annual Energy Cost: \$31,996 Lifecycle* Cost: \$435,790 Annual CO₂ Emissions Electric†: 329.2 tons Onsite Fuel: 76.3 tons H3 Hummer Equivalent: 36.9 Hummers Annual Energy Electric: 264,560 kWh Fuel: 13,154 Therms Annual Peak Electric: 999.3 kW	Carbon Neutral Potential¹ (CO₂ Emissions) Base Run: Requires Corporate Acct. & v.3+ run Onsite Renewable Potential: NA Natural Ventilation Potential: NA Onsite Fuel Offset/Biofuel Use: NA
Energy & Carbon Results US EPA ENERGY STAR Water Usage PV Analysis LEED Daylight Weather 3D VRM View	
General Information Project Title: Foundation Run Title: Foundation 1.xml Building Type: Office Floor Area: 53,017 ft²	Location Information Building: KANSAS CITY, MO 64108 Electric Cost: \$0.057/kWh Fuel Cost: \$1.286/Therm Weather: Kansascity, MO (TMY2)
Estimated Energy & Cost Summary Annual Energy Cost: \$46,529 Lifecycle* Cost: \$639,168 Annual CO₂ Emissions Electric†: 684.0 tons Onsite Fuel: 70.3 tons H3 Hummer Equivalent: 68.6 Hummers Annual Energy Electric: 549,811 kWh	Carbon Neutral Potential¹ (CO₂ Emissions) Base Run: Requires Corporate Acct. & v.3+ run Onsite Renewable Potential: NA Natural Ventilation Potential: NA Onsite Fuel Offset/Biofuel Use: NA

Daylighting

Daylighting is an important part of designing sustainably. Daylighting is the use of natural light for primary interior illumination. This reduces our need for artificial light within the space, thus reducing internal heat gain and energy use. Direct sunlight, once it enters the building, is not only light but heat, and that additional heat will need to be taken into account in your energy analysis.

Natural light is the highest quality and most efficient light source available today, and the source is free.

An effective daylighting design relies heavily on the proper building orientation, massing, and envelope design topics we have already discussed. The proper combination of these strategies allows us to optimize our building's use of natural resources and minimize our dependency on artificial lighting. A fully integrated daylighting system can enhance the visual acuity, comfort, and beauty of a space while controlling external heat gain and glare.

Not only does natural daylight help to light our workplaces and homes, but it also supplies us with a connection to the outdoors. Providing occupants with natural light and ties to the outside has been proven in a number of cases to have a positive effect on human health and productivity. Studies have shown that buildings with good daylighting design have positive effects on their occupants, such as increased productivity levels, low absentee rates, better grades, retail sale increases, improved dental records, and healthier occupants.

Recent releases of Revit have incorporated some tools that can help us do daylighting analysis. While Revit itself cannot perform the actual analysis, we can set up our Revit model to quickly and easily be imported into 3ds Max Design, which can perform the actual analysis. This export process will accurately take all of the Revit model geometry and materiality, if set up correctly. After that, the analysis is quick and easy with 3ds Max Design.

Recently, 3ds Max Design has revised its analysis package (which uses the Radiance engine), making it acceptable for documentation for LEED point 8.1. Since this book is about Revit and not Max, we will cover only how to prepare your model for daylighting analysis. For more information on how to perform the analysis in 3ds Max Design, visit:

<http://www.autodesk.com/3dsMaxDesign>

Quality Control Measures

Before you can jump into daylighting, there are a few quality control measures that need to be taken within Revit. Unless you perform these checks, you can't be sure that the lighting analysis you receive from 3ds Max is accurate. Although some of these things might seem simplistic and almost unnecessary to mention, it's a good idea to double-check your model:

Remember: garbage in, garbage out Make sure you have modeled the project properly and accurately. An improperly modeled building will lead to inaccurate results.


Mind the gap Make sure there are no "holes" in the project. Verify that all the walls meet, that the roof is connected to the top of the walls, and that there isn't any place in the project where light can enter that is not intentionally left open. Unintentional openings can let in light that will taint your daylighting.

Live in a material world Make sure that the elements within the Revit model have the proper materials applied to them. Assemblies and elements within the model that do not have a materiality will more than likely have improper light reflectance, which can change your lighting output.

If you have not decided on a material for a given surface, here are some guidelines for material reflectance:

- ◆ Floors: 20 percent reflectance (0.20)
- ◆ Walls: 50 percent reflectance (0.50)
- ◆ Ceilings: 85 percent reflectance (0.85)


You can access the dialog box shown here by opening the material's properties window or by choosing the Manage tab and clicking Materials.




Achieve that glazed look. Make sure the glazing material is set properly using Promaterial Glazing (do *not* use the material Glass). The glazing material has some specific presets in 3ds Max that allow more accurate analysis. There are a number of different glass types in Revit and even more if you are downloading families from RevitCity.com or other sources.

Make sure all your glazing is consistent and accurate. If not, your results will not be valid. The following graphics show the glazing settings within the materials in Revit and demonstrate some of the inconsistencies in the glazing properties noted in the various colors of the glass.





Finally, you will need to identify the number of planes your glazing has in Revit. While this can be done later in 3ds Max, it's quicker to set it in Revit before the file is exported. Glazing modeled in Revit is typically represented by one plane. This can be beneficial for the modeling process as it will expedite the screen render time. However, when daylight enters a building, the materials and layers of the actual glazing can dramatically affect the light levels. The image that follows shows a typical glazing section in Revit. In reality, this would be shown with two or three panes of glass. To change this in Revit, simply change the material setting (on the Manage tab, click Materials) for the glazing. The example shown here also reveals the number of glazing layers. Choose one for each pane of glass. For example, if you are using a double-glazed unit, set the number to 2.



Once the materials are set within Revit, go to any 3D view. Make sure all the furniture is turned off (it will impact the lighting analysis and is not needed). Then go to the Application Menu and choose Export > FBX. This will put the Revit model geometry and its materiality into a file format readable by 3ds Max.

Now—at last—you are ready to import your model into 3ds Max Design for daylighting.

The Bottom Line

Incorporate a sustainable approach from the very beginning of a project development. Sustainability is quickly becoming a core approach to any design. Learn to leverage the Revit model for a more holistic approach to sustainability.

Master It BIM is also a computational database that can report information about the virtual building. The important thing about a sustainable approach is to know which questions to ask and to ask them at the right time. What is a strategy for doing this?

Use Revit to create sun studies. Understanding the sun's effect on a building is paramount to sustainable design.

Master It How can you use the tools within Revit to produce still and animated solar studies from interior and exterior views in order to understand shading and the sun's effect on the building and space?

Track recycled materials and other sustainability strategies using schedules. Keeping track of project goals is an important part of any project process. By using the schedules and other tools in Revit, you can also track key sustainability goals.

Master It Tracking recycled material usage is key to LEED credits and sustainability. Create a material schedule that tracks recycled content volume for concrete.

Analyze daylighting. Understanding daylighting and its effects within the built environment is a critical part of design and helps with LEED credit 8.1.

Master It Make your designs more sustainable by using the model geometry for daylighting analysis

Chapter 19

Annotating Your Model

No set of documents is complete without annotations to describe the drawings. Even when you are working in BIM and have a digital parametric model, you will need to provide annotated documents by adding dimensions, tags, text, and notes to the drawings, thus making communication of the design to the owner, contractor, and design team clearer and more informative.

In this chapter, you'll learn to:


- ◆ Annotate views
- ◆ Use schedule keys
- ◆ Leverage tags
- ◆ Understand shared parameters
- ◆ Add text and keynotes

Annotating Views

In any set of documents, showing geometry alone isn't sufficient to communicate all the information a builder or fabricator needs in order to construct the building. Annotations assist in clearly describing your model for others to read and understand. Tags, dimensions, text, and keynotes all need to be added to the drawing to clearly and concisely guide construction or fabrication. Revit provides a rich set of tools for accomplishing these tasks.

Text, dimensions, and tags are placed in the views, in relation to real elements, not on the sheet. This allows you to annotate a view at any point in the process, before or after the final (sheet) document has been created. Figure 19.1 shows a floor plan annotated in a drawing set.

FIGURE 19.1
The annotated
floor plan.



Creating and Annotating Rooms


Rooms help define areas and spaces within the Revit model. Even if a room represents the empty space between boundaries of physical elements, it is still considered an *element* in Revit, similar to a door, window, or wall. Rooms have properties and can be created, moved, deleted, modified, queried, and scheduled like every other element in Revit. Rooms can also be used for energy calculations and are critical to gbXML export. For more information on this feature, see Chapter 18, “Evaluating Your Preliminary Design: Sustainability.”

You need bounding elements to define a space in which you can place the room element and thus generate a room that can calculate its area and volume. Bounding elements for rooms include roofs, walls, floors, columns, and room separation lines.

These elements all have an instance property called Room Bounding that determines whether that element participates in calculating room extents. By default, all these elements are set as room bounding. If you do not want an element to affect the calculation of room areas and volumes (for example, toilet partition walls are usually not deducted from the area and should be marked as non-room bounding), select it and clear the Room Bounding option in the Element Properties dialog box (shown checked in Figure 19.2).

FIGURE 19.2

A checked Room Bounding parameter makes a wall room bounding.



Every model element in Revit can be tagged, including rooms. The room tags report information stored in the room element properties. This means you can have the tags report anything about the room based on parameters of the room: name, number, area, finish, and so on. Rooms are separate elements from room tags, which, like all other tags used in Revit, are annotations that can report any information stored in the building elements they are associated with. Door and wall tags, for example, report values of the door or wall elements. Room tags do the same.

Even when rooms exist in a view, they are not visible in the view by default, but if they are tagged, the tag is visible, so it can be easy to confuse the tag with the element. As with other elements in Revit, the tag can be placed automatically when adding a room using the Tag on Placement button on the Options bar. Clearing this box means that when you create a room, no room tag will be added for that room.

In such cases, you can add room tags later in the project, individually for each room or for all rooms that are untagged at once. This means Revit can simultaneously tag any existing rooms in the active view and places the tags in the center of the X formed by the room element. You need to have created the room objects in the project first; then, wherever a room element is found, a room tag is placed in the room. This tool does not create rooms for you if they don't exist.


It's important to note that the tags only report the properties of the room. Deleting the tag does not delete the room element or the information shown in the tag.

You can insert rooms by clicking the Room button on the Home tab. To insert a room, you must be in a plan view of the model, so choose one of the plan views and select the Room tool from the Room & Area panel of the Home tab. When you select this tool, all of the rooms already placed within that view will highlight in transparent blue and an X will appear across the area that bounds that room (Figure 19.3).

☒ Tag on Placement




FIGURE 19.3
Placing a room.



The X is a visual aid to show you where room elements already exist within the model. As you can see in Figure 19.3, we are missing a room element in Room 120. To place a room in that space, with the Room tool selected, click in the white area in the middle of the space to place a room element. A blue box appears and a room tag is automatically placed in the room. The Room tool remains active after the placement of each room and allows you to keep placing rooms in sequence. You'll notice that Revit auto-increments each room tag as you place the rooms. If you change a room number, the number of the room you place next is based on the number of the last room you placed.

Once a room is placed, it extends itself to the boundaries of the space in which it is placed and becomes an object in the model. As we mentioned, the room tag is a separate element and can be removed without removing the room element itself or any of the information you might have added to the room element. In fact, deleting the tag from a room will prompt a warning message alerting you that the room element still exists (see Figure 19.4). In a schedule, all these rooms will continue to show up with their proper room names and any other information you've added, regardless of whether they have been tagged.

FIGURE 19.4
Deleting a
room tag.




Once the tag has been removed, you can still select the room element. By default, the room element is not visible within Revit. This is intentionally done to avoid cluttering up precious space within a view. To select a room for further editing or to access its properties, drag the mouse over the space where the room is placed and click when the room element highlights. Click in an area close to one of the crossing diagonal lines to select the room.

Here are some other features critical to rooms that you will want to be aware of as you begin placing them in your model:

- ◆ Room bounding elements need to create a closed loop. Placing a room in an unenclosed area generates an error message like the one shown in Figure 19.5.

FIGURE 19.5
An unenclosed
room error.



If a room that reports that it is unbounded is not resolved and is left unbounded in the model, it will not properly report in the schedules. There are a few ways to resolve an unbounded room:

- ◆ If you are still in the midst of design, simply finishing the design may give you the walls or other bounding elements you need to complete the enclosure. Once the room is properly enclosed, the room element will recognize this and dynamically stretch to fill the room
- ◆ You can delete the room if it has been incorrectly placed. If you decide to remove a room, you must delete the room element itself, not just the room tag
- ◆ You can use the Room Separation lines tool located in the Home tab, under the Room & Area panel, when expanding the Room tool, which lets you draw a boundary and create room boundaries to define the edges of the space and close the areas where the room leaks

Revit will tolerate a small gap in room boundaries such as walls that don't quite meet or Room Boundary lines that are not quite drawn all the way across a room. In that case, the error message "Small gaps will be ignored by room boundary calculation" will not appear.

- ◆ Room elements must not overlap. Revit does not accept overlapping rooms and will report an error if this occurs. You may come across this issue in any of three ways:
 - ◆ First, you might mistakenly attempt to place a room in a space that already has a room element. If this occurs, Revit will alert you to the issue by showing you both room elements in the space and an error message asking what you'd like to do (see Figure 19.6). Clicking OK in this dialog box will leave both rooms in place. Clicking the Delete Room(s) button will remove the most recently placed room element
 - ◆ The second way this can occur is if you remove a wall or other bounding element between two rooms. Revit will give you the same warning and ask how you would like to resolve the problem (see Figure 19.7)
 - ◆ A third way rooms can overlap is when the height of a room extends into the bounds of another. If a room extends vertically into a room on the next floor, a similar warning message will appear. To view the conflict, you will need to go to section view and check the room extents. It is important to understand that rooms can be volumes with 3D dimensions. Room volumes are covered in more detail in the section "Area and Volume Computations" later in this chapter

FIGURE 19.6
Placing one room
within another.





FIGURE 19.7
Overlapping
rooms.



Room Separation Lines


So, what happens when you need one room to end and another to begin and you don't have a wall in between? For example, you might want a room to end at the end of a corridor that opens to an entry space, or you may have an open living room and dining room not separated by a wall.



For these conditions, use the Room Separation Line tool located when expanding the Room tool in the Room & Area panel of the Home tab. This tool allows you to draw lines in plan that will act as bounding elements.

Room separation lines show in plan views as distinctive green lines (see Figure 19.8). You can turn these lines on or off in the Visibility/Graphic Overrides dialog box, or by right-clicking and hiding the category using the context menu.


FIGURE 19.8
Room separation
lines.




Room separation lines will print in the plans if you leave them visible. If they are turned off, they will still maintain their room boundaries—but just remember they are there! “Out of sight, out of mind” can cause problems later when you move walls and the rooms seem to react in strange ways; so if you do decide to turn off the visibility of room separation lines, make a note to yourself about it and turn them back on after printing.

ADDING A ROOM SEPARATION LINE

In our Foundation project, there was a room named Corridor 127 that needed to be separated into a corridor and an entry area because they had slightly different finishes in the finish schedule. We used Room Separation lines to divide the spaces.



Drawing a room separation line from the stairwell across to the wall created a boundary, allowing a new room to be added named “Entry 139.” In the following view, you can see where the room element ends without requiring us to create a wall to divide the space:



Selecting Rooms


You can select rooms in one of two ways: graphically or from a schedule table.

GRAPHICAL SELECTION

When hovering your cursor over a room object, you will notice that the room object shows up and is represented with its boundary and two diagonal crossing lines, as shown in Figure 19.9.

FIGURE 19.9


Graphic representation of a room object.



The two diagonal lines might seem strange at first, but they are useful for selecting rooms. Without them, the room element could be selected only at its boundaries—but as those are coincident with many other elements (walls, floors, windows, etc.) the selection is quite tedious. The diagonal lines highlight when the cursor moves over them, so you can select the room (see Figure 19.10). These lines are a subcategory of the room element, and if you wish to see them all the time in the view and not just when hovering over them with the mouse or upon selection, you can turn on the Reference subcategory using the Visibility/Graphic Overrides dialog box. From that point on, all available room elements in your project will be graphically visible. When the Tag on Placement option is checked, your room tag is always placed at the intersection of these two diagonal lines.

FIGURE 19.10

A selected room element.



Once you've selected a room element, your cursor turns into a move icon and lets you move the entire room somewhere else if needed. When a room is selected and you move it, it automatically takes the extents of the new space. In principle, you are not moving the geometry of the room but you are displacing the room information and assigning it to another space. Moving a room allows you to take all of the data you've entered for the room (wall finishes, ceiling, floors, and so on) and relocate rather than retype it. The same is true for copying a room into a new space.

The graphical room selection can occur in both plan and section views. (Room selection in 3D views is not possible.) You can see, select, change the properties of, and even manipulate the extents of rooms in section views now. When you select a room in section view, two sets of editing grips appear that allow you to manipulate the base and top extents of the room by dragging.


SELECTING A ROOM FROM A SCHEDULE TABLE

To select rooms from a schedule table, highlight the room within the schedule while in the schedule view. Then click the Show button on the Modify Schedule/Quantities context menu.

Rooms and Room Tags

When you select one of the diagonal or boundary lines of a room, you are selecting the room element and can access its properties. When you select the room tag, you are selecting the tag of that room and can access or change the properties of the tag.

There is a difference between using the Move tool when a room is selected and using it when a room tag is selected. When you select a room tag, you are moving the tag around in the room or outside the room: with small spaces, a tag often needs to be taken out of the space the room tag describes because it doesn't fit inside (remember to select the Leader option first). The most common example is a restroom. When you attempt to move the tag outside of the room it is associated with, the tag displays a question mark and you get this warning message:



If you select the tag that is outside the room, a button appears in the Modify Rooms contextual tab called Show Related Warnings. It gives anyone who later joins the design team, and who isn't aware of why the tag shows a question mark, the ability to understand the error.

To fix the error and clarify which room the tag is associated with, you can use the Leader option on the Options bar. This connects the room and the tag with a line, and it displays the correct room number and name, which will help you understand the relationship between the tag and the room in the model to which it belongs. Figure 19.11 shows the room tag with the leader line checked.

Rooms in Section Views


While you can also tag rooms in a section view, you will not be able to create new room elements in a section view. You can create rooms only in plan views.

VOLUME CALCULATION METHOD DOES NOT AFFECT HOW VOLUMES ARE CALCULATED

Volumes are always calculated up to the wall finish, regardless of the chosen calculation method.

FIGURE 19.11

(A) A room tag doesn't fit well in a small room. (B) Dragging the room tag outside the room it is associated with will turn the tag's content into a question mark (?). (C) The tag leader is activated on the Options bar, so the room tag connects with the room it is associated with and displays its information.



Room Properties

Like all other elements in Revit, rooms have properties. By selecting the room element and clicking the Properties button, you can see the room properties that are available. These properties can be scheduled, displayed in room tags, or used to color-code a floor plan or section with a color fill scheme. The parameters are divided into sections to help organize the information:

Level Reports the level on which the room has been placed.

Upper Limit Defines the top level of the room. For example, if you have a double-height space (like an open atrium), you might want the upper limit to be more than one floor high so the entire space is treated and scheduled as one element. By default, this is set to be the same as the level on which the room is placed so that you define the actual room height as an offset of Level.

Limit Offset Defines the height of the upper limit of the room relative to the Upper Limit setting. This function is critical for volume calculations and gbXML exports. There are some settings that need to be addressed to get accurate results from gbXML exports:

- ◆ Limit Offset needs to coincide with the bottom of the ceiling plane above for any given room on floors below the roof line
- ◆ Limit Offset can exceed the top of the roof for rooms that are on the uppermost floor
- ◆ Rooms cannot overlap vertically for accurate gbXML exports. This means the upper limit of a room cannot encroach into the bottom of the room above it

Base Offset Defines the distance at which the lower boundary of the room is calculated, measuring from the base level that itself is defined by the Level parameter. A positive value of the offset sets it above the base level, a negative below. Zero value is set by default and equals the base level.

Area, Perimeter, Unbounded Height, and Volume These are noneditable fields that report the metrics of the room element. We will review how these numbers are calculated in the next section.

Identity Data This section includes identity information about the room. You can manually add data using these parameters and it will show up in tags. If you're using a color fill scheme, it will also be used to color-code the plan.


Phase This is a noneditable field that reports the phase in which the room was created. Remember that once you place a room you cannot change the room's Phase property (unlike geometric elements). If you need to move the room to another phase, you'll have to re-create it in that phase.

Area and Volume Computations

You can set different rules that dictate the automated calculations of area and volume for room elements. The selection of available rules can be found in the expanded panel of the Room & Area panel on the Home tab, by clicking on Area and Volume Computations. The resulting dialog box, shown in Figure 19.12, gives you the option to select from a number of area calculation schemes by relocating the boundary element of the rooms.

It is important to note the difference between room areas and area plans. *Area plans* follow different rules and treat exterior and interior walls differently. The Area Plans tool places areas automatically in the model, once the Area Plans function is initiated. Room elements have to be manually added in each space within the plan or design, and the rules that are set to define them apply to all the walls.

FIGURE 19.12
Area and Volume
Computations
dialog box.



When calculating room area and volumes, you can choose among the following boundary locations, resulting in different calculations:

- ◆ At wall finish
- ◆ At wall center


- ◆ At wall core layer
- ◆ At wall core center

In addition to calculating room areas, Revit can calculate room volumes. This feature is not enabled by default since volume computation can negatively affect the overall performance of Revit. You can decide at any time to activate the volume computation. This option is available in the Area and Volume Computations dialog box by checking the Areas and Volumes option in the Volume Computation group. We recommend enabling this option only when you need to create or print schedules or other views in which volume computation needs to be visible (such as gbXML exports). How much the volume computation affects the performance depends on the size and complexity of your model and your processor speed, but the general rule is to follow our earlier advice and activate it only when needed.

Here are some rules that you should be aware of when activating room calculations:

- ◆ Every room can have an independent theoretical room height that you define using the Limit Offset room property. This is the height used for calculating room volume if the actual height of the ceiling, floor, or roof above it is higher than the applied height of the room (see Figure 19.13)


FIGURE 19.13
The Room Offset (bounding box) is set to lower than the ceiling height, and the displayed room volume is 214.72m^3 .



- ◆ If the room height is greater than the height of the existing ceiling, floor, or roof, then the height to the first architectural element the room object hits is used to calculate the volume of the room (see Figure 19.14)

FIGURE 19.14


The bounding box is set to 4100mm (above the ceiling). The tag displays 279.14m^3 , which means that the volume was calculated taking a room height only up to the ceiling as a value.



Note that the room height can begin to cause other problems if it extends into the room on a floor above or below, even if the room element does intersect an architectural element, as noted previously (see Figure 19.15).


FIGURE 19.15

A change in the room height doesn't have any effect on the room volume calculation unless it hits the floor or ceiling above or below. (A) Computational height is set to the standard 1200mm. Parts of the volume are missing in the calculation. (B) Change the computational height to floor level for the correct computation.



Usually a room height is set to 8' (3m); so, depending on the default floor-to-ceiling height, it will often not be the real height of the room. You can verify that easily in section, when hovering over and selecting the room element. Adjusting the room height to the actual height of the space is easy in Revit 2010: you can graphically pick the room limits in section and adjust the height, as shown in Figure 19.16.

FIGURE 19.16
 Arrow grips at the base and top limits of a room element allow you to graphically manipulate the height of a room. (A) Default room height; (B) adjusted room height.



CALCULATING VOLUMES OF ROOMS WITH VARIABLE WIDTHS

Revit Architecture uses the perimeter of the room at the computation height when computing the room area and volume. The computation height is a type property of the Level family and can be changed any time. By default, it is set to 4'-0" (1200mm).


You can see the computation height graphically when you select a room element in section: it is represented with a dotted line across the lower part of the room (Figure 19.17).

To view or change the computation height, select a level line in section or elevation view and access its type properties, as shown in Figure 19.17.

For buildings with vertical walls, the room computation is straightforward, as explained earlier. However, if a building includes sloped walls, you may need to adjust the computation height to achieve more accurate room areas and volumes.

The typical case would be when working with rooms that are bound by nonvertical walls. Having the perimeter calculated at a height of 4' (1.2m) would result in omitting portions of the floor area. To fix this, you have to adjust the computation height to be close to the floor plane.


FIGURE 19.17
 Computation Height is a type property of the Level family.



Changing the computation height instantly affects the room perimeter and allows more accurate computation of rooms with variable width. An example of the calculation of the room area and volume is shown in Figure 19.18.

FIGURE 19.18


Changing the computation height allows for more accurate computation of rooms with variable width. (A) Computational height is set to the standard 1200mm. Parts of the volume are missing in the calculation. (B) A change of the computational height to floor level allows for the correct computation.



In general, Revit 2010 has brought some improvements in the calculation of volumes: the computations are now more flexible in adjusting to nonorthogonal room sizes and volumes (Figure 19.19). Revit 2010 can correctly calculate rooms with nonhorizontal top limits. The room element adjusts its shape to the shape of the space it calculates.


FIGURE 19.19

The room element adjusts its shape to the shape of the space it calculates.



When the volume calculation is off, the room in section appears as if it doesn't recognize the room boundaries (Figure 19.20A); when the room volumes are activated, the room shape adjusts to fit the shape of the space (Figure 19.20B).

FIGURE 19.20
Volume calculation
(A) off; (B) on.



If room bounding elements narrow as they rise, Revit calculates volume properly (Figure 19.21). If, however, bounding elements slope in a way that makes the room widen toward the upper limit, Revit ignores the side spaces when calculating the volume (Figure 19.22).

FIGURE 19.21
Section view of
a room: If room
bounding ele-
ments narrow as
they rise, Revit
calculates volume
properly.





FIGURE 19.22


Section view of a room: If room bounding elements widen as they rise, Revit calculates volume incorrectly.



Finally, if a room-bounding element does not reach the upper boundary of the room, the space above the element may not be included in the room volume (Figure 19.23).

FIGURE 19.23

Spaces above bounding elements that do not extend to the limits of the room will be ignored by the room calculation.



Using Schedule Keys

Once you populate your model with rooms and begin adding information to each room about its department and finishes, you'll most likely discover that information about rooms tends to repeat. Representing this information will be useful when you're generating room and finish schedules. In previous chapters, we discussed ways to report the information in those elements using the schedule functionality. But what if you want to define a common set of parameter values that can be shared across many rooms? For instance, if you are working on a large office project, doing a room finish schedule that lists individual rooms might be unnecessary if many of the rooms share identical finishes. For these situations, a specialized schedule called a *schedule key* can save time. Schedule keys can report any number of values that repeat across similar elements.

Creating a Schedule Key

Imagine the time it would take if you had to manually enter all your finishes in each schedule in each project! Schedule keys are a big time-saver and ensure consistency.


Since we have already added rooms to the Foundation model, let's make a room finish schedule using a schedule key for the project. To do this, we need to generate two schedules. The first

one defines the *room styles* by using what is called a key name. The second schedule links our room styles to the rooms themselves.

Let's begin with the room style schedule. On the View tab, choose Schedule ► Schedule/Quantities. The same dialog box you use when making any schedule appears. This time, however, you are going to choose some different values.


Choose Rooms from the list on the left, select the Schedule Keys radio button (see Figure 19.24), and click OK.

FIGURE 19.24
Selecting a
schedule key.



The next dialog box should look familiar (Figure 19.25). It is basically identical to the Schedule Properties dialog box (in fact, it has the same name), but one tab is not included in the dialog box: the Filter tab.


FIGURE 19.25
Making a
schedule key.



When you select the Fields tab, you will notice that one of the values is already on the right side to be included in our schedule: Key Name. Now you want to move the following values from the left to the right (they've already been moved in Figure 19.25):

- ◆ Floor Finish
- ◆ Wall Finish
- ◆ Base Finish

The remaining tabs in this dialog box are identical to the dialog box for other schedule types. For more information on formatting or changing the appearance of a standard schedule, see Chapter 17, “Fine-Tuning Your Preliminary Design.” Once you have these values selected, click OK. A blank schedule like this one appears and is available for you to fill in with finish values:




Click the New button on the Modify Schedule/Quantities context menu to begin to add standard room finishes to the schedule. In this table, the key name is important because it will be the link between the two schedules. Using the New button, add the following room styles to your table: Key Name, Floor Finish, Wall Finish, and Base Finish.

Room Style Schedule			
Key Name	Base Finish	Ceiling Finish	Floor Finish
Lab	Ceramic	Paint	Tile
Office	Wood	Paint	Carpet
Restroom	Plastic	Paint	Tile

Once the schedule is complete (you can always add to it or modify it later), you need to create the finish schedule to be used in the construction document sheets. Again, select Schedule/Quantities from the View tab and select Rooms from the list. This time, leave the default value Schedule Building Components selected (Figure 19.26) and click OK.

FIGURE 19.26
Making the finish schedule.



Again, you’ll see the standard Schedule Properties dialog box. Add the following fields to the Schedule fields list (the right side) in this order and click OK:

- 1. Number
- 2. Name

- 3. Room Style
- 4. Floor Finish
- 5. Base Finish
- 6. Wall Finish
- 7. Area

The schedule that shows up will be a list of the rooms in the project, sorted by room number with (none) set as the value for Room Style. The Floor, Base, and Wall Finish columns will all be blank. Some sample lines are shown in Figure 19.27.

FIGURE 19.27
The finish schedule.

Room Schedule						
Number	Name	Room Style	Floor Finish	Base Finish	Wall Finish	Area
104	DAY CARE	(none)				2022 SF
105	OFFICE	(none)				96 SF
106	OFFICE	(none)				120 SF
107	Room	(none)				200 SF
108	JANITOR	(none)				33 SF
109	VESTIBULE	(none)				37 SF
110	ELECTRICAL RM	(none)				37 SF

From here, adding values and finishes to the rooms by room style is fairly easy. Once you select the (none) value in the Room Style column, you will be given the option to select from the drop-down list of values we defined in the room style table (Figure 19.28).

FIGURE 19.28
Selecting a room style.

Room Schedule						
Number	Name	Room Style	Floor Finish	Base Finish	Wall Finish	Area
104	DAY CARE	(none)				2022 SF
105	OFFICE	(none)				96 SF
106	OFFICE	(none)				120 SF
107	Room	(none)				200 SF
108	JANITOR	Common Areas				33 SF
109	VESTIBULE	Conference Room				37 SF
110	ELECTRICAL RM	Office				37 SF
111	MAIL RECEIVING	Restrooms				505 SF

Selecting a value from this list automatically fills in the values for the Floor Finish, Base Finish, and Wall Finish columns to match the values we defined in the previous schedule. As you modify values in the room style schedule, they are dynamically updated in this schedule, adding consistency and predictability to your workflow (Figure 19.29).

FIGURE 19.29
Adding values to the schedule.

Room Schedule						
Number	Name	Room Style	Floor Finish	Base Finish	Wall Finish	Area
104	DAY CARE	(none)				2022 SF
105	OFFICE	Office	Carpet	Rubber Base	Paint	96 SF
106	OFFICE	Office	Carpet	Rubber Base	Paint	120 SF
107	ENTRY	Common Areas	Stone	Stone	Paint	200 SF
108	JANITOR	(none)				33 SF
109	VESTIBULE	(none)				37 SF
110	ELECTRICAL RM	(none)				37 SF
111	MAIL RECEIVING	(none)				505 SF
112	RESTROOM	Restrooms	Ceramic Tile	Ceramic Tile	Ceramic Tile	43 SF
113	RESTROOM	Restrooms	Ceramic Tile	Ceramic Tile	Ceramic Tile	43 SF


Leveraging Tags

Tags are text labels for elements such as doors, walls, windows, rooms, and a host of other objects that architects typically need to reference in a set of drawings. In Revit, tags are intelligent, bidirectional symbols that report information stored in the properties of an element. A value can be directly edited from the tag; likewise, editing an element's properties affects the tag.

A wall tag, for example (Figure 19.30), can display the wall type that is set in the properties of the wall itself, but it can show much more information, such as the wall's fire rating or area.

FIGURE 19.30

A wall tag.



Loading Tags

Revit comes with a variety of tags that can be customized to meet your office's graphic standards or needs. The preloaded tags in the default templates cover many common requirements but are by no means exhaustive.

Every category of a family can be tagged, and you can load multiple types of tags for each category. Tags are loaded like any other family or component in Revit. From the Insert tab, select the Load Family button, Load Family, and browse to the tag you want to add to the project.


If you have designed some tags that you use frequently in your project, you should load them in your office template.

Placing Tags


Tags can be automatically placed during the creation of an element (using the Options bar setting Tag on Placement) or can be placed later. You can insert tags by clicking the Tag button on the Annotate tab (see Figure 19.31).

FIGURE 19.31

Tagging options by category, multi-category, or material.



During tag placement, the Options bar lets you position a tag in several ways.



When tagging elements, if you don't have the appropriate tag for the element you're trying to tag, click the Tag button. In the resulting dialog box, you can load additional tags without

having to cancel the command and go back to the Load Families tool. If you click the Tag button but don't have a tag of that category loaded for the element you want to tag, you'll be prompted to load one.

Tags can have a horizontal or vertical orientation and can include or omit a leader line. In the case of a wall tag, you typically have a leader coming from the wall, whereas you probably would not use a leader with a door or window tag.

Clicking the Tag button offers three tagging options:

By Category This option allows you to tag elements in the model by category or type. Examples are doors, walls, windows, and other commonly tagged elements. After you choose By Category, the elements you can tag highlight as you hover your mouse over them in your view. Revit also displays a ghost image of the tag you're inserting and the value in that tag.


Multi-Category Use the Multi-Category tag when you want to tag an element across different family types—for instance, when you're using a similar glazing type in your windows and exterior doors and you want to be able to tag the glazing consistently. The Multi-Category tag allows you to have the same tag and tag value for the glazing in both families. (Fire rating is another common application of this tag.)

Material The Material tag lets you tag the materials in a given family. Tagging a wall by material exposes materials used in the wall assembly. This allows you, for example, to tag the gypsum board, sheathing, and studs separately.

Changing a Tag Value

There are two ways to modify text in a tag. Selecting the tag makes the text an active control and turns it blue; just click the blue text and start typing. This changes the value directly in the tag. The second option is to alter the properties of the element being tagged. Using a wall example again, if you select the wall, navigate to its properties, and change the Type Mark field, the wall tag updates to reflect this change. See Figure 19.32 for examples of each location.

FIGURE 19.32
Changing a tag value can happen by changing the value directly in the tag (A) or by changing the Type Mark field in the element's properties (B).



Whichever way you choose, you change the symbol text for every instance of that tag type. Therefore, if you change a wall type from A1 to A2, you change every instance of that wall family that was previously tagged A1.

Some tags only report instance values—values that are unique to the individual element. A room tag or door tag is a common example. The room tag graphics are consistent, but the room name varies from room to room. Doors are often tagged like this, with a unique value for each

door. With these types of tags, Revit detects if you enter duplicate values and warns you when that happens.

Tagging Untagged Elements

You can tag many elements at once using the Tag All tool in the Annotate tab. This time-saving feature lets you tag all the elements in a view simultaneously. When tagging elements, keep in mind that this feature only works with component families and not system families. For example, you cannot use Tag All Not Tagged for walls or floors.

During early phases of design, you often are not concerned with tags and annotations but are more focused on the model. Tags can become graphic clutter that obscure the design at times. Later in the process, when the design is more complete, you may want to annotate the drawing quickly. This is where the Tag All tool can be helpful. When you select this tool, the dialog box shown in Figure 19.33 appears. You can orient your tag or add a leader to it before tagging all the listed elements in your current view.

FIGURE 19.33
The Tag All Not
Tagged dialog box.



If you have elements selected, you can choose to tag only these elements. Note that this option is grayed out in the sample dialog box in Figure 19.33 because nothing in the model is selected.

TAGGING ELEMENTS IN PLAN: DOORS

Try the following exercise.

1. In the Foundation file we have been using, open the view called Level 1. You'll notice in this file we've moved the documents forward a bit by defining the views we'll be using in our callouts. In this view, using the tools mentioned, let's add tags for the doors and walls.
2. On the Annotate tab, choose Tag By Category. Make sure your leaders are turned off in the Options bar before adding any tags to the plans.


3. Mouse over the door, and click when it highlights. This will insert a tag for the door centered on the door opening. By choosing Horizontal or Vertical for the tag orientation from the Options bar, you can quickly run through the plan placing door tags.



These tags might not be ideally located. As we've mentioned, the tag will come in centered on the door. However, it is a simple process to drag the tag to a more appropriate location if necessary.

Now that you have placed the door tags, you can see how each door is tagged and change the tags if appropriate. As we mentioned earlier, to change the value for any of the tags, simply select the tag, and then click on the blue text. This will allow you to enter a new value in that field. For our drawing set, you are going to number the doors with a door number/room number system, as shown in Figure 19.34. You can also change these values directly in the door schedule.


FIGURE 19.34
Numbering doors
in plan.



Another way to quickly tag the doors in this plan would be to use the Tag All function shown in Figure 19.33. This feature applies all the tags of a given family type at one time within the model. It's a quick way to populate a view with tags.


Using the Tag By Category tool on the Annotate tab again, highlight and select the interior walls. For wall tags, be sure to turn on your leaders, but adjust the leader size in the Options bar to $\frac{1}{4}$ " rather than $\frac{1}{2}$ ". The finished floor plan should look like Figure 19.35.

FIGURE 19.35
Adding wall tags.



The number of annotations possible in any given view can be rather large, so it's typically a good idea to conserve the available white space on the sheet by not duplicating notes and tags. As Revit is designed to annotate only single items, avoiding duplication in a given view can be a challenge using only the standard tools. In Figure 19.27, you'll notice that in Room 121, the wall tag A3 has a leader going left and right to each wall. The leader on the left is a drafting line (see Figure 19.36). While this eliminates the parametric value for that single wall condition, in many cases adjacent interior walls have the same type. Before you adopt this approach in a project, you should weigh your need for accuracy against workflow considerations and how much space is available in your documents for this kind of approach.

FIGURE 19.36
Adding leaders to a
wall tag.



Understanding Project and Shared Parameters

Each Revit element has a set of parameters defined by default, such as material, length, area, or other characteristics that describe the element. Often, however, you need additional parameters to describe an element that you don't find in the standard parameter set. For such purposes, Revit lets you add your own parameters to elements and schedule or tag those parameters. There are a couple of ways to add these custom parameters that offer additional information about the element, depending on how you want to leverage them in the further development of the project and where you want them to be visible:

- ◆ If all you intend to do with your custom parameter is to schedule it (for example, a parameter called Lockable that describes whether or not a door has a lock), you can take two approaches:
 - ◆ Add that parameter directly in a schedule using the Add Parameter function. This adds that new parameter *only to the element* that you create the schedule for, such as the door element
 - ◆ Create a new project parameter that you will be able to assign to one or *more element categories*—the difference is that this method allows you to assign the same custom parameter to more than one element (doors and windows, for example)
- ◆ If you wish to be able to both schedule *and* tag your custom parameter, meaning that you wish to see the value of that parameter being called out by the element tag, you will need to use *shared parameters*. As the name indicates, shared parameters in Revit are parameters that can be shared between families and projects. This will allow you to add information to your elements that can be both scheduled and tagged in your project. An example of this might be a custom parameter for a room. It indicates whether the room is public or private, or heated or not heated. To see that information in the room tag, you would make this a shared parameter

Later in this chapter we will use a detailed example to present the whole process of creating and using a shared parameter. First, however, we present a basic procedure for creating a custom parameter that doesn't need to be shared.

Creating a Custom Project Parameter

You can create a custom project parameter at any time in the project cycle. You can then assign it to any one or more element categories and generate schedules that will be able to call it out.

In the following example, we want to track whether or not the materials used in the project are recyclable, so we will create a new custom parameter *recyclable*, which doesn't yet exist in Revit as a standard parameter. We will assign it to the Materials category.

1. To add a new project parameter, select the Manage tab and from the Project Settings panel select Project Parameters. In the resulting dialog box, click the Add button (see Figure 19.37).
2. In the next dialog box, give the new parameter a few definitions (see Figure 19.38):
 - ◆ Name, used for describing the parameter
 - ◆ The group the parameter will belong to. This is specifically for sorting the parameter in the Element Properties dialog box
 - ◆ The discipline. This is also used as a method to help organize the parameters
 - ◆ Whether it is an instance or a type parameter

Instance parameters are specific to any instance or insertion. So if you insert three doors, they can each have different instance parameters. An example might be the door number.


Type parameters remain consistent for the family type. So, in the door example, this might be the door width, and you'd create a separate type for each door style (36", 34", 32", etc.) within the project.

- ◆ What type it will be (text, integer, yes/no)
- ◆ Which Revit category the new parameter will be applied to

FIGURE 19.37
Adding a project
parameter.




FIGURE 19.38
Parameter Properties dialog box.



3. Following a scenario in which we are adding a *recyclable* parameter to the materials, name the parameter **recyclable** and assign it to the category Materials. Make it an instance parameter of the Yes/No type (see Figure 19.39).

FIGURE 19.39
Creating a custom project parameter.




4. Navigate to the Materials dialog box (by clicking Materials on the Manage tab) and select the Identity tab. You will find the parameter you just created (see Figure 19.40).

With these steps, you have just assigned the new Recyclable parameter to all materials used in the project. What is left to do is to define their state for each material (Yes or No). To do this, you can choose Materials on the Manage tab and, for each used material, set the value of the recyclable parameter on the Identity tab.

Once you do, you can create a material takeoff schedule (on the View tab, select Schedule/Quantities > Material Takeoff) and make a schedule that calls out the Recyclable parameter. You will then know how much and which of your materials used are indeed recyclable.


Note that you *cannot* tag the parameter you just created and will not be able to make it appear in the material tag. The reason for that is simple: the existing material tag will not recognize a custom parameter that you create on the fly in a project as it has no label that can call it out attached to it. Tagging a project parameter is only possible using shared parameters. They are used both on the elements and in the tags, and thus the tag understands them and can call them out.

FIGURE 19.40
Locating the new
parameter.



CREATING A CUSTOM PARAMETER WHILE SCHEDULING

When scheduling, you can add a custom parameter to any schedule on the fly. This parameter is assigned only to the category of elements that you are scheduling. To create such a custom parameter, click Add Parameter in the Schedule Properties dialog box.



Creating Shared Parameters

When you want to schedule and tag a custom parameter you have created, use shared parameters. For example, you might wish the hardware set information of a door or window to appear in the door or window tag, or the level of radioactivity of medical equipment to appear in the equipment tag, or the door tag to display whether or not a door has a lock. None of these parameters exist by default in any of the families, so you will need to create them and add them to the families if you want to use them. They also don't exist in any of the family tags, so to be able to call out the information of these customer parameters in the family tags, you will need to add the same parameters to the tag families as well. The concept seems complicated, but it's actually straightforward. Imagine this: you have a set of chairs, some that are original Thonet chairs and some that are reproductions. You want to tag the originals with a special parameter called *original*. To do this, you must add that parameter in the tag (by creating a label and calling it out), and you then have to add the parameter to the chairs that are the originals. Now, if you created the original parameter as a project parameter, that parameter would only exist in the project you created. Neither the chair family nor the tag family would be aware of it, as they were created prior to the creation of the parameter and didn't have it among their parameters. That is where shared parameters come in handy—they allow you to reference the same parameter between project and family.

Let's look at the workflow behind creating these, using the example of a hardware set for doors and windows. We will do an exercise in which you will create a door custom parameter called *hardware* that is schedulable and taggable.

1. Create a new shared parameter file. At this stage, it doesn't matter if you are in a Revit project or in the Family Editor. In both environments, you can choose the Manage tab and click Shared Parameters. This opens the Edit Shared Parameters dialog box.
2. Select the Create option and enter a shared parameter file directory path and name. This is where you will store all your custom-created shared parameters. Make sure that the folder you store your shared parameters in is saved somewhere accessible to the rest of your team.
3. Next, create a group by clicking the New button in the Groups cluster of buttons that is now activated. This might be confusing, but in principle every shared parameter belongs to a group as a higher instance in a hierarchy, so you have to create at least one. If you use lot of shared parameters, the groups can come in handy for locating parameters. So, create a group and name it **Hardware**.
4. Once you have created the group, you can create the shared parameter by clicking the New button. Name the new parameter **Hardware Set**. This is the shared parameter that we wish to have visible in our schedules—and more important, that we wish to tag.

The shared parameter you've just created is nothing more than a simple text (.txt) file that you will find in the directory you created at the beginning of the exercise. You can now assign this parameter to any one of the following:

- ◆ The tag family
- ◆ The project (as a project parameter)
- ◆ The categories of elements you wish to have that parameter


For this exercise, use the *Foundation.rvt* file located in the Chapter 19 folder on the book's companion web page (www.sybex.com/go/masteringrevit2010) to create a shared parameter file.

CREATING THE SHARED PARAMETER FILE

In the following steps, we will first create the shared parameter file:

1. Choose Shared Parameters on the Manage tab.
2. In the Edit Shared Parameters dialog box, click Create (Figure 19.41).

FIGURE 19.41
The Edit Shared
Parameters
dialog box.




3. Specify the directory path and name of the new file; then click Save. The name of the new file that you assign here is not as important as the fact that this file needs to be accessible in Read mode for all team members. Do not give the filename an extension because the .txt extension will be appended automatically.

CREATING A GROUP OF PARAMETERS

Revit requires that you create a group before you can create a shared parameter.

1. In the Edit Shared Parameters dialog box, under Groups, click New to create a new parameter group (Figure 19.42).

FIGURE 19.42
Making a
new group.



2. Give the new group the name **Doors**. To help you organize your shared parameters, you will want to name the group logically.




CREATING THE SHARED PARAMETER

Now that you've created the backbone for the shared parameters, let's create the parameters themselves.

1. Still in the Edit Shared Parameters dialog box, click the New button in the Parameters section (Figure 19.43).

FIGURE 19.43

Adding a new parameter.



2. In the Parameter Properties dialog box, do the following:
 - ◆ Enter a name for the new shared parameter. Call it **Lockable Door**
 - ◆ Under Discipline, keep the default, Common
 - ◆ In the drop-down list under Type of Parameter, select Yes/No
 - ◆ Confirm by clicking OK




And that's it! You've just created the shared parameter for door hardware and are ready for the next step: adding it to a door tag in the Family Editor, then moving into the project environment and assigning it to the Doors category. As explained earlier, you can only tag a custom property that you define if you share it across the families and the project.

CREATING A NEW PROJECT PARAMETER USING THE SHARED PARAMETER AND ASSIGNING IT TO A CATEGORY

In the following steps, we'll make our shared parameter a project parameter and assign it to the Door category.

1. Open the file `Foundation.rvt`.
2. Open the plan view Level 1.
3. Choose the Manage tab and click Project Parameters. A list of parameters will appear. The Lockable Door shared parameter that you just created is *not* among them, so you will need to click the Add button (see Figure 19.44).

FIGURE 19.44
Adding the
parameter.




4. In the Parameter Properties dialog box, in the Parameter Type group you will see a Shared Parameter option. Check it and click Select.




5. The Edit Shared Parameters dialog box opens, and you will see the shared parameter you have just created, automatically selected. Click OK (see Figure 19.45).

FIGURE 19.45
Linking the shared
parameter.




6. In the Parameter Properties dialog box, set the Group parameter to Identity Data. Make sure you select the Instance radio button. This will make the parameter instance based since in the real world the same door type may or may not be lockable.



7. All that is left to do now is select the category to which this shared parameter will apply. In the Categories list, select Doors (see Figure 19.46). Note that you can assign the parameter to as many categories as you wish.
8. Confirm all that you have done by clicking OK.

FIGURE 19.46
Assigning
categories.




SETTING THE SHARED PARAMETER IN THE OBJECTS THAT BELONG TO THE SELECTED CATEGORY (DOORS)

Now that you've created a shared parameter, you need to add the tags to show the lockable and nonlockable doors.

1. In plan view, select a door (let's say the door belonging to Room 131—Storage) and open its properties (see Figure 19.47).

FIGURE 19.47
Selecting a door
in plan.



2. Notice that the newly created parameter appears in the group Identity Data, just as we set it to be. Note, however, that the value is gray, meaning that it has not been set.

Identity Data	
Comments	
Mark	1/131
Lockable Door	

3. To set the parameter to one of the states, lockable or not, click the check box. Click again to clear the check box and void the selection.

Identity Data	
Comments	
Mark	1/131
Lockable Door	☒


You don't have to set this parameter one door at a time. You can select multiple doors that will have a lock and check the box using the same method or set this value through the door schedule itself.

ADDING THE SHARED PARAMETER TO A DOOR TAG

If you only wanted to add a new parameter to the door category and schedule it, you could have done so by using a simple project parameter. The point of making a shared parameter is that you will be able to add it to the door tag family as well as tag the door and display the value of the shared parameter in that tag. You will now add this shared parameter to the door tag family so that the tag understands the shared parameter value and displays it. If you just added a new label for the shared parameter and the door is lockable, the door tag for a lockable door would simply display “Yes.” The parameter we made only reports Yes/No values, which is not very helpful. So you’ll need to add a static textnote next to the label: **Lock** (see Figure 19.48).

FIGURE 19.48

The tag with fixed text.




There are two ways to create a tag that calls out a shared parameter:

- ◆ Take an existing door tag, duplicate it, and then add the shared parameter to the duplicate
- ◆ Make a tag from scratch


In this exercise, we will make a new door tag from scratch.

1. Go to the Application Menu, ➤ New ➤ Family. Select the Annotation folder.
2. In the New dialog box, select the family template `Door Tag.rft` and click Open.
3. The Family Editor opens in plan view, showing two crossing reference planes. The intersection of the two reference planes represents the insertion point (and center point) of the tag to be created. In the tag, you’d like the following information to be displayed: the door mark and whether it has a lock.
4. Click the Label button on the Create tab. Click with the mouse somewhere close to the crossing point of the two references.




5. In the Select Parameter dialog box, select Mark and click OK (see Figure 19.49).

FIGURE 19.49
Selecting the Mark
parameter.




6. The Mark text is set to 1/8" (3mm) by default. This might be a bit big if we want to add a mark and a lockable parameter, so we need to make the font size smaller. In the Element Properties dialog box of the mark, click Edit/New. Click Rename in the Type Properties dialog box and enter a new name, indicating the size of the mark, 3/32" (1.5mm bold). Click OK.



7. In the Type Properties dialog box, set the properties of the mark as shown here:

Parameter	Value
Graphics	
Color	Black
Line Weight	1
Background	Opaque
Text	
Text Font	Swiss/21 Ltcn B/I
Text Size	1.5000 mm
Tab Size	12.7000 mm
Bold	☒
Italic	☐
Underline	☐
Width Factor	1.000000

8. Confirm by clicking OK in the remaining dialog boxes when finished. What you see should be similar to what is shown here:



Note that 1i is just a symbolic representation of the label. Once placed in the project environment, it will read and display the mark of the door.

- 9. Remember, the goal was to display the hardware information about the door within the door tag. For that, we will now add the shared parameter Lockable Door to the door tag. Click again on Label on the Create tab and position this second label below the first, also centered in the tag.



- 10. In the Edit Label dialog box, click the Add a Parameter button, and then in the Parameter Properties dialog box, click Select. The shared parameter list opens; here you will find the Lockable Door parameter. Select it and click OK in all remaining open dialog boxes.



- 11. You can also select the Shared Parameter label in the Drawing area, click Modify to access its element properties, and set Sample Text to Yes.


Parameter	Value	
Graphics		
Sample Text	Yes	

- 12. You will probably want to change the size of the text here as well to 3/32" (1.5mm), so navigate to Edit/New and under Type Properties, select Duplicate. In the Name dialog box, enter 3/32" (1.5mm). Confirm by clicking OK.




- 13. Clear the Bold parameter and click OK in all remaining dialog boxes.

14. Adjust the position or the size of the label if needed.




All that remains for you to do is to add the fixed text that will say “Lock:” and position it just in the front of the shared parameter label.

15. Click Text in the property dialog box. In the drawing area, click somewhere in front of the label Yes.



16. Enter the text **Lock:** and on the Options bar, select Properties. Repeat Steps 6 and 7 of this exercise to adjust the size and name of the new text type to match the label we added. Click OK in all remaining open dialog boxes.




The tag is ready. Save it and load it in the project *Foundation.rvt*. If you have already placed door tags, you can select them all and exchange them with the new tag that contains the shared parameter by simply selecting it in the Type Selector. You will notice that now all your door tags will display the mark on the top and the word *Lock* at the bottom. For doors that you previously defined as lockable, it will also show *Yes*. You will see that many doors have nothing shown in the tag after *Lock:*. Those are the doors that haven’t been marked Yes or No, such as the one in Figure 19.50.

SHARED PARAMETER NOTES AND CAUTIONS

Keep the following point in mind when you create shared parameters: once you have added a shared parameter to your project, you will not be able to change any of the properties of the parameter itself. If you forgot to set the Yes/No parameter, or if you mistakenly selected Type instead of Instance, you will not be able to change this setting. To fix that, you will have to create a new project parameter using the same shared parameter—and be more careful the next time.

FIGURE 19.50

A door without
a Yes or No value
for Lock.



Adding Text and Keynotes

Notes are a critical part of communicating design and construction intent to contractors, subs, and owners. No drawing set would be complete without written definitions and instructions on how to assemble the building. Revit has two primary ways of adding this information to the sheets. One way is through text. Text in Revit consists of words arranged in paragraphs with or without a leader. Text can be used for specialized annotations, sheet notes, legends, and similar applications. Keynotes—the other way of annotating a drawing—are element-specific and can be scheduled and standardized in the Revit project file. Chapter 4, “Setting Up Your Templates and Office Standards,” briefly introduced text and keynotes as elements you can include when customizing your template. In the following sections, we’ll explore the use and function of both tools in more detail.


Text

Text is easy to add to any view. However, it’s important to understand that text is nothing more than a view-specific annotation. Specific text families maintain a parametric relationship throughout the project, and changing one text family type changes each instance of that type throughout the project. While text is a family within Revit, it is not directly tied to values of other families like keynotes or tags. Text is only text, and it will not dynamically report properties from elements it is pointing to.

You can access the Text tool from the Annotate tab. Text can be added to any view, including a 3D axonometric view (but not perspective views). To begin adding text, click the Text button after you’ve opened the view of your choice, select where in the view you wish to place text, and begin typing. To edit text you’ve already placed, click the text to highlight it, and then click it again to activate the text box. To move text once you’ve located it, select it and drag it, or use the Move command.

A
Text

As with all the elements in Revit, there are ways to change the look and feel of the object being created. Once you've selected the Text tool, the Type Selector and Options bar provide some formatting options:



The Type Selector allows you to choose a style for the text you're about to create. You can manage each text style using the Properties dialog box, which lets you modify parameters such as font, size, and color. To create a new text style from an existing one, click the Element Properties button and in the Instance Properties dialog box choose Edit Type and then choose Duplicate to duplicate the type and make adjustments to the properties (see Chapter 4). You can also choose to add a leader to the textnote before placing the note.

There are four options for leaders:

- ◆ No Leader
- ◆ One Segment
- ◆ Two Segments
- ◆ Curved

Once you've placed the text, selecting the note itself provides additional options. You can add or remove additional leaders and rejustify the placed text. Note that when you are adding or removing leaders, the leaders will be removed in the order they were added to the text.



To edit the text, select the element. The letters will turn from black to blue. You can then click to place your cursor inside the text, and begin editing. When you're editing the text, the Options bar will display formatting controls for bold, italic, and underline text styles. These apply to whatever text you've selected in the note.



When you use the Move command, you move both the text and the leader. When you move text by dragging the arrow icon, you move only the text box, leaving the leader anchored in its original position. When moving text with the arrow icon, Revit will automatically align vertical and horizontal text and leader nodes. This is designed to help you achieve a more consistent graphical appearance. One of the biggest limitations of Revit is that you cannot apply changes in text style to multiple elements (tags, schedules, title blocks, keynotes, or dimensions, for example). So, if you want to make all text in Revit use a particular font, you will not be able to change a global project setting. Instead, you will need to edit each element's type individually. A good way to avoid this type of change is to standardize the fonts in your project templates, as covered in Chapter 4.

Keynotes and Textnotes


Keynotes and *textnotes* are written annotations that use an external file to relate text to specific elements in the model. You can format font style, size, and justification in the same manner you can format standard text, but keynotes and textnotes behave similarly to a Revit family. This means you can insert different family types of text in Revit, just as you would door or window families. Changing one instance of the family type changes all the instances in the project. Because keynotes and textnotes act as families in Revit, they can also be scheduled.

What's the difference between a keynote and a textnote? A keynote is a short reference, typically a number followed by a couple of letters. An example would be 03300.AA, which points to a cast-in-place concrete wall. The 03300 portion of the note refers to the specification section the note is generated from, and the AA portion is a sorting mechanism used to differentiate cast-in-place concrete from another note in Division 3 of the specifications.


All of the notes on a given sheet are keyed back to a legend, which is typically placed on the right side of a sheet. This reference helps you add more detail and understanding to the keynote without having to reference the specifications directly. (See Figure 19.55 later in this section for an example of a keynote and legend.)

Textnotes are very similar to keynotes, but they combine a short description of text and the key into one note. This saves you from having to coordinate the legend on the sheet and puts the note right next to the item you are pointing to. (See Figure 19.52, later in this section, for an example of textnotes.) No matter which style you prefer, you can create both the keynote and textnote with the same command in Revit. Since the command is called Keynote in Revit, we will refer to the process from here on out as *keynoting* regardless of the style of keynote (or textnote) you choose to use. See Figure 19.51.

FIGURE 19.51
Textnotes with
keynotes.



The Keynote command is located on the Annotate tab. When you add keynotes in Revit, you have three options:



Element This option allows you to note an element in the model, such as a wall or a floor. This type of note is typically used if you want to note an entire assembly, such as a wall assembly. You can find this value in the family properties of that element.

Material This option allows you to note a specific material in Revit. You can add a note to concrete, gypsum board, or insulation, even if they are a part of an assembly.

User This option allows you to select any model-based component in Revit and define a custom keynote for it. Notes defined this way differ from those defined as element or material because they're unique to the particular object selected. They can be used in conjunction with element and material notes.

All of these note types can be used in conjunction with one another. Using an element note to add a keynote to a wall doesn't mean you can't also use a material note to call out the individual materials in the wall assembly.

Keynote Behavior and Editing

A core concept in keynoting is how the notes react in the model. Keynotes are integrated into Revit just like any model element. Keynoting an object in Revit lets you associate a text value with that family's keynote parameter. This value is consistent for every identical element in the model. For example, all doors have a type parameter that lets you set the keynote value. If you keynote a door—anywhere in the model—the keynote will show that value. Likewise, if you ever change the value of the keynote for the door type, all keynotes for that door type will update automatically.

Keynotes are special in that you *cannot edit the text of a keynote directly in Revit*. All the keynotes in Revit are tied to an external text file, and can only be edited in this location. This file can be modified at any point to add or remove values and notes. A sample list looks like this:

03100	Concrete Forms and Accessories	03000
03200	Concrete Reinforcement	03000
03300	Cast-in-Place Concrete	03000
03400	Precast Concrete	03000
03500	Cementitious Decks and Underlayment	03000

This external text file is designed to keep annotations consistent by storing all of them in one repository. Every time you add or change the text of an annotation and reload the text file, it dynamically updates all the keynotes of that type used in the project.

You can edit a keynote text file (.txt) or add one to a project at any time. You can have multiple text files for various projects, but you can have only one text file per project at a time. The text file works just like any other Revit family. Since all the notes are parametric, changing a note in the text file will change all of the notes in the project when the text file is updated.

A powerful way to ensure consistent use of notes throughout your office is to create a master text file for your various project types. These master note lists can be linked to materials or assemblies within your project template so that you can immediately begin inserting common notes into any project. To link keynotes to a material, click the Materials button on the Manage tab and select the Identity tab. In the Keynote field, a predefined note can be selected from the master list and added to any material. The same is true for any assembly. Simply choose the assembly's properties (such as a wall or floor) and select the keynote field to enter a note value.

Since the keynote text file is separate from the Revit file, if you send a project file to someone and don't send keynote.txt, that person will be able to see all the keynotes you've added to the views but won't be able to add or edit the notes without the text file.

Keynote Filenaming Conventions

The default Keynote text file in Revit is found in C:\Documents and Settings\All Users\Application Data\Autodesk\RAC 2010\Imperial Library (or \Metric Library) and is called RevitKeynotesImperial.txt or RevitkeynotesMetric.txt.

To edit this file, open it in Notepad or Excel and follow the format already established in the file. Let's look at that format to get a better understanding of how to customize keynotes.

The first few rows designate the groupings. They consist of a label (in this case, a number) followed by a tab and then a description. An example grouping looks like this:

```
03000      Division 03 - Concrete
```

Below the groupings, with no empty lines in the file, are the contents of the groupings. These are shown with a minor heading, a tab, a description, a tab, and the original grouping header. Here's an example:

```
03200      Concrete Reinforcement    03000
```

Here, 03200 is the subheading, Concrete Reinforcement is the description, and it all falls under the 03000 grouping from the previous example.

Using this method, you can add or edit notes and groups of notes to the keynote file. It might seem horribly inefficient at the beginning of the process to have to constantly go to the keynote text file to edit or add notes. While this might seem like a burden, it can be a blessing as well. Accessing this file ensures a global consistency within the keynotes on a project that is unattainable in most drafting applications. If you are feeling frustrated with having to access this file to make changes, think about all of the time you are saving *not* having to check your set sheet by sheet to verify that all of the notes pointing to a material are the same.

Keynote Settings

Once you change a keynote text file, you need to reload the file into Revit to update the keynotes. You can open the dialog box to change or update the text file by choosing the Annotate tab, expand the Tag panel, and choosing Keynote Settings (Figure 19.52).

FIGURE 19.52
Keynoting Settings
dialog box.



In the Keynote Table group, you define the path to the text file used for keynoting:

Path Type Path Type defines how Revit looks for your text file using one of three methods:

Absolute This option follows the UNC naming conventions and navigates across your network or workstation for a specified location.

Relative This option locates the text file relative to the Revit project file. If you move the Revit file and the text file and maintain the same folder structure, Revit knows where to look for them.

At Library Locations This option lets you put the text file in the default library location defined on the File Locations tab of the Options dialog box (click the Application button and choose Options).

Numbering Method Numbering Method defines how the keynotes are numbered:


By Keynote This option allows you to number keynotes as they come from the associated text file.

By Sheet With this option enabled, Revit numbers the keynotes sequentially on a per-sheet basis.


Adding Keynotes to a View

To add keynotes to a Revit model, choose one of the three keynote types from the Annotate tab. In your view, hover your mouse over the various model objects until you find the one you want to note, and click to add the keynote. You'll then be prompted to add a two-joint leader, which will end at a box containing the text of the note you assigned to that material or assembly. Once you've placed the note on the sheet, you'll see a dialog box (Figure 19.53) where you can identify the element you're trying to note if it doesn't already have a note associated with it.

FIGURE 19.53
Selecting a keynote.



Expand the plus signs until you find your desired keynote and double-click it. Doing so globally associates that particular note with the element or material in the model. As mentioned previously, you need to make this association only once. For example, if you keynote a material called Concrete, then every time you hover the mouse over that material anywhere else in the model with a keynote tag, you'll see the preview graphic of the tag, which reads "Concrete." This way, you can define the materials and assemblies in the model and begin your documentation process.



With the exception of detail components (covered later in this chapter), you can't keynote lines or other 2D information.

Keynote Legends

Depending on your workflow and style of annotation, you may want to create a legend on each sheet for your keynotes. You might want only the keynotes that are on a given sheet to appear in the legend. Or you may wish to have one legend for the entire project that will show all keynotes used in the project. The legends allow the builder to reference the note number with the text quickly and easily (see Figure 19.54). These lists usually reside on the side of the drawing near the title block information and can take either of two forms. The first type is all-inclusive and shows every note within the project. This style has the benefit of consistency between sheets in the set. The same note will always be in the same location in the list. The other type of keynote list includes only the notes that are present on a particular sheet. This has the advantage of supplying a list of notes customized for each sheet without extraneous information. As you can imagine, this second list can be labor intensive and fraught with opportunities for human error. One of the beauties of Revit is its ability to accurately manage this kind of information for you. We will review how to create both types of lists.

Creating a keynote legend in Revit is simple. Choose the View tab, and in the Legend panel, select Keynote Legend. You'll be prompted to name the legend; enter a name and click OK.

FIGURE 19.54
A keynote legend.

KEYNOTE LEGEND	
Key Value	Keynote Text
03300.AO	CIP CONC FLOOR SLAB (03300)
04810.BF	STONE CLADDING (04810)
05120.AC	STEEL BEAM (05120)
05310.AH	COMPOSITE FLOOR DECK (05310)
05500.BD	STEEL COLUMN (05500)
05500.BU	STEEL ANGLE (05500)
06105.AB	WOOD FURRING (06105)
06105.AC	PLYWOOD (06105)
06105.AD	1X IPE WOOD SUNSCREEN (06105)
07210.AB	RIGID INSULATION (07210)
08411.AA	EXTERIOR ALUMINUM-FRAMED STOREFRONT (08411)
09111.AO	HAT-SHAPED, RIGID FURRING CHANNEL (09111)
09250.AC	GYPSUM BOARD, TYPE X (09250)
09640.AA	BAMBOO FLOORING (09640)


Only two fields are available in a keynote legend, and by default, they are both loaded into the Scheduled Fields pane of the Fields tab. Those fields are as follows:

Key Value This field contains the numeric value of the keynote.

Keynote Text This field contains the text value for the keynote.

A keynote legend works very much like any other schedule as far as formatting and appearance. By default, the sorting and grouping are already established because the key value is used to sort. The one special item to note is located on the Filter tab. At the bottom of this tab is a feature unique to this type of schedule: a Filter by Sheet check box (shown in Figure 19.55) is available. Checking this box gives you the ability to filter the list specifically for each sheet set.

FIGURE 19.55
The Filter by Sheet check box located at the bottom of the Filter tab in the Keynote Legend Properties dialog box.



Either legend style you make can be placed again and again on every sheet in the project. The filtered legend style dynamically modifies the note list based on each sheet and the contents on each sheet. As views are added or removed from a sheet or notes are added to the project, the keynote legend updates accordingly. If the keynote is not used in the view placed on the sheet, it will not show up in the legend for that sheet.

Keynote legends are considered another type of legend view: once created, they appear under the Legends branch of the Project Browser.

A SCHEDULE FOR KEYNOTES

Creating a schedule for keynotes is a great way to find rogue notes and typos in a project. If you are working on a project team of any size, there's always a chance that someone could be inserting an incorrect textnote into the project. Scheduling the notes is an efficient approach to managing this process and gives you the tools to verify consistency. Scheduling textnotes allows you to do two things:

- ◆ List all of the notes within a project and verify their spelling and accuracy
- ◆ Find the odd note. Sometimes a particular note only shows once or twice in a project. When this happens, it can mean the note was accidentally placed in lieu of another note


The Keynote Family

Revit comes with a keynote family that allows you to produce both keynotes and textnotes. If it is not loaded into your project, you can find it under the Annotations folder in the Imperial or Metric library. The family name is **Keynote Tag.rfa**. This family has three family types that let you change note styles within the project. You can see the three note styles in Figure 19.56.

The three default styles are Keynote Number, Keynote Number–Boxed, and Keynote Text. Each of these notes pulls information from the text file we discussed earlier in this chapter. We are simply using the flexibility of family types to report different values within the model from the same note. Like any other family, this family can be edited to change the note length, font style, or other attributes to match your office standards.

FIGURE 19.56

Note styles available in the default Revit keynote tag.



ADDING NOTES TO A WALL SECTION BY MATERIAL

As we discussed earlier in this chapter, there are three styles of keynotes: element, material, and user. With each of these styles, there are limits to what you can note within Revit—and

these three note styles can annotate only objects within Revit. Understanding this is critical to successfully using the keynote system within Revit so you can optimize the value of your pre-defined notes.


Here's a summary of the most common tasks you can perform with keynotes:

- ◆ Add notes to elements such as walls, roofs, floors, and families that are a combination of materials or elements
- ◆ Add notes to the individual materials themselves or to any element that can be given a material
- ◆ Add notes to detail groups and detail components.

While this is an extensive list and covers most of what happens in Revit, there are a couple of things you cannot tag with the Keynote tool: detail lines; and groups (although you can tag elements within groups).


This becomes a critical issue when you begin embellishing details within a model. As a best practice, it is recommended that you optimize the use of detail components and embed them into the project families. Detail components are families created with 2D linework that can be dropped into any view to represent elements that are not directly modeled. For example, blocking that would appear over a window head is not something you would create as a model element, but it is still necessary to show in a section or detail (see Figure 19.57). We cover the technique of creating and noting detail components in Chapter 21, “Moving from Design to Detailed Documentation.”

FIGURE 19.57
Detail components
can be tagged with
keynotes.




Once you've established your keynote style and made your adjustments to font size and type and linked a keynote TXT file, you can add some notes to the drawing. Adding notes to a drawing from this point is quite simple.

1. On the Annotate tab, click the Keynote button.
2. Select Element, Material, or User from the list. In our example, we've selected Material.
3. When you hover your mouse over the material, Revit will try to identify it. If the material already has a note value defined, Revit will show you a floating note identifying the material.




- 4. From here, click to place the arrowhead of the note, click again to locate the joint in the leader, and then click once more to locate the text. If the material is unknown, Revit shows a question mark to tell you this material has not yet been identified in the project.




- 5. Locate the note using the same method for materials that are already defined (see Figure 19.58). After you set the text location, Revit will prompt you to select a value from the Keynotes table.

FIGURE 19.58
Adding notes to a material.



- 6. Once you've selected the note for a material, that same note will be applied every time you select that material with a keynote in every other view in the project.


By default, Revit 2010 includes the Open 30 Deg arrow as a standard for your keynotes. However, this is new to the Revit 2010 default template and will not be the case if you are upgrading your template from a previous version. Revit doesn't provide a way to preset arrowhead styles for notes unless you preset them in the project template. After you first insert a note into Revit, select it to add an arrowhead. To do this, select the note and navigate to its properties, and then select Edit Type. Here you can globally set an arrowhead style for any of the keynote family types. Most of the common arrowhead styles can be found in this properties box. Selecting one from the list will change the arrowheads for all of the notes of that type in the project.



Once you've added a couple of notes, it's an easy process to continue noting the remaining materials in the wall section. The completed section with keynotes looks like Figure 19.59.

FIGURE 19.59

A wall section annotated by material.



ADDING NOTES TO A WALL SECTION BY ELEMENT


Another way to keynote a drawing is to note by assembly or, within Revit, by element. Keynoting by element means that you are not noting the individual materials as we did in the previous example but the entire assembly at once. So, in lieu of noting plywood and gypsum board, you are noting the entire wall assembly at once. The process to add the notes is very similar.

1. On the Annotate tab, click the Keynote button.
2. Select Element, Material, or User from the list. In our example, we've selected Element.
3. When you hover your cursor over the element or assembly, Revit tries to identify it. If the element already has a note value defined, Revit shows you a floating note identifying the material. From here, click to place the arrowhead of the note, click again to locate the joint in the leader, and finally, click to locate the text. If the material is unknown, Revit shows a question mark to tell you this element has not yet been identified in the project. Locate the note using the same method you used for elements that are already defined, but after you set the text location, Revit prompts you to select a value from the keynotes table.

A wall section noted by element looks like Figure 19.60.

FIGURE 19.60

A wall section noted by element.



Remember that element, material, and user notes in Revit are different entities and are allowed their own, unique notes. You can note by material, by element, and by user within the same project.

Predefining Keynotes

There are a variety of other ways to add notes to a project without adding them directly in a view. Within the properties of elements and materials is a field to predefine a keynote. By putting a value in this field before noting the drawings, you can avoid selecting notes from the keynote list when you are actually annotating a view. All of the notes would be preselected. Depending on the note type, the location for these settings varies.

Element This value can be set in the properties of the various families in a Revit project. By selecting a wall, for example, you can select this wall's properties, and then click Edit/New to reach the wall type properties. Under Identity Data, you can then define a keynote (see Figure 19.61). Selecting this field, you will be presented with the same keynote table that you'd receive if you were noting this element in a view. If the note is incorrect for this project or element, you have the option to change the note here as well.

Material This value can also be set by clicking the Materials button on the Manage tab. By selecting a material from this list, and then selecting the Identity tab, you can add keynote values directly to your materials (see Figure 19.62). You will again be presented with the familiar Keynote dialog box to select your materials.

FIGURE 19.61
The type properties of the wall showing the predefined Key-note field.





FIGURE 19.62
Defining keynotes
for materials.



User User notes are view-specific and cannot be predefined. While it is still possible to annotate only model elements and detail components with user notes, this tool will allow you to note the same element with different notes in separate views. This can be dangerous to the consistency of your notes in your drawings if used inappropriately. The advantage of this note type, however, is if you need to note something differently in one view based on a unique condition. For example, you might need to note a material or color change in a special location or a special flashing or sealant issue around a unique window condition. This will spare you from having to create a new family type simply to add a different note.

Revit does not support more than one `keynote.txt` file per project, so if you wish to include keynotes from different standards, you can simply add more text entries to the text file that you have for the project and they will all be available immediately within Revit.

The Bottom Line

Annotate views. Room elements are highly useful tools for a number of different applications in a set of documents. Learning how to use them and tag them will help you find areas, create finish schedules, and identify spaces.

Master It Once the model has been largely built, you need to start adding information about rooms and finishes. What tools would you use?

Use schedule keys. Adding information to the room element is only part of the documentation and design process. Knowing how to schedule that information allows you to communicate effectively with owners and contractors.

Master It Tags are used to report information about an element. How do tags work in Revit so that they always report accurate and consistent information about the elements they tag?

Leverage tags. Revit supplies you with three ways to annotate your model and the project. Knowing when to use each and planning for them early in the documentation phase saves time and frustration.

Master It It is important to understand the relationships between elements and materials in Revit early. How does this help streamline the process of keynoting your project when you reach the documentation phase?

Understand shared parameters. Revit lets its users add as many custom parameters to an element as are needed. When those added parameters need to be visible both in schedules as well as in the elements tags, they need to be created as Shared parameters.

Master It You added a custom parameter to your door and window elements and wish to schedule and tag it such that each window or door tag displays the information about the hardware set. The schedule works well, but your tags seem to be unable to find the hardware set parameter. What is wrong?

Add text and keynotes. No set of drawings is complete without keynotes or textnotes. Understand how to create and modify them for a complete set of documents.

Master It You will need to add notes in every stage of design to communicate your design intent on a project. How do you create and modify the notes to ensure accuracy throughout all the sheets in the set?

Chapter 20

Developing the Design with SmartWorkflows

In this chapter we'll explore scenarios in which elements in a building repeat, and you'll learn how to take advantage of some tools in Revit to help your workflow be more efficient and less prone to error. The tools we'll explore are called *groups* and *links*—tools specifically designed to support design and propagation of repetitive entities, which can range from entire buildings to individual rooms to furniture arrangements.

Both of these tools require an understanding of some basic principles that will help you make decisions about when and where to engage these features in a design. We will introduce the concept behind each tool and present a series of use cases in which groups or links provide a valuable solution to a design problem.

In this chapter, you'll learn to:

- ◆ Work with repetitive elements
- ◆ Understand the use of groups
- ◆ Understand the principles of links
- ◆ Decide whether to use groups, links, or both

Working with Repetitive Elements

Many architectural projects deal with the design and organization of repetitive elements. The concept of a modular unit that is repeatable has been one of the more important principles of architecture and continues today in the form of housing, hospitals, schools, and office buildings. A repetitive element can be found at nearly every scale: from entire buildings to housing units; from hotel rooms, classrooms, and hospital rooms to bathrooms, closets, and furniture layout.

In each case, the basic requirement is to group a collection of elements that is repeatable so that later in the design process any change to the module will be propagated to all the other instances (copies) of the module. This propagation results in huge time savings, as you don't have to manually update the model, element by element. This also guarantees consistency and means there are fewer changes to correlate as documents are reviewed.

At the same time, flexibility must be built into the tool to account for edge conditions where the repetitive unit needs to stray away from base without breaking its relationship to the essential nature of the module. Revit is remarkably well suited to meet both these needs and support a diverse set of design requirements.

Understanding How to Use Groups

Groups significantly improve your workflow when you are working with collections of elements that need to be repeated throughout a project.

When a collection of related elements is made into a *group*, it becomes possible to manage and change any single instance of the group and have the changes propagate throughout the entire model—all in one interaction. It is also possible to execute a change on one group instance only and *not* have that change propagate. As you will see, Revit was designed to be flexible. It lets you group elements in a project or even inside a family and use it to quickly lay out entire floor plans. You can also save groups and reuse them in other projects, making them quite versatile.

As we've discussed previously, the Revit categorization schema is intelligent: objects know what category they are and in what views they are visible. This directly impacts how groups are created and organized. For example, model elements (walls, floors, furniture, etc.) are grouped as *model groups*, and 2D, view-specific elements (dimensions, annotations, etc.) are grouped as *detail groups*. There is also a hybrid category called *attached detail groups*, which relates grouped details to a specific model group. If you create a group that contains both types of elements (model and annotations), Revit automatically stores this group as a model group with an attached detail group for the view-specific information. Keeping tags and keynotes associated with a model element in a group is an example of this. That said, there are certain conditions where information *cannot* be attached within a group. For example, if a dimension between two walls is added to a group but only one of the walls is in the group, Revit cannot attach the dimension. The dilemma is obvious: when new instances of the group are placed, where should the dimension go in the absence of the original, ungrouped wall? Remember that dimensions, tags, and keynotes refer to real model elements and cannot exist without their references (hosts).

Using Groups for Repetitive Rooms

Most architectural firms have projects where repetitive units are used throughout the design. In our first example, we will work on a day-care center for children with cancer (Figure 20.1). The design calls for many typical bedrooms, most of which will be the same size and have the same accommodations (bed, bathroom, furniture). The ability to design, iterate on, and manage all these bedrooms will be a major part of the project, which also has to be easy to maintain, schedule, and update.

We will first work with groups to solve this design challenge; later we will look at the same issue from the vantage point of using links and examine the differences between the two approaches. As you will see, each method leads to different results.

FIGURE 20.1
Repetitive
elements sample
model.



Courtesy of Felipe Manrique Diaz,
Universidad de Las Americas

Creating and Managing Groups

As soon as the building design is roughly oriented on the site and you start laying out the modules inside the project, you can immediately take advantage of group functionality by defining the basic room unit that will repeat. Later, you can add more content in one instance of the group, which will then populate into other instances of the group that are placed throughout the project.


Early on, you'll work with walls and rooms to create reliable area schedules that will show you how the design is stacking up against the program requirements. You'll also take full advantage of BIM by keeping all information centralized in one file. Using links (external file references) rather than groups, you would not get these benefits.

Creating and Placing Repetitive Units Using Groups

Let's step through a workflow using groups to lay out bedroom units.

1. Open the `Chapter_20_Model_Groups_Start.rvt` file from the book's companion web page (www.sybex.com/go/masteringrevit2010). The project should open with the plan view (Level 3) shown in Figure 20.2.

FIGURE 20.2
Floor plan showing just the exterior skin and core (the interior has not yet been designed).



2. Create a room and add a door, as shown in Figure 20.3. Select the front wall with the door and one perpendicular wall and create a group by clicking the Create Group button in the active contextual tab.

FIGURE 20.3

Model group created out of the elements of the first room you created.




When creating the group, you only chose one of the perpendicular walls (the one on the right side) because you need to repeat the module along the length of the space. If you added *both* perpendicular walls to the group, you would end up with *overlapping walls* when the unit was copied along the length of the building. This would result in lots of warning messages to deal with. Not taking these warnings into account would later affect the scheduling of walls, so you need to be smart about how you make your groups.

3. Once the Group tool is activated, you'll be asked to name the group. As soon as this task is finished, the new group will appear in the Project Browser under Groups ► Model Node. The group is listed as a model group because all elements we selected to become a part of the group were model elements.
4. Before you make any changes to the group, take a look at a symbol showing the group origin (Figure 20.4).


The group origin symbol (insertion point) is placed at the middle of group geometry by default, but you can change it to what you feel will be the most appropriate and practical point of insertion when you pick the group to reuse and place again in the project. Move the group origin symbol to the intersection of two walls, which will help when placing new instances of the group. To do so, place the mouse over the intersection of the X and Y axes and drag it to a new position, or use the Move tool.

FIGURE 20.4
 (Left) Group origin
 default location.
 (Right) Origin
 moved to new
 location.



There are many possible ways to proceed in the group placement process. You can insert more instances of this group along this wing of the building using the Copy Multiple Instances tool or the Array tool. An alternate approach is to use the Project Browser, and drag and drop the group instances into the view (Figure 20.5). Let's see how this works.

FIGURE 20.5
 The group can be
 placed from the
 Project Browser.




1. For this exercise, drag and drop from the Project Browser to place new instances of the group in the floor plan. (You can place groups in 3D views as well, but the common use case is in plan.) Once you drag the group from the Project Browser into the view, release the mouse button and take your time zooming in to the insertion point in order to get the correct snap without stressing your hand.

After choosing the insertion point, you'll see that the walls belonging to the group clean up with other walls that do not belong to the group. This is perhaps the most profound difference in behavior between groups and links (which we'll get into a bit later): essentially, linked elements cannot interact with elements in the model they are linked to, while walls belonging to a group will clean up with walls from the main model.

2. Continue to place groups until you arrive at a more developed floor plan. To speed up the process, try using the array command to array the group across the floor plan—just be sure to un-check the Group and Associate option in the Options bar, or you'll end up with redundant groups. (Figure 20.6).

FIGURE 20.6
More groups
are added to the
floor plan.



3. With the basic unit established, you can start adding more complexity and really see the power of groups. Because all the groups are instances of the original model group, any changes to this group will affect the others. Select any one of the groups in the floor plan, and take a look at the Group panel in the ribbon:




4. To change a group during the process of design, select the Edit Group button. This takes you to the Group Edit mode, where a new Edit Group ribbon panel will appear.




The drawing area will turn a pale yellow, indicating that you are now in a special Group Edit mode (Figure 20.7). The group editing panel appears appended to the end of the ribbon.

FIGURE 20.7
The Group Edit
Mode is indicated
with a pale yellow
coloring of the
drawing area, sig-
nifying the special
mode. The floating
group editing bar
offers group-
specific tools.



While in Group Edit mode, move the door to the other side of room. When you click Finish, all the other group instances will update with the new door location (Figure 20.8).

FIGURE 20.8
Editing one
group propagates
changes to all other
instances of the
group.



The need to change a design is quite common throughout the lifecycle of a project; projects evolve over time and are never complete with the first iteration. Groups are not fixed entities and are easily edited. You can make changes and add new elements to a group while in Group Edit mode seamlessly and at any point of your design process. You can access the modeling commands while editing the group, in order to add these elements. If you need a new component added to the group, it's just a matter of creating it while in Group Edit mode.

The Group Edit toolbar provides the following features:

Add This allows you to add any element from the project as the current object in the group.

Remove This allows you to remove elements from the group.

Attach Detail This allows you to add view-specific annotations, which will become attached details and will be displayed as a subcategory of the model group in the Project Browser.

Group Properties This provides access to the Group Properties dialog box, where you can edit the group's name. The level the group is attached to and its offset from that level are presented but not editable.


At this stage, you can generate an area report to check the requirements, and the design can continue to evolve. You will now add the bathroom and some furniture. Both of these will expand on the concept of groups by making new groups and nesting them inside of the unit group. You'll also add some details (dimensioning) to create an attached detail group. To conclude, we are going to explore alternatives in the room's layout.

Adding Rooms to a Group

The next step involves adding rooms so that you can schedule the room units by areas or by room type.


1. Select the unit group, and then click Edit Group in the contextual tab. Once in Group Edit mode, use the Room tool (on the Home tab) to place the room. It will automatically be added to the group (see Figure 20.9).

FIGURE 20.9
While in Group
Edit mode, place
a room.



2. Click the Finish button on the Edit Group panel to finish the change to this group and populate the change into all other instances of this group.
3. To verify that the rooms now exist, tag them using the Room tag command on the Room and Area panel on the Home tab, as shown in Figure 20.10.


FIGURE 20.10
Tagging the rooms.



Note that when you add a room tag to a grouped room, the room will get propagated but not the tag. You will still need to manually tag all the rooms in the copied groups.


4. To see how many rooms you have and their areas, create a room schedule that includes name, number, and area (see Figure 20.11). This can be useful for making decisions about the composition of a floor plan and seeing if you are meeting program requirements as you make changes to the design.

FIGURE 20.11
Room schedule
showing areas.




Nesting a Group into Another Group

Often, repetitive units can be a part of other repetitive units. For example, a standardized bathroom unit will repeat throughout many hotel rooms. To support this in an intelligent way, Revit offers a methodology of nesting a group into a group so that the integrity of the unit is maintained. The bedroom group we just created can be completed with the addition of a nested bathroom group and furniture group. As shown here, a nested group appears in the Project Browser as a subnode of its host group.



Following a typical workflow, you can start designing the bathroom by adding walls and plumbing fixtures. Once you've added new walls and fixtures, select and group them, as you did the initial walls (see Figure 20.12). You'll notice that walls in groups clean up with walls outside of the group, making the grouped wall interaction with walls outside of the group seamless.

FIGURE 20.12
Build the bath-
room with walls
and fixtures, and
then group them
as a new group.




To add the bathroom group that you just created to the bedroom unit group, select the group, click Edit Group, and use the Add button in the Edit Group panel. By selecting the bathroom group, you add it as a nested group in the Bedroom unit group. You will notice that a new entry appears in the Project Browser under the Bedroom Unit node.



Finish the Group Edit mode by clicking the Finish button. The bathroom will be propagated to all other instances of the group (see Figure 20.13).

FIGURE 20.13
All the instances of the group are updated.



Adding Detail Elements to Groups


Now that the unit is more or less complete, you can start adding some annotations and dimensions to the plan in order to better communicate the design. Begin by dimensioning and adding text or tags in one of the units. To repeat the dimensions in other units, you can again take advantage of group functionality.

Select a dimension and group it to make a new detail group. You'll be prompted to give the detail group a name. To then add the detail group to the model group, select the group and then click the Attached Detail Groups button in the Modify Model Groups tab. This opens the Attached Detail Group Placement dialog, where you can choose the detail group to attach.



Once you have a detail group, you can attach it to other instances of the group with relative ease. To do so, select a group and then use the Options bar button Place Detail to attach the detail group. The details will be added to the group (see Figure 20.14).

FIGURE 20.14
Details can be attached to group instances.




Nesting a Group from a Previous Project

To continue designing the unit, you can add furniture to one of the units. You can place the beds, dressers, and chairs and then group them just as you did with the bathroom.

What if you already have a similar grouping of furniture from a previous project that you'd like to use in this project? To use a group from another project, open the other project, right-click on the group in the Project Browser, and choose the Save the Group to File option in the context menu. This creates an RVT file of that group that can be reused in other projects. You can also copy/paste a group from one project to another.

To reuse a saved RVT file as a group, select Load as Group from the Load from Library panel on the Insert tab, as shown in Figure 20.15. The dialog box that appears has some special options that let you choose whether to include attached details or levels and grids when loading. If the Attached Details option is checked, you will import any details attached to the file, such as dimensions and tags. Levels or grids can also be imported with the group, if necessary, but don't bring in levels and grids if you don't need them.


FIGURE 20.15
The Load as Group option.



Load the file furniture.rvt to use it in this project.

The group will appear in the Project Browser and can be dragged into the view like any other group. Drag the group into the view and add it to the unit group. Once you do that, it will propagate to all the other units, as shown in Figure 20.16.

FIGURE 20.16
Furniture group
nested into the
room group.



Making Variations to a Group Instance

In just a few steps, you've developed quite a complex structure with extreme flexibility. Not only can Revit manage model and detail groups, but it can also work with different levels of nested groups within the main group. For example, if an alternative layout is needed, Revit provides tools that can facilitate a smart workflow. By right-clicking on the group's name in the Project Browser, you'll get a better picture of the possibilities (Figure 20.17).

FIGURE 20.17
The context menu
for groups.



The options displayed here provide the following functionalities:

Duplicate This creates a copy of the group with a new name and allows you to edit a copy of the group without disturbing the original and affecting all other instances of the group. This is helpful when you need a significant geometric variation in design from the first group. You can then at any point swap groups using the Type Selector. Just keep in mind that groups swap out about their insertion point. So be sure that when you swap groups (using the type selector) they share an appropriate insertion point.

Copy to Clipboard This provides an easy way to choose a group and copy it to other levels.

Select All Instances This selects all instances of the group in the entire model. Use this to quickly make selections for the purpose of deletion or swapping.

Create Instance This provides an alternative means of placing a group. It's as if you were dragging the group from the Project Browser into a view.

Match This functions the same way as the Match Type tool. Enable the tool by selecting it. By first clicking Room Type A and then clicking a room of Type B, you can change Room B into a room of Type A. Another way of doing this would be to just select a group in the view and change the type directly using the Type Selector.

Edit This opens the group for editing in an independent session rather than in the active project. This allows you to see and edit the group in isolation without the clutter of the project.

Save Group This allows you to save the group as an RVT file and reuse it later in other projects. This option leads to a dialog box where the new file's name is by default the same as the group's name, and you can decide whether or not to include the attached Detail Groups as views.

Reload This lets you reload a group. Use this if you edited the group as a separate file and saved the changes, and now need to reload it to get the most up-to-date version. Reload is not automatic; you'll be prompted to locate the file on disk to do this.

In our example, you can duplicate the unit group, giving it a new name, and then make edits to the newly created group. You can then swap entire groups just as you would any other component in Revit (Figures 20.18 and 20.19). Thus, with just a few clicks, you can explore design variations and propagate changes quickly and reliably.

FIGURE 20.18
Groups before
changing types.





FIGURE 20.19
Groups after
changing types.



If you create a furniture schedule, you will be able to see easily how the changes to the design affect the quantities (Figure 20.20).

FIGURE 20.20
Schedules update
as groups are
swapped in
and out.

Furniture Schedule	
Family and Type	Count
Chair_Corbu: Chair_Corbu	9
Couch19: Couch19	3
M_Pend-Hospital: 0615 x 2063mm	9
M_Dresser: 1220 x 1830 x 0610mm	6
Seating02: Seating02	1
Grand total:	28

To understand the full potential of Revit groups, you should be aware of some other options. Let's consider a practical example. What would you do if you need one of the Room A groups to have eight pieces of furniture instead of nine? The intuitive answer would be to duplicate the group and just take away the chair while in the Group Editor. Although this option would work, it means generating an additional new group and thus additional information for the project to handle, thereby adding more complexity, which always makes the project more prone to performance issues.

Revit groups have a feature called *Exclude*, which basically takes away selected objects from selected instances of a group without altering the rest of the group's instances. The object is not actually deleted (you have the option to restore excluded objects); it is just deactivated in that group and removed from any schedules. This option is more powerful than just overriding the view by hiding individual elements using the Hide Graphics in View by Element feature, because overriding the view would not update your schedules.

To access this option, press Tab to select an element within a group to see the Exclude icon (Figure 20.21).

Clicking the icon excludes the element, so it will no longer be counted in schedules (Figure 20.22).



FIGURE 20.21
The Exclude icon
appears when you
select an element
inside a group.




FIGURE 20.22

The schedule updates to reflect that furniture was excluded.

Furniture Schedule	
Family and Type	Count
Chair-Corbu: Chair-Corbu	0
Couch19: Couch19	3
M_Bed-Hospital: 0813 x 2083mm	9
M_Dresser: 1220 x 1830 x 0610mm	6
Seating02: Seating02	1
Grand total:	27


You can always add the element back to the group by right-clicking and choosing **Restore All Excluded** or by clicking the icon again. Note, however, that the icon will not show up if you are in **Group Edit** mode.

Repeating Groups on Other Levels

If parts of the whole floor plan need to be repeated on other levels, you can make a group out of many groups, generating a new high-level group in the **Project Browser**. For example, you can select the six bedroom-unit groups (also containing nested groups and attached detail groups) and make a new *master* group, which we have called **Complete Level** (see Figure 20.23).

FIGURE 20.23


A master group for the entire floor layout.



The result of this action is represented in the **Project Browser**, shown in Figure 20.24.

FIGURE 20.24


Complete level group.



With the entire collection of rooms on the floor now in one group, you can select that group and copy it to the clipboard. From the **Clipboard** panel, choose **Paste Aligned** ➤ **Select Levels by**

Name and choose which levels you want the bedrooms copied into. In a few clicks, you can have several floors filled with bedrooms, as shown in Figure 20.25.

FIGURE 20.25
The bedroom group can be copied and pasted into other levels with a few clicks.



To recap, we chose to leave the exterior wall outside of the group to treat it as a single element that spans many levels in the project. We proceeded to make a rough definition of the room unit, which was necessary to fill out the building's wing. If we had instead added a portion of the exterior wall to the group, our exterior wall would have consisted of many separate walls, which would violate typical workflows and expectations. By placing just the initial module, we were able to quickly assess the needs for circulation and elevator locations, generate area calculations, and evaluate the design.


Then, by nesting groups, we solved the whole bathroom design and propagated it to the other rooms in one interaction, and likewise the furniture layout. If we had wanted alternatives in the room's layout, a new group made from the previous group could have been created, modified, and swapped out. For more granular changes, such as removing a seat from one single instance of a group, the Exclude option could be used to avoid making unnecessary new group types.

Making the Group a Part of the Project


The ability to make the group a part of the project is a key feature of groups. If there is a slight variation in an instance of a group that requires moving one or more objects, you can select the desired element by right-clicking on it and choosing Move to Project. This option excludes the object from that specific instance of the group and puts it into the model, where it can be freely edited without editing the group. For AutoCAD users, the closest analogy to this is exploding a block.

MOVING AN ELEMENT IN A GROUP TO A NEW LOCATION

In the bedroom design, the dresser needed to be repositioned in the last unit in the layout without making a brand-new group for such a slight variation. By tabbing into the dresser and selecting it, the designer was able to move it to the project using the context menu.



This action moved the element out of the group, allowing it to be relocated to a new position:




The left image shows the dresser before being moved to the project. The right shows the dresser moved to the project and then repositioned.

In terms of workflow, before deciding whether to move or exclude an element, the main question to ask is whether or not that change will be reused. Exclude and Move to Project are solutions for specific problems in an instance of the group, but that's where their whole power resides. Always remember that when you exclude an object, it also disappears from the schedule, whereas Move to Project does not affect scheduling at all since the object is still around.

Editing a Group in a Separate File

When you are working on a large file, it can be difficult to isolate a group for the sake of editing it. For example, when working in a complex building model where you don't want to be burdened with hiding unwanted elements to get a clear view of the group (Figure 20.26), you can use a feature that allows you to edit the group as a separate file. Since this option isolates the group in a single file, you can work from there and then save the file and use the Reload option explained previously. The Edit option that appears when right-clicking a group in the Project Browser opens the group as an independent file outside the project environment, similar to the way you can edit families independently of the project. You can have both the whole project and the single file open at the same time, working with changes that are reflected immediately after saving and reloading.

FIGURE 20.26
Opening a group
for editing in a
separate RVT file.




After editing the group, save it and then go back to the project and reload it from the Project Browser using the right-click context menu. All groups of that type will then be updated.

Detail Groups

We have touched on detail groups, but let’s look at them a bit more closely. You can create annotations to add textual descriptions, add dimensions to measure elements in a group, and then group them in what is called a *detail group*. The detail group can then be attached to instances of the model group. A detail group can be attached to a model group by using the contextual tab when a group is selected. This is a quick way to apply consistent annotations to many groups.


In Figure 20.27, a room is annotated, and then the annotations are grouped.

FIGURE 20.27
Annotations can be
made into a group.



When you multiselect all the unit groups and click the Attached Detail Groups button, your recently created detail group will be applied to all your groups in one interaction (see Figure 20.28).

FIGURE 20.28
The annotation group is then attached to a model group.



Best Practices for Grouping

Here are some aspects to consider when working with groups:

- ◆ When using groups on multiple floors (levels), the levels have to have the same floor-to-floor height if the groups are to work effectively. Currently, there is no way to make walls in a group taller from one floor to the next, so just be aware of that. Always remember that although you are working in a seemingly 2D floor plan, everything is 3D. You'll avoid propagation issues if the walls in groups have unconnected heights.
- ◆ Placing multiple instances of a group affects the file size. The group is not a link but rather is an element repeated inside the project (*instantiated*). Once you load a file as a group, it is part of the project and will add to the file size as often as it is used.
- ◆ If you need to have reduced file sizes, using links instead of groups might be a solution, although it depends on the applicability of the scenario in which you wish to use them, and most important, you should be aware of the consequences of using links.
- ◆ Try not to mirror groups—create left and right versions instead. While this is more time consuming, it avoids mirrored elements that should not be mirrored (such as plumbing fixtures, equipment, and specialty furniture). As an example, mirroring hospital rooms may easily create inadvertent errors from a utility connection standpoint.
- ◆ Keep nested elements and their hosts grouped together.
- ◆ Groups are very processor intensive. You can quickly get to a point of diminishing returns (from a performance standpoint) when groups contain nested groups, or entire floors have been grouped. It works great when you need to disseminate large collections of elements. But editing groups and waiting for them to update can severely affect project workflow.
- ◆ When you have worksharing enabled and you create a group, all the elements are assigned to the active workset. So although groups may contain elements on different worksets, the moment you ungroup and regroup that information is lost. So you might as well plan on assigning elements in groups to a single workset.


Understanding the Principles of Links

You've seen that Revit groups can be a powerful tool for streamlining the design workflow, but the performance hit you take from increased file size can be significant. Revit provides another tool that allows you to work with repeating elements and avoid the file size problem: links. Be aware that links have limitations that you might not be comfortable with, so make sure you understand these limitations before deciding to go with the linking method.

To show how links work, we'll continue with our example project.

When you select a group, you will notice that the Link button appears in the Modify Model Group contextual tab. When you click the Link button, the dialog box shown in Figure 20.29 appears. It presents two options that you need to understand: Create New and Use Existing. In other words, is the information contained in the link going to a new file, or will it be added to an existing file?

FIGURE 20.29
Converting groups
into links.




In this particular case, we are creating a new file, so Revit will automatically create a new file in the folder of the project (by default) and replace the group with a link in the exact same place (see Figure 20.30). The process does not involve any user action at all apart from clicking the Link button. This might look like the ultimate solution for managing file size. In certain cases this may be true, but let's look more closely at the implications.

Walls in a linked file will not create clean wall join conditions with the host file, which can make scheduling of rooms particularly difficult. In fact, the first thing you will probably notice once you convert the group into a link is that the walls belonging to the link do not clean up with walls belonging to the active host model, because joining between elements in a link and those of the project isn't possible. You can override this behavior by selecting the Room Bounding checkbox in the type properties of the link. This will allow the walls in the linked file to enclose space and let you place rooms.

WALL CLEANUPS IN EARLY DESIGN

During the early stages of design, seeing wall joints clean up is necessary for graphical reasons, but it's not needed at this stage for technical accuracy. In conceptual and schematic design, you typically don't want to waste a lot of time dealing with wall join cleanups when you are trying to get the design down. To keep things simple, set the Coarse Fill setting of the wall properties to Solid Fill and set the Color to black. This will give you a great schematic level print of the walls and not show you any of the wall materials. Then, when you are ready to advance the design, change from Coarse to Medium or Fine in your View Level.

FIGURE 20.30
A group converted into a link on the fly. Note that the rooms no longer have boundaries defined by the walls.



If wall cleanups or definition of rooms are not a serious issue in your workflow (an example would be a renovation of an existing building), using links could be a good solution to help manage file size. Even so, it is nice to know that as soon as you *bind* the link (convert it back into a group), you'll get wall cleanup and valid rooms again.

Note that binding links will work on any instance of a linked Revit file. This brings the link file completely into the project file and severs the link to the external file. For AutoCAD users, the closest analogy is binding of XREFs.

Common Link Use Cases

Links are well suited for workflows where you don't need a tight connection between elements, such as linking entire buildings or site plans into your project file. Links are commonly used when working with the following kinds of projects:

- ◆ Separate buildings on a shared site plan
- ◆ A site plan and contextual masses
- ◆ Large-scale divisions in building mass and program
- ◆ Other disciplines (Structure and MEP)

In the following examples, you'll see various situations when linking files can be useful.

Multiple buildings on a shared site plan At Koolhaas's station complex in Lille (see Figure 20.31), there are buildings designed by other architects directly over the station's roof.

Interaction among the models is important in order to identify heights and possible restrictions between the buildings. This interaction could easily be created by linking the buildings for coordination, with each model residing in a separate file. What's more, each building could also use nested links or groups. For example, when working on the building over the station, you could link the train station into your model. Within the train station could be links to mechanical system files. All of these elements would be visible in the main host file. This form of nesting keeps file size down and makes working manageable.

FIGURE 20.31
Rem Koolhaas's
train station would
be a good project
candidate for links.



Photograph by Guillermo Melantoni

Identical buildings on a shared site Another use would be a project where a housing unit is duplicated many times on a site. For example, if you have three identical buildings, you would model one building, link it into a site file, and then make two additional copies. If you then edit the original housing file and update the link, all three instances of the linked file will update in the site file.

COORDINATION WITH OTHER DISCIPLINES


The linking method is not only applicable to buildings with repeating units but can also be used as a methodology for working in a highly coordinated way with other engineers and consultants using Revit Structure or Revit MEP. This workflow is designed as a fully collaborative use of BIM for all the disciplines. Using links, you can integrate structural framing, ductwork, and mechanical systems into your base architectural project for coordination. In a traditional process, this coordination was based on endless revisions, miscommunication, and colliding systems that ended up being resolved on-site during construction at tremendous cost. The Revit BIM platform provides transparent connections between Revit Architecture, Revit Structure, and Revit MEP. In fact, you can open a Revit MEP or Structure file in Revit Architecture because they are all based on the same technology. The only difference will be the available tools: with a Revit Structure or MEP file open, you'll be able to select and modify ductwork, for example, but you won't be able to make new ducts.

Linking different disciplines in Revit provides better coordination and even allows for collision detection. This toolset will not be covered now, but you should be aware that it is all possible in Revit using what are called Copy/Monitor and Interference Checking. For further reading on these subjects, consult the Revit help documentation.

Linking Files

To link an RVT file, choose Link Revit from the Insert tab. The dialog box involves some decisions in terms of how to position the linked model in a project and which worksets to open, as shown in Figure 20.32.

FIGURE 20.32
The Import/Link
RVT dialog box.



The positioning defines the location of the linked model inside the project and can be manually or automatically done. Automatic positioning of the link provides the following options:

AutoCenter to Center This aligns the 3D center points of both models.

Auto-Origin to Origin This places the world origin of the linked file at the model's origin point. If the linked model was created far away from the origin point, linking with this option may put the linked file far away from the main model. (When this happens, Revit may warn you and automatically use the Center to Center option.)

Auto-By Shared Coordinates This places the linked file geometry according to the shared coordinate system created between the two files. If no shared coordinate file has been created, Revit will alert you. These Shared Coordinates settings can be found on the Manage tab; under the Project Location panel, click Coordinates:

Acquire Coordinates This allows taking coordinates of the linked file into the host model. There is no change to the host model's internal coordinates, but it acquires the true north of the linked model and its origin point.

Publish Coordinates This allows publishing the origin and true north settings into the linked model. Revit understands that there may be other things in the linked file and that you may not want this to be a global change to the linked file. An additional dialog box appears, giving the option to name separate locations for each set of coordinates.

Specify Coordinates at a Point This allows you to manually key in X, Y, and Z coordinates relative to the origin or to define where the (0,0,0) will be.

Report Shared Coordinates This shows the E/W (East/West, X), N/S (North/South, Y), and Elevation (Z) coordinates of any point in the model.

Manual—Origin The imported document’s origin is centered on the cursor.

Manual—Base Point The imported document’s base point is centered on the cursor. Use this option only for AutoCAD 2009 files that have a defined base point.

Manual—Center This sets the cursor at the center of the imported geometry. You can drag the imported geometry to its location.


Special Link Features

When you use links, keep these concepts in mind because they can aid in your workflow and help you set proper expectations:

Scheduling elements in links You can schedule elements in link files without any trouble by choosing the option Include Elements in Linked Files, located in the Schedule dialog box.



Displaying nested links in the host file This is another key feature because you can have two different states: Attach and Overlay. As with AutoCAD’s XREFs, if a file has a nested link set to Attachment, when you link it into another one, you will see both files. If the nested link is set to Overlay, it will not show up in other files. This setting is located in the dialog box accessed by choosing File ➤ Manage Links.



Using nested links in the Project Browser The Project Browser provides the same kind of interaction for links as it does for groups: dragging and dropping will place the link into the view. By right-clicking on the link, you’ll get nearly all the options available in the Manage Links dialog box (Reload, Unload, Open, and Reload From).

Making areas and area boundaries in linked files visible and schedulable Since Revit Architecture 2009, you can now show areas from linked files, and this includes the ability to create color fill plans that color linked rooms or areas.

Dimensioning and establishing constraints You can align and dimension to elements in linked files.

Copying and pasting elements By Tab-selecting an element embedded in a link file, you can copy it to the clipboard and paste it into the host file.

Controlling and changing visibility properties You can turn categories of linked files on and off, giving you total flexibility in controlling the display of information.

Binding a Revit link within the parent model This option creates a group inside the parent file, fully integrated to the project. You'll learn more about binding later in the chapter.

UNLOADING AND RELOADING LINKS

If you link a Revit file into the model, you cannot open the link without unloading it from the project. In that case, you need to unload the link, make the necessary changes, and then reload the link after saving what you've done, or open a second session of Revit (you can run multiple instances of the Revit application at the same time) and open the link there. This way, you can have direct feedback on any changes made in the link by reloading in the session with the parent file.


Controlling the Visibility of Links

The linked model will display levels, grids, and any annotations they have because the default visibility is defined by the model's visibility. In an elevation, you will see not only the model's levels, but also the linked levels, which may become a problem. To solve this, apply custom visibility settings that override the link in the view. In the Visibility/Graphic Overrides dialog box, choose the Revit Links tab, and override visibility by selecting the Custom radio button. You can control the visibility of all categories in a linked file by using this custom setting, giving you practically unlimited flexibility for what you can display.



This allows you to turn off visibility of categories in the link file. To hide levels, choose the Annotations tab and turn Levels off, as shown in Figure 20.33.

FIGURE 20.33
You can turn off visibility for categories in a linked file independently of the host file.



Deciding Whether to Use Groups, Links, or Both

So, is it better to use links or groups to handle repetitive content? Or is there a way to capture the advantages of both groups and links without their disadvantages?

The answer depends on the project and definitely on the workflow. How much interactivity do you need between the elements in the link and the ones in the project? For smaller projects, where file size and performance are not an issue, groups should work fine. If you have a huge project with many instances of repeating elements, linking will reduce file size and make working on the model faster. But if you need control over rooms and cleanups, groups are a better solution.


Had we worked with links for the room units in the previous example, the rooms' file size would not have been a major issue since we are working with instances of a link whose information (and file size) resides outside the project file. If you have a massive repetition of something modular, you might want to consider using links over groups.

If you do go with links but later change your mind, no problem: it is possible to convert the link into a group by *binding the link*, which transforms it into a group and thus adds it to the project. An example would be linking an entire floor plate full of hundreds of rooms.

In our example, we could have linked the furniture since there is not much interaction with anything else in the project. Because models of furniture can increase the file size, this approach could be a smart way of managing size. We can start working with the furniture as simple components in the floor plan and, as soon as we have something, group and afterward link them. As soon as we have the link, we can just copy it around the whole floor plan, resulting in a marginal file size (we don't have 100 beds, but one bed repeated in 100 instances). Keep in mind that there is no way of excluding objects from the link without affecting the rest.

If you need to work with the group as a link to reduce file size during the project, you can link it (thus losing wall cleanups) and then later bind it back for final construction documentation. When you bind the link, a dialog box will open, as shown in Figure 20.34.

FIGURE 20.34
When binding links, you can choose to include details, levels, and grids.



Be careful: as stated in the lower panel of the dialog box, if you bind levels and grids, Revit will create additional uniquely named levels and grids in the project, duplicating information and possibly causing problems.

All in all, binding links is a smart workflow that allows working with a sensible file size while restoring the lost relationships within the project as soon as you bind. Depending on the workflow and the size of the project, this seems to be the best of both worlds. Just remember that while the file is linked, you lose many key benefits of using a fully integrated building information model.

Final Considerations

Now that you've gained an understanding of the basic differences between groups and links, there are still some important things to be aware of. We are not trying to sell you on using one or the other, but rather to help you take full advantage of both tools' potential to solve specific problems. Ultimately, your project's criteria should dictate your direction.

The relationship between groups and links is intended to improve workflows. Here are some examples:

- ◆ When you're looking for a tool that maintains consistency throughout the project and enables the management of repetitive content, when file size is not an issue and interactivity with the rest of the model is crucial, groups are the way to go. (Remember, you can at any point swap the group into a link and vice versa.)

- ◆ When you are looking for a tool that lets you work with a massive repetition of elements that have little or no interactivity within the project *and* you want to keep file size down and still be able to schedule the project's contents, think about using links. From a project management standpoint, you could even have someone else on the team work on that information and eventually bind it all into the model, thereby taking advantage of how groups interact with the model.
- ◆ If you want to keep elements as links but still need rooms, you could use room separator lines as a workaround so you will be able to define rooms without binding all the information into the project. This requires some manual work, but it can be a practical solution if you give some intelligence to the separators. Using the Pick Lines tool when drawing room separation lines gives you a chance to lock the line to model elements and thus capture design intent and keep elements connected.

The Bottom Line

Work with repetitive elements. Many projects have repetitive elements and can benefit by using groups and links efficiently.

Master It Think of a scenario in your own practice where elements repeat and how you might use Revit groups to solve the problem.

Understand the use of groups. Groups are a powerful design tool. Anyone working with repetitive elements needs to understand how they work.

Master It Describe a fundamental benefit of using groups.

Understand the principles of links. Links are Revit's second major tool for repetitive elements, avoiding the file size and performance issues associated with groups.

Master It Using a link paradigm means that the BIM model now depends on links to external files. Even so, the links can be scheduled, dimensioned to, and graphically altered. Despite that, there are still some limitations. What are they?

Decide whether to use groups, links, or both. Knowing when to link a file can improve file performance and provides an easy way to operate on large clusters of building data. You can hide links, remove them, and work on them independently. Knowing when to use groups can help replicate repeated elements quickly. Knowing how and when to use both groups and links helps speed the documentation process.

Master It Know that links can reduce the overall file size and thus improve performance when working in Revit; imagine a scenario in which you would most certainly want to employ links over groups.

Chapter 21

Moving from Design to Detailed Documentation

In this chapter we discuss how to expand the model documentation to include construction details. Details are typically created by embellishing section or plan views of the model with additional 2D elements. The use of 2D detail families in Revit allows you to complete a set of construction documents for a client or contractor quickly and easily without the burden of having to model every component and detail within the project in 3D.

In this chapter, you'll learn to:

- ◆ Create drafting views
- ◆ Import and link CAD details
- ◆ Create 2D detail components

Advancing the Design

In the lifecycle of a project, eventually it becomes necessary to add details to the model that are then used to build the building. Historically, the conceptual design, schematic design, and design development project phases progressed through a series of refinements to develop the final set of construction documents. With a BIM process, these discrete phases are redefined, but the workflow remains essentially the same. At the stage prior to adding details, the “big idea” is refined and most plans and building sections are in place. Materiality is added to the design, and the assemblies that make up walls, floors, and ceilings are added. Creating wall sections, schedules, and enlarged plans helps to describe the project further. Eventually, the systems solidify and details are created that truly begin to define how many of these elements are put together in the field. In this chapter, we will explore a few scenarios for detailing the model and creating some of the smaller-scale drawings that go into construction documents. We will look at some of the more common methods:

- ◆ Creating details from scratch
- ◆ Importing details that have already been drawn
- ◆ Creating the detail from the model and embellishing it using 2D detailing tools

Creating Drafting Views


It isn't feasible to model every single construction detail in 3D within Revit. A 2D detail often provides enough information for construction in the field. To this end, Revit provides a means of drafting in views strictly used for 2D information that can be placed on sheets like any other view. These views are called *drafting views* and document typical or special details of the project. They can be created by drawing the details directly within the view or by importing details. They can also have legends, maps, text, or any of a variety of graphics necessary for a construction document set. When placed on a sheet, drafting views have the same intelligent referencing as all the other views within Revit. Even though drafting views present only 2D information, they are still tied parametrically to sheets, so all the references are dynamic and coordinated.

To create a new drafting view, follow these steps:



1. From the View tab, choose the Drafting View tool.
2. In the dialog box that appears, enter a name in the Name field (Figure 21.1) to name the view. This is the default name that will appear when the drafting view is placed on a sheet in the drawing set.

FIGURE 21.1
Making a new
drafting view.




3. Using the Scale drop-down list, choose a scale.
4. Click OK. A new node, Drafting Views, is added to the Project Browser. This new drafting view is primed for either drafting a new detail or importing existing CAD details. This essentially creates a blank sheet within Revit for you to begin drafting (or importing) 2D details.

Importing and Linking CAD Details

It is common to have details from manufacturers you'd like to include in your drawing set, or you may have standard details from an office detail library that need to be included in your documents. What if all these files were created in a 2D CAD application? As we discussed earlier, you can easily import these 2D details into Revit to be used and reused across many BIM projects.

To see the types of CAD files you can import into Revit, open the Insert tab, and choose Import CAD to open the dialog box shown in Figure 21.2. The Files of Type pull-down menu contains all the file types you can import into Revit: .dwg, .dxf, .dgn, .sat, and .skp. You can also import images into Revit by using the Image command, located next to the Import CAD button on the same tab.

FIGURE 21.2
The Import CAD
Formats dialog box.



Later in this chapter, we'll see how each of these file types is used, but first we want to make sure you understand the distinction between importing and linking.

Linking vs. Importing

Use linking when you have files that will update throughout the design process. Imagine a person in your office who does nothing but develop 2D details and who works in parallel with you. With linking, the details will update constantly, as revisions are made, and you won't need to manually re-import the work. By linking the file into Revit, you ensure that the information will update as the source file changes. Linking creates a *live* connection to a file. This allows you to work on the linked file and then have the Revit model update to reflect the changes in the link. This behavior is similar to an XREF in AutoCAD.


Use importing when you want to embed the CAD file within the project file itself. This might be of value if you need to modify imported details slightly, because unlike linked files, imported files can be exploded and thereby modified.

LINKING CAD FORMATS

The ability to link one file into another can be helpful in a collaborative environment. Perhaps someone on your team—a person working on details within your office or an external consultant—is working in a CAD environment while you build the project in Revit. Linking lets you have their latest work updated in your Revit model. If you import without linking, you get a static file that will not update if changes are made to the original file. When you link, however, it's possible to always get the latest state of the DWG by updating the link within Revit.

From the Insert tab, choose Manage Links to access the dialog box shown in Figure 21.3. Using this dialog box you can reload, unload, import, or remove a CAD link, or see what is already loaded.

FIGURE 21.3
The Manage Links dialog box.



IMPORTING OR LINKING CAD FORMATS

Site plans, consultant files, and details or drawings done with CAD technologies on prior projects are all examples of information you may want to link or import into Revit. This isn’t limited to 2D data; you can link 3D files as well. The data you import or link into your model can be view specific, meaning that it is imported in *one* view only—using the Current View Only import option—as opposed to all views. Start by opening the view into which you want to bring data. Go to the Insert tab, and then choose either the Import CAD or the Link CAD button, depending on your workflow. As shown in Table 21.1, you can link/import five types of CAD files in 2D or 3D in Revit.

TABLE 21.1 Importable/Linkable CAD File Types

EXTENSION	TYPES OF FILES
.dwg	Files made from AutoCAD or other applications that can export to this industry standard format.
.dxf	Drawing Exchange Format files. Most software packages can write to DXF in addition to their native format.

TABLE 21.1 Importable/Linkable CAD File Types (CONTINUED)

EXTENSION	TYPES OF FILES
.dgn	MicroStation native files.
.sat	Standard ACIS text files; many modeling and fabrication applications can write to this file type.
.skp	SketchUp native files.

Linking If you link a file, any changes made in that original file will be apparent in the Revit file in which it was linked. If your office or team workflow has personnel who are dedicated to working solely on details in a 2D environment, they can continue creating and changing the details in CAD and you can update the link to reflect the changes automatically. You can also manipulate the linked file through the Manage Links dialog box (Insert ➤ Manage Links).

Note that you cannot modify a linked import, because modifying any information requires explosion of the import, which the linking method does not allow. However, you do have the ability to manage the layers in the linked file and turn them on or off as needed, without the ability to explode the file. This can all be done through the Visibility/Graphic Overrides dialog box.

Importing An import is not tied to an external file, which means you can modify the CAD drawing directly in Revit by first exploding it. Once an import has been exploded, the import ceases to exist and everything becomes part of the Revit file. The import is translated into a bunch of lines and they are just that: lines, with no inherent intelligence. In addition, any line names or styles from the CAD layers that have been imported will become Revit line styles.

OPTIONS DURING IMPORT/LINK

There are a series of options that you will need to understand and set during the Import/Link function, depending on the result you would like to achieve with the file that will be imported or linked:

Current View Only Selecting the Current View Only check box (located at the far left of the dialog box) brings the linked or imported file into *only* the view that is currently active. It's not always desirable to see your CAD files in all the views in your model. A site plan, as an example, doesn't have to be seen in all floors of a building—just the site view and maybe the Level 1 (ground floor) view. More often than not, you'll want to select this check box, because you will likely want to limit the number of views in which your linked files appear. If you import with this option unchecked, the file will be visible in *all* of your views (and any new views you create), plus you'll need to manage the visibility via the Visibility/Graphic Overrides dialog box or view templates. If you import your CAD file into one view and would like to have it in others, you can easily copy and paste it from one view to the next.

LIMITING VISIBILITY OF CAD FILES

If you don't want the CAD file to be "Current View Only" so that it can display in more than one view, it's likely that you don't want it to show up in every 3D view in the project (which it will). To avoid this, create a workset for CAD files that are not Current View Only and uncheck the Visible by Default option. Make this the active workset when you link the CAD file (and make sure that this workset is visible in the current view). The CAD file will not show up in every view but will be available when you need to see it in other views.

Layers The Layers drop-down menu gives you the option to import or link in all the layers, only the layers that were visible at the time the CAD file was last saved, or a selected group of layers from a secondary dialog box. (Layers are a DWG-based naming convention. Revit allows the same functionality with levels from DGN drawings.)

Layer/Level Colors The default view background in AutoCAD is usually black, so the colors used in AutoCAD are easily visible on a black background. When you import a DWG file into Revit, which has a white background, many of the colors usually used in AutoCAD (yellow, light green, magenta, cyan) are often difficult to read. Revit recognizes this issue, and in the Layer/Level Colors section of the Import/Link dialog box you have the option to invert these colors. You also have the option to not change the colors or to convert them to black.

Import Units The Import Units section of the Import/Link dialog box allows you to let Revit autodetect the scale at which the imported or linked drawing was created and convert accordingly. Or you can do the detection manually and apply a scale factor using the Custom Factor option.



Real World Scenario

TIPS ON IMPORTING CAD DETAILS

It is not possible, or always desirable, to communicate the entire project in 3D. At times your workflow will demand using 2D graphics from a past project, manufacturer's library, or other resource. To optimize the performance of imported CAD files in your model, we strongly recommend that you delete all the superfluous data in the CAD file *before* importing it into Revit. Here are some general tips to help your workflow:

- ◆ If your import contains hatches or annotations that you don't intend to use in Revit, delete them before importing.
- ◆ Import only one detail at a time so you can take better advantage of Revit's ability to manage sheet referencing. If you have a series of details organized in a single CAD file that you'd like to import into Revit, isolate each detail, save it as a separate file, and then import.
- ◆ Consider annotating in Revit and removing the annotations from CAD. This can help keep consistency in your documents. If you use arrowheads or leaders in your CAD file, they will import into Revit (when exploded) as polylines. Consider drawing the arrows within Revit.

- ◆ Make sure you import the CAD details using the proper line weights, colors, and styles. Check your CAD file before importing into Revit to make sure it is consistent with your office's standards.
- ◆ Every time you explode a CAD file in Revit, you add objects to the database. An inserted CAD file is one object. An exploded CAD file in Revit consists of many objects—maybe thousands of objects. For best performance, we recommend you explode CAD files as seldom as possible. If you must explode the CAD file, be sure to remove any unwanted or unneeded linework from the file in CAD before inserting it and exploding it in Revit.
- ◆ Revit doesn't allow line segments shorter than 1/32". Take care when exploding CAD details with very small line segments. Revit will remove them upon exploding.

IMPORTING CAD DETAILS

The ability to communicate and share design intent with others is critical to any design and documentation process. With that inevitably comes the need to translate or transfer ideas, drawings, and information from one format to another to create a versatile workflow. Revit recognizes this need to share information and allows you to import and export CAD-based drawings to aid in communication.

If you're working with someone who produces details using only CAD, you can incorporate their work into your Revit model without disrupting the workflow.

It is common to have a library of existing details that can be used for many projects. This example demonstrates the process of getting these details into a Revit project using a DWG file you can download from the book's companion web page (www.sybex.com/go/masteringrevit2010):

1. Create a new drafting view. Under the View tab, choose Drafting View and give it a custom scale of 1:1.




2. Link your CAD detail. In this example, we have a typical doorjamb detail that is already noted and dimensioned. Choose Link CAD from the Insert tab, and set these options:
 - ◆ Colors: Black and White
 - ◆ Positioning: Auto Center to Center (the default)
3. Choose detail B2020A-01.dwg (located on this book's companion web page), and click OK. This will import your CAD file into a new drafting view.


- 4. Now you can change your view scale to match the scale in which you'd like your detail to be displayed. For your detail, change the scale to read 1½" = 1'-0".

In this detail, note that the wall tags are unnecessary. Unfortunately, they were not deleted in the original CAD file (the recommended practice) before we linked the file.

So, you have two options. One is to address the issue in CAD—delete the tags there and relink the file. For this exercise we'll assume that's not feasible. Your second option is to manage the layers of the link within Revit and simply turn off the layer on which the tag has been placed. As mentioned earlier, you can do this using the Visibility/Graphic Overrides dialog box. You can also do it through Revit's graphical interface. Selecting the detail will expose useful tools in the Ribbon, such as the Query tool:




Clicking the Query button allows you to select elements in an imported or linked CAD file and discover what layer they belong to. With Query enabled, you can select any of the lines or hatches of the CAD file. Choose the border of the wall tag. This gives you the dialog box shown here, which tells you the Entity, its Layer, Block Name, and Style:



The Import Instance Query dialog box also allows you to delete the entity (which we do not want to do here) or hide the layer. Choosing Hide in View turns that layer off in this view. It can be turned on again with the Visibility/Graphic Overrides dialog box.

Now the detail is complete, you can drag and drop the drafting view from the Project Browser onto the sheetA350 Details. If you need more details from CAD files for our project, simply create more drafting views.

The finished detail is shown here. The imported detail on the printed sheet should be indistinguishable from the details created in Revit.



Creating 2D Detail Components

Creating two-dimensional detail components is a powerful way to utilize parametric capabilities built into Revit to produce the necessary details that will help tell the contractor how to create the building. Learning how to leverage these detail types can make the detailing process much more efficient.

Detail Groups

Detail groups are similar to blocks in AutoCAD. They're collections of 2D graphics (drafting lines, other detail groups, 2D content) and represent details that you'll probably want to use again and again in the same or different views. A classic example is wood studs or blocking. You can easily set up a Revit group and use that group over and over in the model. Doing so helps control consistency throughout the drawing.


To make a detail group, create the detail elements you'd like to group and then select them. In the contextual tab that shows up, select the Create Group button. When you're prompted for a group name, name the group something clear rather than accepting the default name Revit wants to give it (Group 1, Group 2, and so on).

To place a detail group, use the Detail Group button in the Detail panel on the Annotate tab. Then use the Type Selector to choose which group you want to place.



Detail Components

Detail components are 2D families that can be made parametric. They're similar to detail groups, but are created in the Family Editor and can thus be designed with dimensional variation built into the family. In other words, a full range of shapes can be available in a single detail component. Because they are families, they can also be stored in your office library and shared across projects easily.




To add a detail component to your drawing, select Detail Component from the Component drop-down list located on the Annotate tab. Use the Type Selector to choose which detail to place. If you already have preloaded detail components in your project, you can search in your Project Browser, under Families ➤ Detail Items.

If you need to load a new component, click the Load Family button that shows up in the Ribbon when placing a component. Browse to the Detail Components folder. Revit has a wide range of common detail components in the default library.

To make a new detail component, use the Family Editor and Detail Component.rft template, accessed from the Application menu, under New Family. Once in the Family Editor, you can begin drawing lines, adding parametric values, and then save the file as an independent family that can be loaded into any project.

Masking Regions


A masking region is designed to hide portions of the model that you don't want to see in a certain view. This tool is known to many users of AutoCAD as the “wipeout” tool and serves to make white masks over graphics or text. The masking region places a 2D shape on top of the model that masks elements behind it.



To add a masking region to your view, click the Masking Region button in the Region drop-down on the Annotate tab.


This takes you to a mode where you draw a closed loop of boundary lines over the area you wish to mask. When you draw a masking region, you can assign the boundary lines different line styles—check the Type Selector to make sure you're using the line style you want. One of the line styles that is particularly useful for the Masking Region tool is the Invisible Line style. It allows you to create a borderless region, which is ideal if you want to mask an element in the model. A masking region is shown in Figure 21.4. Note that masking regions do not mask text, annotations, or leaders.

FIGURE 21.4
(A) The detail without a masking region; (B) portion of the detail covered with masking region; (C) masking region with invisible line style outline.



Creating a Repeating Detail Element


Repeating details are a common occurrence in architectural projects. Masonry walls, metal decking, and roof tiles all are potentially repeating shapes that can create a repeating detail. Most of these elements aren't modeled as 3D components in Revit but are repetitions of symbolic detail components.



You create repeating details in Revit by clicking **Annotate** ➤ **Component** ➤ **Repeating Detail**. This tool takes a single detail component and arrays it along a straight line at regular intervals. Open the Element Properties dialog box of any available repeating detail (click the Repeating Detail command and look in the Type Selector) to get a feel for how it's laid out.

Figure 21.5 shows the Type Properties dialog box for a repeating brick detail. When you select a repeating detail, the Type Selector is activated so that you can select any repeating detail you've already loaded in the project. Repeating details are similar to families: they have types and properties. If you don't have the repeating detail that you want loaded, it's easy enough to create one on the fly. All you need is a detail component that you wish to repeat.

FIGURE 21.5
Repeating detail
type properties.




Placing a repeating detail is similar to drawing a line: it requires just one click to indicate a start point and a second click to indicate an end point. After you do this, repeating 2D geometry will fill in between the clicks. Take these steps to create a repeating detail:

1. Select **Annotate** ➤ **Component** ➤ **Repeating Detail**.
2. Click the Element Properties button.
3. Click **Edit Type**.
4. Click **Duplicate**.
5. Give your new repeating detail a name.
6. Select a detail component to repeat.


The default repeating detail in Revit is a running brick pattern. If you look at it in detail, it consists of a brick detail component and a mortar joint (Figure 21.6).

FIGURE 21.6
Single brick detail
component.



When you create a repeating detail layout, measure the distance between the beginning of the brick and the end of the mortar joint to understand the module on which the detail will repeat. When the detail component is inserted, it acts like a Line tool and allows you to pull a line of brick, as shown in Figure 21.7. This line can be lengthened, shortened, or rotated like any other line. The line will automatically expand in length based on the module of the repeating detail.


FIGURE 21.7
A repeating brick
detail.



Detail Component Properties

If you're making a repeating detail from a component that isn't loaded in your project, you won't find it listed next to the Detail parameter in the Type Properties dialog box. This is because you first need to load that detail component in your project and then make a repeating detail component with it. The Properties window will then look like Figure 21.8. Let's take a look at the different parameters that you can set using this dialog box.

FIGURE 21.8
Repeating detail
type properties.



Detail This setting allows you to select the detail component to be repeated.

Layout This option offers four different modes:

Fixed Distance This represents the path drawn between the start and end point when the repeating detail is the length at which your component repeats at a distance of the value set for spacing.

Fixed Number This mode sets the number of times a component repeats itself in the space between the start and end point (the length of the path).

Fill Available Space Regardless of the value you choose for Spacing, the detail component is repeated on the path using its actual width as the Spacing value.

Maximum Spacing The detail component is repeated using the set spacing, and the number of repeated components is set so that only complete components are drawn. Revit creates as many copies of the component as will fit on the path.

Inside This option adjusts the start point and end point of the detail components that make up the repeating detail.

Spacing This option is active only when Fixed Distance or Maximum Spacing is selected as the method of repetition. It represents the distance at which you want the repeating detail component to repeat. It doesn't have to be the actual width of the detail component.

Detail Rotation This option allows you to rotate the detail component in the repeating detail.

Creating Custom Line Types Using Repeating Details

You can use the Detail Component tool to create custom line types (lines with letters or numbers for various services such as fireproofing, rated walls, and fencing). Note that when you create a detail component, you can't use text for the letters; you need to draw the letters or text

using lines. Figure 21.9 shows the creation of a detail component in the Family Editor and the final result used as a repeating detail in the project environment.

FIGURE 21.9
Repeating detail:
(A) in Family
Editor; (B) used
in project.



Miscellaneous Line Tools

Other tools located on the Annotate tab worth understanding are the Insulation tool, Filled Region tool, and Show/Remove Hidden Lines tool. Each serves important purposes in your drawings.

INSULATION



Designed as a symbolic representation for batt insulation, the Insulation tool works just like any other line type. Insulation can be created simply in Revit in two clicks defining the length. When you select the Insulation tool, two blue grips appear at the ends and let you change the length. The element properties of the insulation include two editable parameters:


Width This parameter is used to control the thickness (referred to as *Width* in Revit) of the insulation that is used. The Width parameter is also available in the Options bar when Insulation is selected (see Figure 21.10).

FIGURE 21.10
The width can
be set in the
Options bar.



Insulation Bulge to Width Ratio This parameter is used to control the density of the circles used in the insulation line and can be set in the Options bar when the Insulation tool is selected. In most cases, you'll have two lines representing the space in the wall where the insulation needs to fit. Revit allows you to place the insulation using the centerline of the insulation as a location line.


REGION



The Region tool is a drafting tool for making 2D hatch shapes and solid fill shapes. It can help you color surfaces or areas for graphic representations during the conceptual or design-development phase. It is also a useful tool for showing materials at finer levels of detail.


A region consists of a boundary—which can be created using any line style—and a fill pattern, which fills the area defined in the boundary. Figure 21.11 shows a region with a tile hatch pattern used to show tile in an interior elevation. In lieu of a complex stacked wall condition for bathroom walls, a region with a 4"-square model pattern is used to represent tile on the restroom wall. While this will not be reflected in any material take-offs, it is a quick way to create interior elevations.

FIGURE 21.11
Regions used for quick graphic representation of tile wall finish.



Regions can be either transparent or opaque to show or hide what is behind them. Figure 21.12 shows two regions—the left one is opaque and the right one is transparent—and how they interact differently with a model component.


FIGURE 21.12
Opaque and transparent regions.



Region Type Properties

Region type properties define how a fill appears, including pattern, pattern color, and transparency (Figure 21.13). Notice that the boundary lines of the region are not part of the type properties and are defined independently when the sketch is edited. To change the line thickness of the boundary, select the pattern, click Edit Boundary in the contextual tab, and change the line pattern in the Element Properties dialog box or from the Type Selector.

FIGURE 21.13
Region type
properties.



For each filled region that has a different pattern, transparency, or other variation in appearance, you need to make a new type. Remember that type properties propagate to all instances of the type, so making a change to one type may affect many instances in many different views. If you want to make a filled region that uses a new pattern, be sure to duplicate an existing type before you start changing type parameters.

Regions can use both drafting and model patterns, making them a flexible and handy tool for 2D workflows. As previously noted, drafting patterns are patterns that will maintain their separation distance relative to the printed sheet. Model patterns will maintain their separation distance relative to the model element. To describe this further, let's use two examples. If you were looking to use a cross-hatched pattern of lines, as in the example earlier for 4" restroom wall tile, you would want to use a model pattern. The pattern would be set to 4" and it would maintain a 4" pattern regardless of what scale the drawing was set to. So, the pattern in a 1/8" scale drawing will appear twice as tight as in a 1/4" scale drawing. In the example of a drafting pattern, you would want to use this in places where graphical consistency is more important than actual dimension. So, when creating a filled region that represents rigid insulation, the pattern might be set to a 1/8" grid. It will always print as a 1/8" grid regardless of what scale the view is set to. Just keep in mind that all of these are truly just 2D shapes with no 3D BIM characteristics.


SHOWING HIDDEN ELEMENTS WITH DASHED LINES

In visual communications between architects and engineers, when one element obscures another, the hidden element is usually graphically represented with dashed lines. Often, just a portion of an element is hidden. In the 2D CAD application, it can take a lot of manual work to

make this possible: you will need to explode the block representing the element that has to be half-hidden, and split lines so that one portion remains solid and another converts to dashed.

Revit has a special tool, Show Hidden Lines, for recognizing obscured elements and representing the portion that is hidden with dashed lines while still maintaining the complete object.

1. Select the Show Hidden Lines tool located on the Modify tab.



2. Click the element that obscures the object.
3. Click the element that is obscured. The hidden portion of the element becomes dashed. If an element is obscured with more than one element, keep repeating this operation until you get the desired look.

When you relocate or delete the obscuring element, the hidden element responds intelligently to those changes. Figure 21.14 shows an I-beam hidden by another beam. Figure 21.15 shows the results after using the Show Hidden Lines tool when the second beam is selected as an obscuring element and the I-beam is selected as an obscured element.

The Show Hidden Lines tool applies to 2D and 3D elements in all possible combinations: detail over detail, detail over model, model over detail, model over model. Right below the Show Hidden Lines tool is the Remove Hidden Lines tool, which resets the graphical display of the elements so they look as they did before you applied the hidden line behavior.

FIGURE 21.14

An I-beam
hidden by another
element.





FIGURE 21.15
The I-beam after
using the Show
Hidden Lines tool.



Linework




While Revit does a lot to help you manage your views and line weights automatically, it does not cover all requirements all the time. Sometimes you wish some lines to punch out and be stronger while others stay thinner. This is where the Linework tool comes into play; it allows you to choose any existing line style and apply it to individual edges of elements with a few clicks of the mouse.


To use this tool, click the Linework button located on the Modify tab, choose a line style from the Type Selector, and begin picking lines in any view. Once a line style is selected, you can continue selecting lines to override. To change the length of the new linework that has been applied over the existing model element, use the blue grip controls. Figure 21.16 shows an unaltered elevation of a window and the finished view.

FIGURE 21.16
The outer bound-
ary of the window
with linework
applied.

Before...




After...




Using Callouts

Callouts are another view type in Revit. They are used extensively in plans and sections to indicate a more detailed view of various conditions in any type of construction document package. Figure 21.17 shows two callouts in a wall section.

FIGURE 21.17
Wall section with
callouts.




In Revit, there are two types of callouts you can choose when creating new details: one for floor plans and one for details.



Depending on the type of callout you select, it will appear under different folders in the Project Browser. Choosing a floor plan callout will add a new view under Floor Plans in the Project Browser called Callout of <view name>.

Choosing Detail Callout will add a new view under the Detail Views (Detail) heading. The subsequent view will be by default named Detail 0, Detail 1, Detail 2, and so on (Figure 21.18). For the ease of finding and organizing your views, be sure to choose the correct view type when creating a new view.


FIGURE 21.18
The new detail
views in the
Project Browser.



Adding Information to Your Details

Now that we have discussed many of the tools used for detailing in Revit, let's step through a detail and see how these tools can be put to practical use. For this exercise, a detailed wall section will be used to illustrate a workflow. In the *Foundation_Start.rvt.ext* file found in the Chapter 21 section of this book's companion web page, Detail A14 on Sheet A301 (Figure 21.19) is a wall section at the east entry. Since we already discussed dimensioning and keynoting in Chapter 19, "Annotating Your Model," those items have already been added to the view.

FIGURE 21.19
A typical wall section before callouts are added.



In this view, the only things that have been added are text notes and dimensions. The rest of the model graphics were automatically generated the moment the section was placed in plan view. To add more detail, start by adding callout detail bubbles at each major construction join. Use the Callout tool on the View tab (Figure 21.20).

FIGURE 21.20
The Callout tool.



In this wall section, we need four 1" = 1'-0" callouts:

- ◆ The roof/wall condition (*Roof Detl, Typ*)
- ◆ The wall/floor condition capturing window heads and sills (*Floor Detl, Typ*)
- ◆ The exterior storefront (*Head @ Storefront, typ*)
- ◆ The interior storefront (*Storefront Head Detl*)

Using the Callout tool, create callouts in those locations. You can make the first three callouts by choosing the Callout tool and drawing a rectangle around the detail condition. For the interior storefront, a different method will be used that takes advantage of an existing CAD drawing by referencing it rather than making a new view of the model.


To do this, follow these steps:

1. Create a new drafting view. Under the View tab, choose Drafting View and give it a custom scale of 1:1.
2. Import your CAD detail in the drafting view. In this example, a typical doorjamb detail is already noted and dimensioned. On the Insert tab, choose Import CAD. Choose the detail B2020A-02.dwg found in the project directory on the companion website and select the following options in the dialog box:
 - ◆ Colors: Black and White
 - ◆ Positioning: Auto Place Center to Center (the default)

Click OK to link the file into the view.

3. Change the view scale to match the scale in which you'd like your detail to be displayed. For this detail, set the scale to 1" = 1'-0".
4. Right-click the view in the Project Browser (in the Drafting Views node) and rename it **Storefront Head Detl**.
5. With the drafting view for our detail created, you can now reference that detail when making new callouts. Choose the Callout tool from the View tab, but do not draw a rectangle in the view yet. First go to the Options bar and check the Reference Other View box. This activates a drop-down menu from which you can choose the detail named *Storefront Head Detl* (Figure 21.21).
6. Once the reference view is selected, draw the callout at the interior storefront head condition.
7. Keep the views related by dropping them onto sheet A350.

FIGURE 21.21
Choosing the
Storefront Head
Detl detail.
from the drop-
down menu.




Embellishing the Wall Section: The SIM (Similar) Condition

With the four details identified, you can start to add embellishment to the wall section. Beginning with the most recent detail you cut—the Storefront Head Detail condition—you need to do a little work in the section to match the CAD detail you’ll use for this condition. Because this is a unique condition you will see in only this one detail, you’ll not need to model the assembly but rather create it using the annotation tools. In Figure 21.22, you can see the current condition of the modeled wall section (A) and what we have imported as a similar condition (B) for our CAD detail.

You need to show the soffit and head condition at a lower level of detail within the wall section to make the detail work. As you can see in the detail and wall section shown in Figure 21.22, the ceiling’s condition above the window head does not coincide. The wall section needs to be edited to match the detail by extending the ceiling so that it overhangs 5” (13cm).

1. In the section view, select the ceiling and choose Edit Boundary from the contextual ribbon. Revit will alert you to the fact that the ceiling cannot be edited in the section view and will let you switch views (Figure 21.23). Choose Reflected Ceiling Plan: Level 1.

FIGURE 21.22
The callout (A) and its reference 2D detail (B).




F11 Storefront Head Detail
1" = 1'-0" REA14/A301

FIGURE 21.23
Choosing a new
view to edit the
ceiling.




2. The Reflected Ceiling Plan (RCP) view will open, and you'll be placed in boundary edit mode to modify the ceiling over the entry. According to the detail, we need a 5" (13cm) projection past the head of the door for the design (Figure 21.24).

FIGURE 21.24
Editing the ceiling
in plan view.



3. Finish the ceiling and return to the section view to see the effect (Figure 21.25).

FIGURE 21.25
The edited ceiling
in section.




Adding Detail Components

Looking at the detail, we see the need to add some blocking and 3½" (8cm) studs. This type of element is likely to be used throughout the model, so it makes sense to use a detail component rather than draw them as individual 2D lines. There will be some strictly 2D drafting lines to add later to this wall section for sealant and flashing, but first you'll need to add architectural elements like blocking.

To represent the blocking you need above the window head, you'll use a premade detail component from the Revit library and load it in the project.


- 1. On the Annotate tab, open the Component drop-down list; choose Detail Component and then Load Family. Browse to Detail Components > Div 06-Wood and Plastic > 061100-Wood Framing, and choose Nominal Cut Lumber-Section.rfa.
- 2. A list of predefined types will show up at the bottom of the dialog box. Since you are not sure which type you want right now, select a few of them by holding down the Ctrl key and selecting 2 × 4, 2 × 6, and 2 × 8 from the menu (Figure 21.26).

FIGURE 21.26
Choosing detail
components.



3. This loads the family and the types into the project. Click the Detail Component button and choose 2×4 from the Type Selector. Insert it in the general location shown in Figure 21.27. We can then rotate it and move it into place.

FIGURE 21.27
The finished detail component.




DETAIL COMPONENTS AND PROJECT TEMPLATES

If you find you are inserting the same detail components over and over again, load them into your project templates and make them readily available when you begin any new project.

EDITING A DETAIL COMPONENT


For printing purposes, the line weight for the default 2×4 detail component is too thick and needs to be adjusted. Because elements are so simple to modify, you will find yourself changing stock components to better meet the needs of your office.

1. For the 2×4 you just inserted, the line weight of the border can be changed by selecting the component and clicking the Edit Family button in the contextual tab. You'll get a confirmation dialog box before going directly to the Family Editor to change the component. Click Yes.




2. To change the thickness of the border, first hover the cursor over the element to see what it is. You'll see that this component is made of a masking region and some detail lines. Select the masking region (Figure 21.28) and click Edit Boundary in the contextual tab.

FIGURE 21.28
The masking
region.




- 3. This opens the boundary edit mode of the masking region. Select the boundary lines and use the Type Selector to change them from heavy lines to medium lines. These line styles are actually subcategories of the Detail Items category, which you can access from the Object Styles dialog box shown in Figure 21.29 (select the Manage tab and choose Settings > Object Styles). That is where you can change the line color, thickness, or pattern of the object style.

FIGURE 21.29
Viewing the line
object styles.




- 4. Clicking Finish Region completes the masking region. Clicking the Load into Project button loads the changes back into the model. You will be prompted to override parameter values of existing types. Click Overwrite the Existing Version.



The blocking displays much better, as you can see in Figure 21.30.

FIGURE 21.30

(A) Before changing the detail component line weight.
(B) After changing the detail component line weight.




5. Moving the component into place, use the fact that it was created as a masking region to cover some unwanted gypsum board above the door head.

Don't forget that you have the ability to see multiple views at once. By closing all views but this detail and the wall section, you can choose Tile on the View tab's Windows panel and see both views side by side (Figure 21.31).

FIGURE 21.31

Callout view (left);
Drafting view
(right).




6. The same procedure can be followed to place metal studs in this detail by loading them from Detail Components > Div 09-Finishes > 09100-Metal Support Assemblies > 09110-Non-Load Bearing Wall Framing > Interior Metal Studs-Section.rfa. Place them in a similar location to what is shown in the drafting detail view.

There is one more element to add before we begin drafting lines to finish the detail. There is a $\frac{3}{4}$ " piece of plywood backing over the entryway in our detail that does not appear in our wall section. You can represent that with a filled region.

1. Select the Region tool from the Annotate tab.
2. Set the boundary lines to thin lines using the Type Selector and draw a box $\frac{3}{4}$ " tall on top of the gypsum board that will represent the plywood.

3. Choose Region Properties in the contextual tab; select Edit Type and then Duplicate. Name it **Plywood**.
4. Change the Background parameter to Opaque.
5. Set the Fill Pattern to the Wood_Glu-LamBeam pattern (Figure 21.32).

FIGURE 21.32
Select a plywood-style fill pattern.




6. Click OK to complete the new type; then click the Finish Boundary to complete the filled region.

FINISHING THE DETAIL

To complete the detail, use detail lines on the Annotate tab. These lines are similar in nature to most drafting applications. Choose the Detail Lines tool, select the desired line type from the Type Selector, and start drafting. By using some thin, medium, and hidden lines, you'll be able to quickly complete this detail (Figure 21.33).


FIGURE 21.33
The finished ceiling detail.



Embellishing the Wall Section: The Model Details


Now that you have explored the use of some of the drafting tools for a typical detail, let's look at some of the more common detail types when there is no SIM (Similar) condition and only the model data. You will begin this exercise by working on the detail in the same wall section at the floor of Level 3. This will allow you to work on the head and sill conditions of the windows at the same time. The detail right out of the model looks like Figure 21.34 (again, using the tiled views to see both conditions at same time).

FIGURE 21.34
The detail and the related wall section.



Since Revit is parametric, you can actually work in either the detail or wall section as changes to the model changes will propagate everywhere. For this exercise, you will be working directly in the detail with the understanding that the wall section will also be updated. The finished detail you are going to create is shown on Figure 21.35.

FIGURE 21.35
The finished detail.




REUSING DRAFTING LINES

Design is cyclical in nature. Just because you think that in one phase you won't need more than one detail of a condition doesn't mean it will remain like that throughout the rest of the project. We have found it useful to use Copy and Paste and filtered selections together.



For instance, if you needed to make another detail similar to the drafting lines you drew in the prior exercise, you can make a selection box over a large portion of the detail and then use the Filter button in the Multi-Select tab to open a dialog box where you can choose to filter out all but the drafting lines and detail components. This lets us take the detail with us when we click OK and add a simple Ctrl+C to copy.




MODIFYING THE FLOOR CONDITION

The first thing you need to modify for this detail is the floor condition. Since the project is using a structurally insulated panel (SIP) for the skin, we cannot have the floor slab bearing on the insulation inside the panel. In reality, the panel will be clipped and hung from the side of the floor system. You'll need to pull the edge of the floor back to 1 1/2" from the inside face of the wall. You can do this the same way you fixed the ceiling in the detail earlier.

1. Select the floor and choose Edit Floor from the contextual ribbon.
2. When prompted for a view to edit the floor in, choose Floor Plan: Level 3.
3. Move the slab edge on that wall 1 1/2" from the inside face of the wall and click Finish Sketch.

The revised detail should look like Figure 21.36.

FIGURE 21.36
The modified floor.




CREATING A MASKING REGION

Obviously, you can't run gypsum board back behind the slab and we still don't have a clip to hold up our structurally insulated panel (SIP) panel. However, based on all the wall sections and details we have, it doesn't make sense to create this out of detail lines, and there is no default Revit detail component for this condition. Instead, you will make your own detail component to reuse for this condition. Detail components are like any other family in Revit. Once added to the drawing, you can always reedit and update them with new information. In the next exercise, you will make a quick and simple detail component—a masking region to hide the gypsum board on the SIP wall system.

1. From the Application menu, choose New ➤ Family ➤ Detail Component.rfa.
2. In the Family Editor, select the Masking Region tool from the Family tab in the Design bar.

You need to create a masking region $\frac{7}{8}$ " wide $\times$ 1'-8" long to hide that run of gypsum board. You also want to make three sides (top, bottom, and right) medium lines because they will represent cut material and the left line an <Invisible Lines> type to keep it hidden. Invisible lines will show as gray when drawn in Sketch mode but will not appear at all and hide other lines (if on top) in model views. Since the masking region is overextended, you need to cut the top and bottom lines. Notice in Figure 21.37 that the left line of the rectangle appears as gray because it is an invisible line.

FIGURE 21.37
Creating the
masking region.




Masking regions are very precisely shaped elements. The reason this masking region is $\frac{7}{8}$ " wide is to cover the $\frac{5}{8}$ " gypsum board, taking into account that the line weight of the gypsum adds thickness to the line; this needs to be covered by the masking region.

Now you need to draw the clip. For the moment, the clip can be represented by a simple filled region box 2" high and 1" wide, located 1 ½" down from the top of the finished floor on the right side of the masking region.

1. Using medium lines, create the box as shown in Figure 21.38.

FIGURE 21.38

Creating the filled region.



2. Before finishing the boundary, choose Region Properties and select the Aluminum pattern. Click OK and then choose Finish Sketch. The finished component should look like Figure 21.39.


FIGURE 21.39

The finished component.



3. If you choose Load into Project right now, it will load with a default name of Family1, which is not highly descriptive and not easy to relocate when you want to use it again. Take a moment and save the detail component to your project directory or library as SIP Clip.rfa. Now load it into your project, as shown in Figure 21.40.

FIGURE 21.40
The component
placed in the view.



4. Because you have chosen a detail component, you have the added benefit of being able to keynote it, which you will need for the detail. Because this is a 2D, view-specific element, use the User keynote.

To finish cleaning up this floor condition, a few more items can be added by placing base molding around the floor/wall condition and then bringing the ceiling finish of the second floor to meet the wall and the floor finish to meet the wall.

A NOTE ON ANNOTATION CROP REGIONS


The annotation crop region is designed to allow you to crop annotations separately from model elements. Be aware that if your annotations extend past the annotation crop region in any way, they will not appear in the view. The annotation crop region needs to be outside the entire keynote or other annotation for it to appear in the view.

ADDING THE BASE MOLDING

For this detail, it is easiest to make a simple detail component. This will make it reusable and taggable—something you wouldn't get with mere lines.


1. Choose Application > New > Family > Detail Component.rft.
2. Draw a simple 6" × ½" rectangle using a masking region and thin lines.
3. This time, add a parameter to the base in case you want to change the height later in the design. Add a dimension to the base from top to bottom (Figure 21.41). Selecting the dimension, choose the Label drop-down from the Options bar and choose <Add Parameter...>.

FIGURE 21.41
Adding a
dimension to the
baseboard.



4. In the Parameter Properties dialog box, name it **Height** and choose Dimensions from the categories (Figure 21.42).


FIGURE 21.42
Setting the height
as a parameter.



If you choose to change the height of the base later in the project, you don't have to reedit the family. It is simply a matter of changing the parameter using the following steps:

1. Save the file to your project director or library as 6in base.rfa and load it into the project.
2. Place it in the model (Figure 21.43).

FIGURE 21.43
Creating a param-
eter to control the
baseboard height.



MODIFYING THE FLOOR AND CEILING CONNECTIONS AND DETAILS


In Revit there are a number of ways to create a detail. There is no single best solution, just as there is not one way to build something on site. We chose to cut the floor back from the wall and use filled regions to re-extend the floor to meet the wall condition. We could have left the floor connected to the wall and simply used masking regions and filled regions to give the appearance of the floor structure being pushed back instead of the floor finish being pulled forward. We chose our particular method because our contractor had requested the use of the Revit model to do some concrete take-offs, so we needed to make sure the volume of concrete was as accurate as possible. Overextending or underextending that condition, even by a few inches, would have changed the volume of concrete reported in the schedule. Before choosing a direction for a workflow, it's a good idea to understand all the uses for your model (beyond documentation) and keep those in mind when making these kinds of decisions. In the following steps, these techniques will be demonstrated.

The floor line has been cut back to make room for the clips; you still need to finish detailing the subfloor and finish floor to meet the wall. To do this, you're going to create some simple filled regions.

1. Using the Region tool on the Annotate tab, draw a rectangle boundary at the ceiling of the second floor to close the gap for the gypsum board under our blocking (Figure 21.44).
2. When drawing the region rectangle, be sure to define the left line as invisible using the Type Selector so it appears continuous with the gypsum ceiling. Make the top a thin line, the right medium, and the bottom wide. Be sure to overextend the invisible line a bit to compensate for the line thicknesses.
3. Open the Region Properties dialog box, set Type to Gyp, and click OK. Verify that the region is opaque so you don't see the model geometry through the region.

FIGURE 21.44


Using a region to clean up a detail graphically.



Once you click OK, the region should look like Figure 21.45. Somehow, it is not quite right. This is because the filled region and the detail components layer can rest on top of the others. You need to resolve their order by pushing the gyp-filled region to the top.

FIGURE 21.45


The region does not look correct yet.



By selecting the filled region, you will be given some layering options in the contextual tab. In order from left to right, these are Bring to Front, Send to Back, Bring Forward, and Send Backward. Select the first button, Bring to Front, and the gyp hatch will appear correctly on top of the detail component (Figure 21.46).

FIGURE 21.46

The graphically modified condition.



Using this same example, you can build simple regions for the floor extension under our base. The floor condition looks like Figure 21.47.

ADDING REPEATING DETAILS

To finish this portion of the detail, you need to add material definition to the floor. The concrete has been poured on top of a corrugated metal deck, but it is not possible to add a corrugated metal material pattern as part of our floor materials, so we want to make a repeating detail in the form of our $3\frac{3}{4}$ " corrugated deck. While the structural engineer will show this in detail, you still want to show the material architecturally in our sections and details. First, you'll need to make the profile of the deck.

1. Create a new detail component using the steps described earlier. You need to make a corrugated metal deck $3\frac{3}{4}$ " tall to mimic the height in the model (Figure 21.48). There are

a couple of ways to make the decking in the Family Editor. One option is to simply use lines. Another option is to create it as a masking region or region. It's a matter of personal preference, and one might be better for your project workflow than the other. We only need to draw a section that can be repeated. When you're finished, save the detail component as `Mt1 Deck.rfa` to the project folder or library.

FIGURE 21.47

Floor detail condition.





FIGURE 21.48

Metal deck detail component family.




2. Once the detail component is loaded into the project, click the Repeating Detail button on the Annotate tab. You will need to make a new type, so click the Properties button next to the Type Selector, choose Edit Type, and choose Duplicate. Name the new type **Metal Deck**.
3. In the Detail field, choose `Mt1 Deck` from the drop-down menu.
4. Change the Detail Rotation field to 90 Degrees Clockwise.
5. Start drawing the element as you would a line.

Since this is a 2D element, you will also want to go back to the wall section and add the corrugated deck to all of the appropriate locations. The finished deck in detail and section looks like Figure 21.49.

FIGURE 21.49

The metal deck in section and detail.




NESTING DETAIL COMPONENTS

There are a couple more conditions to address to finish this detail. The head and sill conditions for the storefront system will probably not be affixed directly to the rigid insulation as the detail currently shows. You'll need to add some blocking and flashing to those locations. Again, since you will want to reuse this condition in other views, you can make it with a detail component. This time, however, you are going to add a more significant level of detail to the detail component before inserting it into the model. You'll do this by nesting detail components within each other. Let's start with the storefront head condition.

1. Start a new detail component family using the process described earlier.
2. Notice that in the Family Editor, there is a Detail Component button, similar to the one in the project environment. Click it and load a 2 × 6 from the same path we used earlier (Detail Components > Div 06-Wood and Plastic > 06100-Rough Carpentry > 06110-Wood Framing > Nominal Cut Lumber-Section.rft).
3. Use the horizontal reference plane to simulate the top of the storefront. We want to place our blocking $\frac{1}{4}$ " back from this line, centered on the vertical reference plane.
4. Using a masking region, draw a shim under the 2 × 6.




5. Once you click Finish Sketch, because this is a shim, you'll want to show it with a single diagonal line through it. Using the Detail Line button, you can add a detail line to make this condition.



To help finish the window on the exterior, place a stone header over the window opening. This can be created with a region and a new region type for stone. The stone head is 6" high by 2¼" wide and placed 1⅜" from the edge of our 2 × 6. (This measurement isn't arbitrary: it is taken directly from the wall condition in the model.) Figure 21.50 shows your current progress.

FIGURE 21.50

Nested detail component.




1. You need to add a steel lintel for the stone header. Revit does not provide these as default detail components, so you can create one with a filled region.
2. Save this condition as SIP Storefront Head.rfa and load it into the project.

Once the detail component is inserted into the model, you should see something that looks like Figure 21.51.


FIGURE 21.51

Inserting the nested detail component.



Using simple detail lines and filled regions, you can add any necessary flashing and gypsum returns to the window. The completed head condition should look like Figure 21.52.


FIGURE 21.52
Final detail at head condition.



FINISHING THE DETAIL

By combining the simple tools used in the previous sections, you can easily complete this detail. As we have mentioned throughout this chapter, many of the elements that were imported or created need to be made only once. All of the families and detail components you built in the course of this detail are now available in the project for use in other views. The finished detail looks like Figure 21.53.

FIGURE 21.53
The completed detail with the nested component.



You can easily adapt this process to complete details for the other conditions.

GENERAL TIPS FOR DETAILING

When detailing, keep these ideas in mind:

- ◆ If your model is detailed to begin with, the detailing will go much faster because you will need to add fewer components. However, you must strike a balance and not make an overly detailed model, because that will negatively impact performance. When wondering what to model or what to make into a detail component, ask yourself the following questions:
 - ◆ Will I see or use this in other views in the project?
 - ◆ Will it affect other aspects of the project (like material take-offs)?
 - ◆ How large is it? (Our office tends to use 2D detailing for details 1 1/2" and smaller.)
- ◆ If you insert User keynotes and in the Options bar choose the option Free End for the Leader, you can drag the notes around anywhere on the view and add as many as you'd like. The benefit of this method is that it allows you the consistency of *always* pulling your notes from the keynote text file. And if the note is updated in the text file, it will be updated in the project.
- ◆ Remember to import only CAD files that you have already cleaned up. Only bring in what you need to reduce your overhead and keep file performance optimal.
- ◆ There is no limit to how much information you can place in a detail component. If you will be seeing similar conditions throughout the model, put in as much as you can.
- ◆ You can use detail components at every scale within the model, so it is a great way to draw the information only once.
- ◆ If the lines describing geometry merge when printed into a single graphic element, there's little point in showing that geometry at that scale. You might consider making the model simpler.

The Bottom Line

Create drafting views. Not every drawing or view in Revit is created with model elements. Some of the views on sheets will be made solely with 2D drafting views. Knowing how to create and use these views is critical to any documentation package.

Master It Keeping views hyperlinked together is a key benefit to using Revit. How do you draw simple, 2D details in Revit but still keep them parametrically linked to sheets?

Import and link CAD details. Even if you've been using Revit for years, you will need to import 2D geometry from an old library of standards or manufacturer drawings. Understanding how to do this effectively will keep you from having performance issues with your model.

Master It Your office has a huge repository of standard details. How do you reuse details drawn in CAD in a Revit project?

Create 2D detail components. Detail components can be used again and again within a model to graphically show in 2D different typical building components. Mastering these will result in enhanced productivity when you work on a project.

Master It Detailing is a process of adding more granular layers of information and graphics to the model and view. What tools would you use to add 2D detail?

Chapter 22

Advanced Detailing Techniques

Chapter 21, “Moving from Design to Detailed Documentation,” covered the transition from design to construction documentation. Now you will continue building your skills and learn some additional techniques for more detailed construction documentation. As your project experience grows, your library and detailing capacity within Revit will grow with it. This chapter is dedicated to tools and functionality that you can employ after you become comfortable with creating details in Revit. By building your library and knowledge of detailing workflows, you can cut down the time you spend detailing, leaving more time for design.

In this chapter, you’ll learn to:

- ◆ Create 3D details
- ◆ Add detail components to 3D families
- ◆ Reuse details from other Revit projects

Creating 3D Details

As building designs become increasingly complex and the construction industry continues to specialize its assembly methods, it has become imperative that information be communicated effectively between designer and contractor. A technique for showing construction assemblies that has an established place in the history of architectural representation is the use of 3D detail drawings (Figure 22.1) that show a sectional cut through the building in a 3D format (axonometric or perspective). This type of drawing is used to convey pragmatic detail and constructability information rather than having to create a multitude of 2D sections and elevations to demonstrate complex building details. In recent years, this documentation technique has fallen into disuse because it is difficult and time consuming to re-create axonometric details in a 2D CAD-based environment.

With Revit’s 3D modeling capabilities, it is easy to create such 3D details. By using 3D views and the Orient to Other Views command, you can quickly generate 3D views that focus on a construction condition. These views can be used for constructability or to demonstrate critical building concepts. Figure 22.2 shows a detail of a sustainable solution employed on the Foundation project. In this sectional axonometric, we are able to demonstrate many of the green building concepts simultaneously while also showing dimensional depths of the sunshading and daylighting systems.

FIGURE 22.1
Hand-drawn
perspective detail.





FIGURE 22.2
Sectional axono-
metric showing
details of sunshad-
ing solution.




Creating these kinds of 3D details in Revit is quick and easy to do. There are two ways to do this:

- ◆ Turn on the Section Box tool, and then adjust the section box to focus on your detail
- ◆ Orient a 3D view to an existing view. This method adjusts a 3D view to resemble a chosen 2D view. You can then rotate the cropped 3D view to any new orientation. This method is much more practical than cropping the view manually because it is much faster to generate details and because the size of the detail condition is focused on an existing, pre-established scope

3D Details: Enabling a Section Box in 3D View


Take the following steps to enable the Section Box tool in a 3D view:



1. Start by creating or opening a 3D axonometric of the building. To create one, click the Default 3D View button in the Quick Access toolbar. Be sure to rename your view something unique.
2. Open View Properties and enable the Section Box parameter. A large section box that surrounds the entire model will appear in the view. This is a 3D clipping box that allows you to cut the model from six directions.
3. By clicking and dragging the blue arrows, you reduce the size of the box to a clip that represents the detail area you wish to indicate (Figure 22.3). Manipulating a section box can take a bit of trial and error, regardless of your experience with Revit. Later in this chapter, we'll discuss some ways to make this quicker and more accurate.

FIGURE 22.3


Drag the blue arrows to resize the section box.



3D Details: Orienting to View

An alternative for creating a 3D detail is to orient the 3D view to an existing view. Do this by first creating a detail callout where needed, let's say in a wall section, as shown in Figure 22.4. Then, give the callout detail view a recognizable name by selecting the callout and editing its element properties. Call it **Sunshade Detail**. Having a recognizable name will make the detail easier to find later, as the number of details in a project can become quite large.


FIGURE 22.4
Creating a callout
detail in section.



Now that we have established which detail we'd like to be able to rotate in 3D, let's create the new, 3D view:

1. After creating the callout, open the default (3D) view by selecting the 3D view icon from the toolbar. Right-click the ViewCube and choose View > Orient > To Other View, and select our Sunshade Detail from the list (Figure 22.5).

FIGURE 22.5
Selecting a view
by right-clicking
the ViewCube and
choosing View >
Orient to View
from the context
menu.




2. Once you click OK, the 3D view reorients and appears in the form of a section—just like the detail callout. However, this is a 3D view. By orbiting this view (using either the ViewCube or combining Shift and the middle mouse button), you'll be able to visualize the sectional detail in 3D (Figure 22.6).

The crop boundaries of the 3D detail correlate to the boundaries of the callout, so there is no need to alter the section box as was the case with the first method of creating 3D details. The depth of the section box in this view is defined by the depth of the view you have used for orientation. You can edit the section box using the grip controls as you would any other section box. To hide the section box lines but keep it cutting the model, select it, right-click it, and choose Hide in View > Elements from the context menu.

FIGURE 22.6

Top: Oriented to other view, detail looks like a flat section. Bottom: The rotated (orbited) view reveals a 3D detail.




CREATE A 3D VIEW OF ONE SINGLE FLOOR

Reorienting to view is also practical when you want to isolate an entire floor and show a 3D view on one floor only.

Adding Annotations to the 3D Detail

Even if 3D details are much richer and clearer in information than 2D details, they still need annotations (dimensions, text notes) that add to the graphical explanation. To add dimensions to a 3D view, you first need to define a work plane where the dimensions will appear, as they cannot float free in the 3D space; they need a surface (work plane) to be drawn against. (See Chapter 6, “Modeling Principles in Revit I,” for more on work planes.) We are showing our dimensions at Level 3 in the view. From the Workplane panel on the Home tab, select Level 3 from the drop-down menu. Using the Work Plane Visibility toggle, you’ll be able to see what plane the dimensions will be created on, as shown in Figure 22.7. Dimensioning along this plane is similar to dimensioning in any plan view. By selecting parallel elements, you can apply the necessary dimensions.

FIGURE 22.7
Setting and visualizing the work plane in a 3D view.



You can then begin to add text notes to this view. Note that in a 3D view, you can add text and dimensions but not keynotes or tags. Also, be careful not to rotate the 3D view after you apply your notes. Text is placed perpendicular to the view you have created and will maintain that relationship. Rotation of the 3D detail after you’ve added text will result in leaders or text not pointing to the desired building elements.

By turning on the shadows in the view, you’ll be able to give the view a better sense of depth, as shown earlier in Figure 22.2.

Be sure the ground plane is enabled in the Sun and Shadows Settings dialog box for the view. A good choice is either Sun from Top Right or Sun from Top Left. See Chapter 15, “Presentation Techniques for Plans, Sections, and Elevations,” for more detail on presentation techniques.


Adding Detail Components to Families

In the previous chapter, we investigated how to add levels of detail to a detail component by creating one detail out of a number of separate components, thus making it easier to replicate a detail condition across various project views. Again, this idea of drawing it once and repeating that detail easily is a core theory in Revit. Combining these principles, we can extend this theory to family creation, where you can turn details on or off within a family depending on the Level of Detail view setting.

When we explored the notion of the view detail earlier, we mentioned the ability to show different levels of detail at coarse, medium, and fine settings. Combining this with detail components, you can embed details for typical conditions directly within the families themselves, so that you do not need to add more drafting elements to your views.

Figure 22.8 shows the same window family in coarse, medium, and fine views. All of the detail has been added to the family itself, and the detail is activated by switching between the levels of detail. Note that the fine detail level in this series shows the actual CAD detail from the manufacturer's website and is not modeled in detail in 3D. Modeling this level of detail within the Revit model would be a huge performance killer. Because the detail was created as part of the window family, this highly detailed information will be displayed each time any section or plan view is made that cuts through the window. This method enables you to have the level of detail always present in the drawings without having to give up performance or over-model the building.

FIGURE 22.8
The same awning window shown in (A) coarse, (B) medium, and (C) fine view.




Building this type of window family is not complicated, but it does require a bit of knowledge about how a family is created and assembled. For our purposes, we are going to assume that the window family has been created correctly and we are simply trying to apply more detail to the window itself so that it displays much more detailed information in fine view.

Adding Details to a Window Family


Since we have already created the sill condition, let's now focus on creating the head detail. Start by locating the family within the project using the Project Browser. Select it, right-click, and choose Edit Family from the context menu. The interface changes to the Family Editor environment. Open a section view (or if there is no section view, create a new one using the Section tool). The section view of the window family head will look like Figure 22.9.

FIGURE 22.9
Section view of the window family head.




In Chapter 21 we discussed how to insert default Revit detail components. For the blocking above the window head, we can load a detail component from the Revit default library. Here are the steps:

1. On the Home tab, click the Component button (or choose Place Component from the pull-down list). Next, click Load Family from the Place Component contextual ribbon. Then, once the browsing window opens, you will need to follow the path Detail Components | Div 06-Wood and Plastic | 06100-Rough Carpentry | 06110-Wood Framing and choose Nominal Cut Lumber-Section.rfa.
2. Insert this component $1\frac{1}{4}"$ (3cm) from the exterior face of the wall. This ensures that it ends up in the right location relative to the wall it will be inserted into. If this window was going to be inserted into a variety of wall types, you could make the $1\frac{1}{4}"$ (3cm) dimension a parametric family parameter.
3. Once the component is inserted, lock it to the reference plane that is at the window head. This ensures that as window sizes are changed, the blocking moves as well.



4. Based on the window type, the blocking needs to always be set $1\frac{1}{4}"$ (3cm) from the front face of the wall, so you can add a constraint there as well. Add a dimension to the left edge of the blocking and the left edge of the wall, and lock it into place (Figure 22.10).

FIGURE 22.10
Adding a dimension and locking it into place.




5. We want to create a new detail for the window head showing an added level of detail at the head condition. For this, we've downloaded the manufacturer's standard CAD detail and we want to incorporate it into our window. To begin, you need to create a new detail component using this CAD detail. From the Application Menu select New > Family. Choose Detail Component to open the Family Editor.

6. To import our CAD detail, follow the steps we discussed in the previous chapter. Choosing Import CAD from the Insert tab will bring up the dialog box where you can insert the CAD detail. This time, you'll want to choose slightly different options. Accept the defaults for all but the following:
 - ◆ Select the Black and White option in the Layer/Level Colors area
 - ◆ In the Import or Link area, change the Layers setting to Select (we want to pick the layers to import)


The dialog box will look like Figure 22.11. Click Open.

FIGURE 22.11
Importing CAD
detail into a detail
component.




7. A dialog box similar to Figure 22.12 opens, asking you to choose the correct layers to import. Hatch is something we do not need, and typically, manufacturers are fairly good about keeping their layer management for CAD details consistent and easy to understand. We want to deselect any layers that reference hatch or any layers we know we will not need as part of our detail. Deselect the box and click OK.

FIGURE 22.12
Selecting layers
to import.




8. With the detail inserted, position it using the reference planes in the detail component. While you can reposition things within the Revit families fairly easily, these reference planes provide invisible snap references when loaded into a project—making placement and dimensioning easier and more specific. Because the top of the head and the face of the glass are key to this detail, use those to place the imported file, as shown in Figure 22.13.

FIGURE 22.13
Aligning the reference planes.




9. You are nearly done with this family. Because this detail has such a simple construction (very few lines) and we have removed the hatch, we are going to explode the detail. Select the detail and from the Modify Imports in Families context menu, choose the Explode flyout and click the Full Explode button. This converts the detail into Revit detail lines and allows you to modify some of the line weights and the detail geometry to better fit the family. A detail with too many lines or lines that are very, very small ($< 0.3\text{mm}$) will be deleted when the detail is exploded.
10. With the detail exploded, you can now remove the glazing, which is only partially drawn. We have modeled glazing in the family itself, so including it in the detail as well is a bit redundant. Select the lines shown in Figure 22.14 and delete them. Instead of exploding the detail, another way to do these same steps is to go into the original CAD file and remove the lines and layers you don't need before inserting the detail into a Revit detail component.
11. The last thing you need to do before saving the model is change the line weights. Select all of the lines in the detail by creating a selection box around them, and while they are selected, choose Detail Items from the Type Selector. You could keep all of the lines the way they had been imported from CAD and change them to the appropriate line weight using Settings ➤ Object Styles from the Manage tab. However, this is a little cleaner for future tweaks and does not add unnecessary line types to your project.

FIGURE 22.14
Select the lines for
the glazing and
delete them.



12. Save the detail as **Head.rfa** in your project folder or library and import it into the window family using the Load into Project button on the Create tab.
13. Back in the window family, place the detail component over the existing extruded window frame and lock it to the reference plane that defines the head opening (Figure 22.15).

FIGURE 22.15
Detail component
in window
head detail.



Visibility Settings

With the detail components in place, you can now establish rules for when each of them will be visible when loaded into the model. You might not want to have your details shown in coarse or medium scales of 1:200 or 1:100, but you might wish to show them in 1:50 or 1:20 scale. In the next steps, visibility settings will be applied to some of the model elements and detail components that will link these items to the detail level setting. For this family, we need the detail component to be visible only in fine levels of detail and the 3D solid form window frame sweep to be hidden in fine levels of detail.



1. Still in the Family Editor environment, select the detail component. On the Modify Imports in Families tab, click the Visibility Settings button. Clicking this button opens the Family element visibility settings dialog box shown in Figure 22.16.

FIGURE 22.16
The Family
element visibility
settings dialog box.




2. This dialog box is as simple as it looks, but it's quite powerful at the same time. By deselecting any of the options here, you limit the visibility of components to specific detail levels. For this example, clear the Coarse and Medium check boxes and click OK.

Now you will notice that a funny thing happens—or actually, doesn't happen. If you change the visibility of detail levels, the detail component still appears, although now it is drawn in a gray tone, as if it ignores the visibility settings you just made. You can quickly confirm that you deselected those view levels by checking the visibility settings again. Don't worry. You have done nothing wrong. In the Family Editor, for editing purposes, you will always see everything in each view detail level regardless of its setting. Only when you load the family in the project environment will you really understand if you have modified the visibility correctly.

The goal was to see the highly detailed representation of the window when switching to fine detail view. At the same time, you don't need to see the original 3D window frame because the linework of the frame will overlap with the linework of the newly inserted 2D detailing components. You need to turn off the visibility of the window frame from within the family when in fine detail view:

1. Select the 3D sweep created to represent the window frame and click the Visibility Settings button on the Modify Imports in Families tab. The dialog box that appears is the same as you saw previously when you selected the 2D detail component, but since this 3D element appears in more views, you now have more visibility options (Figure 22.17).

FIGURE 22.17
Visibility settings
for a 3D element.




2. You still want to see the window frame in plan, reflected ceiling plan, and elevation, so leave those boxes checked for now and just uncheck the When Cut in Plan/RCP and Fine boxes, mirroring the settings for the detail component.

CONTROLLING VISIBILITY IN PLAN VIEWS

The same rules can be applied to plan views using this technique, so that the sweep does not show up in fine levels of detail. By clearing the Plan/RCP check box, you turn off the visibility of the window frame in plan view as well.

We will now add a trim. Use a masking region to cover the trim piece above the window frame on the exterior side of the glass. Use the boundary lines of the masking region to define the shape; it's not necessary to draw separate lines. Create it on the fly (Figure 22.18). While visually scanning through the manufacturer's product information, we selected a trim piece, but we don't have any Revit or CAD details for it. So, you have two options: make a new detail family and import it or build it on the spot.

FIGURE 22.18
Draw a masking
region for trim.




Adding More Information Using Symbolic Lines

At this stage of the detailing process, you need to add sealant, flashing, and trim at the window head. For that you can use symbolic lines. *Symbolic lines* are 2D lines that are visible only in the view in which they were added. An example of the use of symbolic lines would be a representation of a door swing in elevation. The dashed lines that represent the hinge points are symbolic lines.

1. Using symbolic lines, add sealant to the detail, as shown in Figure 22.19.

FIGURE 22.19
Adding symbolic
lines for the
sealant.





- Before loading the detail into the project, you need to make sure the visibility of the symbolic lines and the masking region are correct. You cannot change the visibility of those elements simultaneously, so you'll need to select each one independently (choosing the masking region, then the symbolic lines) and set the visibility to show them only in fine detail views.



Real World Scenario


DOORS AND SYMBOLIC LINES

Doors are typically modeled in a closed position but shown as open and with a door swing direction in plan view. To get this dual representation, in the Family Editor turn off the visibility of the door panel (extruded solid form) in the plan view and draw the 90-degree open door panel and its swing using symbolic lines. Symbolic lines can be controlled using the same visibility settings available for detail components and the solid model elements in the family. You can use the same logic and draw the dashed lines that represent the door opening direction in elevations.



Save the family with a unique name before loading it. Once it is loaded, you can quickly cycle through the various view detail options and see the power of using visibility settings in the family, as shown in Figure 22.20.

FIGURE 22.20
Cycling through
to different levels
of detail of the
window.



Imagine that the door has already been modeled and you are adding the lines representing the swing. For that you add the symbolic lines in both plan and elevation to complete the element. When drawing new symbolic lines, use the Type Selector to define the subcategory of the lines.

Reusing Details from Other Revit Projects

There are many times in a project workflow when you want to leverage details already created in other projects and reuse them. So far we have covered how to do this using CAD files from other projects or from manufacturers' websites. This workflow is also possible using details created from other Revit projects. We will explain how to take an active project file and export key details to the library. We'll also discuss how to pull single details out of a Revit file and put them into your active project.

Exporting Details from Revit Projects

As you create more and more details in Revit, you will inevitably want to save some of them to your office's standard library so you can reuse them in other projects and save the work you've invested. Saving a view out of a project creates a separate RVT file that contains only that view. There are a couple of ways to do this, either of which will result in the same outcome. First, if you have a 3D model detail that you've embellished with 2D components and would like to save it for future projects, you can save it as a Revit file.

Right-click any view (or schedule) in the Project Browser and choose **Save to New File**. It might take Revit a minute to compile the view content, but you will be presented with a dialog box asking you for a file location to save the view (Figure 22.21). The default filename will be the same as the view name in the project.

Once the view is exported, it functions like any other RVT file. Opening the view directly will allow you to edit and manipulate any of the elements you exported in the view. You will also see a streamlined version of the Project Browser (Figure 22.22) with only the related views present. These Revit files can be kept in a project library for later use.

FIGURE 22.21
Exporting a
drafting view
from Revit.





FIGURE 22.22
Project Browser
only has views
appropriate to
the ones for the
exported view.



The second way to export a view from Revit is from the Application Menu, using **Save As** ➤ **Library** ➤ **View**. This opens a dialog box of all the exportable views from the project file. Here, you can select any number of views to be simultaneously exported into separate library files (Figure 22.23). This is a great way at the end of a project to export all of the detail views you would like to keep in a project library. Select the desired views by checking the appropriate boxes and click OK.

FIGURE 22.23
Multiple view
can be saved as sepa-
rate Revit files.




Importing Views into Revit Projects

To import any of these files into a new project, switch to the Insert tab and from the Import Panel and choose Insert from File > Insert Views from File with the project open. This lets you navigate to your library containing your exported details. When you choose the exported detail file, a dialog box opens allowing you to select the view (Figure 22.24).

FIGURE 22.24
Selecting a file to
import into the
current project.




Notice that the view is described by both its location within the Project Browser (Drafting View) and its view name (Storefront Head Detail). Selecting this view and clicking OK merges the view into your current project. The view will appear in the location called out by the view name. In this case, you can find this view in the Project Browser under Drafting Views.



Another way to insert content into Revit is to use the 2D views from exported files. For example, elements of a detail you have in your library may need to be inserted into a view you are working on to augment that view. An excellent use case for this would be if you are creating a new detail and want to reference or use parts of one from another project that is similar but not exactly the same. An example of this might be a new detail of a window head in a concrete opening and you are reusing parts of a detail from a masonry opening. You may only want to use a selected portion of the new view in the current detail you are working on. To import the 2D content into your view, follow these steps:

1. Open the view you want to import into, click the Insert tab and from the Import panel choose Insert 2D Elements from File. The resulting dialog box looks similar to the one for importing the full view but with some slight differences (Figure 22.25).

FIGURE 22.25
Importing
2D content.



Unlike Insert Views, the Insert 2D Elements from File command allows you to choose only one view at a time to insert. There is also an option to transfer the view scale with the view elements. Checking this box reconfigures the receiving view to match the view that you have inserted.

- 2. Select the drafting view and click OK. This brings all of the 2D elements in the selected view into your active view. You can repeat this command multiple times in the same view window if you need to repeat the content.

 Real World Scenario

USING DETAILING TO CREATE A SHAFT OPENING


Revit offers a couple of ways to create an elevator shaft. One commonly used approach that we’ve seen discussed on the community forums is to create a door family that also contains all the elevator information (essentially, a combined door and elevator family in 3D). As a door family, it cuts a hole into a wall and gives proper representation of both the door and the elevator. This will give you your elevator, but then you need to perform a secondary task of editing the floor slab profiles to accommodate the shafts. Although this method will work, it can cause a problem with making sure the floor openings stay aligned between the floors. In our practice, we use a different method, which was used in creating the Foundation model. By using the Opening tool on the Modify tab, we can create a shaft opening.



This tool allows you to create one vertical shaft through multiple floors. This has a few benefits over the other method:

- ◆ The openings in the floors will always be aligned
- ◆ We can extend this shaft through as many or as few floors as desired
- ◆ The constraints of the shaft can be locked to reflect the manufacturer's required size
- ◆ Symbolic lines can be embedded in the opening to represent the elevator cab and can be drawn (or imported) to reflect the manufacturer's cab sizes and proportions

This last point is very valuable within our office. After creating the shaft, we can add the elevator cab plan directly from the manufacturer's CAD detail as symbolic lines.



Now, any time we cut the shaft in plan, it will display the elevator cab using these symbolic lines. If our building is complex in form and we need to move our view range up or down, we will always maintain the elevator cab in the plans.

The Bottom Line

Create 3D details. 3D axonometric details are a great way to demonstrate more complex assemblies and conditions in any document set. Knowing how to create them in Revit will expand the ways in which you can detail.

Master It Use a 3D axonometric detail to demonstrate constructability in a unique assembly condition.

Add detail components to 3D families. Adding detail components to 3D families can save time by embedding the linework of a detail within the family itself and making it instantly available throughout all the locations that family is placed.

Master It Create a detail by embedding it into a family so it can be expressed by simply modifying the detail level of a view.

Reuse details from other Revit projects. There are times when details are common between projects. Knowing how to use details from other Revit projects will cut down on your documentation time.

Master It Use details you created in your other Revit projects.

Chapter 23

Tracking Changes in Your Model

Once a project is under way in the construction document phase, changes to the design need to be tracked. This is typically done on a per-sheet basis by adding revision clouds around elements that are changing in the drawings and documenting those changes in the title block of the sheet. The revision history of each sheet is then tracked in the title block with a number, description, and issue date. In this chapter we will look at adding new revisions, adding revision clouds to sheets, and assigning a cloud to a revision. We will also explore some best practice tips and tricks for performing revisions in Revit. Lastly, we will investigate using Autodesk Design Review to pass comments and markups back and forth between team members.

In this chapter, you'll learn to:

- ◆ Add revisions to your project
- ◆ Understand BIM and supplemental drawings
- ◆ Use Autodesk Design Review

Adding Revisions to Your Project

Revisions allow designers and builders to track changes made to a set of construction documents. Typically, these changes are recorded after a set of documents has been issued and permitted. Since the construction documents usually consist of numerous sheets, this methodology allows everyone on the team to track and identify which changes were made by whom and when during the construction process those changes were made. The purpose is not only to ensure correct construction but also to create as-built documentation at the end of the construction process that can be delivered to owners for their continued use of the building.

In a typical workflow, the revisions will look something like Figure 23.1 when they are created in Revit and issued as part of the drawing set.

To create a revision, open the Annotate tab and choose Revision Cloud from the Detail panel. This will put you in Sketch mode. Once you draw your revision cloud, open the Revisions dialog box found on the Manage tab in the Settings drop-down list. Here, you will see the default revision, Sequence1, which is where your revision cloud has been placed. Here, you can also add, delete, merge, issue, and define the behavior of revisions. Let's go through the major elements of this important dialog box.

FIGURE 23.1
A typical-looking revision cloud and triangle-shaped revision tag.





FIGURE 23.2
The Sheet Issues/Revisions dialog box.



The numbering method You can choose to number revisions by Sheet or by Project. (By Project is a global project setting.) Which method you should choose mainly will depend on how your firm tracks revisions. By Sheet allows you to have as many revisions as you want within the drawing set, but on each sheet, the revision numbers always start with 1. In the example shown in Figure 23.2, the tags and revision schedule are unique for each sheet, depending on what revisions are on each sheet. The revisions on each sheet are presented sequentially by sheet. This means you are chronologically numbering and tracking the changes that happened on one particular sheet, not all the changes that happened in the entire project.


Using By Project will tag your revision clouds based on the global sequence established within the project as a whole. In this example, all revisions with the same issue date within the model would have the same revision number. So you might skip a revision number on any given sheet. You can also set up this numbering method in your default office templates.

The revision table The Sheet Issues/Revisions dialog box starts with one default revision already in place, even though you may have not made a revision yourself. This is only so that you have a place to start. No revision will appear in your title blocks until you add revision clouds to your sheet. Each revision has a fixed number of parameters that you can fill out. As you can see in the dialog box, they are fairly self-explanatory and include numbering, date, description, and an Issued check box, in addition to Issued To and Issued By columns and options for showing clouds and tags.

The Add button To create a new revision, click the Add button. The new revision will automatically be placed in sequential order. Only the sequence number will be automatically updated. You'll need to add your own description and date.

Revision numbering The Numbering option allows you to number each revision numerically, alphabetically, or not at all. If you choose alphabetic sequence, the sequence is defined in the Alphabetic Sequence Options, in the lower right of the dialog box. Click the Options button to set your sequence and remove letters you don't want (Figure 23.3). By default, an entire alphabet will appear here. The None option will allow you to add project milestones—non-numbered entries that appear in revision tables—to sheets without having to add revision clouds.

FIGURE 23.3
Sequence options
allow you to use
any order of letters
you want.



Revisions To issue a revision, click the check box in the Issued column. This will lock the revision clouds placed on sheets or in views associated with that revision, preventing them from being moved, deleted, or otherwise edited. The parameter values in the dialog box will gray out and become noneditable. This is to guarantee that the clouds and data do not change downstream once you issue a set of drawings.

REVISIONS IN A LIVE MODEL

Keep this in mind: while the clouds can become fixed in the project, the model will not be. So, if you need to maintain an archive of all project phases and of each revision, be sure to export the sheets either as DWF or PDF files to preserve a snapshot of the sheets at time of issuance.


Revision clouds and tags The visibility of revision clouds and tags related to revisions that have been issued is controlled from this dialog box. As issues occur, you may want to hide clouds or tags from previous revisions. This is where the Show parameter comes in handy. For example, if you've issued a revision and then add revisions later and want to clean up your drawing, you can choose to show the issued revision as the tag only (typically a small

triangle with the revision number inside it, as in Figure 23.4) or not show anything at all, by using the None option (Figure 23.5).

FIGURE 23.4
A revision tag.



FIGURE 23.5
Use the Show parameter to hide clouds and tags of issued revisions on your sheets.



Merge Up or Merge Down If you need to combine two revisions into one, use the Merge Up or Merge Down button. All associated revisions on sheets and tags will update automatically.

TRACKING REVISIONS IN THE TITLE BLOCK

The revision is typically a part of the architectural sheet and is located in a prominent position in the title block to alert readers to changes made in the documents. These revisions can be incorporated into your title block design so Revit will parametrically read them from the sheet into a revision table. To add a revision schedule to a title block, you will need to open the Family Editor and make changes in the title block. Please refer to Chapter 4, “Setting Up Your Templates and Office Standards,” to understand how that can be done.

Placing Revision Clouds




To place a revision, open a view in which changes to the model have occurred and use the Revision Cloud tool found in the Detail panel on the Annotate tab. Once you activate the tool, you will be dropped directly into Modify Revision Cloud Sketch mode. Start drawing lines around the area you are calling out as a revision in a clockwise direction. Revit automatically

Use this dialog box to make revision clouds have thicker line weights or to change patterns or colors. As we mentioned in Chapter 4, the graphical appearances of your elements should be set up in your office templates in advance to guarantee consistency between projects.

Changing the color of the revision cloud to red in the Object Styles helps them stand out as you work. By default, each new revision cloud will be assigned to the last revision in the Sheet Issues/Revisions dialog box (which you access from the Settings menu on the Manage tab). If you need to change the revision that a cloud belongs to, select the cloud and use the drop-down list in the Options bar to change it. This information is also stored in the Instance Properties dialog box of the cloud, as shown in Figure 23.8.

FIGURE 23.8
The revision cloud’s Instance Properties dialog box.



As soon as you have placed a revision cloud onto a sheet, any revision schedules in your title block will update to include the revision number, description, and the date you assigned in the Sheet Issues/Revisions dialog box earlier.

Rev. #	Description	Date Issued
1	Windows Changed	6/15/07

UPDATES IN CUSTOM TITLE BLOCKS

If you are using the default Revit title blocks, updates will happen automatically. If you are using custom title blocks, be sure you’ve added a revision schedule to them in the appropriate location so you can take full advantage of using a parametric model. (See Chapter 4 to learn how to add revision schedules to your title block families.)

Tagging a Revision Cloud


Revision clouds can be tagged like many other elements in Revit. The tags are intelligent and designed to report the revision number or letter that has been assigned to the cloud. To place a revision tag, use the Tag by Category tool in the Tag panel on the Annotate tab.



If a tag for revisions is not in your template, you will be warned that no such tag exists in your project. To continue, simply load a revision tag. The default Revit tag loaded by default in Revit is named Revision Tag.rfa and is located in the default Annotations folder created with a standard installation (see Figure 23.9).

FIGURE 23.9

Load a revision tag if it's not already part of your template.



Once you have a tag loaded, you are ready to go. Hover the cursor over a revision cloud and click to place the tag. You will see a preview of the tag prior to placing. Once the tag is placed, you can drag it around the cloud to reposition it, and it will stay associated with the revision cloud.


CUSTOMIZING THE TAG

Just as with the majority of annotations in Revit, you can design your custom revision tag as you see fit. You can follow the steps presented in Chapter 4 to make a custom annotation tag from scratch, or you can customize the default revision tag provided with the software. To customize the appearance of the default revision tag, select a tag already placed in the project and click the Edit Family button on the Modify Revision Clouds tab. Editing the tag within the project will take you to the Family Editor, where you can tweak its size, font, and appearance. Once you've made your customizations, save the tag to your local library, and then load it into your project and swap it with the default tag using the Type Selector.

DISABLING THE LEADER

You can choose to use a leader line between the tag and the cloud depending on your preference or your office standards. In many cases, the tag just needs to be near the cloud and a leader is not necessary. Disable the leader by selecting the tag and clearing the Leader option in the Options bar (shown in Figure 23.10).

FIGURE 23.10
The revision tag leader is set using the Options bar.



BIM and Supplemental Drawings

The process of making supplemental drawings (SDs) entails making a change to an existing drawing and then issuing that change as a separate package. Sometimes this can be a single 8.5"×11" sheet where the new detail is then pasted over the old one in the construction set in the job trailer. From a workflow perspective, this can be a little disruptive in Revit for a couple of reasons:

- ◆ Placing the new detail into an 8.5"×11" or smaller sheet to issue the individual drawing can lead to other problems. You will need to either remove the view from the sheet it was issued on temporarily (and remember to put it back) or duplicate the view and hope that you do not need to make last-minute additional changes
- ◆ An SD, once issued, is like a snapshot in time. It becomes a numbered change made to the drawing set at a given date. Since the model and all the views in the model always reflect the most current state of the project, making separate SD sheets and views within Revit will show any additional changes made to that view

As a best practice, some architects leave all of the revisions directly on the sheets where they were originally issued. The sheets are printed to PDFs and the PDFs (with the revision clouds) are imported into Adobe Illustrator or a similar application where they can be properly scaled and cropped to the view or detail in question and then placed on an 8.5"×11" template to be issued for the revision. This process not only creates a historic record of the revision, but also allows you to avoid issuing the full sheet. You can also export a portion of a view to DWG and then import it into a drafting view for annotation of supplemental drawings. This keeps everything in Revit.

Using Autodesk Design Review

Autodesk Design Review offers a fast, efficient way to view and mark up 2D and 3D designs for review. This workflow is different from what we just covered and is geared more toward informal design review rather than management of sheet issues. For example, if your drawings must be reviewed for quality and overall design comments by a senior designer who neither owns Revit nor knows how to use it, this tool can streamline the process and offer a way to achieve that need. The senior designer, consultant, or any other third party can make comments and review changes and send it back to the Revit user who needs to follow up on those reviews.

This is the next generation of the DWF format—one that is more closely aligned with emerging technology standards supported by Microsoft. Once a DWFX is exported from Revit, it can be opened in Design Review, marked up, and then linked back into the Revit file, where changes can be picked up and tracked. If you export the drawing sheets from Revit to DWFX, when the DWFX is linked back into Revit, Revit will automatically place the DWFX with the corresponding sheet so there is no need on your part for any sort of alignment or placement of the revisions.

The DWFX format allows you to share drawings and models with stakeholders with a lightweight and easy-to-use application. The navigation and ability to hyperlink between views works well with Revit and is easy to learn.


Design Review is a free tool that you can download from the Autodesk website: www.autodesk.com/designreview.

Once it's installed, you can open any DWFX or DWF file produced by any Autodesk or non-Autodesk software packages.

The Design Review User Interface

The interface for Design Review is straightforward, as shown in Figure 23.11. It contains a main view window, toolbar, and navigation pane.

FIGURE 23.11
The Autodesk Design Review interface.



The view window The main window shows the active view. Using the middle mouse button, you can zoom and pan. If you are looking at a 3D DWF, you'll also see the ViewCube in the upper-right corner of the view. Use this cube to rotate the model by clicking it, or you can hold the mouse down and rotate the cube. Before you start rotating the model, make sure the orbit method is set to Turntable in the toolbar.




This will keep your model rotating with the Z axis always pointing up. If you use the Orbit option, your model will tumble around freely in space on all axes.

SELECTING ELEMENTS IN DESIGN REVIEW

For certain types of elements, selection is very much the same in Design Review as in Revit. For example, when you select a wall, level, grid, or section marker, that element will highlight in other views as well—not just where your cursor is. It behaves this way because the DWFX originated from Revit, where every element is a unique, model-based element and not just a set of abstract lines. When an element is selected, check out the context menu; it contains many options that allow you to zoom, hide elements, make them transparent, and even move them (Figure 23.12).

FIGURE 23.12
The Autodesk
Design Review
context menu.



Exporting to Design Review

The DWFX format allows others to examine your design without needing to own or know how to use Revit. The files are also small, which makes them easy to email, something you cannot do with a large Revit file. There are two ways to share your model using Design Review: as 2D information or as 3D information. If you export to 3D, you create a single 3D representation of your model. Exporting to 2D can create either a view or a whole collection of interconnected views and sheets all packaged as one file.

ARCHIVING WITH DWFS

A 2D DWF of all the sheets of the drawing set is a great way to keep an archive of your project. This allows you to take a snapshot in time of the state of your drawings in a single, small file that is easy to print and easy to reference back into the model should you ever need to return to a previous state in the design. Again, make sure you export sheets, not views.

DWF EXPORTS

You can export to DWF from any view in Revit. To export your active view, click the Application Menu and choose Export > DWF. The resulting Export to DWF dialog box lets you choose which views/sheets to export. The default is your current view. Give your file a unique name and save. Then open the file with Design Review to see the result. When in Design Review, experiment with some of the viewing options in the View panel on the Home tab (Figure 23.13). The Perspective toggle is a nice feature that lets you toggle the 3D view between isometric and perspective with a single click.

FIGURE 23.13


Options for viewing the model—note the Perspective toggle.



Click the Export drop-down list to choose what you want to export. You can choose to include or exclude any sheets or views using the Include column. When you've made your selection of sheets and views to export, click the Export button. By default, all your views and sheets will be combined into a single DWF file. If you want a separate file for each view and sheet, uncheck the option Combine Selected Views and Sheets into Single DWF File. Let's walk through this:


1. Open the Foundation.rvt model in the Chapter 23 folder on the companion web page.
2. Go to the Application Menu and choose Export > DWF to open the dialog box shown in Figure 23.14.
3. Select Sheets in the Set and then choose Export <In session view/sheet set> from the Show in list drop-down list.

FIGURE 23.14
The DWF Export
Settings dialog box.



- To check the export size, open the DWF Properties tab and click the Print Setup button. In the resulting dialog box, you can set explicit sizes for your export. Click the option Use Sheet Size to let Revit autodetect sheet sizes based on the title blocks you are using in the project (Figure 23.15).

FIGURE 23.15
Set the Use Sheet
Size option and
Revit will auto-
detect the size of
your sheets when
exporting to DWF.




- 5. Click the Export button to specify the filename and the location to save it. Make sure you specify to combine all sheets into a single DWF file, as shown in Figure 23.16.

FIGURE 23.16
You can combine sheets into a single DWF file.



- 6. Save the file as **foundation_all_sheets.dwx** to a location on your hard drive.
- 7. This process will take some time because it is exporting all the views on all these sheets. When the process completes, open the file with Design Review. You'll see all the sheets displayed with previews in the navigation pane in the Contents tab (Figure 23.17).

FIGURE 23.17
Sheets are displayed in Design Review as previews in the navigation pane.




Marking Up the Model Using Design Review

Once you have exported a DWF, you can open it in Design Review and add textual markups that can then be shared with your team, or even linked back into Revit. To mark up a view in Design Review, use the callout tools in the Markup & Measure tab (Figure 23.18). Draw the shape using the tool, and then add your text. Figure 23.19 shows a clouded area and associated text note.

FIGURE 23.18
Design Review has a variety of markup graphic styles.




FIGURE 23.19
Type in comments and use the grips to position the markups.




Importing a Design Review Markup

Once you've added markups in Design Review, save the file. You can then link these back into the Revit project. Go the Link panel on the Insert tab, and then choose DWF Markup:



When a DWF file is selected, Revit will link and show only the markups, not the entire DWF file. So if there are no markups in the DWF file, nothing will come into Revit. Markups are any text note, markup, or stamp added in Design Review. Figure 23.20 indicates that three sheets have markups.

FIGURE 23.20
For each markup, there is an associated Revit view.



Note that markups can only be linked to sheets. If you export a view and mark it up, it will not show up in Revit. Always work from sheets when using Design Review for markup transfer.

You cannot move or delete linked DWF markups—they appear with a pin when selected. You can do a number of things to graphically indicate that you’ve dealt with a markup:

Change its graphic appearance Let’s say you have 20 redline markups on your sheet. You need to keep track of which ones you’ve dealt with. One way to do this is to graphically override each one as you finish. Select the markup, then use the context menu option **Override Graphics in View** ➤ **By Element**. Choose a color to indicate “done.” Yellow works well because it suggests a highlight marker.

Hide it This approach is similar to the graphic override, but you hide the markup altogether. Select the markup, and use the context menu option **Hide in View** ➤ **Element**.

Remove it You can remove markups by choosing **Manage Links** from the **Manage** tab. In the **Manage Links** dialog box, select the **DWF Markups** tab, select the markup, and click the **Remove** button. This removes all markups associated with the link.

The Bottom Line

Add revisions to your project. You need the ability to track changes in your design after sheets have been issued. Adding revisions to a drawing is an inevitable part of your workflow.

Master It Add revisions to your project that automatically get tracked on your sheet.

Understand BIM and supplemental drawings. Making an actual revision to a construction document involves adding graphics and coordinating the clouds with revisions.

Master It You need to cloud a design change. How would you do this using Revit?

Use Autodesk Design Review. You’ll often need to share your design with people who do not have Revit, so that your design can be examined and marked up.

Master It How can you export your designs in a lightweight file format?

Chapter 24

Worksharing

Most projects involve more than one person working on a project at any given time. It's common in design for many people to work together to meet deadlines and crank out a set of construction documents. Keeping with the theme of an integrated single-file building model, Revit allows for this workflow without breaking apart the model. A complex model can be edited by many people at once using a feature called *worksharing*. In this chapter, we'll focus on enabling the worksharing feature of Revit.

In this chapter, you'll learn to:

- ◆ Set up a project with worksets
- ◆ Understand worksharing basics
- ◆ Manage workflow with worksets
- ◆ Understand element ownership in worksets

Setting Up a Project with Worksets

Worksharing in Revit refers to the use of *worksets* to divide up the model for the purpose of sharing data between multiple people. A workset is a collection of building elements and components (floors, roofs, walls, windows, and so on) that can be used to manage project workflow and responsibilities by separating these various building components into subsets that allow control over visibility and element ownership. By default, worksharing is not enabled when you start a project in Revit, because the software assumes you are working in a single-user environment until you tell it otherwise.


WORKSHARING WARNING

Once you enable worksharing in a model, you cannot undo it. We suggest that you make a copy of your project file before you enable worksharing so you have an unshared version as a backup.

You share your work by saving a *central file* to a shared network location. This central file becomes the repository where all the individual work on the project is collected and permissions are managed.

Once the central file has been established, each team member then makes a local copy of it and works solely in that local copy. All work is done directly in these copied—but still associated—local files. This enables all users to open their local files simultaneously and work in them (see Figure 24.1).

FIGURE 24.1
The worksharing concept.



The elements in each separate file are tied to an ownership rule linked to the central file, making it impossible to edit an element in your local file if that same element is owned by someone else in another local file. Remember, Revit is a database. In effect, you're obtaining permission to edit one or more elements from the central database. Once you have permission to modify an element, no one else can make changes to that element until it is reconciled with the central file—in other words, "checked back in." This occurs when you use the Synchronize with Central command (hereafter referred to as STC) to copy your work back to the network. If one user has ownership of an element, no other user can edit that element until its permissions, and any changes to it, are reconciled with the central file.

Worksets allow you to group many elements into virtual collections of objects for the purpose of managing visibility and file performance. To that end, there are a number of benefits to enabling worksets beyond allowing multiple team members to work within the same file:

- ◆ Using worksets, you can turn visibility off and on for elements that aren't being worked on or that are not needed for the current tasks.
- ◆ Revit allows you to close a particular workset globally across all views and also remove it from active memory, thus improving performance. Therefore, closing worksets is different than turning them on or off in only one view,
- ◆ You can quickly request and obtain permission to work on groups of elements belonging to someone else.

When you enable worksharing, a new tab appears in the Visibility/Graphic Overrides dialog box for the worksets (see Figure 24.2). You can turn any workset on or off in any view using this tab. Additionally, you can make those settings part of any of your view templates.

FIGURE 24.2
Workset visibility.



Understanding Worksharing Basics

Revit's worksharing features are designed to accommodate any division of labor you see fit. There are no inherent restrictions on how you use worksharing to divide up a model. For example, you can break up a model and have one group work on the shell and another work on the interior core of a building. You can turn worksharing on at any stage of the project, and you can create or remove individual worksets during the project cycle.

Worksharing is found on the Collaborate tab of the Revit UI.




Start worksharing by clicking the Worksets button on the Collaborate panel. It will then be the only active button on the panel.



This action opens a dialog box telling you that you're about to enable worksharing for your project and that once it's enabled it can't be undone (Figure 24.3). After confirming that you do want to proceed, Revit will automatically create two worksets: Shared Levels and Grids, which contains all the levels and gridlines from the project, and Workset1, which contains everything else in the model.


FIGURE 24.3
Activating work-
sets within a
project.



In addition to the two worksets created automatically when you initialize worksharing, Revit maintains three other types of worksets in a project:

View worksets Each view in a project has a dedicated view workset. It contains the view properties and any view-specific elements (text, dimensions, tags, and so on). View-specific elements cannot be moved to another workset. You can take ownership of any view in Revit by simply right-clicking it in the Project Browser and choosing Make Workset Editable (see Figure 24.4). This will give you ownership of the view workset and all of the view-specific annotations, allowing you to easily and quickly make modifications to any of the 2D content within the view. This is a handy feature during the construction document phase when much of the work is segregated, as it allows users to view worksets for dimensioning and annotations.

FIGURE 24.4
Making a view
workset editable
is a property of
any view in a
workset file.



Family worksets For each family loaded in the project, a workset is automatically created. When editing properties of a family, you will take ownership of that family unless someone else already owns it. You can add families to each of the views without having ownership over view worksets, but you cannot make changes to the families or their properties without having permission over the families themselves.

Project standards worksets This workset is dedicated to all the project settings, such as materials, line styles, tags, and dimensions. Any time you edit a project-wide setting, you must take ownership of a workset for that setting. However, you can always add new information, materials, or line styles to a project without having to own a workset. You only need to take ownership of a workset to edit existing settings or elements.

Once you’ve activated the worksets, you’ll see the dialog box shown in Figure 24.5. The Worksets dialog box lets you add and remove worksets from the project. When a new workset is created, it does not contain any model elements or components; it is a blank container that you can then begin to fill.

Also note that at the bottom of this dialog box you have the option to turn on visibility for the automatically created worksets we discussed earlier. By default, they are not activated. To activate them, simply check the box for the workset desired. You can see in Figure 24.6 that enabling any of these check boxes adds a considerable number of elements to the view window.

FIGURE 24.5
Worksets
dialog box.





FIGURE 24.6
Worksets dialog
box with Project
Standards enabled.



When you activate a workset, you become the owner of that workset and all the elements in it. This ownership is what the Yes value in the Editable column refers to; if you are the owner of a workset, the value in the Editable column will be Yes, but if you are not the owner, the value will be No.

WHO CONTROLS WORKSETS?

Worksets are usually activated by the team’s project manager, who initially enables worksharing, creates user-defined worksets, and assigns people and tasks for the project. However, worksets are managed by the team itself. It is up to the team members to make sure they are working on the correct workset. It is also not currently possible to lock a workset from use or editing by any team members beyond simply taking permission of the workset.

Workset Organization

It's important that you think of your project holistically when dividing it into worksets. Technically speaking, you don't need any more than the initial default worksets because Revit manages ownership of elements on a per-element basis and relinquishes elements automatically when you save your changes to the central file. However, you might want to divide up the model into worksets for some of the reasons we described earlier. Some good examples of typical worksets are Shell, Core, Exterior Skin, First Floor Interior Partitions, Second Floor Interior Partitions, Roof, and so on. You may also want to create another workset named Entourage for rendered-only elements (not for documentation).

THINKING IN WORKSETS

One of the biggest challenges facing teams new to Revit is losing the legacy of layers. Many teams that have been drafting in 2D CAD immediately want to begin managing worksets as they would manage a CAD drawing. They make a workset for doors, one for walls, and one for windows. Remember that all of your objects are in one file and you can control visibility of those objects through the Visibility/Graphic Overrides dialog box. Not only is there no need to put your doors into a separate workset, but doing so will actually make your model more difficult to manage. What happens when you have ownership of the doors, your teammate has ownership of the walls, and you want to move or add a door? You can't do so because you don't own the entire assembly. You have to own the door *and* the wall you want to place it in to make those changes. Overall, it is preferable to think about each workset as a collection of ideas that you want to be able to isolate and visualize separately from the rest of the model, such as core, exterior, exterior, and roof, plus entourage (for rendered elements only).

Divide your project into worksets that relate to the roles and responsibilities of people working on the project. By default, you don't need more than two to three worksets per person on a project. When making new worksets, remember the Ludwig Mies van der Rohe dictum, "Less is more."

For our Foundations project, we have divided the model into four worksets, shown in Figure 24.7: Interiors, Shared Levels and Grids, Shell and Core, and Site.


Interiors All of the interior walls, furniture, and other items are managed with this workset.

Shared Levels and Grids This workset contains the level and grid information from the model, as was originally established when worksharing was enabled.

Shell and Core All the exterior skin elements of the building as well as the elevator, stair, and toilet cores that are grouped in any typical office building are in this workset.

Site The topography (toposurface) and any site-specific elements in the project go into this workset.

FIGURE 24.7
Workset
organization.



KEEPING IT SIMPLE

For our project, creating the Site workset meant renaming Workset1. Because the Shell and Core workset will have the most elements in it, renaming allowed us to forgo the additional work of moving all those objects into a blank workset.

Notice that Workset1 has been renamed. That title is not descriptive enough to be of ongoing use, so it can be modified once all the model elements have been moved to relevant worksets. The worksets we've set up demonstrate how a typical breakdown might occur in a project of this size, but it's by no means limited to this scheme. Depending on how you structure work in your office, the worksets might be quite different.

Once you are in a workset environment, you can see or change an object's workset by accessing its element properties. At the bottom of the Element Properties dialog box, you can see which workset an object or group of objects belongs to, and you can change what workset the element belongs to (see Figure 24.8). Note that you can move elements to other worksets only if you own the elements. You do not need to own the entire workset to do this—just the individual elements.

Additionally, you can tell what workset an object belongs to by hovering your cursor over the object and waiting for the tooltip to appear. This tooltip will give you a host of information about the object in question. In our example, the workset is Shell and Core, the element is also part of the Walls category, the name of the family is Basic Wall, and the family type is A3 - 4 3/4":





FIGURE 24.8
Change the
workset an
element belongs
to by selecting a
different workset
using element
properties.



PRACTICE GOOD WORKFLOW

As a best practice, do not work directly in the central file once the worksets have been established. Every user should be working in their user (local) file. Working directly in the central file will change the file attributes and nullify anyone’s ability to successfully use the STC command. *Once someone has worked directly in the central file, any work by anyone else will be lost and everyone will be required to make new local copies.* Working in the central file should only occur if there is a file upgrade or some other historically significant event, and even then should only be done with full knowledge of all the team members.


Moving Elements Between Worksets

Once the worksets are created, there are some simple steps for moving elements quickly to other worksets. As mentioned, the easiest way to move the bulk of the objects is to not move them at all but simply rename Workset1. After that, it is easiest to move elements in a subtractive method from a 3D view. The following exercise will walk you through moving elements to their new worksets using a subtractive method to locate model geometry. Note that this should be done while one person is still the solitary owner of all the worksets.

- 1. Open the default 3D view ({3D}) so that you can see all of your model elements within the project.
- 2. Open the Visibility/Graphic Overrides dialog box, turn off the Site workset, and click OK. Since nothing is in the Site workset, the view should still look the same after you do this.

- Now, in the 3D view select a comfortable number of site elements and click the Properties button. (*Comfortable* means you don't have to try to select them all at once.) In the first image in Figure 24.9, the topographic surface and some trees have been selected and are highlighted.


FIGURE 24.9
Moving objects
between worksets.



- In the Element Properties dialog box, select Site for the Workset value and click OK. All of the elements you selected will disappear. Not to worry: remember, you turned the Site workset off using the Visibility/Graphic Overrides.
- Using the same technique, you can move the remainder of the site elements to the Site workset. The same procedure is repeated in order to move the interior walls to the Interior workset.

At any point in this process, you can check your work by opening the Workset tab in the Visibility/Graphic Overrides dialog box and clearing all of the boxes but one to see what is in each workset. Figure 24.10 shows the Interiors workset with all of the interior elements. As you can see, this is a great way to manage visibility without using the object categories.

FIGURE 24.10
The Interior
workset.



MOVING EVERY INSTANCE OF AN ELEMENT

A quick way to move every instance of a single element to a new workset is to use the Select All Instances option from the context menu. For example, select a tree in the model, right-click on the tree, choose the Select All Instances command from the context menu, and open Element Properties. You can then change the workset for all those elements in one action. This also ensures that you actually selected *all* of the elements, whereas in a window selection it can sometimes be suspect.

Managing Workflow with Worksets

With worksharing there is always one central file that spawns local files and manages element ownerships. This is the file that collects all the work being done by your team members and allows the team to get regular updates of new work saved to the central file. Once the worksets are initialized and the model is divided into various worksets, you will need to complete a few more steps before the team can jump into the model and begin working in a multiuser environment.


To use Revit in a workset environment, start by doing something any IT manager would yell at you for doing: make a local copy of the central file and work directly off your C: drive. Although this approach is a bad idea for most work in an office environment, for the Revit database there are several good things about it:

- ◆ It allows more than one user to make changes to the central file by editing local files and synchronizing those changes with the central file.
- ◆ Your local copy will be more responsive than a networked local file because your access speed to your hard drive is much faster than it is across most networks.
- ◆ Should anything bad happen to your network or your central file, you will have an up-to-date backup to which you can easily apply the Save As command and make a new central file.

Creating a Central File

Now that you've turned on worksharing, you need to set up the central file to be used by more than one person. To do this, first you create a central file located on your network; then you create the local files. To create the central file, choose the Application Menu > Save As and give the model a new name. Before you save, click the Options button at the bottom of the dialog box and verify that Make This a Central File After Save is checked (see Figure 24.11).

FIGURE 24.11
Creating a
central file.




The reason for the new name is twofold. First, it gives you a backup of your original, pre-workset file. Backups never hurt. Second, Revit sometimes does not like to have a new file saved over an active file or a file of the same name. It can cause file corruption.

Creating the Local File

Now that the central file has been created, you need to create the local files that you will work from.

1. Make a new, local copy of the central file by dragging the file you just created to your desktop or another location on your hard drive. Be careful not to *move* the file; you just want to make a copy of it.
2. Now, open this new, local file. The first time any local file is initialized, you will receive the warning message shown in Figure 24.12. All this means is that you've made a local file and you will be the owner of the local copy. If you don't see this message, check to make sure you're opening the correct file.

FIGURE 24.12
Opening the
local file for the
first time.



Once you click OK, you are set and ready to begin working in a worksharing environment.

Now that you're in a worksharing environment, every element added to the file belongs to a workset. Try to keep model elements in a workset other than Shared Levels and Grids because these worksets may be locked down at some point to avoid accidental movement of key datums. To make sure you're placing elements in the proper workset, check the Collaborate tab to see what the active workset is. All newly created elements will be assigned to the workset shown in this box. Remember, you don't have to be the owner of this workset in order for to be able to add new elements to it, nor does the workset need to be editable.



A helpful toggle on the Collaborate tab is the Gray Inactive Workset button. It grays out all elements that aren't in the active workset, helping you identify which elements in the workset are active. This is a temporary view state and will not affect any print output.



Saving Shared Work

Once you begin working in a worksharing environment, you need to know how to save your work and be able to share it with others. There are three ways to save your work when you're using a workshared file:



Save The Save tool saves the work you've done to your local copy only; the work isn't shared or saved back to the central file. This is useful when you're in the design phase and trying out different designs, or if you're not ready to share your work with others but you definitely want to save the work you've done.




Synchronize with Central If you want faster access to synchronizing, a Synchronize with Central button is available on the Quick Access toolbar.

Save to Central The Save to Central button is on the Collaborate tab. Use this to publish your work into the central file. When you do so, your work appears in the central file and becomes available to the entire team. Using Save to Central also acquires the changes that others have made (and likewise saved to the central file) and loads them into your local model. Using the menu option for STC is a good way to save yet maintain permission over the elements you are creating. Choosing this option will open the dialog box shown in Figure 24.13, which allows you to customize how you save to the central file. You can choose to relinquish some permissions or none of them, and you can choose to save a local copy at this time (or not). You can also add comments about this particular version you are saving. The comments are available in the History dialog box (covered later in this book).

FIGURE 24.13
Save to Central
dialog.




Synchronize with Central ➤ **Synchronize Now** This option, found under the Synchronize with Central button, will synchronize your changes and download other people's changes without your needing to interact with the dialog box.



Revit will remind you regularly to save your work. In a worksharing environment, you will see a dialog box reminding you to save locally, and another one reminding you to synchronize

the central file. You can dismiss these reminders from time to time, but remember that it's always a good time to save (and not lose) your work. It's also important to remember that although Revit provides automatic reminders to save your work, it will not autosave.

Each of the dialog boxes comes with three options: you can save/synchronize the project; save/synchronize the project and set reminder intervals (choosing this will bring up the Options dialog box); or you specify that you do not want to save/synchronize or set reminder intervals (this last option dismisses the reminders). However, if you want this dialog box to go away and be reminded again at the interval you've requested, just hit the cancel button.



The reminder time shown in the dialog box can be modified across the application using General > Application > Options.

Loading Work from Other Team Members




It's possible to update your model from the central file without committing your changes to the central file. Think of this process as getting an update of the model. To do so, choose the Collaborate ribbon and click Reload Latest. Revit finds the latest changes saved to the central file and brings them into your local file without publishing any of the changes you've made.

OPTIMIZING RELOAD LATEST

Mapping Reload Latest to a keyboard shortcut can help you see others' edits quickly. Also, much of the time in a Synchronize with Central process is consumed by reloading the latest changes. More frequent use of Reload Latest will shorten the time it takes to save when you use Synchronize with Central.

Understanding Element Ownership in Worksets

While you are working in a worksharing environment, it might become necessary to see if you have ownership of an element. To do so, select the element. If you own it, it will be highlighted in purple and can be readily moved or modified. If you do not own it, it will still be highlighted purple, but you will also see an icon resembling three stacked blocks in blue. This indicates that you do not currently have ownership of that element.



 Real World Scenario

RECOVERING FROM MISTAKES

Inevitably, with any team of people, someone is bound to make a mistake somewhere in the process. It happens; it's just human nature. The important thing is knowing how to recover when those accidents happen. On one project, someone new to our team kept accidentally deleting the west wall of the project while deep into construction documentation. Since Revit is a database and everything is linked to everything else, every time this happened, not only were the plans affected, but we lost the west elevation, wall sections, the door and window details in those sections, and so on. You get the idea. Once the west wall was deleted, the user issued the Synchronize with Central command, thereby changing the central file. Fortunately, we caught the mistake in time and thus did not have to resort to a backup from the previous night and lose a day's worth of work. Because each local copy was a fully functional copy of the model, all we needed to do was find the latest local version with the wall in it, click the Application button, and choose Save As ➤ Project. We then clicked the Options button and selected Make This a Central File after Save. Once everyone on the team made a new local copy, we were back in business.

You can obtain ownership of the element in a few ways:

- ◆ If you edit or move an element, Revit will automatically grant you permission to own it provided no one else currently owns it or the workset it resides within.
- ◆ If you can click the stacked block icon, and if the element is available, Revit will grant you permission to edit or change it.
- ◆ You can right-click the element and choose Make Elements Editable from the context menu (see Figure 24.14).

FIGURE 24.14
Making an element
editable.



Note that in this context menu, you also have the option to make worksets editable and take permission of the *entire* workset the object is assigned to.

Borrowing Elements

Borrowing is a critical technological concept in Revit. It allows users to fluidly transfer permission of objects without having to constantly save all their work to the central file and relinquish all worksets. By borrowing elements, team members can take ownership of some of the elements within a particular workset that belongs to someone else. This is typically used to modify only one or a few elements in a given workset without taking ownership of the entire workset. This is also valuable if you need to edit elements in a workset and someone else already owns it.


The key idea here is that you can borrow elements individually rather than by workset. If you need to work on an element that belongs to someone else, you'll be informed of that and given the option to send a notification asking to borrow it. The owner of the element can then grant permission for you to take ownership. This is referred to as *relinquishing* permission.

Let's look at this workflow in more detail.


Requesting Permission

Say you are happily working away on your model and realize that someone else is the owner of an element you need to modify. Should that occur, you will be presented with the dialog box shown in Figure 24.15. This will occur every time you are working in a model in which work-sharing is enabled and you are attempting to edit an element that is already owned by someone else on the project.

FIGURE 24.15
Placing a request
for permission.



You can click Cancel, which will undo any edits you have made to that element, or you can click Place Request to ask the other user to relinquish permission over the element in question. If you opt to place a request, you will see this dialog box:




It is important to note that the other user does not receive an explicit notification that you have placed the request. To make sure your colleague knows of your request, you'll need to call or instant message (IM) that person, and get them to grant the permissions. (You'll learn how to do this in just a bit.) If owning this element is critical to the task at hand, keep in mind that you will not be able to perform any more work in relation to that element until that other user grants you permission to borrow it. Once the other user has agreed to relinquish ownership, click the Check Now button to see if you do in fact own the element. Or, if you want to just keep working, click the Continue button. This will undo your last command and return you to the view to continue your work.

GET THEIR ATTENTION!


Asking another user to grant permission to an element is a great reason to use an intra-office IM or chat service. It is invasive enough to alert another user to the fact you are requesting permission for an element. However, the phone works well, too. Formatting a Revit username as *Your Name + Phone Extension* is another good trick.

Once you've received notice from the other user that your request has been granted, click Check Now and you will receive the message shown here:



Clicking OK will apply your edits and you will then be the borrower of that element. You can view the Worksets dialog box to see who owns which worksets and who is borrowing from a workset at any time, as shown in Figure 24.16.

FIGURE 24.16
Owning and borrowing worksets.



Granting Permission




Suppose that you have been happily modeling along and you receive a phone call, IM, or tap on the shoulder from someone who wants permission for an element you own in the model. How do

you grant it? On the Worksharing toolbar is a button called Editing Requests, which allows you to see outstanding requests that have been sent your way.

Clicking this button gives you the dialog box shown in Figure 24.17.

FIGURE 24.17
Editing Requests
dialog box.



From here, you have a few options:


Grant This gives your teammate permission for the requested element.

Deny/Retract This denies permission to your teammate (or takes it away).


Show This shows you exactly which element or elements have been requested, which help you make an informed decision.

Once you are ready to grant permission, one of two things will happen. If you haven't made any changes that need to be saved, you can simply grant the permission and notify your teammate that you have done so, and then both of you can continue to work. If you have been editing the requested element, you'll need to save your changes to the central file before anything else can happen. Changes of this nature are specially flagged in the Editing Requests dialog box with an asterisk before the request. This indicates that the element has been modified and a Synchronize with Central command must be issued before permission can be granted (see Figure 24.18).

FIGURE 24.18
Editing requests
for changed
elements.




Trying to grant permission at this point will give you the dialog shown here:



To remedy this issue, close the dialog and perform a Synchronize with Central using one of the methods we discussed earlier. Keep in mind that if you choose Synchronize with Central from the Collaboration tab and uncheck the boxes for relinquishing permission, you will need to come back to the Editing Requests dialog box to grant permission for this element. Once you have saved to the central file and notified the other user, he or she can then click the Check Now button to continue to work.

The user who is requesting permission of the element will see this dialog box after clicking Check Now:



This means that the object the other user was trying to use has been edited. He or she has to choose Reload Latest or Synchronize with Central from the Collaborate tab and reload the most current copy of that object before it can be edited. Unfortunately, any modifications to this element will be lost because the element will be changed in the central file.

Closing Revit

Depending on your role on a project, your schedule, or those annoying urges to eat and sleep, from time to time you might leave your desk and want to close Revit. Revit helps you do this by providing some directions for saving your work. It offers two options:

Relinquish Elements and Worksets This is the default option. It will do exactly what it says: synchronize your work with the central file and relinquish all of your permissions.

Keep Ownership of Elements and Worksets This button gives you the option to save only locally and *keep* ownership of the elements you've checked out. Be careful when using this option, because no one on your project team will be able to gain permission for or edit those elements while you are away.

GETTING PERMISSION WHEN SOMEONE IS AWAY

Inevitably it happens. Someone leaves their desk for a meeting or goes home early (or just closes Revit) without relinquishing permission to their elements or worksets. Now you're stuck, unable to make the changes you need to make. There is a workaround for this dilemma. However, be warned that using it will cause the other person to lose any and all work since their most recent synchronization. If they did a Synchronize with Central and simply chose to keep ownership of their elements, no work will be lost. If they did not, the remaining work will need to be redone.

Should your needs outweigh the risk of data loss, follow these steps:

1. Open a new session of Revit. (You can keep your current session open if you prefer.)
2. Select Application ➤ Options ➤ General.
3. Change the name listed in the Username field from your username to that of the person whose work you are trying to save.
4. Either open the central file where the elements are locked or create a local copy while the temporary username is active.
5. Now you can open and Save to Central, and all the other person's elements will be available to you.
6. When you've finished, remember to change the temporary user name back to the appropriate name.

As a side note, doing this with a username that is not in use by any team members (for example, "Project Admin") is a good way to lock down gridlines or other elements you don't want anyone to accidentally edit by making the Levels and Grids workset editable and then closing the file without relinquishing the workset.

The Bottom Line

Set up a project with worksets. Knowing how to activate worksharing and set up the project file for more than one person at a time is critical in any office environment.

Master It How do you work in a single Revit file on a project team with more than one member in the file at a time?

Understand worksharing basics. Once you've enabled worksharing, you'll need to understand the dynamics of central and local files to fully leverage working in a worksharing environment.

Master It Once you have enabled worksets to allow for multiple users, what's the best way to implement and use the file?

Manage workflow with worksets. Saving to and loading from the central file allow you to view other team members' work and allows them to see what changes to the project you have added.

Master It How can you translate the changes you've made in your local file to the central file on the network? How do you download changes from other team members to your local file?

Understand element ownership in worksets. Editing elements in a central file means you have sole ownership over further changes to those elements. Understanding the permissions will be critical to working in a team.

Master It How do you edit an element in the model if someone has already taken permission of it in a worksharing environment?



Appendix A

The Bottom Line

Chapter 1: Understanding Basic BIM: From the Basics to Advanced Realities

Identify the advantages of building information modeling. The traditional architectural design tools you've mastered are probably serving you well. New software and a new conceptual model of the building process will inevitably involve some adjustments, so they need to provide significant benefits.

Master It What are some of the advantages of using BIM over traditional CAD tools?

Solution BIM is a model-based tool that keeps your documents coordinated in a single file. As a modeling tool, representational drawings such as plan and section are by-products of modeling, not separately managed drawing files. BIM is also well suited for making early design decisions and iterating in the design, because you can run analysis early and frequently.

Know what to expect from BIM. A BIM project is based on a single, centralized database of information. You need to anticipate how that change can affect workflows based on more independent functions.

Master It How can your work process be affected by the adoption of BIM?

Solution BIM changes the way projects are managed and worked on. You'll find that teams must communicate on a regular basis when working on a shared BIM model. This encourages members of the team to take active responsibility for their parts of the model and understand the impact that design changes have on other parts of the model. Using BIM also means you have to shed some old habits and expectations and be willing to change the way you think about producing construction documents. Moving from a drafting-centric workflow to a model-based workflow can be jolting at first, but once you take the plunge, you're unlikely to look back.

Chapter 2: Revit Fundamentals

Understand Revit parametric elements. Although you can find references to objects, families, instances, and components, in the end everything is an element.

Master It What are Revit elements, and how are they managed graphically?

Solution Anything you can select in the view is a Revit element. By using a fixed category structure, Revit lets you quickly identify elements, control their visibility and graphics, and generate reports based on this information. The data is highly structured, but you have tremendous liberty when it comes to the representation of that data.

Work with the Revit user interface. As in any software application, you need to know where all the major components are and what tasks they support.

Master It How do you change the graphics of a category for all views? What if you need to change the graphics for only one view?

Solution Use the Object Styles dialog box to set up and edit the graphics for all elements in the model. This establishes a default behavior for all views. To change the graphics on a per-view basis, use the Visibility/Graphic Overrides dialog box, which you can access from the context menu when elements are selected or by pressing the VG keyboard shortcut. The sooner you embrace this concept and start exploring the opportunities it presents, the better. If you can't get your drawing to look just right, chances are you haven't dug deep enough.

Use the Project Browser. This UI component provides access to all elements in your model. Become accustomed to using it to locate views, families, groups, and links.

Master It Knowing how to navigate views in Revit is essential to completing work. What are some of the ways to open views in Revit?

Solution You can open views from the Project Browser by double-clicking any view. In addition, you can double-click view tag symbols directly (level heads, section heads, elevation tags, and callout bubbles) to open the view.

Navigate views and view properties. Views are also elements. Just like the walls, floors, and roofs you add to the model, you'll also add views. They have properties you should become familiar with.

Master It You need to change the scale of a plan view from 1/8" to 1/4". How do you do this with Revit?

Solution Using either the View Properties option on the view's context menu or the view controls at bottom of the view, change the scale. The annotations and hatch patterns will update automatically. You can change the scale of any view at any time.

Chapter 3: Know Your Editing Tools

Select, change, and replace elements. Learning the basic mechanics of the interface is crucial to just about everything you'll do in Revit.

Master It Selecting elements in the model happens all the time. What are some of the capabilities that the Revit user interface provides when you select elements?

Solution Any time an element is selected, you'll notice that a few things change in the user interface. First, the element changes color, indicating that it's selected. Second, if you select a model element, you get temporary dimensions to help you position the element. Third, icons appear for graphic controls such as drag grips, check boxes, and flip arrows. And finally, the contextual ribbon tabs and sometimes the Options bar updates with element-specific tools. All these features help keep the user interface out of your way until you need it.

Edit elements interactively. The architectural process inevitably involves revision, so be sure you know how to make changes on the fly.

Master It You need to make some major changes to a floor plan, moving the bathroom 20' down a corridor. How might you do this with Revit?

Solution Box-select all the walls, fixtures, and doors that are part of the bathroom. Use the Filter tool to make sure you have the right categories selected. Then, select the Move tool in the toolbar. Click anywhere in the model, and move the mouse in the direction you need to move the bathroom. Type 20'. The whole set of elements then moves 20'.

Use other handy editing tools. Revit provides a wide range of tools for making changes in a project.

Master It In a section view, you notice that the walls and floors aren't cleaning up neatly—you're seeing lines overlap. What tool could you use to try to clean that up?

Solution For quick join cleanups, use the Join Geometry tool. Activate the tool from the Modify tab, and then select the elements you want to join. With each click of the mouse, you see the overlapping lines disappear, and your drawings start to clean up immediately.

Chapter 4: Setting Up Your Templates and Office Standards

Start a project with a custom template. Creating a template that incorporates your firm's styles and preferences is an essential first step in putting Revit to work.

Master It Your firm has some deeply established graphic conventions that were defined in AutoCAD. How would you go about matching these graphics and setting up a Revit template?

Solution Using object styles to customize how elements appear in both projection and cut, you can get model and annotation categories to match the line weight, color, and pattern of those used in AutoCAD.

Create custom annotation tags. Styles for annotations, dimensions, and text are all governed by office standards, and the Family Editor is your tool for setting up those standards in Revit.

Master It You need to create dimensions, text, and annotations that match your office standards. How do you do this with Revit?

Solution Make new types of system families for text and dimensions. With these families, you can control font, color, and size. For tags, open an existing tag and customize its graphics to suit your needs. Be sure to add parametric labels to make your tags smart and associative. This will save you huge amounts of time later.

Create custom title blocks. Title blocks are another important element of office standards that you can configure in the Family Editor.

Master It Most offices have several title blocks with lots of information embedded in them. How would you add multiple title blocks to your project template file?

Solution Make your own title blocks as parametric families, and then load them into the template using the Load family button on the Insert tab. With smart labels, you need to define these only once in the Family Editor; they will adapt to whatever project you load the title block into.

Chapter 5: Customizing System Families and Project Settings in Your Template

Create new types of system families. Incorporating common building components in your project template is fundamental to using Revit effectively.

Master It How do you add/remove wall, floor, and roof types to your template?

Solution Start with an existing template, and draw at least once all the walls, floors, and roofs you're likely to need in your own projects. Then, purge unused wall, floor, and roof types from the file using the Purge Unused tool available in the Project Settings panel of the Manage tab. That way, all unused types will be removed from the template. If you need to add types, duplicate a type, name it, and make changes to properties as needed. When you're done, save your file as a new Revit template (RTE file).

Use type catalogs. Revit's type catalogs are an important tool for keeping the types you create accessible in a project.

Master It What are type catalogs used for?

Solution A type catalog is a tool that lets you easily and quickly create many types of a family that have different dimensions and sizes. The type catalog is a text file connected with a Revit family. This text file can store many definitions of family types. It is imperative that the type catalog have the same name and be located in the same folder as the family for which it defines additional types; otherwise there will be no association between them and the type catalog will fail. When you load a family with an associated type catalog, you can selectively load types from the catalog.

Customize project settings in your template. View templates allow you to tailor views according to the requirements of a project.

Master It How would you set up a new view template for plan views where the surface pattern of floors is turned off?

Solution You can turn off categories and patterns and override the graphics for any view, and store these settings in a view template so they can be applied to many views. First, open the View Templates dialog box by clicking the View Templates button on the

View tab and then clicking on the View Template Settings option. Duplicate an existing plan-view template type, and give it unique name. Next, click the V/G Overrides Model, which takes you to the Visibility/Graphic Overrides dialog box for that view. Scroll down to the Floors category, and click the Surface Pattern Override button. Deselect the Visible option, and click OK twice to get back to the View Templates dialog box. You can now apply this view template to your plan views by right-clicking the view name in the Project Browser and using the Apply View Template feature.

Chapter 6: Modeling Principles in Revit I

Understand the basics of modeling with Revit. Modeling with software is an extension of the traditional art of modeling with the hands. Free-form 3D modeling tools are not designed with BIM workflows in mind, but it is still possible to import shapes into Revit for downstream use. At the same time, Revit provides some basic tools for 3D design, and you should familiarize yourself with these.

Master It Tools such as Alias Design Studio, Rhinoceros, 3ds Max, Maya, SketchUp, and AutoCAD 2010 allow you to create free-form shapes with relative ease. How does Revit let you take advantage of such shapes?

Solution In Revit you can import shapes into the project and family environments and reuse them intelligently in a parametric setting. You can also create shapes from scratch in Revit.

Understand sketch-based design. Sketch-based design allows you to define some basic parameters and shapes in Sketch mode within Revit.

Master it Revit uses a 2D sketch-based approach to modeling. What modeling elements in Revit use this 2D sketch principle to generate their form?

Solution Every model element in Revit has at least one 2D sketch in it. Even walls, while not made initially using a Sketch mode, have a sketch that can be edited. All 3D content is composed of combinations of forms that all derive from 2D sketches.

Understand work planes, levels, grids, reference planes, and reference lines. Using these tools gives you the ability to better control your model and your design by applying and controlling parameters.

Master It In order to sketch a form, the form must reside on a work plane. How do you define and visualize the work plane in Revit?

Solution To see the active work plane in a view, click the Show (work plane) button in the Work Plane panel of the Home tab. Right above it is the Set (work plane) tool, which allows you to change the work plane by choosing an existing level, or by clicking on an existing model face.

Chapter 7: Modeling Principles in Revit II

Understand the principles of modeling in Revit. Understanding how to use Revit's modeling tools is an important part of project documentation. Knowing which modeling tools to use when will aid not only in project visualization but also in documentation, scheduling, and rendering.

Master It There are many unique design elements in any project. Know when to use the appropriate modeling tools at the right times. What tool in Revit might you use to model the following elements?

- ◆ Reception counter
- ◆ Entry canopy
- ◆ A lampshade
- ◆ Custom furnishings

Solution While there is no *right* tool in Revit for a given task, some tend to work better than others:

Reception counter: Use the Create tool on the Modeling tab.


Entry canopy: If there is only one, you might use the Create tool or the Family Editor.

Massing study: Use the Massing tab and the mass and void tools there.

Custom furnishings: Use the Family Editor.

Model with five basic forms. These tools are at the root of practically all form modeling.

Master It Having learned the basics of Revit's form-making tools, how would you build this faucet designed by Philippe Starck?



Solution Start a new generic model family. In the family, use revolves, sweeps, and blends to create the faucet. In this example you would model the base as a revolve, the spout a sweep, and the toggle switch as a blend.

Master It In some cases, a form uses multiple sketch lines to generate its form. What form-making tools in Revit use more than one set of 2D sketches to generate the form?

Solution Sweeps have a profile sketch and a path sketch. Revolves have a profile sketch and an axis line. Blends have two sketches: one for the base and one for the top.

Combine solids and voids to create complex and intriguing forms. Revit's five basic forms can be expressed as either positive space (solids) or negative space (voids).

Master It To make more complex forms, both solids and voids can be used. Think of a case where using voids as a subtractive element makes sense.

Solution If you create an extrusion in plan form, and then need to edit it in elevation, a void is a perfect match. With the void, you can carve the top of the extrusion to give it a unique shape.

Chapter 8: Concept Massing Studies

Understand massing workflows. Using generic forms, you can create early conceptual models and then use the mass to create the walls, floors, and roofs.

Master It You need to explore a design idea early on, in 3D, using abstract forms. How would you do this with Revit?

Solution Revit lets you import a site DWG file and begin building a 3D massing study of the surroundings using the lines from the CAD import. Then, using the massing tools, you can model your conceptual composition. Using design options, you can make a few different proposals. With mass and floor schedules, you can measure what you've done and test against the local regulations as well as program requirements.

Start a conceptual massing study. In the project environment, you can make massing forms at any time. For generic forms that might appear in multiple projects, consider using the Family Editor and creating mass families.

Master It You've imported a 2D site plan, and now you need to start building a massing study model in the project. How would you approach this with Revit?

Solution Once a final design is selected, you can use the Building Maker concept to quickly turn the mass model into a BIM model that contains walls, floors, roofs, and other architectural elements. In the early stage of this conversion, you can keep the dependency with the mass model so that if you decide to make changes you can use the Remake functionality to update the converted building accordingly. The idea is simple—you move from mass to a final building seamlessly, without data loss.

Understand form making and rationalization. You can make many types of form using Revit's form-making tools. You can then rationalize your form using the Divide Surface tool. Get familiar with how to go about creating forms, as it's different from in the standard Family Editor.

Master It You have made a form and want to edit it further. What tools can you use to make changes to the form?

Solution When a form is selected, check the Modify Form panel on the Ribbon. From here you can use the X-Ray tool to see into your form and make edits. Also experiment with using the Add Edge and Add Profile tools.

Chapter 9: From Conceptual Mass to a Real Building

Make conceptual designs and early studies in Revit. You can use massing studies to validate a design against the program requirements.

Master It Conceptual modeling is used early in the design process to explore the building shape and building program. How do you approach schematic design using Revit and perform feasibility studies?

Solution Revit lets you import a site DWG file and begin building a 3D massing study of the surroundings using the lines from the CAD import. Then, using the in-place massing tools, you can model your conceptual composition. Using design options, you can make a few different proposals. With mass and floor schedules, you can measure what you've done and test the fit to the local regulations as well as the program.

Build a real building out of a 3D concept mass. Moving from massing to actual building components is easily done with Revit.

Master It You have the basic massing nailed down, and now you need to study more details such as wall and window fenestrations. How do you approach this with Revit?

Solution Load your mass into a project and use the Model by Face tools to start applying standard components to your model, such as walls, floors, and roofs.

Use imported geometry from other applications for massing. Make your own conceptual massing forms using the new Revit conceptual design tools.

Master It How can you reuse conceptual models created in other modeling applications and turn them into a measurable and documentable building in Revit?

Solution Revit allows you to import models from AutoCAD, SketchUp, Rhino, Maya, 3ds Max, and Inventor. You import early concept studies into a mass element and then apply real components (walls, roofs, floors, and so on) to its faces.

Use smart relationships between the building mass and the underlying mass. Use the update tools to re-sync building elements with changes to the underlying mass surfaces. With Revit, you can change the mass and know that most objects can be recomputed to match the form.

Master It Change your massing model to explore design alternatives.

Solution Edit your mass in place or as loadable family and then update your model with new shape. Update the Model by Face objects to match the new design. Look to the contextual tab for tools specific to this workflow.

Chapter 10: Working with Design Options

Use Revit design options. Design options provide a means to maintain two or more alternative designs for the same project or component.

Master It What are design options in Revit?

Solution Design options allow you to explore alternatives to your current design direction. By creating option sets from the Design Options dialog box, you can make an unlimited number of variations to your design theme. These can be controlled with the

Visibility/Graphic Overrides dialog box, which lets you see the options in any number of view types: plans, elevations, sections, perspectives, schedules, and so on.

Decide on a design solution. The end result of exploring multiple options is to choose one alternative and implement that choice.


Master It You've explored a number of design options for an entry scheme. Your client has selected one, and you need to incorporate it into the rest of the model and remove the unwanted alternates.

Solution In the Design Options dialog box, select the desired option and click the Make Primary button. Doing so pushes that option into all your views in the project as the default option. Now, select the option set and click the Accept Primary button. Each of your other unwanted options is eliminated, and your primary option is incorporated into the design.

Use design options with parametric design. Making quantitative differences visible is an essential part of presenting multiple alternatives.

Master It You need to look at some seating layout options for an auditorium space based on different-sized seating and show the seating counts.

Solution Using design options and a Revit auditorium seat family, you can create two design options for the layout: one for seating 20" wide and one for seating 24" wide. Once these are laid out in their respective design options, you can create a schedule to count the seating based on size. By creating a seating schedule and then duplicating it, you can change the Visibility/Graphics Overrides options of the second schedule to count the second design option. In the following views, the two schemes have 276 and 234 seats, respectively.



Chapter 11: Creating Custom 3D Content

Model parametric 3D families. When you're making a new family, consider how it will be used in the model, and choose an appropriate template.

Master It You found a ceiling-mounted lighting fixture that you want to use in your existing project, but you can't find a Revit family for it in any libraries or online communities. How would you start?

Solution Knowing that you need to build a lighting fixture from scratch, begin by opening the `Lighting Fixture ceiling based.rft` template file. This will ensure that the family is hosted by ceilings and will thus move and stay connected with the ceiling in which the light is placed.

Look carefully at how the fixture is built, and consider what Revit form-making tools are best suited for building it. Proceed to build the family, and assign it materials and any dimensional parameters using reference planes and labeled dimensions. When you think you're done, save the file with a unique name, load it into your project, and place it. Remember, if you need to make edits, the process is simple: select the family, and then click the Edit Family button in the Family panel of the contextual Modify tab. You'll be taken directly into the Family Editor, where you can tweak the design. Clicking the Load into Project button reloads the family into your project and updates all instances of the type with your changes.

Nest one family into another. The ability to nest families in other families lets you create content that's easier to manage and improves your workflow.

Master It Building components are often composed of a series of subcomponents that form an overall assembly. Think of some common examples and what strategies you could use to build such content in Revit.

Solution Consider an office workstation. Typically, a workstation is made of modular components: the desk surface, vertical partitions, file cabinets, bookshelves, and a chair. You could load these elements into a project and manually manage all the parts, maybe even using groups to do so. A more efficient and easier-to-manage method is to nest various parts into one family. Starting with a blank Furniture Systems family template, you could load the desk, partitions, cabinets, and chair into one family. By making each nested family a shared family, you can tag and schedule all the elements.

Build relationships between parameters with formulas. Create smart connections between geometry and dimensions to create efficient and parametric content.

Master It You can use dimensional relationships to tie the size of one object to the size of another. How do you do this in the context of a family?

Solution Using the Family Types dialog box, you can add new parameters and then create formulas that tie the value of one or more parameters to any other parameter. Using a conventional mathematical formula, you can create families that are extremely flexible and dynamic.

Chapter 12: Extended Modeling Techniques—Walls

Use advanced modeling techniques for standard walls. Many design situations require more than just the basic wall features; learn to use the more advanced Revit tools.

Master It A design calls for a horizontal soldier course in a brick wall every 12" on the façade. Using Revit, how would you build this into a wall element?

Solution Create a new wall type and add integrated wall sweeps into the wall definition. Each wall sweep can have a material assigned to it, so you just need to define the correct size and materials to the sweep to get it to look correct. Place several instances at 12" intervals. You can change the preview sample size of the wall to be any height in order to add additional sweeps above the default 20".

Use advanced modeling techniques to create stacked walls. Walls along a building façade usually have different construction layers from foundations to the top of the building. Stacked walls allow for a single wall to be constructed with varying wall types along its height.

Master It You have a building project where you are still experimenting with a number of floors but have already defined the wall types for the foundation, typical floor, and the attic and have combined them in a stacked wall type. How do you define the stacked wall so that it will accommodate middle floors with varying heights?

Solution Stacked wall types allow for one of the walls in the stacked wall to have a variable height. In this case, set the middle wall type as a variable height layer. Thus you will assure that the stacked wall updates correctly when floor to floor heights change.

Use advanced modeling techniques for curtain walls. Curtain walls find their way into many architectural projects and designs. Knowing how to manipulate curtain walls in Revit is a key piece of the software for many design solutions.

Master It You've got to add a doorway to a storefront façade you've made. How would you go about doing this?

Solution Load a curtain wall door panel and then swap out a glazed panel with the door. Remember—you cannot use standard door families with curtain walls.

Chapter 13: Extended Modeling Techniques—Roofs and Floors

Understand the various roof creation methods. There are multiple methods for creating roof forms in Revit, and you should become familiar with each.

Master it When would you use a Roof by Extrusion method?

Solution The Roof by Extrusion method for creating roofs is great for barrel vaults, sawtooths, or any roof with an arc profile.

Create all kinds of roofs. Roofs are an integral part of any building. Knowing how to create them in a variety of shapes and sizes is critical to the success of a project.

Master It In the early design phases of a project, you are exploring a variety of roof forms for your building. Create the base building form and explore different roof options and shapes. How would you go about exploring a variety of roof shapes?

Solution Create a roof using the Roof by Footprint tool. Then by editing the roof, modify the slope on the various roof edges (at times setting some of the options to 0) to explore different roof shapes.

Work with advanced roof and floor shape editing. Roofs are another seemingly simple element that presents architectural challenges, and Revit has tools for them.

Master It You are working on a flat roof retail project, but the roof is not really flat and will need to drain. Using Revit roof tools, how would you go about modeling this?

Solution Start by creating a flat roof, and then select it. Use the shape modification tools to add ridges and low points to the roof. By selecting points, you will get temporary dimension controls to accurately set the height and get correct slopes for drainage.

Chapter 14: Extended Modeling Techniques— Railing and Fences

Work with railings and fences. Railings are a bread-and-butter architectural element whose design can be streamlined with Revit.

Master It You've found some nice-looking railing panels and balusters while scouring the Web for interesting rail designs. How do you go about building the railing in Revit?

Solution Start by figuring out what is baluster and what is rail. For the rails, you'll need to make custom profile families and use those when you define the rails in the system. For the balusters, use the baluster family templates as a starting point and break the system down into Revit-centric constructs: extrusions, blends, revolves, and sweeps. Once you have the baluster made, load it into your project, create a new railing type, set up the baluster spacing, and establish the rail pattern.

Use balusters and rails to construct railings. A railing is a complex set of subelements that Revit lets you organize and control with rules and settings.

Master It You want to make a railing where the balusters are glass panels with fixed width. You wish to make a railing that contains the maximum number of those panels and you wish them to be spread symmetrically. How do you do that?

Solution In the Edit Baluster placement dialog box, under Main Pattern, set Justify to Center and Excess Length Fill to None. Justify Center will assure spreading a full number of patterns from the center toward the two ends of the railing, and the Excess Length set to None will assure that no pattern is truncated and only a full number of patterns find their place in the length of the railing.

Adjust additional settings. Stair railing details are particularly difficult to design and plan at landings. Revit helps you fine-tune the details using additional settings.

Master It After designing the stair railing, you notice that there is a gap between the rails following the stair flight and the horizontal rail on the landing. What options do you have to resolve this situation?

Solution Using the options under the Angled joints in the Type Properties dialog box of the railing, you can choose to add horizontal/vertical connectors that fill the gap or leave the gap as is by choosing No connector.

Chapter 15: Presentation Techniques for Plans, Sections, and Elevations

Use shadows for presentation purposes. Presenting your design to stakeholders is a critical part of your workflow and allows you to sell your ideas. Having tools that make this process easier without compromising your creativity is essential to being successful.

Master It You've been asked to show the effect of your building's shadow on its surrounding site during the winter solstice. How would you do this with Revit?

Solution Use a site-plan view, and enable shadows from the View Control bar. Set the Sun and Shadows Settings to the correct date, time, and place. Remember to set the correct place, because this affects how shadows are calculated.

Create presentation-quality plans and sections. Creating clean, easy-to-read plan and section views using Revit is a huge timesaver.

Master It Your latest design is all the rage, and you've been asked to publish the plans and sections in a magazine. How do you make these?

Solution Turn off all the clutter in the view by selecting unwanted categories and elements and hiding them in the view. Then, give the walls, columns, roof, and floors a bold solid fill hatch override when cut. This will make the drawings jump off the printed page.

Create elevation drawings that convey depth. Two-dimensional drawings can be hard for clients to read, which makes shadows a useful mechanism for illustrating recesses and projections.

Master It You need to give your elevation view more variation in line weight to convey depth beyond the default line styles established in the Object Styles dialog box. How do you do this?

Solution Use the Linework tool to apply heavier lines to element edges in the foreground. Use element overrides to apply halftone or thin line weights to elements in the background.

Chapter 16: Presenting Perspective Views

Create perspective views. Design visualization is a key benefit to using Revit as a documentation solution. Being able to snap quick perspectives of your spaces and building forms can be critical to making good design decisions.

Master It Create a new perspective view showcasing a critical design feature. Use the Rendering dialog, lighting, and the materials dialog to complete the rendering.

Solution Using the Camera tool on the View tab, you can quickly create a perspective from a view to describe the design intent of the project. Using the tools described in this chapter, create a quick rendering to analyze the design further.

Create photorealistic renderings. You know those signs that are put up at a site before and during construction—the ones with the nice rendering showing the final product? Well, you can generate those directly in Revit!

Master It You've been asked to produce an exterior rendering of a building. Can you do this in Revit? Can you tweak the results in Photoshop?

Solution Set up some dramatic exterior camera shots, and assign photorealistic materials supplied in the new Render Appearance Library. Add RPC entourage such as trees, cars, and people. Render the view, and then export the image so it can be touched up in Photoshop. Send the image to the print shop, and get the rendering up on the billboard!

Create animated walkthroughs. Creating animated walkthroughs is an excellent way to visualize the spaces within the project, as walkthroughs are more dynamic than still renderings.

Master It You want to create a compelling animation showing an entry approach to the building. How would you do that with Revit?

Solution Start with a plan view and choose the Walkthrough tool from the View tab. Draw your path, and then adjust the camera at each keyframe to get the desired look and feel.

Export the 3D model for use in other applications. Revit is an excellent application, but a variety of other tools are available that you might want to use for rendering, modeling, or other BIM features such as 3D printing.

Master It You've modeled your project in Revit and assigned materials, and now want to make an animation sequence with 3ds Max. What should you do?

Solution Use the new option to export the model to FBX. This will create a file that can be opened directly with 3ds Max 2009 or later, where you can take advantage of animation tools. To do so, go to the Application Menu, and choose Export > FBX.

Chapter 17: Fine-Tuning Your Preliminary Design

Quantify your preliminary designs. Once your plans are established, create your own area plans to dynamically track changes in the project.

Master It Establish your preliminary design, and then create area plans so you can keep up to date with space sizes, allocations, and your project program.

Solution Use the tools for figuring gross area and rentable area to establish these baseline plans.

Create schedules. One of the benefits of Revit is the ability to manage not only your drawings, but also other information about the project. Create schedules for your project templates to manage the materials within the project.

Master It Schedules have a multitude of uses and value at all levels of the project. Explore a variety of schedules to optimize your workflow and maximize what you can get from the model.

Solution Here is a list of schedules you might try:

- ◆ Wall schedules showing length and area by wall type
- ◆ Multicategory schedules showing a full list of all the families in a project
- ◆ Material schedules—for example, a schedule for reporting the cubic volume of concrete in the project
- ◆ Auditorium seating schedules
- ◆ Door schedules
- ◆ Parking stall schedules for parking counts by type (stalls, accessible stalls, and so on)

Use schedules for preliminary cost estimates. Create a schedule that tracks project costs based on an estimated cost per square foot.

Master It Many developers and facilities managers use BOMA calculations for figuring rentable area, gross area, and R/U (rentable/usable) ratios. Establishing area plans and schedules can help you find these numbers much quicker than a legacy CAD system would have allowed.

Solution Establish the schedules as part of your default templates, and as you create your area plans, the schedules will dynamically fill. Also, become familiar with the typical methods of calculating space. These are some of the formulas you can also incorporate in your default templates:

building rentable area + pro rata building common area = rentable area

gross rentable area / usable area = R/U ratio (load factor)

usable area (1 + load) = rentable area

Chapter 18: Evaluating Your Preliminary Design: Sustainability

Incorporate a sustainable approach from the very beginning of project development. Sustainability is quickly becoming a core approach to any design. Learn to leverage the Revit model for a more holistic approach to sustainability.

Master It BIM is also a computational database that can report information about the virtual building. The important thing about a sustainable approach is to know which questions to ask and to ask them at the right time. What is a strategy for doing this?

Solution Come up with your sustainable goals early on in the project process and revisit them regularly to make sure you stay on track.

Use Revit to create sun studies. Understanding the sun's effect on a building is paramount to sustainable design.

Master It How can you use the tools within Revit to produce still and animated solar studies from interior and exterior views in order to understand shading and the sun's effect on the building and space?

Solution Use the Graphic Display Options dialog box to set the global location of the project. Next, establish a time of day to view the effects of the sun. Create key interior and exterior views of the project and apply these sun settings to the new views. To see the effects of the sun at that time throughout the year, animate the solar study for each week throughout the year.

Track recycled materials and other sustainability strategies using schedules. Keeping track of project goals is an important part of any project process. By using the schedules and other tools in Revit, you can also track key sustainability goals.

Master It Tracking recycled material usage is key to LEED credits and sustainability. Create a material schedule that tracks recycled content volume for concrete.

Solution Create a schedule for the concrete in the building. Using a custom calculated field, apply your percentage of recycled content by building a formula to multiply the percentage of recycled content by the volume of concrete in the model. As you build and refine the design and the model, this value will dynamically update.

Analyze daylighting. Understanding daylighting and its effects within the built environment is a critical part of design and helps with LEED credit 8.1.

Master It Make your designs more sustainable by using the model geometry for daylighting analysis

Solution Set the model up from the beginning of the design process to have the proper reflectivity for your surfaces. Adding these values to your materials helps ensure more accurate daylighting results.

Chapter 19: Annotating Your Model

Annotate views. Room elements are highly useful tools for a number of different applications in a set of documents. Learning how to use them and tag them will help you find areas, create finish schedules, and identify spaces.

Master It Once the model has been largely built, you need to start adding information about rooms and finishes. What tools would you use?

Solution Once the rooms in the project are roughly defined by walls, you can use the Room tool to add room elements to your project. After these are defined, use the schedule key in combination with a room finish schedule to quickly create finish values for each room that are easy to control and define.

Use schedule keys. Adding information to the room element is only part of the documentation and design process. Knowing how to schedule that information allows you to communicate effectively with owners and contractors.

Master It Tags are used to report information about an element. How do tags work in Revit so that they always report accurate and consistent information about the elements they tag?

Solution Elements defined in Revit such as walls, doors, and rooms all have parameters. These parameters can be used to drive information into tags by adding labels to the tag families. If you change the parameter value, the tag will update automatically. Likewise, by editing the value in the tag, you are affecting the element.

Leverage tags. Revit supplies you with three ways to annotate your model and the project. Knowing when to use each and planning for them early in the documentation phase saves time and frustration.

Master It It is important to understand the relationships between elements and materials in Revit early. How does this help streamline the process of keynoting your project when you reach the documentation phase?

Solution If this is your first project in Revit, discuss the keynoting strategy used within your office and see how easily that transitions into Revit. Set up your keynotes and schedules for those notes long before you need to document the project. This will ensure that when the time comes to begin laying out your sheets, you can do it with a minimum amount of disruption to your workflow.

If this is not your first project in Revit, begin embedding notes into your project template, building from the experiences of past projects.

Understand shared parameters. Revit lets its users add as many custom parameters to an element as are needed. When those added parameters need to be visible both in schedules as well as in the elements tags, they need to be created as Shared parameters.

Master It You added a custom parameter to your door and window elements and wish to schedule and tag it such that each window or door tag displays the information about the hardware set. The schedule works well, but your tags seem to be unable to find the hardware set parameter. What is wrong?

Solution To be able to display a custom parameter in a tag, that parameter needs to be created as a shared parameter. Create a shared parameter as a .txt file, and assign it to the tag family as well as in the project environment (to the Door and Window category) to achieve the desired result.

Add text and keynotes. No set of drawings is complete without keynotes or text notes. Understand how to create and modify them for a complete set of documents.

Master It You will need to add notes in every stage of design to communicate your design intent on a project. How do you create and modify the notes to ensure accuracy throughout all the sheets in the set?

Solution Use the Keynote tool on the Annotate tab to insert element, material, and user notes. As these notes are all tied to a single file and are not modifiable within the project, they will always be identical. To modify the notes, simply use the linked text file found under the Tag flyout and choose Keynote Settings.

Chapter 20: Developing the Design with Smart Workflows

Work with repetitive elements. Many projects have repetitive elements and can benefit by using groups and links efficiently.

Master It Think of a scenario in your own practice where elements repeat and how you might use Revit groups to solve the problem.

Solution A hotel room in a multistory tower is a good example of where groups could come in handy. You can draw the walls, add the bathroom and all the fixtures for one unit, and then group them in what will be a typical hotel room. Once they're grouped, you can place instances of the group throughout the model to fill out the design. From there on out, any change to any group will propagate to the other group instances.

Understand the use of groups. Groups are a powerful design tool. Anyone working with repetitive elements needs to understand how they work.

Master It Describe a fundamental benefit of using groups.

Solution When you make a group of elements and then duplicate it many times, it is important to maintain consistent and predictable results. Using groups, you are guaranteed that a change to one instance will propagate to all other instances in the model. At the same time, Revit recognizes that some group instances might have to be slightly different from the rest and that it must be flexible enough to support slight differences without the necessity of creating a separate new group.

Understand the principles of links. Links are Revit's second major tool for repetitive elements, avoiding the file size and performance issues associated with groups.

Master It Using a link paradigm means that the BIM model now depends on links to external files. Even so, the links can be scheduled, dimensioned to, and graphically altered. Despite that, there are still some limitations. What are they?

Solution One of the major limitations is how walls in a linked file interact with walls in the host file. For example, when a Revit link is used, none of the walls in the link will clean up with the host walls and rooms will not be calculated. Note that you can make the walls of a linked file room bounding using its type properties.

Decide whether to use groups, links, or both. Knowing when to link a file can improve file performance and provides an easy way to operate on large clusters of building data. You can hide links, remove them, and work on them independently. Knowing when to use groups can help replicate repeated elements quickly. Knowing how and when to use both groups and links helps speed the documentation process.

Master It Know that links can reduce the overall file size and thus improve performance when working in Revit; imagine a scenario in which you would most certainly want to employ links over groups.

Solution A campus layout master plan would be a great candidate for using links. By building a master site file and building each campus building as a separate file, you could then link them all together in the master file and have good performance in each of the separate files. This also keeps levels and grids from neighboring buildings from interfering with your workflow.

Chapter 21: Moving from Design to Detailed Documentation

Create drafting views. Not every drawing or view in Revit is created with model elements. Some of the views on sheets will be made solely with 2D drafting views. Knowing how to create and use these views is critical to any documentation package.

Master It Keeping views hyperlinked together is a key benefit to using Revit. How do you draw simple, 2D details in Revit but still keep them parametrically linked to sheets?

Solution By creating drafting views, you can use detail lines (found on the Drafting tab) to draft 2D details in from within Revit. These drafting views can then be placed on sheets, keeping all the same parametric values maintained by any other view created in Revit. You can also reference these drafting views with the Callout tool.

Import and link CAD details. Even if you've been using Revit for years, you will need to import 2D geometry from an old library of standards or manufacturer drawings. Understanding how to do this effectively will keep you from having performance issues with your model.

Master It Your office has a huge repository of standard details. How do you reuse details drawn in CAD in a Revit project?

Solution Make sure the CAD detail is free of extraneous information and then import it into a drafting view at a 1:1 scale. Reset the scale to the proper scale of the view and place the new drafting view in the appropriate sheet. When forming a new detail callout from a plan or section, check the box Reference Other View on the Options bar and select the CAD detail from the list. This will give the new detail a SIM (similar) annotation.

Create 2D detail components. Detail components can be used again and again within a model to graphically show in 2D different typical building components. Mastering these will result in enhanced productivity when you work on a project.

Master It Detailing is a process of adding more granular layers of information and graphics to the model and view. What tools would you use to add 2D detail?

Solution Create detail components for content that can be reused in other views. Add as much detail to the component as is applicable, including nesting components within one another. Use masking regions (also referred to as whiteout) to cover unneeded model geometry, taking care to balance proper modeling techniques with efficiency and productivity. Use filled regions to add additional levels of detail and materiality to the view. Use repeating details in lieu of copying or arraying simple 2D elements. Finish the detail by drafting necessary areas with detail lines.

Chapter 22: Advanced Detailing Techniques

Create 3D details. 3D axonometric details are a great way to demonstrate more complex assemblies and conditions in any document set. Knowing how to create them in Revit will expand the ways in which you can detail.

Master It Use a 3D axonometric detail to demonstrate constructability in a unique assembly condition.

Solution Locate the new detail in a wall section or enlarged plan. Navigate to the default 3D view, and using the Orient to View option in the view cube right-click menu, orient the 3D view to match the desired detail. By orbiting the orientated view, you can begin adding annotations and dimensions to describe the construction of the assembly.

Add detail components to 3D families. Adding detail components to 3D families can save time by embedding the linework of a detail within the family itself and making it instantly available throughout all the locations that family is placed.

Master It Create a detail by embedding it into a family so it can be expressed by simply modifying the detail level of a view.

Solution Open the family in the Family Editor. By adding detail components to the family, you can begin building the corresponding detail (flashing, blocking, sealant, trim, etc.). Next, select these elements and modify their visibility to make them viewable only in specific conditions (in this case, the fine level of detail). Reinserting the family into the project allows you to control what is displayed in any view by modifying the view detail in each view.

Reuse details from other Revit projects. There are times when details are common between projects. Knowing how to use details from other Revit projects will cut down on your documentation time.

Master It Use details you created in your other Revit projects.

Solution After finishing the detail or project, from the Application Menu choose Save As > Library > Views to select a variety of views and export them to your project or office standards library.

Chapter 23: Tracking Changes in Your Model

Add revisions to your project. You need the ability to track changes in your design after sheets have been issued. Adding revisions to a drawing is an inevitable part of your workflow.

Master It Add revisions to your project that automatically get tracked on your sheet.

Solution Use the Sheet Issues/Revisions dialog box (choose the Manage tab, then use Settings > Revisions) to add, edit, and manage revisions. Be sure to set the numbering scheme to By Sheet.

Understand BIM and supplemental drawings. Making an actual revision to a construction document involves adding graphics and coordinating the clouds with revisions.

Master It You need to cloud a design change. How would you do this using Revit?

Solution Draw clouds with the Revision Cloud tool. Next, tag your revision clouds with parametric tags. In turn, your title block will also be parametrically tied to each revision placed on the sheet.

Use Autodesk Design Review. You'll often need to share your design with people who do not have Revit, so that your design can be examined and marked up.

Master It How can you export your designs in a lightweight file format?

Solution Export your sheets to Autodesk Design Review by opening the Application Menu, and choosing Export > DWF.

Chapter 24: Worksharing

Set up a project with worksets. Knowing how to activate worksharing and set up the project file for more than one person at a time is critical in any office environment.

Master It How do you work in a single Revit file on a project team with more than one member in the file at a time?

Solution Worksharing allows for multiple users in a Revit environment. Understanding and using worksharing is a vital part of any large-scale project where you will have more than one person doing the drawing. Worksharing will be the most successful when implemented in an organized, well-thought-out division of model assemblies. To set up worksets, first enable worksharing (Collaborate tab > Worksets). Then save the file as a central file and inform team members to make their own local files.

Understand worksharing basics. Once you've enabled worksharing, you'll need to understand the dynamics of central and local files to fully leverage working in a worksharing environment.

Master It Once you have enabled worksets to allow for multiple users, what's the best way to implement and use the file?

Solution Set up a central file on your network. Each of your users makes new, local files from the central file on their local drives and works directly in these copies. These files are smart enough to be able to manage changes between all the members of the project team while updating the central file.

Manage workflow with worksets. Saving to and loading from the central file allow you to view other team members' work and allows them to see what changes to the project you have added.

Master It How can you translate the changes you've made in your local file to the central file on the network? How do you download changes from other team members to your local file?

Solution Use the Save to Central command from the Application Menu. This will copy all of your changes up to the networked central file *and* download their changes to your local file. If you are simply looking for changes others have made to update your local copy (without posting your own changes), you can use the Reload Latest command located in the Synchronize panel of the Collaborate tab.

Understand element ownership in worksets. Editing elements in a central file means you have sole ownership over further changes to those elements. Understanding the permissions will be critical to working in a team.

Master It How do you edit an element in the model if someone has already taken permission of it in a worksharing environment?

Solution By simply trying to edit the element, you can request permission for the object from another user on the team if permission is not readily available. They can similarly grant or deny you permission for any element they own by using the Editing Requests button on the Collaborate tab.

Appendix B

Tips and Troubleshooting

This appendix provides tips and tricks about how to keep your project file running smoothly. Listed here are some pointers to keep you from getting into trouble, along with some solutions in case you do.

Optimizing Performance

It should make sense that a small file on a good network runs the quickest. “Typical” file sizes can vary widely. We’ve seen file sizes range from 30MB to 200MB. Much of that variation depends on the level of detail you’ve put into your model, the presence of imported files (like other 3D files or CAD files), and the overall complexity of your model. Your hardware configuration is also a factor. There are a number of things you can do to be proactive about keeping your model performance optimized. Here are a few we recommend:

Use the 3GB switch. Revit now supports Microsoft XP’s 3GB switch. Use of this setting will give your machine more RAM to draw from before it goes to virtual memory. Windows XP allows any given application access to only 2GB of RAM at a given time; if the application needs more, it gets the rest from virtual memory. Microsoft’s switch (which is available in XP Service Pack 2) allows you to change that 2GB limit to 3GB. To find out how to do this, visit www.autodesk.com/support, choose Revit Building from the menu, and read the support article on enabling the 3GB switch. Of course, you need more than 2GB of RAM in your workstation for this switch to do you any good.


More information on RAM and virtual memory can be found at the Autodesk knowledge website. Visit this site for details:

<http://usa.autodesk.com/adsk/servlet/ps/item?siteID=123112&id=8018971&linkID=9243099>

As another option, Revit supports 64-bit operating systems like Windows XP 64-bit and Windows Vista. This allows you to tap into even more RAM and go well beyond 3GB. Keep in mind, on a 64 bit OS, two gigs are used by the OS itself (rather than one gig in a 32 bit OS), so you will need more than 4 GB of RAM before you will see any difference in RAM allocation.

Don't explode imported CAD files. A CAD file imported into Revit is a collection of objects that is managed as a single entity. If you explode a CAD file, the single object immediately becomes many—and becomes that much more data that Revit needs to track and coordinate. If you're unfortunate enough to explode a hatch pattern, one object becomes many thousands. If you're importing DWG files, leave them unexploded as much as possible. If you need to hide lines, use the Visibility/Graphic Overrides dialog box to turn layers on and off. Explode *only* when you need to change the imported geometry, and start with a partial explode. Figure B.1 shows the tools available in the Import Instance panel of the contextual Modify tab when you select an imported or linked DWG file. Also note that lines smaller than $\frac{1}{32}$ " are not retained with CAD files are exploded. This can result in unusable imports.

FIGURE B.1
Explode options
for an imported
CAD file.



Another option is to change the DWG file directly in CAD by deleting lines and layers you don't need, then reimporting the file into Revit.

As a final option, if you really feel like you need to edit the linework in Revit directly, import your CAD file into a 2D Detail Component family, edit the linework there, and import that Detail Component into your project file. This is a great way to keep the CAD file editable but also keep the number of objects in your project file minimized.

Delete or unload unused DWGs. Often, you import a DWG as a reference, but then you don't need it later in the project lifecycle. It's easy to forget, but if you no longer need an import, go ahead and delete it by selecting it in the view, right-clicking it, and choosing Select All Instances from the context menu, and then delete it. This will delete the import in all views.

Close unused views. Keeping the number of open views to a minimum helps the model's performance. Choose the View tab ➤ Close Hidden Windows often (Figure B.2), because it's easy to have many views open at once, even if you're concentrating on only a few views. Once you reduce your open views to just two or three, you can take advantage of the view switch toggle: press Ctrl+Tab, and you'll cycle through your open views. Press Ctrl+Shift+Tab to reverse the view cycle.

FIGURE B.2
Close hidden win-
dows that you're
not using.




Turn on volume computation only when necessary. You can turn on room volume calculation by choosing the Manage tab ➤ Area and Volume Computations. Check Areas and

Volumes under Volume Computations (shown in Figure B.3) only if you need room tags or a schedule to display volumetric information. Don't forget to switch off this option after you print or view the information. Otherwise, the volumes will recalculate each time you edit something in the model, and this can affect the overall performance of your file dramatically.

FIGURE B.3

Do not compute room volumes unless necessary.



Using Best Practices

The following best practices will not only help you keep your project files running smoothly but will also keep frustration levels with poorly performing files low.

Workshared files: Make a new local copy once a week. Sometimes in a workshared environment, your local copy can begin to perform poorly but others on your team don't share the same problems. If this is the case, we recommend that you make a new local file. Local files can become problematic because of any of the things that commonly cause issues with large files in a networked environment. As a general practice, it's a good idea to make a new local copy once a week.

Use graphics card options to improve drawing performance. In the Application Options ➤ Graphics tab, make sure you have both Use OpenGL Hardware Acceleration and Use Overlay Planes to Improve Display Performance checked (Figure B.4). Deselecting the Use Overlay Planes check box can cause significant degradation in performance—we recommended you never deselect this option.

Import or link DWGs in one view only. Importing in all views can seriously affect performance. Figure B.5 shows the Link (Instead of Import) check box in the Import or Link dialog box. Linking is better than importing if you don't need to edit the geometry.

Watch out for imported geometry. Although Revit has the ability to import files from a number of other sources, you should exercise caution when doing so. If you're importing a 60MB NURBS-based Rhino file into your model, expect your Revit model to grow in size and

react a bit slower than it did before the import. Delete unneeded imports or convert them to Revit content to reduce file size and improve overall performance.

FIGURE B.4
Enable graphics
card options
for better
performance.





FIGURE B.5
Import into
one view.




Purge unused elements. Revit has a built-in tool that allows you to purge unused families and content. This is a good way to reduce file size, improve performance, and minimize the list of things you need to search through when adding content in the project. Loaded but unused families can make your file grow quickly. To purge, choose the Manage tab ➤ Purge Unused. If your file is very large, it may take a few minutes to run this command before you see the dialog box shown in Figure B.6. Here, you can opt to keep or purge families individually.

This is typically *not* a good idea at the beginning of a project, because your template may contain families that you intend to use but haven't yet inserted (such as wall types).

USE PURGE TO REDUCE FILE SIZE

Some Revit families can only be removed from the project with the Purge command. You will notice with elements such as dimensions and text notes, there is no way to delete a family type from the Properties dialog box. To get rid of unused elements of these types, use Purge Unused. Everything included in the Other Styles group falls into this category.

FIGURE B.6
Use the Purge
Unused dialog box
to reduce file size.



Manage the amount of information shown in views. Learn to manage the amount of information needed in your views. Don't show more than you need to show in a view either in depth or in your level of detail. Here are a few easy ways to keep your views opening and printing smoothly:

Minimize the level of detail. Set your detail level (in the View Control bar) relative to the scale you're viewing. For example, if you're working on a $\frac{1}{32}$ " (1:50) plan, you probably don't need Detail Level set to Fine—it will cause your view performance to suffer needlessly.

USE LEVEL OF DETAIL TO SPEED UP VIEW PERFORMANCE

One project was taking upward of 20 minutes to open plan views. As you can imagine, this was very frustrating for the users, especially when you opened those views accidentally. As it turned out, the views were set to a $\frac{1}{16}$ " scale and a fine level of detail. For many of the elements in the plan, none of them showed any significant information at this level of detail. By setting the View Detail to Coarse, users were able to reduce the time to open those views to under two minutes. We further optimized view performance by modifying complex families in the view to show less detail at a coarse level.

Minimize view detail. This goes along with the level of detail, but this tip is more user based than tool based. If you're printing a $\frac{1}{32}$ " (1:50) drawing, make sure you're showing the proper level of detail in the view. Even if Detail Level is set to Coarse, do you really need to show balusters in an elevation on your railing at that scale? They will print as a


thick, black line. Turning them off in this view will help improve not only your printing speed but also the quality of the resulting printed sheet.

Minimize view detail in Components/Families. Along these lines, make sure that component families only display what needs to be shown with regard to orientation. Minimizing detail is a practice that will result in good performance through many aspects of Revit. When creating families, make sure to use the View Levels to control the amount of detail you can see in a family.

Minimize view depth. View depth is a great tool to enhance performance. It's especially valuable in section views. A typical building section is shown in Figure B.7. The default behavior causes Revit to regenerate all of the model geometry the full depth of that view every time you open the view. To reduce the amount of geometry that needs to be redrawn, drag the section's far clip plane (the green dashed line when you highlight the section) in close to the cutting plane.

FIGURE B.7

Minimize the section's Far Clip Offset (the Depth of the section).




Turn off shadows. Shadows can help you make beautiful presentations, give a sense of depth in façades, and show the effect of the sun in a site-plan view; however, shadows are performance intensive and can significantly slow a view's time to open, print, or regenerate as you pan and move around in it. Make sure you turn shadows off whenever you don't need them.

Open only what you need. One of the benefits of having worksets is that you don't have to turn them all on at once. When you open the project, go to the Workset dialog box. There, you can highlight a workset and click the Close button (see Figure B.8). Doing so drops that workset from active memory and gives you better performance. Remember, if worksets are closed, you can't do anything with them. If a workset isn't visible, it won't print. To print a current copy of the whole model, you'll need to turn the worksets back on.

FIGURE B.8


Worksets can be closed to reduce the amount of memory used to open a file.



Break up your model. For larger projects, or campus-style projects, you can break up your model into smaller submodels that are referenced together. You can also do this on a single building. If you decide to divide your project, make your cuts along lines that make sense from a holistic-building standpoint. Don't think of the cuts as you would in CAD, but think about how the actual assemblies will interact in the building. As an example, don't cut between floors 2 and 3 on a multistory building unless you have a significant change in building form or program. Here's a list of some good places to split a model. See Figure B.9 for an example:

- ◆ At a significant change in building form or massing
- ◆ At a significant change in building program
- ◆ Between separate buildings on the site
- ◆ At the building site

FIGURE B.9
Splitting up a
model can improve
performance.



Consider printing paper sheets from DWFs or PDFs. Printing big Revit files can sometimes take a long time. Enabling raster printing speeds up printing, although there is a trade-off compared to the quality that vector printing offers. Depending on the printer, you may get better line quality by going to a DWF or PDF first, then printing your physical sheets. Experiment on a few sheets to see what your printer responds to best before sending your entire set. Printing a digital set first will also give you a record of what you have just printed as well as a quick way to make additional copies later if needed.

Model just what you need. Don't fall into the trap of overmodeling. Just because you *can* doesn't mean you *should*. Be smart about the level of detail you choose to model based on the complexity and size of your project. Some data is just easier and better to show in a 2D detail rather than as 3D model data. The amount of information you model or do not model should be based on your project size and complexity, your timeframe, and your comfort level with the software.

Ask yourself three simple questions when detailing. Many people who understand the principles of modeling in Revit struggle with the changes in methodology when actually creating a set of construction documents. When moving from modeling to detailing, you will find that you are creating and modifying families to add details specific to the current state of the design. When doing this, it always begs the question "How much do I model?" As a rule of thumb, here are three simple questions to help you make the right decision:

Scale *What scale will this detail be seen in?* If it's a very small-scale detail, it might be simpler to just draft it in a drafting view.

Repetition *How many times will this detail appear in the drawing set?* If it will appear only in one location, it might be easier again to just draft it in 2D rather than try to model the element. If it will appear in several locations, modeling is probably the better solution.

Quality *How good at modeling families in Revit are you?* Don't bite off more than you can chew. If you're new to Revit, keep it simple and use 2D components. The more projects you complete in Revit, the better you'll begin to understand the change to a BIM workflow.

Don't overconstrain. You must embed user-defined relationships and constraints in the design to help keep important dimensions constant. However, if you don't need to lock a relationship, don't. Even though the option to lock all alignments is available, it's often not necessary to do so. Overconstraining the model can cause problems later in the project process when you want to move or modify an element and you need to figure out (or remember) what you locked and where to allow the particular element to be moved or modified.

Assign proper view detail. It is possible to create families in Revit with a seemingly infinite amount of detail. Use the Visibility tool found in the Family Editor to set the appropriate level of detail for when the element is viewed in plan, elevation, or section. Setting elements to Coarse, Medium, or Fine can also keep your families from looking like blobs in Coarse view and small scales as well as quicken your screen-refresh times.

Fix an overconstrained object. If you keep encountering a dialog box telling you the model is overconstrained and this is impeding your workflow, you can delete the constraint. If it is a simple element (such as a wall with no openings or sections), it might be easier to simply delete and redo the troubled object.

Close Revit with an empty view. To avoid long opening times for really large files, establish an office standard that you always close your last view as a drafting view or legend that is empty, or maybe contains only some text with the project name. This way, when Revit first opens the project it will need much less processing time. By default, Revit always opens with the view from when the project was last saved. We've seen some nice-looking "project pages" made with a drafting view using text and some simple instructions.

Upgrade to new versions. Many CAD workflows required you to use the same version of CAD over the lifecycle of the project. With each new release of Revit, many changes have been put in place to make large files easier to manage and saving faster, as well as improve overall performance.


Dealing with File Corruption

If your file becomes corrupted and begins to crash frequently, there are a few things you can do to help fix the problem before you call Revit Support in a panic. To proactively avoid this issue, focus on the previous tips before you begin having problems. Otherwise, here are some suggestions on what to do when you get into trouble:

Audit the file. Auditing the file will review the data structures and correct problems that are found within the model. An audited file won't look any different when the audit is completed; however, it should (ideally) not crash. This is not a cure-all, by any means, but it can help you get out of a tight spot when necessary.

Get everyone out of any worksets and local files, and have them relinquish their permissions. Open the file using the Application Menu > Open > Project. The resulting Open dialog box lets you browse to a project location. Select your project and before clicking the Open button to open the file, select the Audit check box in the lower-right corner (shown in Figure B.10). Revit gives you a warning before performing an audit on your file. The audit itself can take several minutes to complete. When this process is finished, save the project with a new name or in a new file location; don't save this file over the old Revit file. Saving over an existing Revit file can sometimes lead to instability. When you're finished, have everyone make a new local file, and you can get back to work.

FIGURE B.10
The Audit option is located in the Open dialog box.




Review warnings. Each time you create something that Revit considers a problem, a warning is issued. Warnings will accumulate if left unresolved. Think of all these errors as unresolved calculations. The more there are, the more your computer will have to struggle to resolve them, and eventually you will have performance issues or file instability. Revit provides an interface where you can review all the warnings in the project and fix problems.

Try to read and react to all warnings that Revit sends. You don't have to do it when you're under a tight deadline or when doing so will interrupt your work. But once a week, you should spend 30 minutes reviewing the warnings, as this can improve your model's overall performance. You can find the list of warnings in your file on the Modify tab on the Inquiry panel. Choose the Warnings button (Figure B.11).

Purge unused elements. We referred to this earlier in the "Best Practices" section. Purge can also be used to get rid of poorly built families that might be wreaking havoc in your file.

FIGURE B.11
Review the warnings in this dialog box.



Getting Started in Revit

Knowing how and where to begin your journey can be a challenge, and we want to give you a few pointers to help you get started. Although this list isn't complete by any means, it should help steer you in the right direction:

Begin with the end in mind. Planning is always a good way to start a project. Regardless of your project, when working with Revit it's always harder to go back and modify the model to fit a new goal than to build to suit the goal along the way. You can set yourself up for a successful implementation from the beginning by using a bit of forethought about your process, workflow, and desired outcome. If you are using Revit for the first time, set some reasonable limits for how far you plan to take the modeling and detail process. This will help guide the development of families along the way. If you are trying to push into some higher-level BIM challenges like 4D, costing, or energy modeling using Revit model geometry, set those goals at the beginning of the project process as each will require you to focus on aspects of the BIM model you might not have typically considered.

Get your project and office standards in place early. As design professionals, we have a tendency to develop unique graphic conventions and styles for our documents. This is a specific area where good planning leads to a good project. If possible, get your standards in place before you begin a project. Revit does an excellent job of getting you started with a good template of graphic standards to work with. However, if you're like most architects, an application right out of the box is never quite nice enough. Revit provides a good starting point for customization, and with some up-front time, you soon can have your project and office standards up and running. Once you nail down your standards, they can be easily applied to your project using the Transfer Project Standards command on the Manage tab.

Remember that the first project you do in Revit will require a change in methodology. You're leveraging technology to help you change the way you approach design and documentation. Don't expect the process to have the same workflow as it did in a CAD-based system. Try to stay flexible in your expectations and schedule and allow yourself time to adapt to the change.

Don't try to conquer the world on the first project. There are many advantages to using BIM as a design and documentation methodology. As this process becomes more mainstream within the industry, those benefits will only increase. All of these things and more are possible with the use of Revit, but it will take a couple of projects to get there. Tailor the use of BIM to the project, and use the features that will maximize the benefits of using BIM. Choose your goals realistically based on the expertise of your project team, and plan ahead so those goals can be met successfully. Consider a project that is less complex for your initial pilot.

LEARNING A MODELING WORKFLOW

One of the most important rules to follow as you begin your project is to model the building as it will be built. That said, keep in mind that you do not need to model every condition three-dimensionally. Use Revit to get the essential dimensions and building form coordinated. You can then embellish the model with 2D details to convey the fine grain.

Model correctly from the beginning. We can't stress this enough. As you refine your design, it's critical to model correctly right from the beginning so you don't have to fix things later. What does this mean? As an example, think of a wall. Does it sit on the floor, or does the floor attach to the wall? If you can begin to think about how your project will be assembled, it will save you a lot of time at the end. It's good practice to plan ahead, but remember that Revit will allow you to make major changes at any stage in the process and still maintain coordination. If you are still in an early phase of design and do not know the exact wall type, use generic walls to capture your design intent; changing these later will be simple.

Get information into the project as soon as it is known. A key advantage of using Revit is the ability to change your project schedule. In a traditional design process, most of the effort on a project is realized during the construction-document phase. At that time, a typical project has the most staff working on the project, and it can be fairly difficult to implement major changes to the project design. This is due to the complexity of the documents by this time and the amount of effort for the team to redraw all the changed information. You'll find that with Revit, design change is largely managed by the software itself. This gives you a great deal of flexibility in both your design and documentation. Take advantage of this shift in the process, and add information to your model early. It can be in the form of more detailed content or showing the material construction of your wall system. Remember that you can change all this information much more quickly and easily than you ever could in CAD, so don't assume you're locked into the information you displayed early in the design process.

Plan for good communication among team members early in the process. Communication within a team is critical for understanding a project and documenting it successfully. One of the downfalls inherent in a CAD-based system is that there is no connection among the different files that make up the drawing set. This phenomenon carries through to the project team and is a function of project workflow and project management. In CAD, it's possible for team members to work in some degree of isolation. They aren't forced to immediately reconcile their changes with changes made by their teammates. Revit's single-file environment forces a much higher degree of team communication between not only the architects but also your structural and mechanical engineers.

Don't try to model everything. Most of us have drafted in a 2D environment until now. Moving to a 3D world is a significant change. Do you have to model every single screw? Every mullion? Every stud? That's a good question. The simple answer is no, you don't have to, and in fact you should not attempt to do so. Like any BIM system, Revit isn't 100 percent 3D information. Standard computer workstations aren't capable of handling all the data of a building in model form. Additionally, few projects have the time in their schedule to model the screws in a sheet of gypsum board or the sealant around all the windows; some of that information is best presented in 2D or in the specifications. This still leaves you with a wide range of options for modeling. In the beginning, err on the side of simplicity. It's far easier to add complexity to your model later on as you gain experience and confidence than it is to troubleshoot overconstrained parameters early in the process. Start with the big ideas: walls, openings, roofs, and so forth. Work your way down to a comfortable level of detail for both you and your computer.

Organize your team. A BIM project team includes three basic technical roles. These roles are interchangeable, especially on smaller projects with fewer team members. However small the team, it's useful to make sure all these roles are filled:

Building designer This is the person or team whose primary responsibility is to figure out what the project will look like and how it will be made. They create walls, floors, and roofs and locate windows, doors, and other building elements.

Content/family creator The family creator's primary role is to create the parametric content in the Revit model. This is typically someone with 3D experience who also has a firm understanding of Revit and Revit families. The families, as you'll see later, have parameters that can control visibility, size, color, proportion, and a number of other things.

Documenter This role supplies the bulk of the documentation. It consists of drafting some of the 2D line work over portions of the 3D model to show detail, adding annotations and keynotes, and creating details.

Finding Additional Resources

If you get stuck along the way, don't assume you're alone. There are myriad resources in the help file, in books, or on the Web to help you find a specific solution to your problem. Chances are, someone has tried the same thing before. In our digital age, a wealth of information is available online; powerful communities of passionate users are out there willing to help. So before you spend hours trying to work through a particular problem on your own, try tapping some of the existing resources:

Revit Help menu Your first stop, if or when you get stuck, should be the Revit Help menu. It's one of the easier and more robust help menus out there, and it can give you a lot of useful information very quickly. It's also the most accessible help source. As with most applications, it's at the far right of the menu bar.

Subscription Support If you have bought Revit on subscription, Revit Subscription Support offers an exemplary web-based support system. Their responses are speedy, and their advice is top-notch. If you need information more quickly, Revit also has an online knowledge base of FAQs that is available without a subscription. Both of these resources can be accessed at www.autodesk.com/revit.

AUGI Autodesk User Group International (AUGI) is also an excellent source for tips and tricks. It's an online user community free to participate in, ask questions, get answers, and share families and examples. To get the benefit of this fantastic online resource, go to www.augi.com and look for Revit Architecture as a product. If you never logged in, you will have to register once; from then on it's easy!

Revit City Looking for content and families? Revit City, another free online service, has a growing database of free families posted by other users. Its address is www.revitcity.com.

Autodesk Discussion Groups These pages offer insightful discussions and some great Q&A threads: <http://discussion.autodesk.com/>.

AECbytes A website dedicated to following and reporting on the trends in the AEC industry, with a strong focus on BIM, technology, and the direction of the industry—put together by Lachmi Khemlani: www.aecbytes.com.

Blogs There are numerous blogs from passionate, experienced Revit aficionados. Here are some of them in no particular order:

<http://revit4you.blogspot.com> (Philippe Drouant [French])

<http://insidethefactory.typepad.com> (Tom Vollaro, Revit Product Designers)

<http://revitoped.blogspot.com> (Steve Stafford)

<http://revitnorge.blogspot.com> (Håvard Vasshaug [English and Norwegian])

<http://designreform.net> (Dave Fano)

<http://www.allthingsbim.blogspot.com> (James Vandezande)

<http://architechture.blogspot.com> (Phil Read)

<http://irevit.blogspot.com> (Craig Barbieri)

<http://dorevit.blogspot.com> (Robert Manna)

<http://do-u-revit.blogspot.com> (David Baldacchino)

<http://malleristicrevitation.blogspot.com> (Aaron Maller)

<http://www.bimx.blogspot.com> (Laura Handler)

<http://www.revitbeginners.blogspot.com> (Bradley Hartnagle)

<http://revitbeginners.blogspot.com> (David Duarte)

<http://www.revitcoaster.blogspot.com> (Troy Gates)

<http://revitit.blogspot.com> (Daniel Hurtubise)

<http://revitrocks.blogspot.com> (Daryl Gregoire)

<http://www.revitfamilies.blogspot.com> (Shaun Van Rooyen)

<http://www.revit-alize.blogspot.com> (Bruce Gow)

<http://www.revitrants.blogspot.com> (Chris Price)

<http://blog.reviteer.com> (Tom Dorner)

<http://www.revitlution.blogspot.com> (Christopher Zoog)

<http://www.revit-up.blogspot.com> (The PPI Group's Revit evangelist)

<http://www.greenrevit.blogspot.com> (Beau Turner and Bradley Hartnagle)

<http://www.revitup.co.za> (Justin Taylor)

<http://gmcowelljr.wordpress.com> (Greg McDowell, Jr.)

<http://www.autodesk-revit.blogspot.com> (David Light)

<http://www.auservice-bim.blogspot.com> (Simone Cappochin [Italian])

<http://www.cmotion.net/products/revit-tools.html> (Siggi Pfundt and Gotthard Lanz [German and Italian])

Index

Note to the Reader: Throughout this index **boldfaced** page numbers indicate primary discussions of a topic. *Italicized* page numbers indicate illustrations.

Numbers

- 2D elements, importing, 669–670
- 2D line-based families, **325–326**
- 3D components on divided surfaces, **286–290**, 287–290
- 3D line-based families, **327–328**, 328
- 3D models, **3–4**, 6, 6
 - conceptual, importing, **262**, 262
 - context, **269–270**, 270–271
 - Building Maker tools. *See* Building Maker tools
 - design options, **273**, 273–274
 - program check and feasibility, **271–272**, 272
 - custom content. *See* custom 3D content
 - details
 - annotations, **658**, 658
 - creating, **653–658**, 654–658
 - physical, **228–229**, 228
- 3D views
 - axonometric, **71**
 - orienting, **71–72**, 71, **655–656**, 656–657
 - perspective. *See* perspective views
 - section boxes in, **655**, 655
- 3GB switch, **731**

A

- Absolute keynote paths, 573
- accelerators, **95–96**, 95

- Acquire Coordinates option, 269, 605
- Activate View option, 53
- activating
 - Project Browser views, **53**, 53
 - worksets, 691, 691
- Add Current Folder to Places option, 29
- Add Point tool, 416
- Add Split Line tool, **416–417**, 417
- Add to Design Option Set dialog box, 303, 303
- Add tool
 - groups, 589
 - parameters, 555, 555
- additive selections, 76
- AEC (Architecture, Engineering, Construction) world, 3, 12
- AECbytes site, 743
- Align tool, 173, 173
- aligned dimensions, 113
- aligning
 - elements, **87–88**, 88, 173, 173
 - fill patterns, 109, 110
- Always Vertical parameter, **334**, 335
- analytical drawings, 439–443, 440–443
- angles
 - elevation tags, 132
 - extrusions, 384, 384
 - fill patterns, 110
 - joins, 431, 431
 - railings, 427, 427
 - reference lines, 187, 187
 - revolves, 206–207, 206–207
 - roof slope, 394
 - rotation, 83, 85
 - segments, 214, 214
 - shadows, 443
 - sun, 441, 443, 514–515
 - sweeps, 211, 211
 - units, 165, 169
- Angles Greater Than setting, 427, 427
- angular dimensions, 113
- animation
 - sun studies, **515–519**, 516–518
 - walkthroughs, **477–478**, 478
- Annotate tab, 40, 40
 - tags, 550–551, 550
 - text, 568, 571, 573
- Annotation Objects tab, 119, 119
- annotations, **531**
 - 3D detail, **658**, 658
 - callouts, 127–128, 127
 - crop regions, 643
 - keynotes. *See* keynotes
 - material definitions, **101**
 - object categories, **19**
 - revision clouds, 677, 677
 - rooms. *See* rooms
 - schedule keys, **546–549**, 547–549
 - separation lines, **535–536**, 536
 - shared parameters. *See* shared parameters
 - tags. *See* tags
 - text, **568–570**
 - views, **531**, 531
 - visibility, 499
- appearance
 - materials, **108**
 - schedules, 143, 496, **503–506**, 504–505
- application button, 36
- application frame, **36–44**, 36–44

application menu, **36–37**, 36
 Apply Nosing Profile
 option, 159
 Apply View Template
 option, 175
 Architecture, Engineering,
 Construction (AEC) world,
 3, 12
 architecture history, 1–2
 Area and Volume
 Computations dialog box
 area plans, 484, **484–485**
 automated calculations,
 541, 541
 settings, **168–169**, 169
 Area Boundary tool, 487
 Area Boundary Line tool, 490
 area plans
 calculations, **483–484**,
 483–485
 complex, 490
 gross, **485–487**, 485–487
 rentable, **487–490**, 487–490
 vs. room areas, 540
 area schedules, 493
 Area Schemes tab, 484, 485
 areas
 adding, **491–492**, 491–492
 computation settings,
 168–169, 169
 rooms, **540–542**, 540–543
 units, 165
 arrays
 creating, **346–348**, 347–348
 elements, **85–87**, 86
 formulas for, **343–344**,
 343–344
 parametric, **340–341**,
 340–341
 Arrow Angle setting, 132
 arrowheads
 keynotes, 578
 leaders, 118
 articulation, wall, **356–360**,
 357–360
 Artificial Light dialog box,
 469, 469

artificial lighting, **469**, 469, 509
 Associate Family Parameter
 dialog box, 247, 348–349
 Associate Parameter dialog
 box, 342
 associations
 arrays, 87
 bidirectional, 23
 shutter width, 342
 asymmetric slopes on gable
 roofs, 394, 394
 At Library Locations
 method, 573
 Attach Detail tool, 589
 Attached Detail Group
 Placement dialog box, 592
 attached detail groups, 584,
 592, 593
 auditing files, **739**, 740
 auditorium railings, 436
 Auto - By shared coordinates
 option, 268, 605
 Auto - Center-to-center
 option, 268
 Auto - Origin-to-origin option,
 268, 605
 auto-hiding sections, **68**
 AutoCenter to Center option,
 605
 Autodesk Design Review. *See*
 Design Review
 Autodesk Inventor software,
 294–295, 295–296
 Autodesk Maya, **293–294**, 294
 Autodesk Online services, 38
 Autodesk User Group
 International (AUGI), 743
 automated dimensioning,
 173, 173
 automating area calculations,
 488, 541, 541
 axes for revolves, 206, 206,
 208, 209
 axonometric 3D views, **71**

B

background
 photorealistic renderings,
 470–471, 471
 text, 118, 118
 balusters
 main patterns, **428–429**,
 428–429
 placement, 426, 427
 railings, 424, 424
 per tread on stairs,
 429–431, 430
 barrel roofs, 383, 383, 385,
 410, 410
 Base blend setting, 216
 Base Extension parameter,
 366–367
 Base Level property, 381
 base molding, **643–644**, 644
 Base Offset property, 539
 Base Offset from Level
 property, 381
 Baseline dimension style, 114
 Basics Design bar, 66
 Begin with a Riser setting, 159
 Beginning setting for baluster
 patterns, 429, 430
 behavior of keynotes, **571–572**
 Bernini, Giovanni, 2
 bidirectional associations, 23
 bidirectional relationships,
 22–23, 22–23
 BIM. *See* Building Information
 Modeling (BIM)
 Binding a Revit link within the
 parent model option, 607
 binding links, 603, 607–608,
 608
 black and white high-contrast
 effects, **444**, 444
 blends, **215–216**, 215–216
 examples, **221**, 221
 for lamp, **219–221**, 219–220
 troubleshooting, **217**,
 218–219
 vertices, **216**, 217–218
 walls, **368**

- blocks, 21
- blogs, 744
- Bold setting, 118
- BOMA (Building Owners and Managers Association) area calculations, 484
- Boolean joins, 286
- boolean operations, **240–242**, 240–242
- Borromini, Francesco, 2
- borrowing elements, **703**
- Bottom view range for floor plans, 57, 58
- boundary lines, 485–486, 486
- bounding boxes, 541, 541
- Break Symbol in Plan setting, 158, 159
- Broken Section Display Style setting, 121, 121
- broken section lines, 67, 67
- Browser Organization
 - Properties dialog box, 52, 52
- Brunelleschi, Filippo, 2
- Build panel, 47, 47
- building area schedule updates, 501
- Building Information Modeling (BIM), 1
 - advantages, 1–4
 - for creativity, 6, 6
 - drafting, 9, 9
 - Family Editor, 9, 10
 - interaction, 7
 - layers and X-References, 10
 - as new technology, 12
 - problem-solving, 8, 8
 - process change, 4–5, 5, **10–11**
 - properties, 6, 7
 - tool support, 8–9
 - working with, **12–13**, 13
- Building Maker tools
 - advantages, **274–275**
 - design verification, **278–281**, 279–281
 - Mass Floors, **275–278**, 276–278

- Model by Face tool, **281–284**, 282–283
- Building Owners and Managers Association (BOMA) area calculations, 484
- By Category tag option, 551–552
- By Date, Time, and Place sun angle setting, 443, 514
- By Host railings option, 433
- By Keynote numbering option, 573
- By Project revision numbering option, 674
- By Sheet option
 - keynote numbering, 573
 - revision numbering, 674
- By Type railings option, 433, 433

C

- CAD files and formats
 - details, **617–618**, 617–618
 - exploding, 732
 - linking, **614–615**, 614
- calculated fields, 503, 503
- Calculated Value dialog box, 503, 503
- calculations
 - area plans, **483–484**, 483–485, 488, 541, 541
 - room volume, 732–733, 733
 - stairs, **158**, 158
- Callout tool, 630–631
- callouts and callout tags
 - custom, **127–130**, 127–130
 - elevation, 133
 - working with, **628–629**, 629
- Camera tool, 461
- cameras
 - 3D views, **72–73**, 72
 - perspective views, **461–462**
 - showing, **463**, 463
 - sun studies, 511–512, 511–512
- carbon footprints, 507
- cars, 475–476

- Cascade option, 45
- Cast Shadows option, 513
- categories, **15–17**, 16–17
 - annotation, **19**
 - imported, **20**, 21
 - Model Object, **17–18**, 18–19
 - for shared parameters, **561–562**, 561–562
- CDs (Construction Documents), 7
- ceilings
 - floor connections and details, **645–646**, 645–646
 - types, **156**, 156
- Center setting, 429, 430
- Centerline Pattern option, 116
- Centerline Symbol option, 116
- Centerline Tick Mark option, 116
- central files
 - saving, 694
 - workflows, **698–699**, 698
 - working on, 696
 - in worksharing, 690, 690
- CFDs (computational fluid dynamics), 522
- chain selections, 76
- chairs
 - arrays, **346–348**, 347–348
 - nesting, **346**, 346
 - visibility, **348–349**, 348–349
- Change Sweep Return option, 364
- change tracking, **673**
 - BIM and supplemental drawings, **680**
 - Design Review. *See* Design Review
 - revisions, **673–680**, 674–680
- classification system, 16
- Close Hidden Windows option, 45, 733
- closed loops
 - blends, 221, 221
 - lofts, 252
 - profiles, 324, 324
 - revolves, 207–208, 207–208
 - sketches, 182, 182
 - sweeps, 210

- closing
 - Revit, **706**
 - unused DWGs, 733
- clouds, 470–471
- coarse settings
 - Scale Fill parameter, **451–452**
 - wall detail, 153
- Collaborate tab, 41, 41
- color
 - dimensions, 116
 - elevation tags, 132
 - elevations, **455–456**, 455–456
 - fill schemes, **176, 446–448**, 447–448
 - in importing and linking, 616
 - legends, 446–447, 447
 - level tags, 134
 - lines, 102
 - text, 118
- color-coded plans and sections, **445–446**, 446
 - fill schemes, **446–448**, 447–448
 - sections, **449–450**, 450
- Color Fill Schemes dialog box, 446, 448
- commas (,) in type-catalog syntax, 164
- common edges, 168, 168
- communication with teams, 742
- Communications Center, 38
- complex area plans, 490
- complex roofs, 224, 224
- component families, **27–28**, 28, 30, 31
- compound walls, 356, 357
- Computation Height property, 543, 543–544
- computational fluid dynamics (CFDs), 522
- Computations tab, 484, 484
- conceptual design and early studies, **265**, 266
 - positioning imported files, **268–269**
 - site data and context, **266–268**, 267–268
- conditional visibility, **338–339**, 339
- cone roofs, 408, 408
- constraints
 - design stage, 25, 25
 - move, 82, **92**, 92
 - in performance, 739
- construction document sets, 331
- Construction Documents (CDs), 7
- context, building, **266–268**, 267–268
- contextual tabs, 39, 39
- Continuous dimension style, 114
- converting groups into links, 602–603, 603–604
- coordinates for UV surface divisions, 260, 260–261
- copies in performance, 733
- Copy tool, 83
- copying
 - area boundaries, 491–492, 491
 - color, 448–449, 449
 - with Copy, 83
 - groups, 594
 - with Move, 82
 - options, **78–79**, 78
 - sweeps, 212
 - system families, 27, 27
- cores, walls, **351–353**, 352–353
- Corner Posts At dialog box, 427
- Corner Radius option, 127
- corruption, file, **739–740**, 740
- cost estimates, **502–506**, 502–505
- cost schedules, **313–314**, 313
- Count Selection tool, **38–39**, 38
- Create Floors tool, 282
 - Create Form tool, 238–239, 238
 - parametric extrusions, 244
 - revolves, 250–251
 - void and solid forms, 240, 240
 - Create In-Place Mass tool, 270
 - Create Instance group
 - option, 594
 - Create Mass tool, 236
 - Create Roof tool, 293
 - Create Similar tool, **79**
 - Create tab, 40, 40
 - Create View Template From
 - View option, 50, 50
 - creativity, 6, 6
 - Crop Region Size dialog box, 73
 - crop regions
 - annotations, 643
 - perspective views, 73, 73
 - cupolas, 208, 208
 - Current View copying
 - option, 79
 - Current View Only option, 269, 615
 - Curtain Grid tool, 371
 - Curtain Grid Line tool, 373
 - curtain panel families, **332**, 332–333
 - Curtain System tool, 282
 - curtain systems
 - 3D components on divided surfaces, **286–290**, 287–290
 - Model by Face tool, **283–284**
 - with Rhino, 292–293
 - Curtain Wall Panel.rtf
 - template, 373
- curtain walls, **369–370**, 369–370
 - designing, **370–373**, 371–373
 - doors and windows, **374**, 374
 - panels, **373–375**, 374–375
- custom 3D content, **319**
 - encoding design rules, **341–344**, 341–344

families
 building, **345–349**,
 345–349
 categories and
 parameters, **333–335**,
 333–335
 curtain panel, **332**,
 332–333
 detail component,
331, 331
 face-based, **328**, 329
 host-based, **322–323**, 323
 line-based, **326–328**,
 327–328
 linking parameters,
337–339, 338–339
 modeling, **319**, 320
 nesting, **335–339**,
 336–340
 profile, **323–326**,
 324–326
 RPC, **329–330**,
 330–331, 334
 template selection,
320–321, 320–321
 types, **322**
 work plane-based, **329**
 parametric arrays, **340–341**,
 340–341
 custom images for materials,
474–475, 474–475
 custom keynotes, **139–140**,
 139–140
 custom line types, **623–624**, 624
 custom patterns, **108–112**,
 108–110, 433
 custom tags, **119**, 119,
135–136, 135
 doors, **136–138**, 136–138
 revision clouds, **679**
 view. *See* view tags
 custom templates, **97–100**,
 98–99
 custom title blocks, **140–145**,
 141–145

custom walls, **148**, 148–150
 default wrapping, **153**, 153
 layers, **150–154**, 151–152
 preview window, **150**

cut graphics, 18, 19
 Cut Line Styles, 166
 Cut Pattern option, 107
 Cut Plan Profile tool, 384
 Cut planes, **57–60**, 59–60
 Cutoff Level property, 381
 Cutoff Offset property, 382

D

daylighting, **527–530**, 528–529
 Deactivate View option, 53

defaults

graphics settings, 168
 keynote text files, 572
 project settings, **172–176**,
 173–176
 view templates, 175
 wall wrapping, **153**, 153
 work planes, **193–197**,
 193–197

Defines Slope option, 380–381

Delete Dedicated Options

Views dialog box, 308, 308

Delete Inner Segment option, 90

deleting

dimension types, 117
 line styles, 103
 markups, 688
 materials, 106
 tags, 532, 533
 text type, 119
 unused DWGs and
 views, 733

Deny/Retract option, 705

dependencies

views, 19
 work planes, 184

depth

blends, 215
 elevations for, **453–455**,
 453–456
 extrusions, 204
 view, **60–62**, 60–61

design cycle, **509**

Design Option Set dialog box,
 307, 307

design options, **299–300**, 299

accessing, **300**, 300

design-option sets,
300–301, 301

displaying, **306–307**,
 306–307

editing, **304–306**, 304

elements for, **301–304**,
 302–303

with parametric design,
313–316, 314–316

in practice, **308–312**,
 308–312

quantities and cost
 schedules, **313–314**, 313

rooms, **314–316**, 314–316

selecting, **307–308**, 308

Design Options dialog box,
 301–302, 302, 309, 309

Design Review, **682**

exporting to, **684–686**,
 684–686

importing markups,
687–688, 687

interface, **682–683**, 682–683

model markup in, **686**,
 686–687

design rules, encoding,
341–344, 341–344

designer role, 743

designing curtain walls,
370–373, 371–373

Detail Component.rtf file, 331

Detail Component Line based.
 rtf file, 331

detail groups, 584, **600–601**,
 600–601, **619**

Detail Level setting, 735

details and detail components,
 17–18, 18–19, **611**

3D

annotations, **658**, 658

creating, **653–658**,
 654–658

callouts, **628–631**, 629
 creating, **619–620**
 drafting views, **612**, 612
 exporting, **667–670**, 668
 families, **331**, 331, **659–663**, 659–663
 groups, **592**, 593
 importing and linking, **612–618**, 613–614, 617–618
 importing views, **669–670**, 669–670
 information for, **630–631**, 630–631
 keynotes, 577, 577
 line tools. *See* line tools
 for line types, **623–624**, 624
 nesting, **648–650**, 649–650
 properties, **623**, 623
 repeating, **621–622**, 621–622, **646–647**, 647
 rotating, 623
 shaft opening, **670–671**, 670–671
 symbolic lines for, **665–667**, 665–667
 tips, **651**
 visibility settings, **663–665**, 664–665
 wall sections
 components, **634–638**, 634–638
 model details, **639–650**, 639–650
 SIM condition, **632–633**, 632–634
 .dgn files, 615
 dialog launchers, **42–44**, 42–44
 Dimension Line Extension
 setting, 115
 Dimension Line Snap Distance
 setting, 117
 Dimension String Type
 parameter, 114
 Dimension tool, 435
 dimensions
 defaults, **173**, 173
 in family details, 660, 660

formulas for, **342**, 342–343
 in moving elements, **80–81**, 80–81
 styles, **113–117**, 114–115
 in views, 531
 Direct Editing tool, 416
 directions in reference planes, **205**, 205
 Directly sun angle setting, 443
 Disallow Join option, 354, 354
 Disassociate option, 192
 discussion groups, 743
 disjoining
 hosted elements, 82
 walls, **354**, 354
 displaying design options, **306–307**, 306–307
 Dist. from Previous setting, 429
 Divide Surface tool, 260–261, 260
 divided surfaces, 3D
 components on, **286–290**, 287–290
 documentation. *See* annotations
 documenter role, 743
 documents, **8–9**
 dome roofs, 208, 208, 385, 385, 409, 409
 Don't Cut tool, 241
 Door category, 62
 Door-Curtain Wall.rtf
 template, 374
 door knobs, 209, 209
 doors
 curtain wall, **374**, 374
 defaults, 172
 host-based families, 322, 323
 in modeling principles, 200, 200
 rotating, **83**, 83
 symbolic lines for, **666**, 666
 tags, 532, **552–554**
 custom, **136–138**, 136–138
 shared parameters for, **564–567**, 564–568
 types, **161–162**

dormers
 creating, **412–415**, 412–415
 hipped roofs with, 404–405, 404–405, 407, 407
 drafting, **9**, 9
 drafting lines
 for elevations, **455**
 reusing, **640**, 640
 drafting patterns, 108–109
 drafting views, **612**, 612
 drainage points, 418
 Draw panel, 238, 238
 drawing list schedules, 494
 Duplicate option
 groups, 594
 materials, 106
 Dutch gables, 402–403, 403–404
 DWF Export Settings dialog
 box, 683–684, 684
 DWF files
 exporting, **684–686**, 684–686
 in performance, 738
 sharing, 682
 DWG files
 importing and linking, 266, 614
 in performance, 733
 with SketchUp, 290
 .dxf files, 614

E

edges
 common, 168, 168
 silhouetted, **464**, 464–465
 Edit Assembly dialog box
 floors and roofs, 155, 155
 split sections, 358–360, 360
 sweeps and reveals, 361
 wall cores, 352, 352
 wall extensions, 366
 wall tools, 356, 357–358
 walls, 148, 149–150, 153
 Edit Baluster Placement dialog
 box, 426–428, 427
 Edit Blend Base setting, 216
 Edit Blend Top setting, 216

- Edit Color Scheme dialog box, 446–447, 447
- Edit Extrusion option, 203
- Edit In-Place button, 239
- Edit Joins tool, 432
- Edit Label dialog box
 - callouts, 128
 - custom title blocks, 142, 142
 - door tags, 136, 136
 - parameters, 124, 124, 566
- Edit option for groups, 595
- Edit Rail Joins tool, 432
- Edit Rails dialog box, 425–426, 426
- Edit Roof Structure dialog box, 418, 419
- Edit Shared Parameters dialog box, 559–562, 559–560
- Edit Vertices tool, 216
- Edit Work Plane option, 192, 204–205, 204
- editable worksets, 692, 692
- editing
 - actions for, 75
 - aligning, 87–88, 88
 - arraying, 85–87, 86
 - constraints, 92, 92
 - copying and pasting, 78–79, 78
 - Create Similar, 79
 - extending lines and walls, 90, 90
 - joins, 93–94, 93
 - keyboard shortcuts, 95–96, 95
 - moving, 79–82, 80–82
 - offsetting, 91, 91
 - painting, 94–95, 95
 - pinning, 91–92
 - rotating and mirroring, 83–85, 84–85
 - scaling, 87, 87
 - selecting, 75, 76–78, 77
 - splitting, 90, 90, 94–95, 94
 - trimming lines and walls, 89, 89
- blend vertices, 216, 217–218
- design options, 304–306, 304
- detail components, 635–638, 635–638
- groups, 599–600, 600
- keynotes, 571–572
- materials, 105–108, 105–107, 472, 472
- schedules, 503–506, 504–505
- sketches, 183
- wall joins, 354, 354
- work planes, 192
- Editing Requests dialog box, 705–706, 705
- electrical lighting, 509
- Element Assembly dialog box, 361
- Element Properties button, 43, 43
- Element Properties dialog box, 6, 7
 - color fill, 449
 - parameters, 555, 565
 - parametric forms, 242
 - regions, 626
 - repeating elements, 621
 - roofs, 391, 392
 - rooms, 532
 - stacked walls, 356
 - sweeps, 211
 - visibility, 348–349
 - wall extensions, 366
 - wall wrapping, 361
 - walls, 172
 - worksets, 695, 697
- elements
 - aligning, 87–88, 88
 - arraying, 85–87, 86
 - borrowing, 703
 - default settings, 172–176, 173–176
 - for design options, 301–304, 302–303
 - for keynotes, 139, 571, 579–580, 579
 - moving, 80–82, 80–82
- ownership, 701–706, 702–706
- pinning, 91–92
- rotating and mirroring, 83–85, 84–85
- scaling, 87, 87
- tagging, 532
- Elevation Base setting, 134
- elevations, 453, 453
 - default settings, 174, 174
 - images in, 457–458, 458
 - Linework tool, 454–455, 454
 - Project Browser views, 68–71, 70
 - tags for, 130–134, 131–133
 - transparent materials, 456–457, 457
 - true-color, 455–456, 455–456
- Empty glazing setting, 410
- enabling
 - design rules, 341–344, 341–344
 - shadows, 442, 442
- End setting for baluster patterns, 429, 430
- End angle resolve setting, 204, 207
- End with a Riser setting, 159
- energy analysis, 522–525, 523–526
- Entire Walls option, 173
- entourage, 475–476, 476
- Exclude feature, 596, 596
- expanded panels, 41, 41
- exploding imported CAD files, 732
- Export to DWF dialog box, 684
- exporting, 478–479, 479
 - to Design Review, 684–686, 684–686
 - details, 667–668, 668
 - to gbXML, 523–525, 524
 - sun studies, 517, 517
 - sun views, 515
- Exposure Control dialog box, 472, 472

exposure settings, **472**, **472**
 expressive drawings, shadows
 for, **439–440**, **440**, **444–445**,
 444–445
 Extend Below Base setting, **158**
 extending
 lines and walls, **90**, **90**
 walls, **366–367**, **366–367**
 extending pergola, gable roofs
 with, **399**, **399**
 exterior skins, **305**, **305**
 external text files, **572**
 extruded roof dormers, hipped
 roofs with, **407**, **407**
 Extrusion end setting, **203**, **203**
 Extrusion start setting, **203**, **203**
 extrusions
 parametric, **244–247**,
 244–247
 roofs by, **193–197**, **193–197**,
 383–384, **383–384**
 working with, **202–205**,
 203–205

F

face-based families, **328**, **329**
 faces with extrusions, **205**
 families and Family Editor, **9**,
 10, **15–16**, **16**, **26**
 3D. *See* custom 3D content
 vs. blocks, **21**
 callout tags, **127–129**,
 127–129
 ceilings, **156**, **156**
 component, **27–28**, **28**, **30**, **31**
 custom title blocks,
 141–145, **141–145**
 details, **659–663**, **659–663**
 door tags, **564**
 doors and windows,
 161–162
 elevation tags, **134**
 floors and roofs, **155–156**, **155**
 in-place, **31–32**, **32**
 keynotes, **576–580**, **576–579**
 loadable, **200**, **200**
 managing, **120**

mass placement, **242–243**
 organizing, **29–30**, **29–30**
 parametric extrusions,
 244–245, **245**
 parametric material,
 247–249, **249**
 for primary forms, **202**, **202**
 profiles, **361–362**
 Project Browser views,
 54, **54**
 section view tags, **122–125**,
 123–125
 stairs, **157–161**, **157–161**
 system, **26–27**, **26–27**
 templates, **320–321**,
 320–321
 type creation in, **162–163**
 types. *See* types and type
 catalogs
 visibility settings, **325**, **325**,
 663–665, **664–665**
 wall wrapping, **361**, **361**
 walls. *See* walls
 worksets, **692**
 Family Category and
 Parameters dialog box,
 333–334, **334**
 family creator role, **743**
 Family Element Visibility
 Settings dialog box, **325**, **325**
 Family Types dialog box,
 333, **333**
 arrays, **344**, **344**, **346**
 dimensions, **342**, **343**
 parametric extrusions,
 245, **245**
 RPC, **330**, **330**
 visibility, **349**
 FAR (Floor Area Ratio), **271**
 feasibility, program, **231–233**,
 231–233, **271–272**, **272**
 feet units, **170**
 fences. *See* railings
 Fields tab, **495–496**, **495**, **502**, **547**
 File Locations tab, **29**, **29**, **98**, **99**
 File Save Options dialog box,
 698, **698**

filenaming conventions,
 keynotes, **572**
 files
 corruption, **739–740**, **740**
 linking, **605–606**, **605**
 workflow, **698–699**, **698–699**
 Fill Available Space modes, **623**
 Fill Patterns dialog box, **108**,
 108, **111**
 fills and fill patterns
 color, **446–448**, **447–448**
 custom title blocks, **142**
 for details, **645–646**,
 645–646
 elevation tags, **132**
 graphics, **451–452**, **452**
 materials, **108–113**,
 108–110, **112–113**
 Filter dialog box, **76**, **77**
 Filter tool, **491**, **491**
 filtering
 area boundaries, **491**, **491**
 keynotes, **575**, **575**
 schedules, **495–496**, **498**, **506**
 selections, **38**, **38**, **76**, **77**
 Fine level of detail, **153**
 Finish Mass button, **239**
 Finish option for wall layers, **151**
 First end blend setting, **215**
 Fixed Distance modes, **623**
 Fixed Number modes, **623**
 Flat railing option, **433**
 flat roofs, **393**, **393**
 flip controls, **83**, **83–84**
 Flipped Dimension Line
 Extension option, **115**
 Floor Area Ratio (FAR), **271**
 floor plans, **55–56**, **55**
 Cut planes, **57–60**, **59–60**
 primary range, **59–60**,
 59–60
 View Depth, **60–62**, **60–61**
 View Range, **56–58**
 floors
 bidirectional relationships,
 22–23
 ceiling connections and
 details, **645–646**, **645–646**

Mass Floors tool, **275–278**, 276–278
 Model by Face tool, **282–283**, 282–283
 in modeling principles, 199–200
 sketch-based design, **181–183**, 181–183
 types, **155–156**, 155
 focal length in perspective views, 461–462, 463
 Font setting, 159
 fonts for elevation tags, 132
 footprint roofs, **378–382**, 378–383
 force units, 165
 form making and rationalization, **243**, 243
 importing models, **262**, 262
 lofts, **252–256**, 252–256
 parametric extrusions, **244–247**, 244–247
 parametric material, **247–249**, 248–249
 revolves, **249–252**, 250–252
 surfaces, **259–261**, 259–261
 sweeps, **256–259**, 256–259
 Format dialog box, 381, 381
 formats
 CAD, **614–615**, 614, 617–618
 exporting to, **478–479**, 479
 roofs, 381, 381
 formatting schedules, 496, 497, 503, 504
 formulas
 arrays, **343–344**, 343–344
 dimensions, **342**, 342–343
 Foundation model, **481–482**
 area plan calculations, **483–484**, 483–485
 areas and tags, **491–492**, 491–492
 change tracking, **681**, 681
 rentable area plans, **487–490**, 487–490
 schedules. *See* schedules
 worksets, **694–695**, 695

four-sided gable roofs, 406, 406
 freestanding elements
 railings, 423, 423
 rotating, **84**
 Full Navigation Wheel, 46, 46
 Full Ribbon display, 39, 39
 Function column for wall layers, **150–151**
 Furniture category, 62
 Furniture System category, 62

G

gable roofs, 398, 398
 with asymmetric slopes, 394, 394
 Dutch gable with glazed roofs, 402, 402
 Dutch gables, 403, 403
 with extending pergola, 399, 399
 four-sided, 406, 406
 hip and gable, 400, 400
 gambrel roofs, 401, 401
 gbXML, **523–525**, 524
 Generic Model face based.rft template, 328
 Generic Models category, 17
 Generic Tag.rft template, 138
 glazed panels, 370
 glazing, **528–529**, 528
 global settings, **168**, 169
 area and volume computation, **168–169**, 169
 defaults, **172–176**, 173–176
 keynotes, **170**, 171
 materials, **171–172**, 171
 units, **169–170**, 170
 Go to View dialog box, 190, 190, 632, 633
 granting permissions, **704–706**, 705–706
 graphic appearance
 consistency settings
 dimension styles, **113–117**, 114–115
 Fill Patterns, **108–113**, 108–110, 112–113

Line Patterns, **103–104**, 104–105
 Line Styles, **102–103**, 102–103
 Materials Editor, 106–107, 106
 Object Styles, **100–102**, 101
 text, **117–119**, 118
 markups, 686, 686, 688
 schedules, **503–506**, 504–505
 Graphic Display Options dialog box
 elevations, 456, 456
 silhouetted edge displays, 464, 464
 sun and shadows, 442–443, 442
 sun studies, 512–513, 513, 515–516
 true-color shading, 456
 graphic overrides, **166–168**, 167–168, **452–453**, 452
 graphical selection, **537–538**, 537
 graphics cards, 733, 734
 Graphics tab, **106–107**
 Green Building Studio service, **525**, 525–526
 Green Building xml, **523–525**, 524
 grids, 185–186, 185
 curtain walls, 369–370, 369–370, 372, 372
 tags, **135**
 work planes, 190, 191
 Grids worksets, 691
 grips
 markup, 686, 687
 mass manipulation, 239, 239
 gross area
 calculations, 483
 floors, 279, 279
 plans, **485–487**, 485–487
 gross building schedules, 493
 Group Edit mode, 588–589, 588–589

Group Edit toolbar, 589
 Group Properties dialog
 box, 589
 groups, 584
 adding rooms to, 589–590, 590–591
 arrays, 85–87, 86
 best practices for, 601
 creating and managing, 585
 detail, 600–601, 600–601, 619
 detail elements for, 592, 593
 editing, 599–600, 600
 lights, 469–470, 470
 vs. links, 607–609, 608
 moving elements in, 599, 599
 nesting, 591–593, 591–593, 598
 parameters, 559–560, 559–560
 as parts of projects, 598
 Project Browser views, 55
 repeating, 584–589, 584–589, 597–598, 597–598
 variations, 594–597, 594–597

H

hatch patterns, 108–113, 108–110, 112–113
 head graphics in section tags, 125–126, 125–126
 heads, callout, 127–130, 127–130
 height
 railings, 433, 433
 text, 118
 Height Offset At Head
 setting, 391
 Help menu, 743
 Hide option, 506
 hiding
 markups, 688
 schedule elements, 506
 sections, 68–69, 69

high-contrast black and white
 effects, 444, 444
 hip and gable hybrid roofs, 400, 400
 hipped roofs, 397–398, 397–398
 with extruded roof
 dormers, 407, 407
 with sloped arrow
 dormers, 404–405, 404–405
 historical data, 525
 History dialog box, 700
 history of design and
 documentation, 1–2
 Home tab
 design bar, 315
 Ribbon, 39–40, 39–40
 Horizontal tag orientation, 553
 host-based elements, 303
 host-based families, 322–323, 323
 Host Layer Line Styles dialog
 box, 167–168, 168
 host objects in graphic
 overrides, 166–168, 167–168

I

identical buildings on shared
 sites, 604
 Identity Data property, 540
 Identity tab, 107, 556, 557
 IES <Virtual Environment>
 application, 522–523, 523
 images
 in elevation views, 457–458, 458
 for materials, 474–475, 474–475
 Imperial library, 576
 imperial units, 170
 Import CAD Formats dialog
 box, 291, 291
 Import/Link dialog box, 616, 661, 661
 Import/Link RVT dialog box, 605–606, 605
 Import Unit section, 616

imported files and geometry
 AutoDesk Maya for, 293–294, 294
 categories and
 subcategories, 20, 21
 exploding, 732
 Inventor for, 294–295, 295–296
 limitations, 20
 in performance, 733–734
 positioning, 268–269
 Rhino for, 292–293, 292–293
 SketchUp for, 290–292, 291–292
 importing
 3D conceptual models, 262, 262
 Design Review markups, 687–688, 687
 details, 612–618, 613–614, 617–618, 661, 661
 DWG/DGN site
 information, 266
 patterns, 111–113, 112–113
 with SketchUp, 291–292, 291
 views, 669–670, 669–670
 in-place families, 31–32, 32, 200, 201, 368
 In-Place Mass tool, 236–237, 237, 291
 in-place roofs, 385, 385
 in-place walls, 368, 368
 inches units, 170
 Increase/Decrease Focal
 Length option, 461–462, 463
 infill wall types, 370
 InfoCenter, 37–38, 37
 information for details, 630–631, 630–631
 Insert 2D Elements dialog box, 669–670, 670
 Insert tab, 40, 40
 Inside detail option, 623
 instance parameters, 21–22, 555–556

Instance Properties dialog box, 52, 53
 callout tags, 130
 cost schedules, 313, 313
 door tags, 137
 elevation tags, 133
 parametric extrusions, 246, 246
 parametric material, 247–249, 249
 revision clouds, 678, 678
 revolves, 251, 251
 scope boxes, 188, 188
 section tags, 126
 templates, 175, 175
 UV surface divisions, 260
 wall extensions, 367, 367
 walls, 148
 worksets, 695, 696
 instances, selecting, 76–77, 77
 Insulation Bulge to Width Ratio setting, 624
 Insulation tool, 624, 624
 intensities, sun, 443, 443
 interaction, 7
 interface. *See* user interface
 Interior Tick Mark option, 116
 Interiors workset, 694
 Inventor software, 294–295, 295–296
 invisible lines, 138
 Isolate option, schedules, 506
 Italic setting, 118

J

jogged sections, 67, 67
 Join Geometry tool, 93–94, 93, 241, 285
 joins, 93–94, 93
 masses, 284–286, 284–286
 solids, 241–242, 241–242
 walls, 354, 354

K

Keep Readable option, 109, 110, 118
 keyboard shortcuts, 48, 48, 95–96, 95
 Keyboard.txt file, 96
 KeyboardShortcuts.txt file, 48
 Keynote command, 571
 keynote legend schedules, 494
 keynotes, 138–140, 139–140, 570–571, 570–571
 behavior and editing, 571–572
 elements for, 579–580, 579
 family, 576–580, 576–579
 filenaming conventions, 572
 legends, 494, 574–576, 575
 predefining, 580–581, 580–581
 schedules, 576
 settings, 170, 171, 573
 in views, 531, 573–574, 574
 wall sections, 576–580, 577–579
 keys, schedule, 546–549, 547–549
 keytips, 48, 48
 Koolhaas, Rem, 603–604, 604

L

labels
 custom title blocks, 142, 143
 keynotes, 139
 section view tags, 122
 shared parameters, 566–567
 lamp, 219–221, 219–220
 lampshade, 221, 221
 Landing Carriage Height setting, 161
 Landing Overlap setting, 158
 landings, 431, 431
 layer joins cleanup, 353–354, 353
 layers, 10
 custom walls, 150–154, 151–152

extending, 366–367, 366–367
 importing and linking, 616
 merging, 360, 361
 overrides, 166–168, 168
 position, 154, 154
 splitting, 358–359, 359–360
 Layout modes, 623
 LCR (Lot Coverage Ratio), 271
 Le Corbusier, 2
 Leader Arrowhead setting, 118
 leader lines, 680, 680
 Leader option, 538
 Leadership in Environmental and Energy Design (LEED) system, 508–509, 521
 Legend tool, 446
 legends, keynotes, 494, 574–576, 575
 length
 keynotes, 139
 lines, 116
 nosing, 159
 units, 165, 169
 Length/Format dialog box, 478, 478, 517, 517
 Level tool, 275–277
 levels, 185–186
 bidirectional relationships, 22–23
 default settings, 173
 floor plans, 55–56, 55
 roof slopes, 23–24, 24
 rooms, 539
 selection by, 79
 tags, 134, 134
 levels of detail
 families, 658–659
 in performance, 735
 walls, 153, 154
 Libeskind, Daniel, 4, 4
 libraries
 keynotes, 576
 materials, 473, 473, 476
 organizing, 29–30, 29–30
 lifecycle costs, 229
 Light Fixtures option, 469

- lighting
 - daylighting, **527–529**, 528–529
 - settings, **468–470**, 468–470
- lighting fixtures, 322, 323
- Limit Offset property, 450, 450, 539–540
- line-based families, **326–328**, 327–328
- Line Pattern Properties dialog box, 103–104, 104
- line patterns
 - creating, **103–104**, 104–105
 - elevation tags, 132
 - level tags, 134
- Line Patterns dialog box, 103–104, 104
- Line Styles dialog box, 102–103, 102
- line tools
 - custom title blocks, 141
 - Insulation, **624**, 624
 - Linework, **454–455**, 454, **628**, 628
 - regions, **625–626**, 625–626
 - Show Hidden Lines, **626–627**, 627–628
- Line Weights dialog box, 102–103, 103
- linear arrays, 86
- linear force units, 165
- lines
 - boundary, 485–486, 486
 - extending, **90**
 - invisible, 138
 - offsetting, **91**, 91
 - repeating details for, **623–624**, 624
 - separation, **535–536**, 536
 - silhouetted edge displays, 464, 465
 - splitting, **90**, 90
 - styles, **102–103**, 102–103, 166–168, 167–168
 - symbolic, **665–667**, 665–667
 - trimming, **89**
- lineweights, 102–103, 102
 - dimensions, 115
 - elevation tags, 132
 - level tags, 134
 - text, 118
- links and linking, **602–603**, 602–603
 - common uses, **603–604**, 604
 - details, **612–613**, 614
 - CAD details, **617–618**, 617–618
 - CAD formats, **614–615**, 614
 - files, **605–606**, 605
 - vs. groups, **607–609**, 608
 - markups, 687
 - parameters, **337–339**, 338–339
 - Project Browser views, **54**, 54
 - special features, **606–607**
 - unloading and reloading, 607
 - visibility, **606–607**, 607
- live connections, links for, 613
- Load Family dialog box, 28–30, 28–30
- loadable family types, 200, 200
- loaded profiles for sweeps, 211
- loading
 - group files, 593, 593
 - shared work, **701**
 - tags, **550**
 - from type catalogs, **166**, 166
- local files
 - in performance, 733
 - in workflows, **698–699**, 699
- Lockable Door parameter, 566
- lofts, **252–256**, 252–256
- loops
 - blends, 221, 221
 - lofts, 252
 - profiles, 324, 324
 - revolves, 207–208, 207–208
 - sketches, 182, 182
 - sweeps, 210
- Lot Coverage Ratio (LCR), 271

M

- M_Generic Tag.rtf template, 138
- main model, 299–303, 306
- Make Elements Editable
 - option, 702, 702
- Make Workset Editable
 - option, 692
- Manage Links dialog box, 614, 615
- Manage Place and Locations dialog box, 441, 441, 514
- Manage tab, 41, 41
- Manual - Base Point option, 269, 606
- Manual - Center option, 269, 606
- Manual - Origin option, 269, 606
- manual dimensioning, 173
- markups
 - Design Review for, **686**, 686–687
 - importing, **687–688**, 687
- masking regions, **620**, 620, **641–643**, 641–643
- Mass Floors tool, **275–278**, 276–278, 282
- Mass.rft file, 242, 244
- Massing & Site tab, 41, 41, 237
- massing and massing studies, **227–229**, 227–229
 - 3D components on divided surfaces, **286–290**, 287–290
 - 3D contexts. *See* 3D models
 - best practices, **273**, 273–274
 - boolean operations, **240–242**, 240–242
 - direct manipulation, **239–240**, 239
 - Floor Area tool, **275–278**, 276–278
 - form making. *See* form making and rationalization

- imported files and geometry, **290–296**, 291–296
- importing 3D conceptual models, **262**, 262
- join geometry, **241–242**, 241–242
- mass creation, **237–239**, 237–238
- mass element creation, **236**
- mass element visibility, **236–237**, 236–237
- mass family creation, **242–243**, 243
- mass joining, **284–286**, 284–286
- massing forms, **238–239**, 238
- Model by Face tool, **281–284**, 282–283
- scheduling, **284–286**, 284–286
- tools, **234**, 234–235
- uses, **230–233**, 230–233
- workflows, 201, 201, **229–230**
- master builders, 2
- Match option for groups, 594
- Match Type option, 77–78
- Material column for wall layers, **151–152**, 152
- materials, **472**
 - custom images, **474–475**, 474–475
 - editing, **105–108**, 105–107, **472**, 472
 - entourage, **475–476**, 476
 - fills, **108–113**, 108–110, 112–113
 - keynotes, 139, 571, **576–580**, 577–579
 - parameters, 556, 557
 - parametric, **247–249**, 248–249
 - replacing, **473–474**, 473
 - settings, **171–172**, 171
 - stairs, 159
 - tags, 551
 - takeoff schedules, 494
 - tracking, **519–520**, 520–521
 - true-elevation color, 455, 455
 - for types, 162
 - wall finish, **358–360**, 358–360
- Maximum Riser Height setting, 159
- Maximum Segment Angle setting, 214, 214
- Maximum Spacing modes, 623
- Maya, **293–294**, 294
- Medium level of detail, 153
- Membrane Layer option, 151
- MEP models, 507
- merging layers, 360, 361
- Mesh Modeler, 296, 296
- metal decks, 647–648, 647–648
- Metric library, 576
- Metric Mass.rft file, 244
- metric units, 170
- Middle Stringers setting, 161
- Minimum Tread Depth setting, 159
- Mirror tool, **85**, 85
- mirroring elements, **83–85**, 84–85
- mistakes in worksharing, **702**
- miter joins, 354, 354
- MMiscellaneous Wide Flange-Column.rfa family, 164
- Model by Face tool, **281–284**, 282–283
- model groups, 584
- Model Object categories, **17–18**, 18–19
- model patterns, 108–109
- Modeling In-Place tool, 200, 200
- modeling principles, **179**, 180–181
 - blends, **215–223**, 215–222
 - extrusions, **202–205**, 203–205
 - overview, **199–201**, 200–201
 - revolves, **206–209**, 206–209
- sketch-based design, **179–180**
 - floors and roofs, **181–183**, 181–183
 - work planes. *See* work planes
- solids and voids, **222–224**, 223–224
- sweeps, **209–214**, 209–214
- Modeling tab, 20
- models
 - 3D physical, **228–229**, 228
 - details, **639–650**, 639–650
 - importing, **262**, 262
 - objects, **100–102**, 101
- Modify Roof panel, 384
- Modify Schedule/Quantities tab, 505, 505
- Modify Sub Elements tool, 416
- Modify tab, 40, 40
- Modify Vertical Structure options, 362
- Modify Walls tab, 42, 42
- Monolithic Stair setting, 158
- Move To 2nd option, 85, 86
- Move tool, **81–82**, 81
- moving elements, **79–80**
 - in groups, **599**, 599
 - with nearby elements, **82**, 82
 - nudging, **82**
 - with temporary dimensions, **80–81**, 80–81
 - between worksets, **696–698**, 697
- mullions, 369, 369, 372, 372–373
- Multi-Category tags, 551
- Multi-Day sun settings, 513, 515–516, 516, 518, 518
- multicategory schedules, 493
- multipitch roofs, 411, 411
- Multiple Alignment option, 88
- multiple buildings on shared site plans, **603–604**, 604
- Multiple Copy or Array command, 275
- multiple massing design options, **273**, 273–274
- muntins, 341, 341

N

Name dialog box
 callout tags, 129, 129
 elevation tags, 133, 133
 section tags, 125–126,
 125–126

names
 callout tags, 129, 129
 dimension types, 117
 door tags, 565, 565
 elevation tags, 132–133, 133
 line patterns, 104
 materials, 106
 section tags, 125–126,
 125–126
 text type, 119
 work planes, 189

natural lighting, 509, 527–530,
 528–529

Navigation bar, 45–46, 46

navigator pane, 686

Nearby Elements feature, 82, 82

nesting
 chairs, 346, 346
 detail components,
 648–650, 649–650
 families, 335–339, 336–340
 groups, 591–593,
 591–593, 598
 links, 606

New Area Plan dialog box,
 485, 485

New dialog box for door
 tags, 564

New Drafting View dialog box,
 612, 612, 617, 617

New Pattern dialog box, 109,
 112–113, 112–113

New Schedule dialog box,
 277, 277, 493, 496, 547–548,
 547–548

No Edge option, 168

Noguchi, Isamu, 221

nonlinear sections, 121

Nosing Length setting, 159

Nosing Profile setting, 159

note block schedules, 494

notes

 keynotes. *See* keynotes
 text, 138–140, 139–140

nudging elements, 82

numbering
 keynotes, 573
 revisions, 674

NURBS shape, 262, 262

NURBS surfaces, 292–293,
 292–293

O

Object Styles dialog box, 16, 16,
 636, 636
 Annotation Objects tab, 19,
 119, 119
 component families, 27
 cutting, 58
 floor plans, 56
 for graphic consistency,
 100–102, 101
 Imported Objects tab, 20, 21
 Model Object tab, 17–18
 Modeling tab, 20
 revision clouds, 677, 677

offsets
 Floor by Face tool, 283, 283
 lines and walls, 91, 91

opaque filled regions, 625, 625

Open dialog box
 auditing files, 739
 libraries, 30

Open Stringer Offset
 setting, 161

optimizing. *See*
 troubleshooting and
 optimizing tips

Options bar, 44, 44, 432

Options dialog box
 application frame, 37, 37
 File Locations tab, 98, 99
 folders, 29

order of panels, 47, 47

Ordinate dimension style, 114

Orient to Other View dialog
 box, 656, 656

orientation

 3D views, 71–72, 71,
 655–656, 656–657
 fill patterns, 109, 109
 imported site data,
 266–268, 267–268
 tags, 553

origins
 groups, 586, 587
 linked files, 268, 605–606
 orienting, 109
 rotation, 83–85, 84

output settings, 467–468, 468

overconstrained objects, 739

Overhang parameter, 380, 380

overlapping items
 rooms, 534, 535
 walls, 586

overrides. *See* Visibility/
 Graphic Overrides dialog box

ownership of elements,
 701–706, 702–706

P

Paint tool, 94–95, 95

Palladio, Andrea, 1–2

Panel Tiles display, 39, 39

panels
 curtain, 332, 332–333,
 369–370, 370, 373–375,
 374–375
 SIPs, 640–641

Parameter Properties dialog box
 arrays, 346–347, 347
 base modeling, 644, 644
 custom parameters,
 555–556, 555–556, 560, 560
 extrusions, 245, 245
 visibility, 348, 349

parameters and parametric
 elements, 15–16, 16–17
 3D models and families, 3
 building, 345–349,
 345–349
 modeling, 319, 320

Annotation object
 categories, 19

- arrays, **340–341**, 340–341, **346–348**, 347–348
- base molding, 644, 644
- bidirectional relationships, **22–23**, 22–23
- constraints, **25**, 25
- design options with, **313–316**, 314–316
- dimensions, 342, 342–343
- door tags, 566
- extrusions, **244–247**, 244–247
- families, **26–31**, 26–32
- forms, 242
- imported categories/ subcategories, **20**, 21
- linking, **337–339**, 338–339
- material, **247–249**, 248–249
- Model Object categories, **17–18**, 18–19
- overriding, **32–34**, 33
- shared. *See* shared parameters
- subcategories, **20**, 20
- sun shades, **345**, 345
- type and instance parameters, **21–22**
- views, **20**
- visibility, 348, 349
- pasting, **78–79**, 78
- .pat files, **110–111**, 113
- paths
 - keynotes, 573
 - sweeps, **209–210**, 209–210
- patterns
 - balusters, **428–429**, 428–429
 - custom, **108–112**, 108–110
 - fill, **108–113**, 108–110, 112–113
 - importing, **111–113**, 112–113
 - line, **103–104**, 104–105
 - surfaces, **261**, 261
- PDFs in performance, 738
- people, 475–476
- performance
 - best practices, **733–739**, 734–738
 - recommendations, **731–733**, 732–733
 - shadows, **445**
- Perimeter property, 540
- perimeters in volume calculations, 543–544, 543–544
- periods (.) in type-catalog syntax, 164
- permissions
 - granting, **704–706**, 705–706
 - requesting, **703–704**, 703–704
 - taking, **706–707**
- perspective views, **461**
 - 3D, 71–72, **72–73**
 - animated walkthroughs, **477–478**, 478
 - cameras, **463**, 463
 - creating, **461–462**, 462–463
 - exporting, **478–479**, 479
 - photorealistic renderings. *See* photorealistic renderings
 - silhouetted edge displays, **464**, 464–465
- Phase property, 540
- photorealistic renderings, **465**, 466
 - background settings, **470–471**, 471
 - exposure settings, **472**, 472
 - families, **329–330**, 330–331
 - guidelines, **476–477**
 - lighting settings, **468–470**, 468–470
 - materials, **472–476**, 473–476
 - output settings, **467–468**, 468
 - quality settings, **466–467**, 467
 - rendering process, **471**, 471
 - saving as images, **472**
- Physical tab, 107
- Pick 3D Edges option, 210
- Pick a Line and Use the Work Plane It Was Sketched In option, 190, 190
- Pick a Plane option, 189, 190
- Pick Level Graphics option, 79
- Pick New Host tool, 192
- Pick Path option, 210
- Pick Plane option, 190
- Pick Supports tool, 416
- Pick Walls method, 378, 379
- pinning elements, **91–92**
- Place Mass tool, 236
- Place Request option, 703
- Place tab, 441, 441
- Place Wall tab, 42, 42
- placing
 - balusters, 426, 427
 - repetitive units, **585–589**, 586–589
 - revision clouds, **676–678**, 677–678
 - tags, **550–551**, 550–551
- Plan/RCP option, 665
- plan regions, 66
- plan views
 - default settings, 173
 - Project Browser views, **62–66**, 63–66
 - visibility in, 665
- planes. *See* work planes
- planning projects, 742
- plans, presentation-quality, **451–453**, 451–453
- plywood, **327**, 327
- positioning imported files, **268–269**
- posts, railings, 424, 424, **426–428**, 427
- predefined color schemes, 448
- predefined profiles, 210
- predefining keynotes, 580–581, 580–581
- preliminary cost estimate schedules, **502–506**, 502–505

preliminary designs, **481**
 Foundation model. *See* Foundation model
 sustainability. *See* sustainability
 presentation techniques, **439**
 color-coded plans and sections, **445–450**, 446–450
 elevations, **453–455**, 453–456
 plans and sections, **451–453**, 451–453
 shadows, **439–445**, 440–445
 previewing
 custom walls, **150**
 material images, 475, 475
 sun studies, **517**
 primary design set options, **300**
 primary range for floor plans, **59–60**, 59–60
 principles of modeling. *See* modeling principles
 Print Setup dialog box, 684, 684
 printing
 Design Review, 684, 684
 in performance, 738
 problem-solving, **8**, 8
 process change, **4–5**, 5, **10–11**
 Profile Family template, 361
 profiles
 3D content, **323–326**, 324–326
 reveals, 361–362, 362–363
 revolves, 206, 208, 208
 subtractive, 364
 sweeps, **210–212**, 210–211, 361–362
 programs
 feasibility, **271–272**, 272
 verification, **231–233**, 231–233
 Project Browser, **46**, 46
 for callouts, 629, 629
 details, 667–669, 668–669
 family details, 659
 groups, 586–587, 587

nesting links in, 606
 undocking, 48, 48
 views, **49–51**, 49–51
 3D, **71–73**, 71–73
 activating, **53**, 53
 custom organization, **51–52**, 51–52
 elevations, **68–71**, 70
 families, **54**, 54
 floor plans, **55–62**, 55–62
 groups, **55**
 links, **54**, 54
 plan views, **62–66**, 63–66
 section views, **66–68**, 67–68
 sheets, **52–53**, 53
 project environment types, **162–163**
 project parameters, **555–556**, 555–557, **561–562**, 561–562
 Project Settings menu, 168, 169
 project standards worksets, **692**
 Project Units dialog box, 169–170, 170
 projection graphics, 18, 19
 projects on Start screen, 34, 34
 Promotional Glazing material, 528
 properties
 elements, **6**, 7
 rooms, **539–540**
 prototyping, 232
 Publish Coordinates option, 269, 605
 Purge Unused dialog box, **734**, 735, 740
 Purge Unused Elements dialog box, 119

Q

quality
 daylighting, **527–530**, 528–529
 rendering settings, **466–467**, 467

quantities for design options, **313–314**, 313
 Quick Access toolbar, 37, 37

R

radial arrays, 86, 86
 radial dimensions, 113
 Radius setting for arrays, 346, 347
 Rafter property, 382
 Rafter Cut property, 382
 railings, **421–423**, 421–423
 in auditoriums, 436
 balusters per tread on stairs, **429–431**, 430
 construction, 425, 425
 main pattern, **428–429**, 428–429
 miscellaneous controls, **431–433**, 431–434
 post settings, **426–428**, 427
 rails, 424–425, 425
 subelements and principles, **423–425**, 423–425
 on walls, **434–436**, 434–436
 rapid prototyping, 232
 RCP (Reflected Ceiling Plan) view, 633
 recessed walls, hip roofs following, 397, 397
 Rectangle tool, 244
 Rectangular Handrail profile, 426
 recyclable parameters, 555–556
 recycled materials, **519–520**, 520–521
 Reference Label settings, 132
 reference lines, **187**, 187
 reference planes, **186**, 186, **205**, 205
 Reflected Ceiling Plan (RCP) view, 633
 Region Properties dialog box, 645
 Region tool, **625–626**, 625–626

- regions
 - filled, 645–646
 - masking, **620**, 620, **641–643**, 641–643
- rehost elements, 192
- Related to Mass property, 381
- relationships
 - bidirectional, **22–23**, 22–23
 - building mass and underlying mass, **297**, 297
- Relative keynote path
 - method, 573
- relinquishing permissions, 703
- reloading
 - groups, 595
 - links, 607
- Remove tool for groups, 589
- renaming
 - dimension types, 117
 - door tags, 565, 565
 - line patterns, 104
 - materials, 106
 - text type, 119
- Render Appearance Library, 171, 171, 473, 473, 476
- Render Appearance tab, **108**, 472, 473, 528, 528
- Render Quality Settings dialog box, 467, 467
- rendering. *See* photorealistic renderings
- Rendering Appearance Source parameter, 334
- Rendering dialog box, 466, 466
 - background settings, **470–471**, 471
 - exposure settings, **472**, 472
 - lighting settings, **468–470**, 468–470
 - output settings, **467–468**, 468
 - quality settings, **466–467**, 467
 - rendering process, **471**, 471
- Rendering Progress dialog box, 471, 471
- rentable area
 - calculations, 483
 - plans, **487–490**, 487–490
 - schedules
 - making, **495–499**, 495, 497–499
 - on sheets, **499–500**, 499–500
- repetitive details and elements, **583**
 - creating and placing, **585–589**, 586–589, **621–622**, 621–622
 - floors, **646–647**, 647
 - groups, **584**, 584, **597–598**, 597–598
 - for line types, **623–624**, 624
- replacing materials, **473–474**, 473
- Report Shared Coordinates
 - option, 269, 606
- requesting permissions, **703–704**, 703–704
- resizing elements, 87, 87
- Restore All Excluded option, 597
- Return Panels to Ribbon
 - command, 47, 47
- reusing details, **667–670**, 668–670
- Reveal Hidden Elements
 - mode, 68
- reveals, **361–365**, 361–365
- Review Warnings option, **740**, 740
- revision clouds
 - placement, **676–678**, 677–678
 - tagging, **679–680**, 679–680
 - visibility, **675–676**, 676
- Revision Properties dialog box, 143, 144
- revision schedules, **143–145**, 144–145
- Revit City service, 743
- Revit OpEd blog, 744
- revolve forms, **249–252**, 250–252
- revolves, **206–209**, 206–209
- .rfa files, 28
- Rhino software, **292–293**, 292–293
- ribbons, **35**, 35, **39**, 39
- Rich Photorealistic Content (RPC) families, **329–330**, 330–331, 334, 475, 476
- ridge skylight roofs, **388–391**, 388–391
- Riser Thickness setting, 160
- Riser to Tread Connection
 - setting, 160
- Riser Type setting, 160, 160
- Roof by Extrusion tool, 384, 384
- roofs, **377**
 - barrel, 383, 383, 385, 410, 410
 - bidirectional relationships, 22, 22
 - complex, 224, 224
 - cone, 408, 408
 - creation methods, **377–378**
 - dome, 208, 208, 385, 385, 409, 409
 - dormers, **412–415**, 412–415
 - by extrusion, **193–197**, 193–197, **383–384**, 383–384
 - flat, 393, 393
 - footprint, **378–382**, 378–383
 - gable, 398, 398
 - with asymmetric slopes, 394, 394
 - Dutch gable with glazed roofs, 402, 402
 - Dutch gables, 403, 403
 - with extending pergola, 399, 399
 - four-sided, 406, 406
 - hip and gable, 400, 400
- gambrel, 401, 401
- hipped, 397–398, 397–398
 - with extruded roof dormers, 407, 407
 - with sloped arrow dormers, 404–405, 404–405
- in-place, **385**, 385

- Model by Face tool, **283**
- in modeling principles, 199–200
- multipitch, **411, 411**
- ridge skylight, **388–391, 388–391**
- shapes, **416–417, 416–417**
- shed, **392, 392, 395–396, 395**
- sketch-based design, **181–183, 181–183**
- sloped, **23–24, 24, 416–419, 416–419**
- sloped arrows, **391–392, 391–392**
- sloped glazing, **386, 387**
- types, **155–156, 155**
- with warped surfaces, **419, 419**
- Room/Area Reports, **521, 522**
- Room Bounding property, **381, 532, 532**
- rooms
 - annotating, **532–534, 532–535**
 - area calculations, **540–542, 540–543**
 - area plans, **483–484, 483–485**
 - creating and placing, **585–589, 586–589**
 - design options for, **314–316, 314–316**
 - groups for, **584, 584, 589–590, 590–591**
 - overlapping, **534, 535**
 - properties, **539–540**
 - in section views, **538**
 - selecting, **537–538, 537**
 - separation lines, **535–536, 536**
 - styles, **549, 549**
 - tags, **483, 483, 538, 538–539**
 - volume calculations, **541–546, 541–546, 732–733, 733**
 - window surface
 - percentage, **521, 522**
- Rotate True North option, **268**

- rotating
 - detail components, **623**
 - elements, **83–85, 84–85**
 - orientation, **268**
 - sweeps, **211, 211**
- RPC (Rich Photorealistic Content) families, **329–330, 330–331, 334, 475, 476**
- RPC Family.rft template, **330**

S

- Same Place option, **79**
- SAT files
 - importing and linking, **616**
 - with Inventor, **295**
 - with Rhino, **292**
- Save Group option, **595**
- Save to Central dialog box, **700, 700**
- saving
 - photorealistic renderings
 - as images, **472**
 - shared work, **700–701, 700–701**
 - sun studies, **517**
- scale
 - coarse scale fill patterns, **451–452**
 - elements, **87, 87**
 - imported site data, **266**
 - material images, **475**
- Schedule Properties dialog
 - box, **495–496, 495, 497–498, 502–504, 504**
- schedules
 - capabilities, **501–502, 501–502**
 - cost, **313–314, 313**
 - creating, **492–494**
 - custom parameters, **557, 557**
 - floors, **277–278, 277**
 - graphic appearance of, **503–506, 504–505**
 - keynotes, **576**
 - keys, **546–549, 547–549**
 - link elements, **606**

- mass elements, **284–286, 284–286**
- nested families, **337**
- preliminary cost estimates, **502–506, 502–505**
- rentable area, **495–499, 495, 497–499**
- revision, **143–145, 144–145**
- on sheets, **499–500, 499–500, 505**
- schemes
 - color fill, **446–448, 447–448**
 - settings, **176**
- scope boxes, **188–189, 188**
- search function in InfoCenter, **38**
- Second end blend setting, **215**
- section boxes, **655, 655**
- Section Head setting, **121**
- Section Tail setting, **121**
- sections and section views
 - colored, **449–450, 450**
 - presentation-quality, **451–453, 451–453**
 - Project Browser views, **66–68, 67–68**
 - rooms in, **538**
 - split, **358–359, 359–360**
 - tags, **121–126, 121–126**
 - walls
 - details, **632–650, 632–650**
 - keynotes for, **576–580, 577–579**
- segmented sweeps, **213–214, 213–214**
- Select Items to Copy dialog box, **27, 27**
- Select Layers/Levels to Import/Link dialog box, **661, 661**
- Select Levels option, **78**
- Select Parameter dialog box, **565, 565**
- Select Views option, **79**
- Selection Count tool, **76**
- Selection Filter dialog box, **38**

- selections, 75, **76–78**, 77
 - for copying, 27, 27, **78–79**, 449, 449
 - Design Review, **683**, 683
 - element editing by, **306**
 - filtering, **76**, 77
 - floor areas, 282
 - instances, **76–77**, 77, 594, 698
 - layers, 661, 661
 - levels, 597–598
 - parameters, 565
 - rooms, **537–538**, 537
- semicolons (;) in type-catalog syntax, 164
- separation lines, **535–536**, 536
- Set Host option, 436
- sets, design-option, **300–301**, 301
- shades
 - parametric, **345**, 345
 - from sweeps, 211–212, 211
- shadows and shading, **439–440**
 - for analytical purposes, **441–443**, 441–443
 - enabling, **442**, 442
 - for expressive drawings, 440, 440, **444–445**, 444–445
 - high-contrast black and white effects, **444**, 444
 - materials, 107
 - performance, **445**, 737
 - with SketchUp, 292, 292
 - soft, **445**, 445
 - sun, 509–510, 509–510
 - sun and shadow studies, **441–443**, 441–443
- shaft opening, **670–671**, 670–671
- Shape Editing tools, 282
- shapes
 - elevation tags, 131
 - floors, 155
 - roofs, 155, **416–417**, 416–417
- Shared Coordinates settings, 269
- Shared Levels and Grids workset, 691, 694
- shared parameters, **334–335**, **554**
 - creating, **558–562**, 559–562
 - door tags, **564–567**, 564–568
 - groups, **559–560**, 559–560
 - notes and cautions, **567**
 - project, **555–556**, 555–557, **561–562**, 561–562
- shared site plans, buildings on, **603–604**
- shared work, saving, **700–701**, 700–701
- shed roofs, **392**, 392, 395–396, 395
- Sheet Issues/Revisions dialog box, 674–676, 674, 676
- sheets
 - exporting, **684–686**, 684–686
 - Project Browser views, **52–53**, 53
 - schedules on, **499–500**, 499–500, 505
 - views on, **145**
- Shell and Core workset, 694
- shortcuts, keyboard, **48**, 48, **95–96**, 95
- Show Hidden Lines tool, **626–627**, 627–628
- Show Mass tool, 236
- Show Opening Height option, 117
- Show option
 - schedules, 506
 - shared elements, 705
- Show Related Warnings option, 538
- Show View Name setting, 132
- shower fixture, 212, 212
- shutters, 342
- silhouetted edge displays, **464**, 464–465
- SIM (Similar) condition, **632–633**, 632–634
- Simple fill pattern option, 110, **112–113**, 112
- Single-Day sun settings, 513, 515–516, 516
- SIPs (structurally insulated panels), 640–641
- site data, **266–268**, 267–268
- site studies, **230**, 230
- Site workset, 694
- size
 - elements, **87**, 87
 - text, 118, 132, 159
 - type catalogs for, 162
- sketch-based design, **179–180**
 - floors and roofs, **181–183**, 181–183
 - modeling principles, **180–181**, 180–181
 - rules of thumb, **183**
- Sketch mode, 26
 - for elements, 43
 - railings, 432
- SketchUp software, **290–292**, 291–292
- skins, exterior, **305**, 305
- SKP format
 - importing and linking, 616
 - with SketchUp, 290–292
- sky background, 470–471
- skylight roofs, **388–391**, 388–391
- skylights, 322, 323
- slicing masses, 277
- Slope tool, 433, 433
- Slope Arrow tool, 435
- sloped glazing curtain panel type, 410
- slopes
 - floors, 155
 - railings, 433, 435–436
 - sloped roofs, **23–24**, 24, 155, **416–419**, 416–419
 - barrel, 410, 410
 - ridge skylight roofs, **388–391**, 388–391
 - slope arrows for, **391–392**, 391–392
 - sloped arrow dormers, hipped roofs with, 404–405, 404–405
 - sloped glazing roofs, **386**, 387
- smart workflows
 - groups. *See* groups
 - links. *See* links and linking
 - repetitive elements, **583**
- snap distance for dimension lines, 117

- soft shadows, **445, 445**
- Solid Form options, **202, 202**
- solid panels, **370**
- solids and solid shapes
 - characteristics, **222–224, 223–224**
 - with extrusions, **205, 205**
 - massing forms, **240–241, 240–241**
- Sorting tab, **503**
- Sorting/Grouping tab, **496, 497**
- Space parameter for railings, **428**
- Spacebar for rotation, **83, 83**
- Spacing detail option, **623**
- Specify Coordinates at a Point option, **269, 605**
- Specify Types dialog box, **634, 634**
- Split Face tool, **94, 94**
- Split Region tool, **359, 359**
- Split Segment tool, **121**
- splitting
 - layers, **358–359, 359–360**
 - lines and walls, **90, 90**
- Spread Pattern To Fit setting, **429, 430**
- stacked walls, **355–356, 355–356**
- Stafford, Steve, **744**
- Stair Calculator dialog box, **158, 158**
- stairs, **157, 157**
 - balusters per tread, **429–431, 430**
 - properties, **158–161, 159–161**
- standard families, **27–28, 28, 30, 31**
- Start angle revolve setting, **207, 207**
- Start screen, **34–35, 34**
- starting Revit, **34**
- startup tips, **741–743**
- static text, **122**
- status bar, **38, 38**
- SteeringWheel
 - cameras, **72, 72**
 - perspective views, **461–462, 462–463**
 - working with, **45–46, 46**
- Still settings for sun studies, **513, 516**
- Stringer Carriage Height setting, **161**
- Stringer Left/Right setting, **161**
- strong reference planes, **186, 186**
- structurally insulated panels (SIPs), **640–641**
- Structure option for wall layers, **150**
- Structure panel, **42**
- Structure Settings dialog box, **42**
- styles
 - dimensions, **113–117, 114–115**
 - lines, **102–103, 102–103, 166–168, 167–168**
 - objects. *See* Object Styles dialog box
 - rooms, **549, 549**
- subcategories, **20, 20**
- subdivision surfaces, **296**
- submodels, **737, 738**
- Subscription Center, **38**
- Subscription Support, **743**
- Substrate option for wall layers, **151**
- subtractive profiles, **364**
- sun and shadow studies, **441–443, 441–443, 509–510, 509–510**
 - animated, **515–519, 516–518**
 - daylighting, **527–529, 528–529**
 - exporting, **517, 517**
 - making, **511–515, 511–515**
 - multi-day, **515–516, 515**
 - photorealistic renderings, **468, 468**
 - previewing, **517**
 - time of day, **513**
 - time of year, **515**
 - true-color shading, **456, 456**
- Sun Shade family, **338**
- sun shades
 - parametric, **345, 345**
 - from sweeps, **211–212, 211**
- sunlight renderings, **468, 468**
- sunny vs. overcast days, **525**
- supplemental drawings, **680**
- surfaces
 - lofts, **252–256, 252–256**
 - massing forms, **240, 240**
 - materials, **107, 107**
 - NURBS, **292–293, 292–293**
 - patterns, **261, 261**
 - rationalization, **259–261, 259–261**
 - subdivision, **296**
 - units, **165**
 - warped, **419, 419**
- sustainability, **507**
 - daylighting, **527–529, 528–529**
 - energy analysis, **522–525, 523–526**
 - incorporating, **507–508**
 - LEED rating system, **508**
 - recycled materials, **519–520, 520–521**
 - sun studies. *See* sun and shadow studies
 - window surface percentage vs. room area, **521, 522**
- sweeps, **209, 209, 256–259, 256–259**
 - examples, **212–213, 212–213**
 - lamp from, **219–220, 219–220**
 - paths, **209–210, 209–210**
 - profiles, **210–212, 210–211**
 - trajectory segmentation, **213–214, 213–214**
 - walls, **361–365, 361–365**
- Symbol setting, **134**
- Symbol at End 1/2 Default settings, **134–135**

symbolic lines, **665–667**,
665–667
system families, **26–27**, 26–27, **147**
 ceilings, **156**, **156**
 creating, **147**
 doors and windows,
 161–162
 floors and roofs, **155–156**, 155
 stairs, **157–161**, 157–161
 walls. *See* walls
System Panel Glazed panel, 373
System Panel Solid panel, 373

T

Tab Size setting, 118
tables, revision, 675
Tabs display on Ribbon, 39, 39
Tag on Placement option, 537
tags, **550**, 550
 adding, **491–492**, 491–492
 changing values,
 551–552, 551
 custom, **119**, 119,
 135–136, 135
 doors, **136–138**, 136–138,
 552–554, 553
 loading, **550**
 placing, **550–551**, 550–551
 revision clouds, **679–680**,
 679–680
 rooms, **483**, 483, **538**,
 538–539
 untagged elements,
 552–554, 552–554
 view. *See* view tags
 visibility, **675–676**, 676
 walls, 553–554, 554
tail graphics in section tags,
 125–126, 125–126
Tangent Joins tool, 431
teams
 communication with, 742
 organizing, **742–743**
templates
 creating, **97–100**, 98–99
 custom 3D content,
 320–321, 320–321

 custom title blocks, 141
 family, 30, 31
 fill patterns, 452–453
 graphic overrides of host
 objects, **166–168**, 167–168
 in performance, 741
 strategies, **100**
 views, 170, **175–176**, 175,
 452–453, 452–453
Temporary Dimension
 Properties dialog box, 81, 81
temporary dimensions, **80–81**,
80–81
testing design options, 231, 231
text
 annotating, **568–570**
 dimensions, 117–118
 elevation tags, 131–132, 131
 for graphic consistency,
 117–119, 118
 section view tags, **122**, 122
 stairs, 159
 in views, 531
textnotes, **138–140**, 139–140,
 570–571, 570–571. *See also*
 keynotes
Thermal/Air option, 151
Thickness column for wall
 layers, 152
Thickness/Height of Stringers
 setting, 161
Tick Mark Line Weight
 setting, 115
tick marks, **114–116**, 114–116
Tile option, 45
title blocks
 custom, **140–145**, 141–145
 revision tracking in, **676**
 updates in, 678
TMY2 (Typical Meteorological
 Year 2) data, 525
tool support, **8–9**
toolbars, 589
tooltips, 17
Top Extension Distance
 parameter, 366

Top setting
 blends, 216
 railings, 428
Top view range for floor plans,
57, 58
tracking changes, **673**
 BIM and supplemental
 drawings, **680**
 Design Review. *See* Design
 Review
 revisions, **673–680**, 674–680
tracking recycled materials,
 519–520, 520–521
Trajectory Segmentation
 option, **213–214**, 213–214
transferring color-fill schemes,
 448–449, 449
transparency
 elevation views, **457–458**,
 457–458
 filled regions, 625, 625
Tread Thickness setting, 159
trees, 475–476, 476
Trim Stringers at Top
 setting, 160
trimming
 lines and walls, **89**, 89
 railings, 431
troubleshooting and
 optimizing tips, **731**
 best practices, **733–739**,
 734–738
 blends, **217**, 218–219
 file corruption, **739–740**, 740
 performance, **731–733**,
 732–733
 resources for, **743–744**
 startup tips, **741–743**
true-color elevations, **455–456**,
455–456
Truss property, 382
turning off lights, **469–470**, 470
Twisting blend setting, 216
Type Mark field, 551
type parameters, 555
Type properties, 43, 43

Type Properties dialog box,
70, 70
callouts, 129–130, 130
color fill schemes,
447–448, 447
detail elements, 621–622, 623
dimensions, 114–115, 114, 117
door tags, 137, 565
elevation tags, 131–134, 131
filled regions, 626, 626
keynotes, 580, 580–581
linking parameters, 338, 338
profile families, 324–326, 325
railing construction, 425, 425
room volumes, 543, 543
stairs, 158, 158
text, 118–119
tick marks, 115, 115
view tags, 120, 125–126, 126
walls, 148, 153, 153

Type Selector
family types, 42–43, 43
materials, 93–94, 95
selection by, 77
text, 569

types and type catalogs, 162, 162
3D content. *See* custom 3D
content
creating, 162–163, 164
loadable, 200, 200
loading from, 166, 166
parameters, 20
in project environment,
162–163
syntax, 164–165
units, 165

Types dialog box for
revolves, 252

Typical Meteorological Year 2
(TMY2) data, 525

U

UIState.dat file, 47
Unbounded Height
property, 540
Underline setting, 119

Underside of Winder setting,
158, 159
undocking Project Browser,
48, 48
unenclosed room errors,
534, 534
units
settings, 169–170, 170
type catalogs, 165
Unjoin Geometry option,
241–242, 286
unloading
links, 607
unused DWGs and
views, 733
unused elements
in performance, 734,
735, 740
unloading, 733
updates
building area schedules,
501
in title blocks, 678
Upper Limit property, 539
usable area calculations, 484
Use Baluster Per Tread On
Stairs option, 429–431, 430
Use Common Edge Style
option, 168
Use Function option, 168
Use OpenGL Hardware
Acceleration option, 733
Use Overlay Planes to Improve
Display Performance
option, 733
Use Project Settings option, 504
Use Render Appearance for
Shading option, 107
Use Sheet Size option, 684, 684
user interface, 34
application frame, 36–44,
36–44
Design Review, 682–683,
682–683
modifying and
personalizing, 47–48,
47–48

Project Browser. *See* Project
Browser
ribbons, 35, 35
Start screen, 34–35, 34
starting Revit, 34
SteeringWheel and
ViewCube, 45–46, 46
View window, 45
user keynotes, 139, 571, 581
UV surface divisions, 260,
260–261, 286–287, 288

V

Variable property, 155, 155
variable widths, rooms
calculations for, 543–546,
543–546
variations to group instances,
594–597, 594–597
vaults, 223, 223
verifying
designs, 278–281, 279–281
programs, 231–233,
231–233
Vertical Opening tool, 384
vertical shapes, 223, 224
Vertical tag orientation, 553
vertices, blend, 216, 217–218
video card options, 733, 734
View Control bar, 45, 45
view depth
floor plans, 60–62, 60–61
in performance, 736, 736
plan views, 62–66, 63–66
section views, 68, 68
View Detail setting, 735
View/Floor Plan tool, 275
View Range dialog box, 56–58,
57, 62–66, 63–66
View tab, 41, 41
view tags, 120, 120, 531
callouts, 127–130, 127–130
elevation, 130–134, 131–133
grid, 135
levels, 134, 134
section, 121–126, 121–126

View Templates dialog box, 175, 176, 453, 453

View window, 45, 683

ViewCube, 45–46, 46

views, 20

- annotating, 531, 531
- default settings, 175, 175
- dependent, 19
- drafting, 612, 612, 631
- elevation tags, 132
- importing, 669–670, 669–670
- keynotes in, 573–574, 574
- lists of, 494
- in performance, 735, 739
- perspective. *See* perspective views
- plan
 - default settings, 175
 - Project Browser views, 62–66, 63–66
 - visibility in, 665
- Project Browser. *See* Project Browser
- selection by, 79
- on sheets, 145
- for sketches, 183
- templates, 170, 175–176, 175, 452–453, 452–453
- worksets, 692

visibility

- chairs, 348–349, 348–349
- conditional, 338–339, 339
- details, 663–665, 664–665
- extrusions, 204, 204
- link, 606–607, 607
- mass elements, 236–237, 236–237
- revision clouds and tags, 675–676, 676
- work planes, 190, 191
- worksharing files, 690

Visibility/Graphic Overrides dialog box, 10, 11, 32, 33

- colored sections, 449
- cost schedules, 313
- cutting, 58

- design options, 306, 306
- exterior skins, 305
- fill patterns, 452–453, 452
- graphics, 166–168, 167–168
- imported CAD files, 732
- line patterns, 104
- links, 615
- mass elements, 236–237
- Project Browser views, 50
- room elements, 315
- room separation lines, 535, 537
- schedules, 499
- site data, 266
- worksets, 694, 696
- worksharing files, 690, 691

Void Form options, 202, 202

void shapes, 205, 205, 222–224, 223–224

volume

- computation settings, 168–169, 169
- rooms, 541–546, 541–546, 732–733, 733
- units, 169

Volume property, 540

W

walkthroughs, 462, 477–478, 478

Wall tool, 42

Wall by Face tool, 282

Wall Editor, 152

Wall Joins tool, 354, 354

Wall Sweep tool, 364

Wall Sweeps dialog box, 362, 362

walls, 147–148, 149

- articulation, 356–360, 357–360
- bidirectional relationships, 22–23, 23
- blends, 368
- compound, 356, 357
- cores, 351–353, 352–353
- curtain, 369–370, 369–370
- designing, 370–373, 371–373
- doors and windows, 374, 374
- panels, 373–375, 374–375
- custom, 148, 148–150
- default wrapping, 153, 153
- layers, 150–154, 151–152
- preview window, 150
- defaults, 172
- disjoining, 354, 354
- extending, 90, 90, 366–367, 366–367
- finish materials, 358–360, 358–360
- functions, 154–155
- host-based families, 322, 323
- in-place, 368, 368
- join editing, 354, 354
- layer join cleanup, 353–354, 353
- levels of detail, 153, 154
- Model by Face tool, 281–282
- in modeling principles, 199–200
- offsetting, 91, 91
- overlapping, 586
- railings on, 434–436, 434–436
- rotating, 84, 84
- sections
 - details, 632–650, 632–650
 - keynotes for, 576–580, 577–579
- splitting, 90, 90
- stacked, 355–356, 355–356
- sweeps and reveals, 361–365, 361–365
- tags, 532, 550, 550, 553–554, 554
- trimming, 89, 89
- wrapping, 361, 361

warnings
 overlapping items, 586
 reviewing, **740**, 740
 tags, 533, 533, 538
 warped surfaces, **419**, 419
 weak reference planes, 186, 186
 Weld setting, 431
 Where Is My Command? tool,
 44, 44
 width
 elevation tags, 132
 Insulation tool, 624
 shutter, 342
 text, 119
 Window category, 62
 Window.rft template, 322
 window surface percentage,
 521, 522
 windows
 curtain wall, **374**, 374
 defaults, 172
 host-based families, 322, 323
 in modeling principles,
 200, 200
 with muntins, 341, 341
 rotating, **83**
 selection, 76
 types, **162**
 witness lines, 115–116

work plane-based families, **329**,
 334–335
 Work Plane-based option,
 334–335
 work planes, **183–184**, 184
 grids, 190, 191
 levels, 185–186
 operations, **190–192**,
 191–192
 roofs by extrusion, **193–197**,
 193–197
 visibility, **190**, 191
 working with, **189–190**,
 189–190
 workflows, **698**
 central files, **698–699**, 698
 local files, **699**, 699
 massing studies, **229–230**
 smart
 groups. *See* groups
 links. *See* links and
 linking
 repetitive elements, **583**
 worksets, 696
 worksets, **689–690**, 690,
 692–693, 692–693
 moving elements between,
 696–698, 697

organization, **694–695**,
 695–696
 in performance, 735
 permissions, 704–705,
 704–705
 worksharing, **689**
 basics, **691–693**, 692
 element ownership,
 701–706, 702–706
 mistakes in, **702**
 in performance, 733
 saving shared work,
 700–701, 700–701
 workflows, **698–701**,
 698–699
 workset methods. *See*
 worksets
 wrapping walls, **361**, 361
 Wraps column for wall layers,
 152, 152

X

X-Ray mode, 256
 X-References, **10**

Z

Zoom tool, 46


Mastering Revit Architecture Project Gallery

This gallery comes from architects from all around the globe who have embraced the move to a smarter way of working on projects. They all have different skill levels with Revit, but what ties them together is that they have produced beautiful architectural examples using BIM.


BIM is not a myth. These are real architects, real projects, and real sources of inspiration. And don't forget, it's technology, it's digital—but still, what really matters is that it's good architecture.



COURTESY OF DARK ARKITEKTER AS, NORWAY




Burt, Hill USA



Various Projects: Student Centre; Hamilton Plaza





Nemeth, Polakova, Senteska Slovakia






Hviezdoslav Apartments




Case Design USA



Tower Study


Gensler USA





American University of Beirut, School of Engineering


To Pluss To Norway



Commercial Rehabilitation project, Norway

HOK

Worldwide



DC Consolidated
Forensic Laboratory
Owner: Government of
the District of Columbia,
Architect—HOK; Washington, DC



Residencias Garza Sada, Monterrey
Architect—HOK, Mexico



Internacional de
Inversiones
Conjunto Torre 40
Monterrey, N.L.
Architect—
HOK, Mexico


DC Consolidated
Forensic Laboratory
Owner: Government of
the District of Columbia,
Architect—HOK;
Washington, DC



Reston Heights, Reston VA
Owner: The JBG Companies,
Architect—
HOK; Washington, DC
MEP Engineers—
R.G. Vanderweil; Boston, MA




Residencias Garza Sada, Monterrey
Architect—HOK, Mexico



Estadio de Fútbol Rayados
Design Architect—Populous
Prime Architect—HOK, Mexico



WATG USA



Four Seasons Cove 4 Restaurant and Sofitel Qiandaohu Lakeside Resort




Ellerbe Becket

USA



Medical and Research Center




Montealegre Beach Arquitectos Ltda Chile



Stadium


Link Landskap

Norway



Nedre Jarlsberg Brygge, Residential Harbor Development, Midtbygda Skole, Norway

E. N. Raycroft; T. Castro; A. Blood; D. Belcher USA



Redefine How You Design and Document with Revit Architecture 2010

Join the BIM revolution with the new edition of this bestselling guide from an expert author team of Revit professionals. Using clear explanations, detailed tutorials, and practical examples, they show you how to immediately implement and use Revit with spectacular results.

You'll start with a thorough look at Revit and BIM basics, before quickly moving into setting up and customizing tools, preparing templates and settings, and creating a library of components. From there, the book guides you through a wealth of information, including the new conceptual modeling environment, using Revit for green building analysis, implementing smart workflows, creating rich construction documents, and more. Packed with techniques, tips, and 16 pages of stunning examples in full color, this is the perfect resource to help you unleash your creativity with Revit Architecture 2010.

COVERAGE INCLUDES:

- Customizing system families and project settings to create templates and make Revit match your style and needs
- Using the new conceptual design tools to quickly build and rationalize complex geometry
- Verifying early design decisions using massing studies and schedules
- Mastering modeling principles of Revit
- Understanding smart workflows—the power of groups, links, and design options
- Learning practical techniques to achieve rich construction documentation
- Collaborating, tracking changes, and coordinating processes
- Measuring the effects of sun and shadow using solar animations

ABOUT THE AUTHORS

Greg Demchak is a product designer for Revit Architecture. He also teaches at Boston Architectural College and holds a master's degree in architecture from MIT. **Tatjana Dzambazova** is an internationally recognized AEC industry technology speaker. She was project manager for Revit Architecture for two years and previously practiced architecture for twelve years in Vienna and London. **Eddy Krygiel** is an Autodesk Authorized Author and registered architect at HNTB Architects. He has used Revit to complete projects of all scopes and sizes. Eddy is responsible for implementing BIM at his firm and also consults for other architecture and contracting firms looking to implement BIM.

www.sybex.com

www.sybex.com/go/masteringrevit2010

Sybex®
An Imprint of
 **WILEY**

Autodesk®
Authorized Publisher

CATEGORY
COMPUTERS/CAD-CAM

Autodesk®
Authorized Author

\$59.99 US
\$71.99 CAN

Move to BIM and Increase Your Productivity

Implement Revit and BIM Principles, and Learn Best Practices

Improve Your Workflows, Worksharing, and Collaboration

Learn Advanced Modeling and Presentation Techniques

Explore Sustainable Design with Revit Architecture

Enjoy Interoperability with Civil 3D® 2010 and 3ds Max® Design 2010

ISBN 978-0-470-45649-1

